

DATE : December 20, 2001  
LAHOMA DEPARTMENT OF TRANSPORTATION  
NOTICE TO CONTRACTORS -- January 24, 2002

LNTCNCA  
LETTING

LNTCNCA-D

SEALED PROPOSALS SENT BY REGISTERED MAIL WILL BE RECEIVED THROUGH THE ODOT REPRODUCTION BRANCH UNTIL 30 MINUTES PRIOR TO THE SCHEDULED BID OPENING. FROM 30 MINUTES PRIOR TO THE BID OPENING UNTIL THE TIME OF THE BID OPENING, BID PROPOSALS MUST BE TURNED IN DIRECTLY TO THE ODOT COMMISSION ROOM LOCATED ON THE EAST SIDE OF THE LOBBY. THE SCHEDULED BID OPENING OF 2:00 P.M. January 24, 2002 , FOR THE WORK LISTED BELOW.

NO PROPOSAL FOR CONSTRUCTION OR MAINTENANCE WORK OF THE DEPARTMENT WILL BE ISSUED TO ANY CONTRACTOR AFTER 2:00 P.M. ON THE WORKING DAY PRECEDING OPENING OF BIDS FOR ANY CONTRACT.

EACH SEPARATE PROPOSAL SHALL BE ACCOMPANIED BY A CERTIFIED OR CASHIER'S CHECK OR BID BOND EQUAL TO 5% OF THE BID MADE PAYABLE TO THE STATE OF OKLAHOMA, DEPARTMENT OF TRANSPORTATION, AS A PROPOSAL GUARANTY. PROPOSAL CHECKS WILL BE HELD OR RETURNED BY THE DEPARTMENT AS PER SECTION 103.04 OF THE STATE STANDARD SPECIFICATIONS.

THIS WORK WILL BE DONE UNDER THE OKLAHOMA DEPARTMENT OF TRANSPORTATION COMMISSION'S APPLICABLE SPECIFICATIONS FOR HIGHWAY CONSTRUCTION.

THE MINIMUM WAGE TO BE PAID LABORERS AND MECHANICS EMPLOYED ON THIS PROJECT WILL BE INCLUDED IN THE PROPOSAL.

PROPOSALS MUST BE PREPARED AS DIRECTED BY THE STATE STANDARD SPECIFICATIONS.

PLANS, FORMS OF PROPOSALS, CONTRACTS AND SPECIFICATIONS MAY BE EXAMINED AT THE DIVISION HEADQUARTERS IN THE DIVISION THE WORK IS TO BE PERFORMED OR AT THE OKLAHOMA DEPARTMENT OF TRANSPORTATION OFFICE ENGINEER'S DIVISION IN OKLAHOMA CITY, OKLAHOMA.

PLANS AND PROPOSAL FORMS MAY BE ORDERED FROM JACK STEWART, DIVISION ENGINEER, OKLAHOMA DEPARTMENT OF TRANSPORTATION BUILDING, 200 N.E. 21ST STREET, OKLAHOMA CITY, OKLAHOMA 73105. COST OF BIDDING DOCUMENTS ARE \$25.00 + tax FOR EACH BIDDING PROPOSAL. STATE STANDARD SPECIFICATION 1988 EDITION (RED BOOK) AND 1991 SUPPLEMENT MAY BE PURCHASED FOR \$8.00 + tax, OR 1996 METRIC STANDARD SPECIFICATION \$27.00 + TAX, OR 1999 METRIC AND ENGLISH STANDARD SPECIFICATION \$55.00 + TAX. (OKLAHOMA TAX IS 7.875%). MAKE CHECKS PAYABLE TO OKLAHOMA DEPARTMENT OF TRANSPORTATION.

NO REFUNDS WILL BE MADE FOR BIDDING DOCUMENTS OR SPECIFICATION BOOKS PURCHASED BY PROSPECTIVE BIDDERS.

UPON AWARD OF CONTRACT TO A SUCCESSFUL BIDDER, THE CONTRACT WILL BE COMPLETELY AND CORRECTLY EXECUTED BY THE CONTRACTOR AND RETURNED TO THE DEPARTMENT WITHIN TEN (10) WORKING DAYS FROM THE DATE OF AWARD. THE DEPARTMENT WILL HAVE FOURTEEN (14) WORKING DAYS FROM THE DATE OF AWARD TO COMPLETE ITS EXECUTION OF THE CONTRACT.

THE OKLAHOMA DEPARTMENT OF TRANSPORTATION HEREBY NOTIFIES ALL BIDDERS THAT IT WILL AFFIRMATIVELY INSURE THAT IN ANY CONTRACT ENTERED INTO PURSUANT TO THIS ADVERTISEMENT, DISADVANTAGED BUSINESS ENTERPRISES WILL BE AFFORDED FULL OPPORTUNITY TO SUBMIT BIDS IN RESPONSE TO THIS INVITATION AND WILL NOT BE DISCRIMINATED AGAINST ON THE GROUNDS OF RACE, COLOR, SEX, RELIGION, NATIONAL ORIGIN, OR DISABILITY IN CONSIDERATION FOR AN AWARD.

BIDDERS ARE HEREBY NOTIFIED THAT ALL BIDS ARE LIKELY TO BE REJECTED IF THE LOWEST RESPONSIVE BID RECEIVED EXCEEDS THE ENGINEER'S ESTIMATE BY MORE THAN SEVEN (7) PERCENT. IN THE EVENT ALL BIDS ARE REJECTED FOR THIS REASON, THIS PROJECT MAY BE DEFERRED FOR READVERTISING FOR BIDS UNTIL A MORE COMPETITIVE SITUATION EXISTS.

DESCRIPTION OF WORK AND LOCATION OF PROJECT:

CALL ORDER : 030  
 LETTING DATE : January 24, 2002  
 LETTING TIME : 2:00 P.M.

CONTRACT ID : 020023  
 PCN : 1788504  
 PROJECTS : CB-106C(24)  
 CALENDAR DAYS : 100  
 RES. ENG. :  
 LIQ. DAM. : \$ 600

CONTRACT DESCRIPTION:  
 BRIDGE & APPROACHES COUNTY ROAD (NS-254) OVER RELAY CREEK  
 APPROX. 4.5 MI. W. AND 1.1 MI. N. AND 1.3 MI. N OF US-281  
 IN GREENFIELD PROJECT LENGTH 0.340 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 E000 - ROADWAY			
202(G) 0185	EARTHWORK	1.000	LSUM
222 2801	TEMPORARY BALE BARRIER	385.000	LF
227 0100	TEMPORARY SILT DIKE	300.000	LF
233(A) 2817	VEGETATIVE MULCHING	1.020	AC
509(D) 0325	CLASS C CONCRETE	10.000	CY
SECTION NO. 0002 X028 - BRIDGE "A".			
202(A) 1301	UNCLASSIFIED EXCAVATION	675.000	CY
501(A) 1306	STRUCTURAL EXCAVATION UNCLASSIFIED	37.000	CY
504(E) 1380	CONCRETE RAIL (TR1)	53.700	LF
509(B) 1328	CLASS A CONCRETE	120.300	CY
511(A) 1332	REINFORCING STEEL	16,430.000	LB
623(F) 6033	GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 X028 - BRIDGE "B"			
202(A) 1301	UNCLASSIFIED EXCAVATION	280.000	CY
501(A) 1306	STRUCTURAL EXCAVATION UNCLASSIFIED	32.000	CY
504(E) 1380	CONCRETE RAIL (TR1)	44.000	LF
509(B) 1328	CLASS A CONCRETE	102.700	CY
511(A) 1332	REINFORCING STEEL	14,290.000	LB
623(F) 6033	GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
SECTION NO. 0004 STAK - STAKING			
642 0098	STAKING	1.000	LSUM

CALL ORDER : 150  
 LETTING DATE : January 24, 2002  
 LETTING TIME : 2:00 P.M.  
 COUNTIES : MCCLAIN

CONTRACT ID : 010436  
 PCN : 1896704  
 PROJECTS : STP-144B(38)IP  
 DBE GOALS : 9.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 20.50  
 CALENDAR DAYS : 210  
 RES. ENG. :  
 LIQ. DAM. : \$ 500

CONTRACT DESCRIPTION:  
 GRADE, DRAIN, SURFACE AND BRIDGE ON SH-9: BEGIN 1.0 MILE  
 WEST OF I-35, EXTEND EAST TO I-35 PROJ. LGTH.= 1.688 KM.  
 FLEX. ESALS= 6.1 MILLION ASPH. GRADE= 64-22 OK, 76-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
-----			
SECTION NO. 0001	I000-ROADWAY		
201	M0102 CLEARING AND GRUBBING	1.000	LSUM
202(A)	M0183 UNCLASSIFIED EXCAVATION	15,289.000	M3
202(C)	M0184 UNCLASSIFIED BORROW	19,141.000	M3
205	M4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
222	M2801 TEMPORARY BALE BARRIER	103.000	M
223	M2802 TEMPORARY SILT FENCE	973.000	M
226	M2805 TEMPORARY SEDIMENT REMOVAL	20.000	M3
229	M4318 DITCH LINER PROTECTION	77.000	M
230(A)	M2806 SOLID SLAB SODDING	46,990.000	M2
233(A)	M2817 VEGETATIVE MULCHING	4.500	HA
303	M5912 AGGREGATE BASE	5,416.000	T
317(A)	M4252 (SP)FLY ASH	1,985.000	T
317(B)	M4254 SUBGRADE MODIFICATION	34,405.000	M2
317(C)	M4253 LIME	66.000	T
317(D)	M4254 SCARIFY,MIX BLADE OF SUBGRADE W/LIME TRT	3,441.000	M2
403(E)	M0225 TRAFFIC BOUND SURFACE COURSE TYPE E	250.000	T
407	M0250 TACK COAT	22,286.000	L
408	M5774 PRIME COAT	23,519.000	L
411(S3)	M5935 (SP)ASPH.CONC.,TYPE S3(PG 76-28 OK)	6,692.000	T
411(S3)	M5945 (SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	8,491.000	T
411(S4)	M5950 (SP)ASPH.CONC.,TYPE S4(PG 76-28 OK)	3,766.000	T
411(S4)	M5960 (SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	1,614.000	T
414(A)	M0260 200MM P.C. CONCRETE PAVEMENT	1,236.000	M2
420(A)	M4242 FABRIC REINFORCEMENT	14,705.000	M2
420(B)	M4268 BITUMINOUS BINDER	15,476.000	L
501(A)	M0313 STRUCTURAL EXCAVATION UNCLASSIFIED	89.000	M3
509(B)	M1328 CLASS A CONCRETE	172.000	M3
509(D)	M0325 CLASS C CONCRETE	25.000	M3
511(A)	M1332 REINFORCING STEEL	14,230.000	KG
609(A)	M0300 CONC.CURB(150MM BARRIER-INTEGRAL)	585.000	M
609(B)	M1513 500MM COMB.CRB.& GUT.(150MM BAR.)	299.000	M
610(B)	M0399 150MM CONCRETE DRIVEWAY (H.E.S.)	1,566.000	M2
610(G)	M4475 BITUMINOUS DRIVEWAY (150MM)	2,014.000	M2
613(B)	M0405 450MM R.C.PIPE CLASS III	18.000	M
613(B)	M0409 600MM R.C.PIPE CLASS III	18.000	M
613(B)	M0413 750MM R.C.PIPE CLASS III	19.000	M
613(B)	M0415 900MM R.C.PIPE CLASS III	42.000	M

CALL ORDER : 150  
 LETTING DATE : January 24, 2002  
 LETTING TIME : 2:00 P.M.  
 COUNTIES : MCCLAIN

CONTRACT ID : 010436  
 PCN : 1896704  
 PROJECTS : STP-144B(38)IP  
 DBE GOALS : 9.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 20.50  
 CALENDAR DAYS : 210  
 RES. ENG. :  
 LIQ. DAM. : \$ 500

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 I000-ROADWAY			
613(B) M0417	1050MM R.C.PIPE CLASS III	65.000	M
613(B) M4419	1110MM X 675MM R.C.PIPE ARCH CLASS A-III	69.000	M
613(B) M4423	1300MM X 795MM R.C.PIPE ARCH CLASS A-III	29.000	M
613(CC)M7186	TYPE A4 CULVERT END TREATMENT	2.000	EA
613(CC)M7187	TYPE B4 CULVERT END TREATMENT	2.000	EA
613(CC)M7188	TYPE C4 CULVERT END TREATMENT	2.000	EA
613(CC)M7189	TYPE D4 CULVERT END TREATMENT	16.000	EA
613(P) M1092	200MM PERFORATED PIPE UNDERDRAIN ROUND	157.000	M
613(Q) M1097	200MM NON-PERF.PIPE UNDERDRAIN RND.	40.000	M
619(A) M0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619(B) M0291	REMOVAL OF HEADWALL	2.000	EA
619(B) M4728	REMOVAL OF ASPHALT PAVEMENT	15,461.000	M2
619(B) M4766	REMOVAL OF CONCRETE DRIVEWAY	1,572.000	M2
619(C) M0924	SAWING PAVEMENT	1,398.000	M
629(E) M5048	REMOVE AND RESET MAILBOX	1.000	EA
641 M1552	MOBILIZATION	1.000	LSUM
SECTION NO. 0002 X028-BRIDGE 'A'			
202(A) M1301	UNCLASSIFIED EXCAVATION	151.000	M3
501(A) M1306	STRUCTURAL EXCAVATION UNCLASSIFIED	57.000	M3
509(B) M1328	CLASS A CONCRETE	108.000	M3
511(A) M1332	REINFORCING STEEL	9,620.000	KG
619(B) M2505	(PL)REMOVAL OF BRIDGE ITEMS	1.000	EA
SECTION NO. 0003 Y000-TRAFFIC			
627(E) M4314	PRECAST CONC. MEDIAN BARRIER, PORT. TYPE	347.000	M
850(A) M8110	SHEET ALUMINUM SIGNS	13.700	M2
851(C) M8324	50MM SQUARE TUBE POST	48.320	M
851(C) M8327	57MM SQUARE TUBE POST	51.880	M
855(A) M8812	TRAFFIC STRIPE(PLASTIC)(100MM WIDE)	9,152.000	M
855(B) M8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	40.000	EA
855(B) M8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	4.000	EA
856(A) M8839	CONSTR.TRAFF.STR.(PAINT)(100MM WIDE)	6,756.000	M
856(C) M8851	REM.PAVEMENT MARKING TAPE(100MM WIDE)	150.000	M
856(G) M8887	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-1	2,450.000	EA
857(A) M8935	PAVE.MARKERS CLASS C TYPE 1-B	209.000	EA
857(A) M8947	PAVE.MARKERS CLASS C TYPE 2-C	81.000	EA
857(A) M8950	PAVE.MARKERS CLASS C TYPE 2-D	253.000	EA
859(A) M8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	3,378.000	M
870(A) M8011	SAND FILLED IMPACT ATTEN.MODULE	15.000	EA
880(J) M8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

CALL ORDER : 150  
 LETTING DATE : January 24, 2002  
 LETTING TIME : 2:00 P.M.  
 COUNTIES : MCCLAIN

CONTRACT ID : 010436  
 PCN : 1896704  
 PROJECTS : STP-144B(38)IP  
 DBE GOALS : 9.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 20.50  
 CALENDAR DAYS : 210  
 RES. ENG. :  
 LIQ. DAM. : \$ 500

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003	Y000-TRAFFIC		
890(A) M8722	(PL)REMOVAL OF EXISTING SIGNS	1.000	LSUM
SECTION NO. 0004	STAK-STAKING		
642 M0098	STAKING	1.000	LSUM

CALL ORDER : 160  
 LETTING DATE : January 24, 2002  
 LETTING TIME : 2:00 P.M.  
 COUNTIES : MAYES

CONTRACT ID : 020013  
 PCN : 1815204  
 PROJECTS : STPY-149A(39)TR  
 DBE GOALS : 0.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 3.78  
 CALENDAR DAYS : 30  
 RES. ENG. :  
 LIQ. DAM. : \$ 500

CONTRACT DESCRIPTION:  
 TRAFFIC SIGNALS INTERSECTION OF SH-20 & HOGAN IN PRYOR  
 PROJECT LENGTH 0.00 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	Y031 - TRAFFIC SIGNAL		
610(A) 0602	4" CONCRETE SIDEWALK	26.680	SY
641 1552	MOBILIZATION	1.000	LSUM
802(B) 8332	1" PVC SCH.40 PLASTIC CONDUIT BORED	120.000	LF
802(B) 8336	1 1/2" PVC SCH.40 PLASTIC CONDUIT BORED	150.000	LF
802(B) 8338	1 1/2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	284.000	LF
802(B) 8342	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	44.000	LF
802(B) 8344	3" PVC SCH.40 PLASTIC CONDUIT BORED	152.000	LF
802(B) 8346	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	142.000	LF
803 8065	PULL BOX(SIZE I)	5.000	EA
803 8066	PULL BOX(SIZE II)	1.000	EA
803 8067	PULL BOX(SIZE III)	2.000	EA
804(A) 2915	STRUCTURAL CONCRETE	10.690	CY
804(B) 2916	REINFORCING STEEL	1,595.000	LB
806(A) 8832	40' MHP 20' TS & 10' LMA(G.STL.)	1.000	EA
806(A) 8844	40' MHP 30' TS & 10' LMA(G.STL.)	2.000	EA
806(A) 8858	40' MHP 40' TS & 10' LMA(G.STL.)	1.000	EA
806(B) 8892	8' MTG.HT.TS PED.POLE(G.STL.)	1.000	EA
809(A) 8090	(PL)ROADWAY LUMINAIRE	4.000	EA
811 8040	1/C NO.6 ELECT.COND.	102.000	LF
811 8044	1/C NO.10 ELECT.COND.	1,417.000	LF
825 8550	VEH.ACT.SOL.ST.TRAF.SIG.CON.ASM	1.000	EA
828(A) 8135	SOL.STE.DIGITAL IND.VEH.LP.DET.	11.000	EA
828(B) 8138	LOOP DETECTOR WIRE	3,480.000	LF
830 8000	PEDESTRIAN PUSH BUTTON	8.000	EA
831 8231	1WAY3SEC.ADJ.SIG.HD.S-6	8.000	EA
831 8295	1WAY2SEC.ADJ.PED.SIG.HD.S-20	8.000	EA
833 3030	BACKPLATE	8.000	EA
834(A) 8207	5/C TRAF.SIG.EL.CABLE	1,066.000	LF
834(A) 8209	9/C TRAF.SIG.EL.CABLE	469.000	LF
834(B) 8220	2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	909.000	LF
850(A) 8110	SHEET ALUMINUM SIGNS	28.500	SF
850(C) 8118	MAST ARM MOUNTED SIGNS(ALUM.)	51.500	SF
851(C) 8327	2 1/4" SQUARE TUBE POST	60.000	LF
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	694.000	LF
855(B) 8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	3.000	EA
855(B) 8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	1.000	EA
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
890(A) 8724	(PL)REMOVAL OF EXISTING SIGNS	5.000	EA

CALL ORDER : 160  
 LETTING DATE : January 24, 2002  
 LETTING TIME : 2:00 P.M.  
 COUNTIES : MAYES

CONTRACT ID : 020013  
 PCN : 1815204  
 PROJECTS : STPY-149A(39)TR  
 DBE GOALS : 0.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 3.78  
 CALENDAR DAYS : 30  
 RES. ENG. :  
 LIQ. DAM. : \$ 500

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	Y031 - TRAFFIC SIGNAL		
890(A) 8726	(PL)REMOVAL OF TRAFFIC SIGNAL EQUIPMENT	1.000	LSUM
SECTION NO. 0002	STAK - STAKING		
642 0098	STAKING	1.000	LSUM

CALL ORDER : 220  
 LETTING DATE : January 24, 2002  
 LETTING TIME : 2:00 P.M.  
 COUNTIES : PITTSBURG

CONTRACT ID : 020015  
 PCN : 1843504  
 PROJECTS : BRO-161D(059) CO  
 DBE GOALS : 5.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 4.32  
 CALENDAR DAYS : 150  
 RES. ENG. :  
 LIQ. DAM.: \$ 600

CONTRACT DESCRIPTION:  
 BRIDGE AND APPROACHES CO. BR. OVER SCIPIO CREEK, .4 MILE S.  
 AND 1.6 MILE W. OF SCIPIO PROJECT LENGTH 0.178 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 E000 - ROADWAY			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(G)	0185 EARTHWORK	1.000	LSUM
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
210	0121 OBLITERATING ABANDONED ROAD	5.600	STA
227	0100 TEMPORARY SILT DIKE	2,484.000	LF
230(A)	2806 SOLID SLAB SODDING	2,282.000	SY
233(A)	2817 VEGETATIVE MULCHING	1.200	AC
403(E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	539.000	TON
509(D)	0325 CLASS C CONCRETE	84.000	CY
613(B)	4496 28" X 18" R.C.PIPE ARCH CLASS A-III	34.000	LF
613(C)	4804 SP. END SECTION OF 28" X 18" RCP ARCH	2.000	EA
629(A)	4958 MAILBOX INSTALLATION-SINGLE	1.000	EA
629(C)	4960 MAILBOX	1.000	EA
629(D)	4961 REMOVAL OF MAILBOX INSTALLATION	1.000	EA
SECTION NO. 0002 X081 - BRIDGE "A"			
501(B)	1307 SUBSTRUCTURE EXCAVATION COMMON	92.000	CY
501(D)	6353 UNCLASSIFIED BACKFILL	102.000	CY
503(A)	1312 PRESTRESSED CONCRETE BEAMS (TYPE III)	276.170	LF
503(A)	1313 PRESTRESSED CONCRETE BEAMS (TYPE IV)	316.170	LF
504(E)	1380 CONCRETE RAIL (TR1)	369.200	LF
506(A)	1322 STRUCTURAL STEEL	3,580.000	LB
509(A)	1326 CLASS AA CONCRETE	115.300	CY
509(B)	1328 CLASS A CONCRETE	81.400	CY
511(A)	1332 REINFORCING STEEL	37,640.000	LB
514(A)	6010 PILES, FURNISHED (HP 10X42)	86.000	LF
514(A)	6011 PILES, FURNISHED (HP 12X53)	200.000	LF
514(B)	6292 PILES, DRIVEN (HP 10X42)	86.000	LF
514(B)	6294 PILES, DRIVEN (HP 12X53)	200.000	LF
516(A)	6093 DRILLED SHAFTS 42" DIAMETER	31.000	LF
601(A-1)	1353 TYPE I-A PLAIN RIPRAP	820.000	TON
601(A-2)	1355 TYPE I-A FILTER BLANKET	225.000	TON
619(D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F)	6033 GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
641	1399 MOBILIZATION	1.000	LSUM
880(J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAK - STAKING			



CALL ORDER : 220  
LETTING DATE : January 24, 2002  
LETTING TIME : 2:00 P.M.  
COUNTIES : PITTSBURG

CONTRACT ID : 020015  
PCN : 1843504  
PROJECTS : BRO-161D(059) CO  
DBE GOALS : 5.00  
GUARANTY : 5% OF BID TOTAL  
PLAN PRICE : 4.32  
CALENDAR DAYS : 150  
RES. ENG. :  
LIQ. DAM. : \$ 600

642 0098 STAKING 1.000 LSUM

CALL ORDER : 280  
 LETTING DATE : January 24, 2002  
 LETTING TIME : 2:00 P.M.  
 COUNTIES : SEQUOYAH

CONTRACT ID : 020016  
 PCN : 1253004  
 PROJECTS : STPY-68A(298)  
 DBE GOALS : 5.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 27.51  
 CALENDAR DAYS : 310  
 RES. ENG. :  
 LIQ. DAM. : \$ 1000

CONTRACT DESCRIPTION:  
 GRADE, DRAIN AND SURFACE US-59: FROM I-40 APPROX. 2.09 KM  
 SOUTH PROJ LNGTH=2.12 KM ASPHALT TYPE PG 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS	
SECTION NO. 0001	J000-ROADWAY			
201	M0102	CLEARING AND GRUBBING	1.000	LSUM
202(A)	M0183	UNCLASSIFIED EXCAVATION	43,185.000	M3
202(C)	M0184	UNCLASSIFIED BORROW	12,500.000	M3
205	M4229	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
222	M2801	TEMPORARY BALE BARRIER	100.000	M
223	M2802	TEMPORARY SILT FENCE	50.000	M
226	M2805	TEMPORARY SEDIMENT REMOVAL	25.000	M3
227	M0100	TEMPORARY SILT DIKE	75.000	M
230(A)	M2806	SOLID SLAB SODDING	94,460.000	M2
232(B)	M2814	SEEDING METHOD B	9.940	HA
233(A)	M2817	VEGETATIVE MULCHING	9.940	HA
241	M2832	MOWING	9.940	HA
303	M0192	AGGREGATE BASE	7,346.000	M3
317(A)	M4252	(SP)FLY ASH	3,000.000	T
317(B)	M4254	SUBGRADE MODIFICATION	52,010.000	M2
317(C)	M4253	LIME	400.000	T
317(D)	M4254	SCARIFY,MIX BLADE OF SUBGRADE W/LIME TRT	20,804.000	M2
403(E)	M0225	TRAFFIC BOUND SURFACE COURSE TYPE E	4,840.000	T
407	M0250	TACK COAT	5,163.000	L
408	M5774	PRIME COAT	95,456.000	L
411(A)	M6500	(SP)ASPHALT CONCRETE TYPE A(PG 64-22 OK)	3,224.000	T
411(B)	M6530	(SP)ASPHALT CONCRETE TYPE B(PG 64-22 OK)	6,875.000	T
414(A)	M0262	250MM P.C. CONCRETE PAVEMENT	4,759.000	M2
414(A1)	M5755	250MM P.C. DOWEL JOINTED CONCRETE PAVE.	41,027.000	M2
501(A)	M0313	STRUCTURAL EXCAVATION UNCLASSIFIED	307.000	M3
509(B)	M0321	CLASS A CONCRETE	625.000	M3
509(D)	M0325	CLASS C CONCRETE	60.000	M3
511(A)	M0332	REINFORCING STEEL	50,249.000	KG
601(A)	M0297	TYPE I PLAIN RIPRAP	1,353.000	T
609(A)	M0300	CONC.CURB(150MM BARRIER-INTEGRAL)	2,658.000	M
610(B)	M0604	150MM CONCRETE DRIVEWAY	773.000	M2
611(E)	M5106	INLET CICI DES. 1 (2A)	2.000	EA
611(F)	M5320	INLET CICI DES 1 (ADD'L DEPTH)	0.780	M
611(G)	M4489	INLET FRM&GRT (SSIF-FRM,CIG-GRT-RVG-F)	2.000	EA
611(K)	M4488	CAST IRON CURB INLETS	6.000	EA
613(B)	M0405	450MM R.C.PIPE CLASS III	139.000	M
613(B)	M4411	725MM X 460MM R.C.PIPE ARCH CLASS A-III	139.000	M
613(B)	M4415	920MM X 570MM R.C.PIPE ARCH CLASS A-III	24.000	M

CALL ORDER : 280  
 LETTING DATE : January 24, 2002  
 LETTING TIME : 2:00 P.M.  
 COUNTIES : SEQUOYAH

CONTRACT ID : 020016  
 PCN : 1253004  
 PROJECTS : STPY-68A(298)  
 DBE GOALS : 5.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 27.51  
 CALENDAR DAYS : 310  
 RES. ENG. :  
 LIQ. DAM. : \$ 1000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 J000-ROADWAY			
613(B) M4419	1110MM X 675MM R.C.PIPE ARCH CLASS A-III	75.000	M
613(CC)M7186	TYPE A4 CULVERT END TREATMENT	4.000	EA
613(M) M0897	450MM PREFAB. CULVERT END SEC., ROUND	20.000	EA
613(M) M4518	725MM X 460MM PREFAB.CULV.END SEC., ARCH	18.000	EA
613(M) M4528	920MM X 570MM PREFAB.CULV.END SEC., ARCH	4.000	EA
613(M) M4534	1110MM X 675MM PREFAB.CULV.END SEC.,ARCH	12.000	EA
613(P) M1092	200MM PERFORATED PIPE UNDERDRAIN ROUND	100.000	M
613(Q) M1097	200MM NON-PERF.PIPE UNDERDRAIN RND.	396.000	M
619(A) M0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619(B) M4728	REMOVAL OF ASPHALT PAVEMENT	18,201.000	M2
619(B) M4763	REMOVAL OF CONC.PAV.W/ASPH.OVERLAY	1,386.000	M2
619(B) M4766	REMOVAL OF CONCRETE DRIVEWAY	2,220.000	M2
619(C) M0924	SAWING PAVEMENT	581.000	M
624(C) M4459	FENCE-STYLE SWF (5 BARBED WIRE)	841.000	M
629(A) M4958	MAILBOX INSTALLATION-SINGLE	3.000	EA
629(B) M4959	MAILBOX INSTALLATION-MULTIPLE	1.000	EA
629(C) M4960	MAILBOX	7.000	EA
629(D) M4961	REMOVAL OF MAILBOX INSTALLATION	7.000	EA
629(E) M5048	REMOVE AND RESET MAILBOX	3.000	EA
641 M1552	MOBILIZATION	1.000	LSUM
643 M0087	(SP)CONTRACTORS QUALITY CONTROL	1.000	LSUM
SECTION NO. 0002 Y008-TRAFFIC CONTROL			
856(A) M8839	CONSTR.TRAFF.STR.(PAINT)(100MM WIDE)	4,250.000	M
856(G) M8887	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-1	5,652.000	EA
859(A) M8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	100.000	M
880(B) M8818	CONSTRUCTION SIGNS 0 TO 0.59 M2	27,300.000	SD
880(B) M8821	CONSTRUCTION SIGNS 0.60 M2 TO 1.47 M2	39,480.000	SD
880(B) M8824	CONSTRUCTION SIGNS 1.48 M2 TO 3.06 M2	6,720.000	SD
880(C) M8836	BARRICADES(TYPE II)	2,100.000	SD
880(C) M8842	BARRICEDES(TYPE III)	40,320.000	SD
880(C) M8848	WING BARRICADES	1,680.000	SD
880(D) M8854	VERTICAL PANELS	34,440.000	SD
880(E) M8860	WARNING LIGHTS(TYPE A)	89,460.000	SD
880(E) M8872	WARNING LIGHTS(TYPE C)	68,880.000	SD
880(F) M8878	DRUMS	34,440.000	SD
SECTION NO. 0003 Y002-SIGNING AND STRIPING			
850(A) M8110	SHEET ALUMINUM SIGNS	11.860	M2
851(C) M8327	57MM SQUARE TUBE POST	89.150	M
853 9027	DELINEATORS(TYPE 1, CODE 2)	16.000	EA

CALL ORDER : 280  
 LETTING DATE : January 24, 2002  
 LETTING TIME : 2:00 P.M.  
 COUNTIES : SEQUOYAH

CONTRACT ID : 020016  
 PCN : 1253004  
 PROJECTS : STPY-68A(298)  
 DBE GOALS : 5.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 27.51  
 CALENDAR DAYS : 310  
 RES. ENG. :  
 LIQ. DAM. : \$ 1000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003	Y002-SIGNING AND STRIPING		
855(A) M8812	TRAFFIC STRIPE(PLASTIC)(100MM WIDE)	13,700.000	M
855(B) M8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	61.000	EA
855(B) M8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	3.000	EA
SECTION NO. 0004	Y030-LIGHTING		
890A/B M8744	(PL)REMOVE & RESET LIGHT POLE	3.000	EA
SECTION NO. 0005	STAK-STAKING		
642 M0098	STAKING	1.000	LSUM

CALL ORDER : 290  
 LETTING DATE : January 24, 2002  
 LETTING TIME : 2:00 P.M.  
 COUNTIES : TULSA

CONTRACT ID : 020034  
 PCN : 1961404  
 PROJECTS : BHIY-NBIP-0(280)000  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 2.70  
 CALENDAR DAYS : 120  
 RES. ENG. :  
 LIQ. DAM. : \$ 1000

CONTRACT DESCRIPTION:  
 BRIDGE PAINTING I-244: 23RD STREET OVER I-244, 3.5 MILES  
 NORTH OF I-44 IN THE CITY OF TULSA. PROJ. LGTH.= 0.00 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	MAIN-BRIDGE		
512(A) 1323	PAINTING EXISTING STRUCTURES	1.000	LSUM
512(B) 6303	COLLECTION & HANDLING OF WASTE	1.000	LSUM
641 1399	MOBILIZATION	1.000	LSUM
876(C) 8482	(PL)TRUCK MOUNTED ATTENUATOR	39.000	SD
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

CALL ORDER : 320  
 LETTING DATE : January 24, 2002  
 LETTING TIME : 2:00 P.M.  
 COUNTIES : BEAVER

CONTRACT ID : 020007  
 PCN : 1955604  
 PROJECTS : MC-104N(023)  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 COMPLETION DATE : 09/15/02

RES. ENG. :  
 LIQ. DAM. : \$ 500

CONTRACT DESCRIPTION:  
 ASPHALT OVERLAY SH3/US-412: BEGIN AT MILEPOST 9.0, EXTEND  
 EAST FLEX ESALS=2.9 ASPH=PG 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	0200-ROADWAY		
411(C) 6560	(SP)ASPHALT CONC.TYPE C(PG 64-22 OK)	12,200.000	TON
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

CALL ORDER : 327  
 LETTING DATE : January 24, 2002  
 LETTING TIME : 2:00 P.M.  
 COUNTIES : COTTON

CONTRACT ID : 020026  
 PCN : 1959104  
 PROJECTS : MC-117B(20)  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 CALENDAR DAYS : 60  
 RES. ENG. :  
 LIQ. DAM. : \$ 500

## CONTRACT DESCRIPTION:

BRIDGE REPAIR SH-5: BRIDGE OVER TRIBUTARY OF BRUSH CREEK,  
 APPROX. 0.25 MILES EAST OF TILLMAN COUNTY LINE. PROJ. LGTH.  
 = 0.00 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	MAIN-BRIDGE REPAIR		
502 6116	(PL)FALSEWORK JACKING	1.000	LSUM
535 6217	(PL)REPAIR BRIDGE PILING	11.000	EA
540 4510	(PL)REPAIR BRIDGE ITEM (TYPE A)	1.000	LSUM
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

CALL ORDER : 340  
 LETTING DATE : January 24, 2002  
 LETTING TIME : 2:00 P.M.  
 COUNTIES : KAY

CONTRACT ID : 020008  
 PCN : 1955704  
 PROJECTS : MC-136B(63)  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 COMPLETION DATE : 09/30/02

RES. ENG. :  
 LIQ. DAM. : \$ 700

CONTRACT DESCRIPTION:  
 ASPHALT OVERLAY US-77: BEGIN AT NEWKIRK CITY LIMITS, EXTEND  
 SOUTH APPROX. 4.5 MILES TO JCT SH-11 PROJ. LGTH.= 4.5 MILES  
 FLEX ESALS = 3.1 MILLION ASPH GRADE = 64-22 & 70-28 PG-OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	1000-ROADWAY		
202(A) 0183	UNCLASSIFIED EXCAVATION	2,200.000	CY
303 5912	AGGREGATE BASE	200.000	TON
411(A) 6500	(SP)ASPHALT CONCRETE TYPE A(PG 64-22 OK)	2,800.000	TON
411(B) 6530	(SP)ASPHALT CONCRETE TYPE B(PG 64-22 OK)	4,400.000	TON
411(B) 6540	(SP)ASPHALT CONCRETE TYPE B(PG 70-28 OK)	9,000.000	TON
411(D) 6590	(SP)ASPHALT CONC.TYPE D(PG 64-22 OK)	2,800.000	TON
619(B) 4727	REMOVAL OF CONCRETE PAVEMENT	2,000.000	SY
619(B) 4763	REMOVAL OF CONC.PAV.W/ASPH.OVERLAY	1,000.000	SY
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	56,000.000	LF
855(B) 8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	2.000	EA
855(B) 8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	1.000	EA
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM



CALL ORDER : 400  
 LETTING DATE : January 24, 2002  
 LETTING TIME : 2:00 P.M.  
 COUNTIES : OKLAHOMA

CONTRACT ID : 020011  
 PCN : 1955504  
 PROJECTS : CMC-155A(311)  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 COMPLETION DATE : 09/30/02

RES. ENG. :  
 LIQ. DAM. : \$ 1000

CONTRACT DESCRIPTION:  
 RESURFACE (OVERLAY) SH-66: BEGIN AT MACARTHUR, EXTEND TO  
 I-44 PROJ LENGTH=2.33 MILES ASPH GRADE= PG 70-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
-----			
SECTION NO. 0001	0200-ROADWAY		
411(B) 5280	(SP)ASPH.CONC.TYPE B(PATCH)(PG 64-22 OK)	1,000.000	TON
417 5267	COLD MILLING PAVEMENT	51,700.000	SY
828(B) 8138	LOOP DETECTOR WIRE	33,000.000	LF
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	59,000.000	LF
855(B) 8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	41.000	EA
855(B) 8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	22.000	EA
880(A) 8812	ARROW DISPLAY(TYPE C)	100.000	SD
880(B) 8818	CONSTRUCTION SIGNS 0 TO 6.25 SF	100.000	SD
880(B) 8821	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,000.000	SD
880(B) 8824	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	3,000.000	SD
880(C) 8836	BARRICADES(TYPE II)	100.000	SD
880(C) 8842	BARRICADES(TYPE III)	300.000	SD
880(C) 8848	WING BARRICADES	500.000	SD
880(E) 8860	WARNING LIGHTS(TYPE A)	5,000.000	SD
880(E) 8872	WARNING LIGHTS(TYPE C)	7,000.000	SD
880(F) 8878	DRUMS	7,000.000	SD
880(H) 8896	CONES(36" LARGE)	7,000.000	SD
880(L) 8911	TRAFFIC SURVEILLANCE, POLICE	150.000	HOURL
882(B) 8306	PORT.CHANGEABLE MESSAGE SIGN	60.000	SD
SECTION NO. 0002	0200-ROADWAY		
411 4280	(SP)ULTRATHIN BONDED WEARING COURSE	111,000.000	SY
859(A) 8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	59,000.000	LF
859(B) 8007	PAVEMENT MARKING REMOVAL(ARROWS)	41.000	EA
859(B) 8008	PAVEMENT MARKING REMOVAL(WORDS)	22.000	EA
SECTION NO. 0003	0200-ROADWAY		
411(B) 6540	(SP)ASPHALT CONCRETE TYPE B(PG 70-28 OK)	9,600.000	TON
612(A) 0641	MANHOLES ADJUST TO GRADE	3.000	EA
612(G) 0647	VALVE BOXES ADJUST TO GRADE	2.000	EA
859(A) 8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	1,000.000	LF
859(B) 8007	PAVEMENT MARKING REMOVAL(ARROWS)	2.000	EA
859(B) 8008	PAVEMENT MARKING REMOVAL(WORDS)	2.000	EA