

## Notice

Electronic bid packages are available for the [September 25, 2003](#) Letting. Instructions for using the electronic bidding system (EBS) are available from the Office Engineer's office. The printed bid sheets created from the EBS system must be placed in front of the bid item pages in the bidding proposal and will be turned in with the bid documents along with the proper disk. They should be placed and attached there without detaching the original proposal. (The paper copy of the bid items is the official bid document.) Please remember that you must use the electronic bidding system (EBS) when bidding projects in the highway Letting. Failure to use the EBS system could mean possible rejection of bids. Plans and proposals should be ready for sale on [August 28, 2003](#).

The direct line to the ODOT order desk is 522-3474. Please use this number when ordering plans and proposals. If ordering plans only please call the Reproduction Branch at 521-2586.

A Pre-Bid Conference will be held at [10:00 a.m.](#) on [September 12, 2003](#) concerning this [September](#) Bid Opening at the Oklahoma Department of Transportation (ODOT) Commission Room. Please review plans and proposals and send your comments and questions to the Office Engineer Division (attn: Masoud Pajoh or Jack Stewart) as early as possible at Fax: (405) 522-0972 or phone: (405) 521-2625. This will help both ODOT and Contractor.

All proposals not mailed must be turned into the Reproduction office off the main lobby of the ODOT building until 30 minutes before the Opening. From 30 minutes before the Bid Opening until the time of the Bid Opening, bid proposals must be turned in directly to the ODOT Commission Room on the east side of the lobby.

Please write the call order number of the jobs you are bidding electronically on the disk label of the original disk. Be sure to save your work and any revisions you receive to your original disk and submit that disk with your bid.

**Beginning with this Letting and until further notice all projects which include a pay item for Contractors Quality Control (Item 643) will require the bidder to bid a minimum amount for that item.**

This minimum will be specified at the end of the Special Provision 648-1QA(a)99, Payment for Contractor's Quality Control. You may increase this amount as necessary to cover the estimated Quality Control expenses.

***Failure to include at least this amount will be considered grounds for rejection of Contractor's bid as nonresponsive.***

Note:

ODOT will no longer allow DBE credit towards project DBE goals for the supplying of liquid asphalt cement or other bituminous materials.

**These Long Form and Short Form Notices and those in the future can be accessed on ODOT's Web site  
<http://www.okladot.state.ok.us/>**

Reminder

The low bidder must submit to the Office Engineer Division written confirmation from the DBE that it is participating in the contract as provided in the prime contractor's commitment. This may be submitted with the bid or not later than the Department's close of business on the Wednesday following the bid opening. Otherwise the bid shall be considered nonresponsive and shall be rejected by the Department.

*Reminder*

*Please be sure that bid bonds are stapled to the **back** of the proposal as instructed on the cover sheet of all proposals.*

Note:

The **Order Form** included in this Short Form Notice may be used to order plans and proposals for this letting.

Please check off the proposal(s) in which you are interested and fax to:

***405-522-0972 attention Linda Stoltz.***

The Bid Opening can be heard from the AGC website which is:

<http://www.okagchwy.com/>

### **Mandatory Pre-Bid Conference - September 12, 2003 - 1:30 p.m.**

At 1:30 p.m. on Friday, September 12, 2003, a mandatory Pre-bid Conference will be held at the Oklahoma Department of Transportation Training Center, located at 1025 S.E. 59th Street (Northeast corner of I-35 and S.E. 59th) in Oklahoma City. The purpose of the Conference is to familiarize prospective bidders and ODOT Field personnel with the new Percent Within Limits QC-QA Specifications for asphalt and P.C. concrete pavements.

Contractors bidding on any of the following September or October Letting Projects must attend the conference. Another Mandatory Pre-bid Conference may be set up for projects in October Letting. The date and location of that Pre-bid Conference will be announced once it is established. However, attendance at the scheduled one in September will suffice for both.

#### *September Projects:*

##### PC Concrete:

- IMY-0040-6(286)253; J/P 19563(04); McIntosh; I-40 from milepost 254 to 260.
- IMY-0040-4(382)123; J/P 19571(04); Canadian; I-40 from milepost 124 to 128.

#### *October Projects:*

##### Asphalt Concrete:

- IMY-0035-4(196)177; J/P 20247(04); Noble; I-35 from milepost 179.5 to 185.
- STPY-125C(069); J/P 18774(04); Garvin; SH- from 2 miles east of Lindsay extending east 2 miles.

**Oklahoma Department of Transportation  
Long Form Notice to Contractors — September 25, 2003 Letting**

Sealed proposals sent by registered mail will be received through the ODOT Reproduction Branch until 30 minutes prior to the scheduled Bid Opening. From 30 minutes prior to the Bid Opening until the time of the Bid Opening, bid proposals must be turned in directly to the ODOT Commission Room located on the east side of the lobby. The scheduled Bid Opening is 10:30 A.M. September 25, 2003 ,for the work listed below.

No proposal for construction or maintenance work of the Department will be issued to any contractor after 10:30 A.M. on the working day preceding opening of bids for any contract.

Each separate proposal shall be accompanied by a certified or cashier's check or bid bond equal to 5% of the bid made payable to the State of Oklahoma, Department of Transportation, as a proposal guaranty. Proposal checks will be held or returned by the Department as per section 103.04 of the State Standard Specifications.

This work will be done under the Oklahoma Department of Transportation Commission's applicable specifications for highway construction.

The minimum wage to be paid laborers and mechanics employed on this project will be included in the proposal.

Proposals must be prepared as directed by the State Standard Specifications.

This work will be done under the Oklahoma Department of Transportation Commission's applicable specifications for highway construction as depicted on the lower left corner of the plan's title sheet.

Plans, forms of proposals, contracts and specifications may be examined at the division headquarters in the division the work is to be performed or at the Oklahoma Department of Transportation Office Engineer's Division in Oklahoma City, Oklahoma.

Plans and proposal forms may be ordered from Jack Stewart, Division Engineer, Oklahoma Department of Transportation Building, 200 N.E. 21st street, Oklahoma City, Oklahoma 73105. Cost of bidding documents are \$25.00 + tax for each bidding proposal. State Standard Specification 1988 edition (Red Book) and 1991 supplement may be purchased for \$8.00 + tax, or 1996 Metric Standard Specification \$27.00 + tax, or 1999 Metric and English Standard Specification \$55.00 + tax. (Oklahoma tax is 8.375%). Make checks payable to Oklahoma Department of Transportation.

No refunds will be made for bidding documents or specification books purchased by prospective bidders.

Upon award of contract to a successful bidder, the contract will be completely and correctly executed by the contractor and returned to the Department within ten (10) working days from the date of award. The Department will have fourteen (14) working days from the date of award to complete its execution of the contract.

The Oklahoma Department of Transportation hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, disadvantaged business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, sex, religion, national origin, or disability in consideration for an award.

Bidders are hereby notified that all bids are likely to be rejected if the lowest responsive bid received exceeds the engineer's estimate by more than seven (7) percent. In the event all bids are rejected for this reason, this project may be deferred for re-advertising for bids until a more competitive situation exists.

Description of work and location of project:

CALL ORDER : 020  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : CANADIAN

CONTRACT ID : 030359  
 PCN : 0517308  
 PROJECTS : NHY-11N(004)  
 BRFY-11N(005)  
 DBE GOALS : 6.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 80.74  
 CALENDAR DAYS : 380  
 RES. ENG.:  
 LIQ. DAM.: \$ 2000

CONTRACT DESCRIPTION:

GRADE, DRAIN, SURFACE AND BRIDGE US-81; BEGIN APPROX. 6.6  
 KM SOUTH OF I-40, EXTEND NORTH TO I-40. PROJECT LENGTH = 6.  
 596 KM. FLEXIBLE ESALS = 12.02 MILLION ASPHALT GRADE = PG  
 64-22 OK, PG 76-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY NHY-11N(004)		
201	M0102 CLEARING AND GRUBBING	1.000	LSUM
202(A)	M0183 UNCLASSIFIED EXCAVATION	174,260.000	M3
205	M4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
223	M2802 TEMPORARY SILT FENCE	500.000	M
224	M2803 TEMPORARY SEDIMENT FILTER	7.000	EA
226	M2805 TEMPORARY SEDIMENT REMOVAL	60.000	M3
227	M0100 TEMPORARY SILT DIKE	226.000	M
229	M4318 DITCH LINER PROTECTION	46.000	M
230(A)	M2806 SOLID SLAB SODDING	32,989.000	M2
230(D)	M2810 BROADCAST SPRIGGING (METHOD A)	166,168.000	M2
230(F)	M2812 WATERING	8,848.000	KL
232(B)	M2814 SEEDING METHOD B	44.340	HA
233(A)	M2817 VEGETATIVE MULCHING	44.000	HA
234(A)	M2824 FERTILIZING (10-20-10)	26.000	T
234(A)	M4406 FERTILIZING (0-46-0)	7.650	T
235(A)	M0100 (PL)ROCK FILTER DAM, TYPE 1	45.000	M3
241	M2832 MOWING	45.000	HA
326(B)	M4210 (SP)LIME	2,992.000	T
326(F)	M4250 (SP)LIME STABILIZED SUBGRADE	172,944.000	M2
403(A)	M0217 TRAFFIC BOUND SURFACE COURSE TYPE A	1,216.000	T
407	M0250 TACK COAT	131,082.000	L
408	M5774 PRIME COAT	149,127.000	L
411(S2)	M5930 (SP)ASPH.CONC.,TYPE S2(PG 64-22 OK)	72,560.000	T
411(S3)	M5935 (SP)ASPH.CONC.,TYPE S3(PG 76-28 OK)	19,955.000	T
411(S3)	M5945 (SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	31,589.000	T
411(S4)	M5950 (SP)ASPH.CONC.,TYPE S4(PG 76-28 OK)	13,615.000	T
411(S4)	M5960 (SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	7,554.000	T
501(A)	M0313 STRUCTURAL EXCAVATION UNCLASSIFIED	155.000	M3
509(B)	M0321 CLASS A CONCRETE	382.000	M3
509(C)	M0322 CLASS A CONCRETE FOR SMALL STRUCTURES	3.000	M3
509(D)	M0325 CLASS C CONCRETE	20.000	M3
511(A)	M0332 REINFORCING STEEL	46,196.000	KG
611(E)	M5707 INLET CDI 900MM RCP	1.000	EA
611(E)	M6002 INLET (SMD-TYPE 2)	5.000	EA
611(J)	M0487 JUNCTION BOXES	2.125	M3

CALL ORDER : 020  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : CANADIAN

CONTRACT ID : 030359  
 PCN : 0517308  
 PROJECTS : NHY-11N(004)  
 BRFY-11N(005)  
 DBE GOALS : 6.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 80.74  
 CALENDAR DAYS : 380  
 RES. ENG.:  
 LIQ. DAM.: \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY NHY-11N(004)		
611(L) M4479	DROP INLET GRATE (600MM SPDI)	1.000	EA
613(B) M0405	450MM R.C.PIPE CLASS III	245.000	M
613(B) M0409	600MM R.C.PIPE CLASS III	180.000	M
613(B) M0413	750MM R.C.PIPE CLASS III	56.000	M
613(B) M0415	900MM R.C.PIPE CLASS III	49.000	M
613(B) M4415	920MM X 570MM R.C.PIPE ARCH CLASS A-III	23.000	M
613(B) M4419	1110MM X 675MM R.C.PIPE ARCH CLASS A-III	28.000	M
613(CC)M7186	TYPE A4 CULVERT END TREATMENT	8.000	EA
613(CC)M7187	TYPE B4 CULVERT END TREATMENT	6.000	EA
613(CC)M7188	TYPE C4 CULVERT END TREATMENT	4.000	EA
613(CC)M7189	TYPE D4 CULVERT END TREATMENT	1.000	EA
613(CC)M7196	TYPE A6 CULVERT END TREATMENT	10.000	EA
613(CC)M7197	TYPE B6 CULVERT END TREATMENT	8.000	EA
613(CC)M7198	TYPE C6 CULVERT END TREATMENT	4.000	EA
613(CC)M7199	TYPE D6 CULVERT END TREATMENT	1.000	EA
613(D) M0689	450MM CORR. GALV. STEEL PIPE	245.000	M
613(D) M0690	600MM CORR. GALV. STEEL PIPE	180.000	M
613(D) M0691	750MM CORR. GALV. STEEL PIPE	85.000	M
613(D) M0692	900MM CORR. GALV. STEEL PIPE	23.000	M
613(M) M0897	450MM PREFAB. CULVERT END SEC., ROUND	5.000	EA
613(M) M0898	600MM PREFAB. CULVERT END SEC., ROUND	4.000	EA
613(M) M0900	900MM PREFAB. CULVERT END SEC., ROUND	2.000	EA
613(M) M4528	920MM X 570MM PREFAB.CULV.END SEC., ARCH	2.000	EA
613(P) M1091	150MM PERFORATED PIPE UNDERDRAIN ROUND	500.000	M
613(Q) M1096	150MM NON-PERF.PIPE UNDERDRAIN RND.	200.000	M
613(R) M1100	PIPE UNDERDRAIN COVER MAT'L.	126.000	M3
613(S) M1180	TRENCH EXCAVATION	649.000	M3
613(T) M1181	STANDARD BEDDING MATERIAL	420.000	M3
619(A) M0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619(B) 8610	(PL)REMOVE AND RESET CATTLE GUARD	2.000	EA
619(B) M0291	REMOVAL OF HEADWALL	2.000	EA
619(B) M4728	REMOVAL OF ASPHALT PAVEMENT	51,890.000	M2
619(B) M4763	REMOVAL OF CONC.PAV.W/ASPH.OVERLAY	3,553.000	M2
619(C) M0924	SAWING PAVEMENT	607.000	M
623(A) M0932	BEAM GUARD RAIL-W-BEAM-SINGLE	724.000	M
623(E) M7113	BEAM GUARD RAIL-THRIE-BEAM TRANS. SECT.	7.000	EA
623(F) M4447	GUARD RAIL ANCHOR UNIT (TYPE B)	1.000	EA
623(H) M8571	(SP)G.E.T. GUARD RAIL END SECTION	8.000	EA
624(A) M4281	FENCE-STYLE WWF	32.000	M
624(C) M4459	(SP)FENCE-STYLE SWF (5 BARBED WIRE)	12,684.000	M
629(A) M4958	MAILBOX INSTALLATION-SINGLE	1.000	EA
629(B) M4959	MAILBOX INSTALLATION-MULTIPLE	2.000	EA

CALL ORDER : 020  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 030359  
 PCN : 0517308  
 PROJECTS : NHY-11N(004)  
 BRFY-11N(005)  
 DBE GOALS : 6.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 80.74  
 CALENDAR DAYS : 380  
 RES. ENG.:  
 LIQ. DAM.: \$ 2000

COUNTIES : CANADIAN

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY NHY-11N(004)		
629(C) M4960	MAILBOX	7.000	EA
629(D) M4961	REMOVAL OF MAILBOX INSTALLATION	7.000	EA
640 M1426	FIELD OFFICE	1.000	EA
641 M1552	MOBILIZATION	1.000	LSUM
643 M0087	(SP)CONTRACTORS QUALITY CONTROL	1.000	LSUM
653(C) M5946	OUTLET LATERAL HEADWALL	5.000	EA
SECTION NO. 0002	Y008-TRAFFIC CONTROL NHY-11N(004)		
856(A) M8839	CONSTR.TRAFF.STR.(PAINT)(100MM WIDE)	26,000.000	M
856(C) M8851	REM.PAVEMENT MARKING TAPE(100MM WIDE)	1,000.000	M
859(A) M8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	3,000.000	M
880(A) M8812	ARROW DISPLAY(TYPE C)	840.000	SD
880(B) M8818	CONSTRUCTION SIGNS 0 TO 0.59 M2	7,980.000	SD
880(B) M8821	CONSTRUCTION SIGNS 0.60 M2 TO 1.47 M2	10,080.000	SD
880(B) M8824	CONSTRUCTION SIGNS 1.48 M2 TO 3.06 M2	22,680.000	SD
880(C) M8842	BARRICEDES(TYPE III)	18,480.000	SD
880(C) M8848	WING BARRICADES	840.000	SD
880(E) M8860	WARNING LIGHTS(TYPE A)	36,960.000	SD
880(E) M8872	WARNING LIGHTS(TYPE C)	39,480.000	SD
880(F) M8878	DRUMS	39,480.000	SD
SECTION NO. 0003	Y002-TRAFFIC SIGNING & STRIPING NHY-11N(004)		
804(A) M2915	STRUCTURAL CONCRETE	2.880	M3
804(B) M2916	REINFORCING STEEL	232.320	KG
850(A) M8110	SHEET ALUMINUM SIGNS	52.410	M2
851(B) M3218	75MM@11.28 GALV.STL.PIPE POST	75.600	M
851(C) M8324	50MM SQUARE TUBE POST	37.760	M
851(C) M8327	57MM SQUARE TUBE POST	185.130	M
855(A) M8812	TRAFFIC STRIPE(PLASTIC)(100MM WIDE)	33,350.000	M
855(B) M8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	20.000	EA
855(B) M8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	10.000	EA
890(A) M8722	(PL)REMOVAL OF EXISTING SIGNS	1.000	LSUM
SECTION NO. 0004	STAK-STAKING NHY-11N(004)		
642 M0098	STAKING	1.000	LSUM
SECTION NO. 0005	X081-BRIDGE 'A' BRFY-11N(005)		
202(A) M1301	UNCLASSIFIED EXCAVATION	4,680.000	M3

CALL ORDER : 020  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 030359  
 PCN : 0517308  
 PROJECTS : NHY-11N(004)  
 BRFY-11N(005)  
 DBE GOALS : 6.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 80.74  
 CALENDAR DAYS : 380  
 RES. ENG.:  
 LIQ. DAM.: \$ 2000

COUNTIES : CANADIAN

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0005	X081-BRIDGE 'A' BRFY-11N(005)		
501(B) M1307	SUBSTRUCTURE EXCAVATION COMMON	80.000	M3
501(F) M6352	GRANULAR BACKFILL	96.000	M3
503(A) M1311	PRESTRESSED CONCRETE BEAMS (TYPE II)	168.500	M
504(A) M1304	APPROACH SLAB	191.200	M2
504(F) M6190	1067MM F-SHAPED PARAPET	92.400	M
506(A) M1322	STRUCTURAL STEEL	810.000	KG
509(A) M1326	CLASS AA CONCRETE	147.400	M3
509(B) M1328	CLASS A CONCRETE	89.800	M3
511(A) M1332	REINFORCING STEEL	890.000	KG
511(B) M6010	EPOXY COATED REINFORCING STEEL	26,060.000	KG
514(A) M6011	PILES, FURNISHED (HP 250X62)	140.800	M
514(B) M6292	PILES, DRIVEN (HP 250X62)	140.800	M
514(F) M6354	PILE LOAD TEST (DYNAMIC)	2.000	EA
515(A) M6013	WATER REPELLENT (VISUALLY INSPECTED)	427.000	M2
516(A) M6093	DRILLED SHAFTS 1050MM DIAMETER	63.600	M
535 M6164	(PL)FIXED BEARING ASSEMBLY	30.000	EA
535 M6282	(PL)ELASTOMERIC BEARING PADS	20.000	EA
601A-1 M1353	TYPE I-A PLAIN RIPRAP	650.000	T
601A-2 M1355	TYPE I-A FILTER BLANKET	185.000	T
613(P) M6204	150MM PERFORATED PIPE UNDERDRAIN ROUND	32.000	M
613(Q) M6207	150MM NON-PERF.PIPE UNDERDRAIN RND.	40.000	M
619(D) M1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
SECTION NO. 0006	X081-BRIDGE 'B' BRFY-11N(005)		
501(B) M1307	SUBSTRUCTURE EXCAVATION COMMON	70.000	M3
501(F) M6352	GRANULAR BACKFILL	74.000	M3
503(A) M1311	PRESTRESSED CONCRETE BEAMS (TYPE II)	134.800	M
504(A) M1304	APPROACH SLAB	148.000	M2
504(F) M6190	1067MM F-SHAPED PARAPET	92.400	M
506(A) M1322	STRUCTURAL STEEL	595.000	KG
509(A) M1326	CLASS AA CONCRETE	114.000	M3
509(B) M1328	CLASS A CONCRETE	71.200	M3
511(A) M1332	REINFORCING STEEL	655.000	KG
511(B) M6010	EPOXY COATED REINFORCING STEEL	21,510.000	KG
514(A) M6011	PILES, FURNISHED (HP 250X62)	115.500	M
514(B) M6292	PILES, DRIVEN (HP 250X62)	115.500	M
514(F) M6354	PILE LOAD TEST (DYNAMIC)	2.000	EA
515(A) M6013	WATER REPELLENT (VISUALLY INSPECTED)	403.000	M2
516(A) M6093	DRILLED SHAFTS 1050MM DIAMETER	42.000	M
535 M6164	(PL)FIXED BEARING ASSEMBLY	24.000	EA
535 M6282	(PL)ELASTOMERIC BEARING PADS	16.000	EA



CALL ORDER : 020  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.

COUNTIES : CANADIAN

CONTRACT ID : 030359  
 PCN : 0517308  
 PROJECTS : NHY-11N(004)  
 BRFY-11N(005)  
 DBE GOALS : 6.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 80.74  
 CALENDAR DAYS : 380  
 RES. ENG.:  
 LIQ. DAM.: \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0006	X081-BRIDGE 'B' BRFY-11N(005)		
601A-1 M1353	TYPE I-A PLAIN RIPRAP	630.000	T
601A-2 M1355	TYPE I-A FILTER BLANKET	175.000	T
613(P) M6204	150MM PERFORATED PIPE UNDERDRAIN ROUND	24.800	M
613(Q) M6207	150MM NON-PERF.PIPE UNDERDRAIN RND.	40.000	M
SECTION NO. 0007	X081-BRIDGE 'C' BRFY-11N(005)		
501(B) M1307	SUBSTRUCTURE EXCAVATION COMMON	90.000	M3
501(F) M6352	GRANULAR BACKFILL	152.000	M3
503(A) M1313	PRESTRESSED CONCRETE BEAMS (TYPE IV)	111.600	M
504(A) M1304	APPROACH SLAB	214.000	M2
504(F) M6190	1067MM F-SHAPED PARAPET	91.600	M
506(A) M1322	STRUCTURAL STEEL	100.000	KG
509(A) M1326	CLASS AA CONCRETE	112.700	M3
509(B) M1328	CLASS A CONCRETE	54.600	M3
511(B) M6010	EPOXY COATED REINFORCING STEEL	15,550.000	KG
514(A) M6011	PILES, FURNISHED (HP 250X62)	133.000	M
514(B) M6292	PILES, DRIVEN (HP 250X62)	133.000	M
514(F) M6354	PILE LOAD TEST (DYNAMIC)	2.000	EA
515(A) M6013	WATER REPELLENT (VISUALLY INSPECTED)	324.000	M2
535 M6164	(PL)FIXED BEARING ASSEMBLY	8.000	EA
601A-1 M1353	TYPE I-A PLAIN RIPRAP	725.000	T
601A-2 M1355	TYPE I-A FILTER BLANKET	175.000	T
613(P) M6204	150MM PERFORATED PIPE UNDERDRAIN ROUND	25.600	M
613(Q) M6207	150MM NON-PERF.PIPE UNDERDRAIN RND.	40.000	M
SECTION NO. 0008	X081-BRIDGE 'D' BRFY -11N(005)		
501(B) M1307	SUBSTRUCTURE EXCAVATION COMMON	90.000	M3
501(F) M6352	GRANULAR BACKFILL	152.000	M3
503(A) M1313	PRESTRESSED CONCRETE BEAMS (TYPE IV)	111.600	M
504(A) M1304	APPROACH SLAB	214.000	M2
504(F) M6190	1067MM F-SHAPED PARAPET	91.600	M
506(A) M1322	STRUCTURAL STEEL	100.000	KG
509(A) M1326	CLASS AA CONCRETE	113.000	M3
509(B) M1328	CLASS A CONCRETE	54.600	M3
511(B) M6010	EPOXY COATED REINFORCING STEEL	15,550.000	KG
514(A) M6011	PILES, FURNISHED (HP 250X62)	145.600	M
514(B) M6292	PILES, DRIVEN (HP 250X62)	145.600	M
514(F) M6354	PILE LOAD TEST (DYNAMIC)	2.000	EA
515(A) M6013	WATER REPELLENT (VISUALLY INSPECTED)	324.000	M2
535 6164	(PL)FIXED BEARING ASSEMBLY	8.000	EA

CALL ORDER : 020  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 030359  
 PCN : 0517308  
 PROJECTS : NHY-11N(004)  
           : BRFY-11N(005)  
 DBE GOALS : 6.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 80.74  
 CALENDAR DAYS : 380  
 RES. ENG. :  
 LIQ. DAM. : \$ 2000

COUNTIES : CANADIAN

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0008	X081-BRIDGE 'D' BRFY -11N(005)		
601A-1 M1353	TYPE I-A PLAIN RIPRAP	730.000	T
601A-2 M1355	TYPE I-A FILTER BLANKET	195.000	T
613(P) M6204	150MM PERFORATED PIPE UNDERDRAIN ROUND	25.600	M
613(Q) M6207	150MM NON-PERF.PIPES UNDERDRAIN RND.	40.000	M
619(D) M1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM

CALL ORDER : 030  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : CANADIAN

CONTRACT ID : 030360  
 PCN : 1957104  
 PROJECTS : IMY-40-4(382)124  
 DBE GOALS : 6.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 37.93  
 CALENDAR DAYS : 210  
 RES. ENG. :  
 LIQ. DAM.: \$ 2000

CONTRACT DESCRIPTION:

UNBONDED OVERLAY(CONCRETE) I-40; BEGIN APPROX. 0.9 MILE  
 WEST OF US-81(MILE POST 124), EXTEND EAST. PROJECT LENGTH =  
 3.005 MILES FLEXIBLE ESALS = 3.96 MILLION ASPHALT GRADE =  
 PG 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	J000-ROADWAY		
202(C) 0184	UNCLASSIFIED BORROW	42,120.000	CY
205 4229	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
223 2801	TEMPORARY SILT FENCE	5,400.000	LF
224 2803	TEMPORARY SEDIMENT FILTER	7.000	EA
226 2805	TEMPORARY SEDIMENT REMOVAL	100.000	CY
227 0100	TEMPORARY SILT DIKE	140.000	LF
230(A) 2806	SOLID SLAB SODDING	62,358.670	SY
233(A) 2817	VEGETATIVE MULCHING	22.750	AC
241 2832	MOWING	600.000	AC
303 0192	AGGREGATE BASE	12,606.270	CY
326(A) 4200	(SP)FLY ASH	4,052.020	TON
326(B) 4210	(SP)LIME	202.000	TON
326(E) 4240	(SP)CEMENTITIOUS STABILIZED SUBGRADE	75,036.310	SY
326(G) 4260	(SP)LIME PRETREATMENT	11,255.420	SY
407 0250	TACK COAT	6,997.070	GAL
408 5774	PRIME COAT	34,017.540	GAL
411 4275	(PL)ASPHALT CONCRETE	900.000	SY
411(S3) 5945	(SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	11,406.020	TON
411(S4) 5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	23,537.890	TON
411(S4) 6310	(SP)ASPH.CONC.,TYPE S4(PATCH)(PG64-22OK)	200.000	TON
413(D) 4868	(SP)RUMBLE STRIP-METHOD PCC-CON	63,459.000	LF
414(A1) 5755	10" P.C. DOWEL JOINTED CONCRETE PAVEMENT	8,280.530	SY
414(A1) 5763	14" P.C. DOWEL JOINTED CONCRETE PAVEMENT	55,970.670	SY
414(B) 0303	11" H.E.S. CONCRETE PAVEMENT	5,911.120	SY
414(B) 5913	H.E.S. CONCRETE (FULL DEPTH PATCHING)	800.000	SY
414(H) 5225	(SP)P.C. C. FOR UNBONDED PAVE. OVERLAY	20,546.100	CY
414(I) 5280	(SP)P.C.C. PAVE.UNBONDED O/L, PLACE ONLY	70,443.770	SY
417 4267	COLD MILLING BITUMINOUS PAVEMENT	20,050.670	SY
509(B) 0321	CLASS A CONCRETE	30.000	CY
511(A) 0332	REINFORCING STEEL	1,150.000	LB
613(D) 0689	18" CORR. GALV. STEEL PIPE	1,882.000	LF
613(D) 0691	30" CORR. GALV. STEEL PIPE	74.000	LF
613(P) 1091	6" PERFORATED PIPE UNDERDRAIN ROUND	1,600.000	LF
613(Q) 1096	6" NON-PERF.PIPE UNDERDRAIN RND.	200.000	LF
619(B) 4727	REMOVAL OF CONCRETE PAVEMENT	39,204.470	SY
619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	39,032.020	SY

CALL ORDER : 030  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : CANADIAN

CONTRACT ID : 030360  
 PCN : 1957104  
 PROJECTS : IMY-40-4(382)124  
 DBE GOALS : 6.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 37.93  
 CALENDAR DAYS : 210  
 RES. ENG. :  
 LIQ. DAM. : \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	J000-ROADWAY		
619(B) 4780	REMOVAL OF GUARD RAIL	4,387.500	LF
619(C) 0924	SAWING PAVEMENT	4,375.960	LF
623(A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	5,125.000	LF
623(E) 7114	THRIE BEAM BRIDGE CONNECTION-TYPE A	16.000	EA
623(F) 4447	GUARD RAIL ANCHOR UNIT (TYPE B)	1.000	EA
623(F) 4453	GUARD RAIL ANCHOR UNIT (TYPE GE)	1.000	EA
623(H) 8571	(SP)G.E.T. GUARD RAIL END SECTION	16.000	EA
641 1552	MOBILIZATION	1.000	LSUM
643 0087	(SP)CONTRACTORS QUALITY CONTROL	1.000	LSUM
653(C) 5946	OUTLET LATERAL HEADWALL	4.000	EA
853 9066	GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	110.000	EA
SECTION NO. 0002	X171-BRIDGE 'A'		
202(A) 1301	UNCLASSIFIED EXCAVATION	30.000	CY
501(F) 6352	GRANULAR BACKFILL	20.000	CY
501(G) 6309	CLSM BACKFILL	15.000	CY
504(A) 1304	APPROACH SLAB	171.400	SY
504(F) 1381	CONCRETE PARAPET	383.000	LF
504(H) 6390	RAPID CURE JOINT SEALANT	304.000	LF
505(B) 6019	CLASS B BRIDGE DECK REPAIR	30.000	SY
505(C) 6020	CLASS C BRIDGE DECK REPAIR	10.000	SY
505(D) 6071	HIGH DENSITY BRIDGE DECK OVERLAY	623.000	SY
509(A) 1326	CLASS AA CONCRETE	36.000	CY
510(C) 6137	SLOPE WALL (4")	140.000	SY
511(B) 6010	EPOXY COATED REINFORCING STEEL	7,140.000	LB
515(A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	135.000	SY
520(A) 6058	PREPARATION OF CRACKS ABOVE WATER	200.000	LF
520(C) 6060	EPOXY RESIN ABOVE WATER	13.000	GAL
521(A) 6210	PNEUMATICALLY PLACED MORTAR	30.000	SY
535 6130	(SP)CORROSION INHIBITOR(SURFACE APPLIED)	35.000	SY
619(B) 2505	(PL)REMOVAL OF BRIDGE ITEMS	2.000	EA
619(B) 2510	(PL)REMOVAL OF BRIDGE ITEM (TYPE A)	1.000	LSUM
619(B) 2520	(PL)REMOVAL OF BRIDGE ITEM (TYPE B)	1.000	LSUM
619(B) 2530	(PL)REMOVAL OF BRIDGE ITEM (TYPE C)	1.000	LSUM
SECTION NO. 0003	X171-BRIDGE 'B'		
202(A) 1301	UNCLASSIFIED EXCAVATION	30.000	CY
501(F) 6352	GRANULAR BACKFILL	22.000	CY
501(G) 6309	CLSM BACKFILL	20.000	CY
504(A) 1304	APPROACH SLAB	171.400	SY
504(F) 1381	CONCRETE PARAPET	383.000	LF

CALL ORDER : 030  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : CANADIAN

CONTRACT ID : 030360  
 PCN : 1957104  
 PROJECTS : IMY-40-4(382)124  
 DBE GOALS : 6.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 37.93  
 CALENDAR DAYS : 210  
 RES. ENG.:  
 LIQ. DAM.: \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003	X171-BRIDGE 'B'		
504(H) 6390	RAPID CURE JOINT SEALANT	304.000	LF
505(B) 6019	CLASS B BRIDGE DECK REPAIR	30.000	SY
505(C) 6020	CLASS C BRIDGE DECK REPAIR	20.000	SY
505(D) 6071	HIGH DENSITY BRIDGE DECK OVERLAY	623.000	SY
509(A) 1326	CLASS AA CONCRETE	36.000	CY
510(C) 6137	SLOPE WALL (4")	190.000	SY
511(B) 6010	EPOXY COATED REINFORCING STEEL	7,140.000	LB
515(A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	135.000	SY
520(A) 6058	PREPARATION OF CRACKS ABOVE WATER	200.000	LF
520(C) 6060	EPOXY RESIN ABOVE WATER	13.000	GAL
521(A) 6210	PNEUMATICALLY PLACED MORTAR	40.000	SY
535 6130	(SP)CORROSION INHIBITOR(SURFACE APPLIED)	45.000	SY
619(B) 2505	(PL)REMOVAL OF BRIDGE ITEMS	2.000	EA
619(B) 2510	(PL)REMOVAL OF BRIDGE ITEM (TYPE A)	1.000	LSUM
619(B) 2520	(PL)REMOVAL OF BRIDGE ITEM (TYPE B)	1.000	LSUM
619(B) 2530	(PL)REMOVAL OF BRIDGE ITEM (TYPE C)	1.000	LSUM
SECTION NO. 0004	X271-BRIDGE 'C'		
202(A) 1301	UNCLASSIFIED EXCAVATION	30.000	CY
501(F) 6352	GRANULAR BACKFILL	10.000	CY
501(G) 6309	CLSM BACKFILL	20.000	CY
504(A) 1304	APPROACH SLAB	207.000	SY
504(F) 1381	CONCRETE PARAPET	466.000	LF
504(H) 6390	RAPID CURE JOINT SEALANT	421.000	LF
505(B) 6019	CLASS B BRIDGE DECK REPAIR	45.000	SY
505(C) 6020	CLASS C BRIDGE DECK REPAIR	32.000	SY
505(D) 6071	HIGH DENSITY BRIDGE DECK OVERLAY	965.000	SY
509(A) 1326	CLASS AA CONCRETE	11.800	CY
510(C) 6137	SLOPE WALL (4")	50.000	SY
511(B) 6010	EPOXY COATED REINFORCING STEEL	3,830.000	LB
515(A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	164.000	SY
520(A) 6058	PREPARATION OF CRACKS ABOVE WATER	500.000	LF
520(C) 6060	EPOXY RESIN ABOVE WATER	33.000	GAL
521(A) 6210	PNEUMATICALLY PLACED MORTAR	50.000	SY
535 6130	(SP)CORROSION INHIBITOR(SURFACE APPLIED)	55.000	SY
619(B) 2505	(PL)REMOVAL OF BRIDGE ITEMS	2.000	EA
619(B) 2520	(PL)REMOVAL OF BRIDGE ITEM (TYPE B)	1.000	LSUM
619(B) 2530	(PL)REMOVAL OF BRIDGE ITEM (TYPE C)	1.000	LSUM
890A/B 8758	(PL)REMOVE & RESET OVERHEAD SIGN STR.	1.000	EA
SECTION NO. 0005	X271-BRIDGE 'D'		

CALL ORDER : 030  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : CANADIAN

CONTRACT ID : 030360  
 PCN : 1957104  
 PROJECTS : IMY-40-4(382)124  
 DBE GOALS : 6.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 37.93  
 CALENDAR DAYS : 210  
 RES. ENG. :  
 LIQ. DAM. : \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
-----			
SECTION NO. 0005	X271-BRIDGE 'D'		
202(A) 1301	UNCLASSIFIED EXCAVATION	30.000	CY
501(F) 6352	GRANULAR BACKFILL	10.000	CY
501(G) 6309	CLSM BACKFILL	20.000	CY
504(A) 1304	APPROACH SLAB	207.000	SY
504(F) 1381	CONCRETE PARAPET	466.000	LF
504(H) 6390	RAPID CURE JOINT SEALANT	421.000	LF
505(B) 6019	CLASS B BRIDGE DECK REPAIR	45.000	SY
505(C) 6020	CLASS C BRIDGE DECK REPAIR	32.000	SY
505(D) 6071	HIGH DENSITY BRIDGE DECK OVERLAY	965.000	SY
509(A) 1326	CLASS AA CONCRETE	11.800	CY
510(C) 6137	SLOPE WALL (4")	150.000	SY
511(B) 6010	EPOXY COATED REINFORCING STEEL	3,830.000	LB
515(A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	164.000	SY
520(A) 6058	PREPARATION OF CRACKS ABOVE WATER	500.000	LF
520(C) 6060	EPOXY RESIN ABOVE WATER	33.000	GAL
521(A) 6210	PNEUMATICALLY PLACED MORTAR	40.000	SY
535 6130	(SP)CORROSION INHIBITOR(SURFACE APPLIED)	45.000	SY
619(B) 2505	(PL)REMOVAL OF BRIDGE ITEMS	2.000	EA
619(B) 2520	(PL)REMOVAL OF BRIDGE ITEM (TYPE B)	1.000	LSUM
619(B) 2530	(PL)REMOVAL OF BRIDGE ITEM (TYPE C)	1.000	LSUM
SECTION NO. 0006 X071-BRIDGE 'E'			
202(A) 1301	UNCLASSIFIED EXCAVATION	30.000	CY
417 5267	COLD MILLING PAVEMENT	496.000	SY
501(F) 6352	GRANULAR BACKFILL	12.000	CY
504(A) 1304	APPROACH SLAB	171.400	SY
504(F) 1381	CONCRETE PARAPET	321.000	LF
504(H) 6390	RAPID CURE JOINT SEALANT	76.000	LF
505(B) 6019	CLASS B BRIDGE DECK REPAIR	50.000	SY
505(C) 6020	CLASS C BRIDGE DECK REPAIR	25.000	SY
505(D) 6071	HIGH DENSITY BRIDGE DECK OVERLAY	496.000	SY
509(A) 1326	CLASS AA CONCRETE	56.600	CY
510(C) 6137	SLOPE WALL (4")	10.000	SY
511(B) 6010	EPOXY COATED REINFORCING STEEL	12,730.000	LB
515(A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	113.000	SY
535 6282	(PL)ELASTOMERIC BEARING PADS	20.000	EA
619(B) 2505	(PL)REMOVAL OF BRIDGE ITEMS	2.000	EA
619(B) 2510	(PL)REMOVAL OF BRIDGE ITEM (TYPE A)	1.000	LSUM
619(B) 2520	(PL)REMOVAL OF BRIDGE ITEM (TYPE B)	1.000	LSUM
619(B) 2530	(PL)REMOVAL OF BRIDGE ITEM (TYPE C)	1.000	LSUM
SECTION NO. 0007 X071-BRIDGE 'F'			

CALL ORDER : 030  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : CANADIAN

CONTRACT ID : 030360  
 PCN : 1957104  
 PROJECTS : IMY-40-4(382)124  
 DBE GOALS : 6.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 37.93  
 CALENDAR DAYS : 210  
 RES. ENG. :  
 LIQ. DAM. : \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
-----			
SECTION NO. 0007	X071-BRIDGE 'F'		
202(A) 1301	UNCLASSIFIED EXCAVATION	30.000	CY
417 5267	COLD MILLING PAVEMENT	496.000	SY
501(F) 6352	GRANULAR BACKFILL	12.000	CY
504(A) 1304	APPROACH SLAB	171.400	SY
504(F) 1381	CONCRETE PARAPET	321.000	LF
504(H) 6390	RAPID CURE JOINT SEALANT	76.000	LF
505(B) 6019	CLASS B BRIDGE DECK REPAIR	50.000	SY
505(C) 6020	CLASS C BRIDGE DECK REPAIR	25.000	SY
505(D) 6071	HIGH DENSITY BRIDGE DECK OVERLAY	496.000	SY
509(A) 1326	CLASS AA CONCRETE	56.600	CY
510(C) 6137	SLOPE WALL (4")	10.000	SY
511(B) 6010	EPOXY COATED REINFORCING STEEL	12,730.000	LB
515(A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	113.000	SY
535 6282	(PL)ELASTOMERIC BEARING PADS	20.000	EA
619(B) 2505	(PL)REMOVAL OF BRIDGE ITEMS	2.000	EA
619(B) 2510	(PL)REMOVAL OF BRIDGE ITEM (TYPE A)	1.000	LSUM
619(B) 2520	(PL)REMOVAL OF BRIDGE ITEM (TYPE B)	1.000	LSUM
619(B) 2530	(PL)REMOVAL OF BRIDGE ITEM (TYPE C)	1.000	LSUM
SECTION NO. 0008	Y000-TRAFFIC		
627(G) 4316	RELOC.PORT.TYPE PRECAST CONC.MEDIAN BARR	18,300.000	LF
627(H) 5856	DEL.PORT.TYPE PREC. CONCRETE MEDIAN BARR	36,600.000	LF
804(A) 2915	STRUCTURAL CONCRETE	21.200	CY
804(B) 2916	REINFORCING STEEL	4,082.000	LB
850(A) 8110	SHEET ALUMINUM SIGNS	409.900	SF
850(B) 8112	EXTRUDED ALUMINUM PANEL SIGNS	1,210.800	SF
851(A) 3206	4"@13 GALV.STL.WD.FLANGE BM.POST	481.300	LF
851(A) 3207	6"@15 GALV.STL.WD.FLANGE BM.POST	120.000	LF
851(A) 3209	6"@25 GALV.STL.WD.FLANGE BM.POST	104.800	LF
851(A) 3210	8"@31 GALV.STL.WD.FLANGE BM.POST	55.400	LF
851(B) 3217	2 1/2"@5.79 GALV.STL.PIPE POST	56.000	LF
851(B) 3218	3"@7.58 GALV.STL.PIPE POST	15.000	LF
851(C) 8321	1 3/4" SQUARE TUBE POST	23.000	LF
851(C) 8327	2 1/4" SQUARE TUBE POST	28.000	LF
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	206,000.000	LF
856(A) 8839	CONSTRUCTION TRAFF.STR.(PAINT)(4" WIDE)	94,500.000	LF
856(G) 8887	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-1	1,440.000	EA
857(A) 8911	PAVE.MARKERS CLASS A TYPE 2-C	11.000	EA
857(A) 8947	PAVE.MARKERS CLASS C TYPE 2-C	470.000	EA
859(A) 8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	78,300.000	LF
870(A) 8485	SAND FILLED IMPACT ATTEN.MODULE	500.000	SD
876(C) 8482	(PL)TRUCK MOUNTED ATTENUATOR	200.000	SD

CALL ORDER : 030  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : CANADIAN

CONTRACT ID : 030360  
 PCN : 1957104  
 PROJECTS : IMY-40-4(382)124  
 DBE GOALS : 6.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 37.93  
 CALENDAR DAYS : 210  
 RES. ENG. :  
 LIQ. DAM. : \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
-----			
SECTION NO. 0008	Y000-TRAFFIC		
878(C) 8487	MODULAR GLARE SCREEN	102,750.000	SD
880(A) 8812	ARROW DISPLAY(TYPE C)	500.000	SD
880(B) 8818	CONSTRUCTION SIGNS 0 TO 6.25 SF	32,750.000	SD
880(B) 8821	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	36,765.000	SD
880(B) 8824	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	5,000.000	SD
880(C) 8845	BARRICADES(TYPE III)	8,500.000	EA
880(C) 8848	WING BARRICADES	1,000.000	SD
880(D) 8854	VERTICAL PANELS	12,500.000	SD
880(E) 8860	WARNING LIGHTS(TYPE A)	24,000.000	SD
880(E) 8872	WARNING LIGHTS(TYPE C)	75,000.000	SD
880(F) 8878	DRUMS	62,500.000	SD
880(L) 8911	TRAFFIC SURVEILLANCE, POLICE	20.000	HOURL
882(B) 8306	PORT.CHANGEABLE MESSAGE SIGN	1,000.000	SD
SECTION NO. 0009	Y031-FLASHERS		
802(B) 8342	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	97.000	LF
802(B) 8344	3" PVC SCH.40 PLASTIC CONDUIT BORED	286.000	LF
802(B) 8346	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	20.000	LF
803 8065	PULL BOX(SIZE I)	2.000	EA
803 8066	PULL BOX(SIZE II)	2.000	EA
803 8067	PULL BOX(SIZE III)	2.000	EA
804(A) 2915	STRUCTURAL CONCRETE	10.500	CY
804(B) 2916	REINFORCING STEEL	1,604.000	LB
806(A) 8311	32'MH POLE 35'TS & 10'LMA(G.STL.)	2.000	EA
806(A) 8350	32'MH POLE,30'TS & 10'LMA(G.STL.)	1.000	EA
806(A) 8351	32'MH POLE 25',TS & 10'LMA(G.STL.)	1.000	EA
809(A) 8090	(PL)ROADWAY LUMINAIRE	3.000	EA
810(A) 3118	SERVICE POLE	1.000	EA
811 8040	1/C NO.6 ELECT.COND.	150.000	LF
811 8044	1/C NO.10 ELECT.COND.	1,496.000	LF
827 8620	SOLID STATE FLASHER CONTROLLER(TYPE I)	1.000	EA
831 8301	1WAY1SEC.ADJ.SIG.HD.S-22	8.000	EA
833 3030	BACKPLATE	8.000	EA
834(A) 8207	5/C TRAF.SIG.EL.CABLE	1,260.000	LF
850(A) 8110	SHEET ALUMINUM SIGNS	26.520	SF
850(C) 8118	MAST ARM MOUNTED SIGNS(ALUM.)	27.800	SF
851(C) 8327	2 1/4" SQUARE TUBE POST	60.000	LF
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	2,300.000	LF
856(C) 8851	REMOVABLE PAVEMENT MARKING TAPE(4" WIDE)	2,000.000	LF
859(A) 8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	2,000.000	LF
890(A) 8724	(PL)REMOVAL OF EXISTING SIGNS	2.000	EA
SECTION NO. 0010	STAK-STAKING		



CALL ORDER : 030  
LETTING DATE : September 25, 2003  
LETTING TIME : 10:30 A.M.  
COUNTIES : CANADIAN

CONTRACT ID : 030360  
PCN : 1957104  
PROJECTS : IMY-40-4(382)124  
DBE GOALS : 6.00  
GUARANTY : 5% OF BID TOTAL  
PLAN PRICE : 37.93  
CALENDAR DAYS : 210  
RES. ENG. :  
LIQ. DAM.: \$ 2000

642 0098 STAKING 1.000 LSUM

CALL ORDER : 040  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : CANADIAN

CONTRACT ID : 030361  
 PCN : 2067204  
 PROJECTS : SAP-109N(76)  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 3.25  
 COMPLETION DATE : 11/17/03

RES. ENG. :  
 LIQ. DAM. : \$ 500

## CONTRACT DESCRIPTION:

BRIDGE REPAIR I-40; AT N.W. 10 TH STREET. PROJECT LENGTH =  
 0.00 MILE FLEXIBLE ESALS = N/A ASPHALT GRADE = PG 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	X271-BRIDGE 'A'		
202(G) 6181	EARTHWORK	1.000	LSUM
407 0250	TACK COAT	61.000	GAL
408 5774	PRIME COAT	188.000	GAL
411(S3) 5945	(SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	280.000	TON
411(S4) 5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	136.000	TON
502(A) 6173	ENGINEERED FALSEWORK	1.000	LSUM
502(B) 6174	FALSEWORK ENGINEERING SERVICES	1.000	LSUM
520(A) 6058	PREPARATION OF CRACKS ABOVE WATER	17.000	LF
520(C) 6060	EPOXY RESIN ABOVE WATER	1.000	GAL
540 4500	(PL)REPAIR BRIDGE ITEMS	1.000	LSUM
641 1399	MOBILIZATION	1.000	LSUM
SECTION NO. 0002	Y008-TRAFFIC		
823 8478	(PL)PORTABLE TRAFFIC SIGNAL SYSTEM	3.000	SD
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	1,200.000	LF
856(G) 8887	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-1	1,000.000	EA
859(A) 8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	1,000.000	LF
876(C) 8482	(PL)TRUCK MOUNTED ATTENUATOR	9.000	SD
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
880(L) 8911	TRAFFIC SURVEILLANCE, POLICE	20.000	HOURL
882(B) 8306	PORT.CHANGEABLE MESSAGE SIGN	18.000	SD

CALL ORDER : 050  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : CHOCTAW

CONTRACT ID : 030362  
 PCN : 1888604  
 PROJECTS : NHY-22N(112)  
 DBE GOALS : 7.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 18.42  
 CALENDAR DAYS : 300  
 RES. ENG. :  
 LIQ. DAM. : \$ 2000

CONTRACT DESCRIPTION:

GRADE, DRAIN, SURFACE AND EROSION CONTROL US-70; FROM  
 US-271 IN HUGO, EXTEND EAST. PROJECT LENGTH = 1.902 MILES  
 FLEXIBLE ESALS = 10.9 MILLION ASPHALT GRADE = PG 64-22 OK,  
 PG 70-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY		
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(A)	0183 UNCLASSIFIED EXCAVATION	112,998.000	CY
202(C)	0184 UNCLASSIFIED BORROW	1,000.000	CY
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
222	2801 TEMPORARY BALE BARRIER	100.000	LF
223	2801 TEMPORARY SILT FENCE	1,500.000	LF
224	2803 TEMPORARY SEDIMENT FILTER	5.000	EA
225	2804 TEMPORARY SEDIMENT BASIN	1.000	EA
226	2805 TEMPORARY SEDIMENT REMOVAL	100.000	CY
227	0100 TEMPORARY SILT DIKE	500.000	LF
229	4318 DITCH LINER PROTECTION	800.000	LF
230(A)	2806 SOLID SLAB SODDING	12,223.000	SY
230(D)	2810 BROADCAST SPRIGGING (METHOD A)	44,989.000	SY
230(F)	2812 WATERING	2,290.000	MGAL
232(B)	2814 SEEDING METHOD B	22.180	AC
233(A)	2817 VEGETATIVE MULCHING	31.480	AC
234(A)	2824 FERTILIZING (10-20-10)	6.500	TON
234(A)	4406 FERTILIZING (0-46-0)	1.280	TON
235(A)	0100 (PL)ROCK FILTER DAM, TYPE 1	25.000	CY
241	2832 MOWING	17.000	AC
303	0192 AGGREGATE BASE	24,354.000	CY
326(A)	4200 (SP)FLY ASH	1,008.000	TON
326(B)	4210 (SP)LIME	1,199.000	TON
326(E)	4240 (SP)CEMENTITIOUS STABILIZED SUBGRADE	18,665.000	SY
326(F)	4250 (SP)LIME STABILIZED SUBGRADE	34,663.000	SY
403(E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	8,471.000	TON
407	0250 TACK COAT	7,735.000	GAL
408	5774 PRIME COAT	19,826.000	GAL
411(S2)	5930 (SP)ASPH.CONC.,TYPE S2(PG 64-22 OK)	14,104.000	TON
411(S3)	5940 (SP)ASPH.CONC.,TYPE S3(PG 70-28 OK)	6,379.000	TON
411(S3)	5945 (SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	2,329.000	TON
411(S4)	5955 (SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	4,224.000	TON
411(S4)	5960 (SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	1,483.000	TON
413(A)	4861 RUMBLE STRIP-METHOD AC-CON	38,519.000	LF
501(A)	0313 STRUCTURAL EXCAVATION UNCLASSIFIED	56.000	CY
509(B)	0321 CLASS A CONCRETE	223.900	CY

CALL ORDER : 050  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : CHOCTAW

CONTRACT ID : 030362  
 PCN : 1888604  
 PROJECTS : NHY-22N(112)  
 DBE GOALS : 7.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 18.42  
 CALENDAR DAYS : 300  
 RES. ENG. :  
 LIQ. DAM. : \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY		
509(D) 0325	CLASS C CONCRETE	195.000	CY
511(A) 0332	REINFORCING STEEL	34,242.000	LB
611(E) 6000	INLET (SMD-TYPE 1)	4.000	EA
611(E) 6002	INLET (SMD-TYPE 2)	1.000	EA
613(B) 0491	18" R.C.P.I.P.E CLASS III	362.000	LF
613(B) 0492	24" R.C.P.I.P.E CLASS III	120.000	LF
613(B) 0494	36" R.C.P.I.P.E CLASS III	104.000	LF
613(D) 0690	24" CORR. GALV. STEEL PIPE	143.000	LF
613(M) 5726	18" PREFAB. CULVERT END SEC., ROUND	4.000	EA
613(M) 5730	24" PREFAB. CULVERT END SEC., ROUND	3.000	EA
613(M) 5734	36" PREFAB. CULVERT END SEC., ROUND	1.000	EA
613(P) 1092	8" PERFORATED PIPE UNDERDRAIN ROUND	750.000	LF
613(Q) 1097	8" NON-PERF.P.I.P.E UNDERDRAIN RND.	250.000	LF
613(R) 1100	PIPE UNDERDRAIN COVER MAT'L.	225.000	CY
613(S) 1180	TRENCH EXCAVATION	729.000	CY
613(T) 1181	STANDARD BEDDING MATERIAL	224.000	CY
619(A) 0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619(B) 0291	REMOVAL OF HEADWALL	4.000	EA
619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	14,330.000	SY
619(C) 0924	SAWING PAVEMENT	8,780.000	LF
624(A) 4281	FENCE-STYLE WWF	1,330.000	LF
640 1426	FIELD OFFICE	1.000	EA
641 1552	MOBILIZATION	1.000	LSUM
643 0087	(SP)CONTRACTORS QUALITY CONTROL	1.000	LSUM
SECTION NO. 0002	Y008-TRAFFIC CONTROL		
850(A) 8110	SHEET ALUMINUM SIGNS	241.960	SF
851(C) 8327	2 1/4" SQUARE TUBE POST	485.000	LF
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	58,504.000	LF
855(B) 8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	8.000	EA
855(B) 8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	4.000	EA
855(B) 8824	TRAFFIC STRIPE(PLASTIC)(SYMBOLS)	4.000	EA
856(A) 8839	CONSTRUCTION TRAFF.STR.(PAINT)(4" WIDE)	14,100.000	LF
856(B) 8848	CONSTRUCTION TRAFFIC STR.(PAINT)(SYMBOL)	1.000	EA
856(C) 8851	REMOVABLE PAVEMENT MARKING TAPE(4" WIDE)	500.000	LF
856(G) 8887	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-1	1,000.000	EA
880(A) 8812	ARROW DISPLAY(TYPE C)	720.000	SD
880(B) 8818	CONSTRUCTION SIGNS 0 TO 6.25 SF	7,300.000	SD
880(B) 8821	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	8,030.000	SD
880(B) 8824	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	7,300.000	SD
880(C) 8836	BARRICADES(TYPE II)	1,440.000	SD
880(C) 8842	BARRICADES(TYPE III)	9,360.000	SD

CALL ORDER : 050  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : CHOCTAW

CONTRACT ID : 030362  
 PCN : 1888604  
 PROJECTS : NHY-22N(112)  
 DBE GOALS : 7.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 18.42  
 CALENDAR DAYS : 300  
 RES. ENG. :  
 LIQ. DAM.: \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
-----			
SECTION NO. 0002	Y008-TRAFFIC CONTROL		
880(C) 8848	WING BARRICADES	1,440.000	SD
880(E) 8860	WARNING LIGHTS(TYPE A)	25,920.000	SD
880(E) 8872	WARNING LIGHTS(TYPE C)	26,640.000	SD
880(F) 8878	DRUMS	26,640.000	SD
890(A) 8722	(PL)REMOVAL OF EXISTING SIGNS	1.000	LSUM
SECTION NO. 0003	STAK-STAKING		
642 0098	STAKING	1.000	LSUM

CALL ORDER : 051  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : CHOCTAW

CONTRACT ID : 030291  
 PCN : 1804704  
 PROJECTS : BRF-112C(27) CO  
 DBE GOALS : 10.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 5.42  
 CALENDAR DAYS : 90  
 RES. ENG. :  
 LIQ. DAM. : \$ 500

CONTRACT DESCRIPTION:  
 BRIDGE AND APPROACHES COUNTY ROAD; OVER OWL CREEK, 3.0  
 MILES EAST AND 4.0 MILES SOUTH OF HUGO. PROJECT LENGTH = 0.  
 151 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 E000-ROADWAY			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(A)	0183 UNCLASSIFIED EXCAVATION	2,771.000	CY
202(C)	0184 UNCLASSIFIED BORROW	3,216.000	CY
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
227	0100 TEMPORARY SILT DIKE	2,724.000	LF
230(A)	2806 SOLID SLAB SODDING	3,902.000	SY
233(A)	2817 VEGETATIVE MULCHING	2.000	AC
403(E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	1,100.000	TON
509(D)	0325 CLASS C CONCRETE	10.000	CY
613(D)	4819 96" CORR. GALV. STEEL PIPE	174.000	LF
SECTION NO. 0002 X081-BRIDGE 'A'			
501(B)	1307 SUBSTRUCTURE EXCAVATION COMMON	71.000	CY
501(D)	6353 UNCLASSIFIED BACKFILL	123.000	CY
503(B)	6144 PRESTRESSED CONCRETE DOUBLE TEE	272.500	LF
504(E)	1380 CONCRETE RAIL (TR1)	176.000	LF
509(A)	1326 CLASS AA CONCRETE	37.600	CY
509(B)	1328 CLASS A CONCRETE	51.800	CY
511(A)	1332 REINFORCING STEEL	12,030.000	LB
514(A)	6010 PILES, FURNISHED (HP 10X42)	257.000	LF
514(B)	6292 PILES, DRIVEN (HP 10X42)	257.000	LF
601(A-1)	1353 TYPE I-A PLAIN RIPRAP	570.000	TON
601(E)	6312 FILTER FABRIC (RIPRAP)	570.000	SY
619(D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F)	6033 GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
641	1399 MOBILIZATION	1.000	LSUM
880(J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAK-STAKING			
642	0098 STAKING	1.000	LSUM
SECTION NO. 0004 NON-PARTICIPATING (FENCE)			
624(C)	4459 (SP)FENCE-STYLE SWF (5 BARBED WIRE)	1,437.000	LF

CALL ORDER : 060  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : CLEVELAND

CONTRACT ID : 030328  
 PCN : 2027804  
 PROJECTS : BHFY-114B(102)  
 DBE GOALS : 0.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 9.21  
 CALENDAR DAYS : 150  
 RES. ENG. :  
 LIQ. DAM.: \$ 700

## CONTRACT DESCRIPTION:

BRIDGE REPAIR US-77; OVER SOUTH CANADIAN RIVER AND RAILROAD.  
 PROJECT LENGTH = 0.695 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	X331-BRIDGE 'A'		
502(A) 6173	ENGINEERED FALSEWORK	1.000	LSUM
504(F) 1381	CONCRETE PARAPET	7,343.700	LF
505(B) 6019	CLASS B BRIDGE DECK REPAIR	250.000	SY
506(A) 1322	STRUCTURAL STEEL	2,980.000	LB
509(A) 1326	CLASS AA CONCRETE	340.600	CY
511(B) 6010	EPOXY COATED REINFORCING STEEL	70,700.000	LB
512(A) 1323	PAINTING EXISTING STRUCTURES	1.000	LSUM
512(B) 6303	COLLECTION & HANDLING OF WASTE	1.000	LSUM
535 6188	(PL)RAISE EXISTING SPAN	8.000	EA
545 4815	(PL)REPLACE BRIDGE ITEM (TYPE A)	33.000	EA
623(A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	650.000	LF
623(F) 5686	GUARD RAIL ANCHOR UNIT (TYPE D-BF)	1.000	EA
641 1399	MOBILIZATION	1.000	LSUM
SECTION NO. 0002	Y008-TRAFFIC		
627(G) 4316	RELOC.PORT.TYPE PRECAST CONC.MEDIAN BARR	5,000.000	LF
627(H) 5856	DEL.PORT.TYPE PREC. CONCRETE MEDIAN BARR	2,600.000	LF
823 8478	(PL)PORTABLE TRAFFIC SIGNAL SYSTEM	150.000	SD
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	16,000.000	LF
855(B) 8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	2.000	EA
855(B) 8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	1.000	EA
870(A) 8485	SAND FILLED IMPACT ATTEN.MODULE	300.000	SD
876(C) 8482	(PL)TRUCK MOUNTED ATTENUATOR	20.000	SD
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
880(L) 8911	TRAFFIC SURVEILLANCE, POLICE	100.000	HOURL
882(B) 8306	PORT.CHANGEABLE MESSAGE SIGN	300.000	SD

CALL ORDER : 070  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : CLEVELAND

CONTRACT ID : 030372  
 PCN : 2066804  
 PROJECTS : STPIG-35-2(283)108 TR  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 23.30  
 CALENDAR DAYS : 60  
 RES. ENG.:  
 LIQ. DAM.: \$ 700

CONTRACT DESCRIPTION:  
 SAFETY IMPROVEMENT I-35: FROM SH-9 (EAST), EXT. NORTH TO  
 INDIAN HILLS ROAD (CABLE BARRIERS). PROJECT LENGTH = 6.383  
 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	Y000 - TRAFFIC		
209	0120 MACHINE GRADING	276.500	STA
222	2801 TEMPORARY BALE BARRIER	512.000	LF
223	2801 TEMPORARY SILT FENCE	512.000	LF
230(A)	2806 SOLID SLAB SODDING	6,700.000	SY
509(D)	0325 CLASS C CONCRETE	1,144.000	CY
511(A)	0332 REINFORCING STEEL	562.000	LB
611(E)	6002 INLET (SMD-TYPE 2)	16.000	EA
619(B)	4741 REMOVAL OF DRAINAGE INLETS	16.000	EA
619(C)	0924 SAWING PAVEMENT	32.000	LF
627(H)	5856 DEL.PORT.TYPE PREC. CONCRETE MEDIAN BARR	6,740.000	LF
628	5105 (PL)CABLE BARRIER SYSTEM SOCKETED	30,730.000	LF
628	5110 (PL)CABLE END ANCHOR UNIT	4.000	EA
641	1552 MOBILIZATION	1.000	LSUM
870(A)	8011 SAND FILLED IMPACT ATTEN.MODULE	19.000	EA
876(C)	8482 (PL)TRUCK MOUNTED ATTENUATOR	180.000	SD
880(J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
880(L)	8911 TRAFFIC SURVEILLANCE, POLICE	300.000	HOURL
882(B)	8306 PORT.CHANGEABLE MESSAGE SIGN	180.000	SD
SECTION NO. 0002	STAK - STAKING		
642	0098 STAKING	1.000	LSUM



CALL ORDER : 080  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : CREEK

CONTRACT ID : 030319  
 PCN : 1044004  
 PROJECTS : BRFY-19C(268)  
 DBE GOALS : 5.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 22.76  
 CALENDAR DAYS : 210  
 RES. ENG. :  
 LIQ. DAM. : \$ 700

## CONTRACT DESCRIPTION:

BRIDGE AND APPROACHES US-75A; AT DUCK CREEK, 0.74 MILE  
 NORTH OF OKMULGEE COUNTY LINE. PROJECT LENGTH = 0.818 MILE  
 FLEXIBLE ESALS = 2.91 MILLION ASPHALT GRADE = PG 64-22 OK,  
 PG 70-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY		
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(A)	0183 UNCLASSIFIED EXCAVATION	46,965.000	CY
202(C)	0184 UNCLASSIFIED BORROW	1,000.000	CY
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
210	0121 OBLITERATING ABANDONED ROAD	43.230	STA
222	2801 TEMPORARY BALE BARRIER	542.000	LF
223	2801 TEMPORARY SILT FENCE	1,750.000	LF
229	4318 DITCH LINER PROTECTION	125.000	LF
230(A)	2806 SOLID SLAB SODDING	25,468.000	SY
232(A)	2813 SEEDING METHOD A	14.880	AC
233(A)	2817 VEGETATIVE MULCHING	14.880	AC
241	2832 MOWING	19.080	AC
303	0192 AGGREGATE BASE	4,439.000	CY
326(A)	4200 (SP)FLY ASH	1,203.000	TON
326(B)	4210 (SP)LIME	221.000	TON
326(E)	4240 (SP)CEMENTITIOUS STABILIZED SUBGRADE	22,276.000	SY
326(F)	4250 (SP)LIME STABILIZED SUBGRADE	12,252.000	SY
403(E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	741.000	TON
408	5774 PRIME COAT	9,563.000	GAL
411(S3)	5940 (SP)ASPH.CONC.,TYPE S3(PG 70-28 OK)	6,408.000	TON
411(S3)	5945 (SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	600.000	TON
411(S4)	5955 (SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	2,163.000	TON
411(S4)	5960 (SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	770.000	TON
509(D)	0325 CLASS C CONCRETE	17.000	CY
610(B)	0399 6" CONCRETE DRIVEWAY (H.E.S.)	131.000	SY
613(D)	0689 18" CORR. GALV. STEEL PIPE	114.000	LF
613(D)	0690 24" CORR. GALV. STEEL PIPE	148.000	LF
613(D)	0692 36" CORR. GALV. STEEL PIPE	482.000	LF
613(D)	4527 21" X 15" CORR. GALV. STEEL PIPE ARCH	244.000	LF
613(D)	4528 28" X 20" CORR. GALV. STEEL PIPE ARCH	66.000	LF
613(M)	4516 28" X 20" PREFAB. CULVERT END SEC., ARCH	4.000	EA
613(M)	5726 18" PREFAB. CULVERT END SEC., ROUND	6.000	EA
613(M)	5730 24" PREFAB. CULVERT END SEC., ROUND	8.000	EA
613(M)	5734 36" PREFAB. CULVERT END SEC., ROUND	16.000	EA
613(P)	1091 6" PERFORATED PIPE UNDERDRAIN ROUND	297.000	LF
613(Q)	1096 6" NON-PERF.PIPE UNDERDRAIN RND.	99.000	LF

CALL ORDER : 080  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : CREEK

CONTRACT ID : 030319  
 PCN : 1044004  
 PROJECTS : BRFY-19C(268)  
 DBE GOALS : 5.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 22.76  
 CALENDAR DAYS : 210  
 RES. ENG. :  
 LIQ. DAM. : \$ 700

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY		
619(A) 0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619(B) 4727	REMOVAL OF CONCRETE PAVEMENT	152.000	SY
619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	4,939.000	SY
619(B) 4780	REMOVAL OF GUARD RAIL	866.000	LF
619(C) 0924	SAWING PAVEMENT	2,807.000	LF
623(A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	500.000	LF
623(E) 7114	THRIE BEAM BRIDGE CONNECTION-TYPE A	4.000	EA
623(H) 8571	(SP)G.E.T. GUARD RAIL END SECTION	4.000	EA
624(C) 4459	(SP)FENCE-STYLE SWF (5 BARBED WIRE)	3,872.000	LF
624(D) 4292	FENCE-STYLE CLF (6'HIGH, CLASS A)	824.000	LF
624(E) 5964	GATES-STYLE CLF (6'HIGH X 16'LONG)	2.000	EA
629(A) 4958	MAILBOX INSTALLATION-SINGLE	13.000	EA
629(C) 4960	MAILBOX	13.000	EA
629(D) 4961	REMOVAL OF MAILBOX INSTALLATION	13.000	EA
653(C) 5946	OUTLET LATERAL HEADWALL	1.000	EA
SECTION NO. 0002	X081-BRIDGE 'A'		
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	97.000	CY
501(F) 6352	GRANULAR BACKFILL	118.800	CY
503(A) 1313	PRESTRESSED CONCRETE BEAMS (TYPE IV)	378.700	LF
504(A) 1304	APPROACH SLAB	234.400	SY
504(E) 6239	CONCRETE RAIL (TR3)	291.400	LF
506(A) 1322	STRUCTURAL STEEL	180.000	LB
509(A) 1326	CLASS AA CONCRETE	151.000	CY
509(B) 1328	CLASS A CONCRETE	51.300	CY
509(D) 1331	CLASS C CONCRETE	20.200	CY
511(A) 1332	REINFORCING STEEL	5,230.000	LB
511(B) 6010	EPOXY COATED REINFORCING STEEL	46,320.000	LB
514(A) 6010	PILES, FURNISHED (HP 10X42)	351.000	LF
514(B) 6292	PILES, DRIVEN (HP 10X42)	351.000	LF
514(F) 6354	PILE LOAD TEST (DYNAMIC)	18.000	EA
515(A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	627.000	SY
601(A-1)1353	TYPE I-A PLAIN RIPRAP	360.000	TON
601(A-2)1355	TYPE I-A FILTER BLANKET	70.000	TON
613(P) 6204	6" PERFORATED PIPE UNDERDRAIN ROUND	90.000	LF
613(Q) 6207	6" NON-PERF.PIPE UNDERDRAIN RND.	60.000	LF
619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
640 1398	FIELD OFFICE	1.000	EA
641 1399	MOBILIZATION	1.000	LSUM
SECTION NO. 0003	Y008-TRAFFIC		

CALL ORDER : 080  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : CREEK

CONTRACT ID : 030319  
 PCN : 1044004  
 PROJECTS : BRFY-19C(268)  
 DBE GOALS : 5.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 22.76  
 CALENDAR DAYS : 210  
 RES. ENG. :  
 LIQ. DAM.: \$ 700

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
-----			
SECTION NO. 0003	Y008-TRAFFIC		
627(G) 4316	RELOC.PORT.TYPE PRECAST CONC.MEDIAN BARR	1,050.000	LF
627(H) 5856	DEL.PORT.TYPE PREC. CONCRETE MEDIAN BARR	3,900.000	LF
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	18,000.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0004	STAK-STAKING		
642 0098	STAKING	1.000	LSUM

CALL ORDER : 090  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : CREEK

CONTRACT ID : 030334  
 PCN : 2070204  
 PROJECTS : STPY-119B(94) 3R  
 DBE GOALS : 5.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 CALENDAR DAYS : 100  
 RES. ENG.: DIVISION 8 (TULSA)  
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:  
 RESURFACE SH-99: BEG. 1.7 MI. N. OF JCT. SH-99/SH-33  
 EXTEND NORTH. PROJECT LENGTH 3.7 MILES FLEXIBLE ESALS = 1.0  
 MILLION ASPHALT GRADE = PG 70-28OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 L000 - BASE BID (ROADWAY ITEMS)			
411(S4) 5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	4,168.000	TON
414(B) 5071	8" H.E.S. CONCRETE (PATCHING)	1,278.000	SY
417 5267	COLD MILLING PAVEMENT	35,560.000	SY
419 4152	CONCRETE JOINT REHABILITATION	42,228.000	LF
425 5195	DIAMOND GRINDING CONCRETE PAVEMENT	44,445.000	SY
436 0100	DOWEL BAR RETROFIT	12,724.000	EA
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	6,668.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0002 L000 - ADD ALTERNATE 1 (ROADWAY ITEMS)			
411(S4) 5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	980.000	TON
414(B) 5071	8" H.E.S. CONCRETE (PATCHING)	260.000	SY
417 5267	COLD MILLING PAVEMENT	7,900.000	SY
419 4152	CONCRETE JOINT REHABILITATION	8,900.000	LF
425 5195	DIAMOND GRINDING CONCRETE PAVEMENT	8,200.000	SY
436 0100	DOWEL BAR RETROFIT	2,500.000	EA
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	1,100.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 L000 - BASE BID (GUARDRAIL ITEMS)			
619(B) 4780	REMOVAL OF GUARD RAIL	750.000	LF
623(A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	450.000	LF
623(H) 8571	(SP)G.E.T. GUARD RAIL END SECTION	6.000	EA
853 9069	GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	15.000	EA

CALL ORDER : 100  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : CUSTER

CONTRACT ID : 030017  
 PCN : 1268705  
 PROJECTS : IMY-40-3(63)76  
 DBE GOALS : 6.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 4.34  
 CALENDAR DAYS : 150  
 RES. ENG. :  
 LIQ. DAM. : \$ 800

CONTRACT DESCRIPTION:

RESURFACE(ASPHALT) I-40; FROM APPROX. 2.38 MILES WEST OF  
 THE CUSTER/CADDO COUNTY LINE, EXTEND EAST. PROJECT LENGTH =  
 1.894 MILES FLEXIBLE ESALS = 75.88 MILLION ASPHALT GRADE =  
 PG 64-22 OK, 76-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 I000-ROADWAY			
202(C) 0184	UNCLASSIFIED BORROW	9,500.000	CY
223 2801	TEMPORARY SILT FENCE	3,000.000	LF
230(A) 2806	SOLID SLAB SODDING	14,777.000	SY
233(A) 2817	VEGETATIVE MULCHING	10.000	AC
406 4276	(SP)OPEN GRAD.FRIC.SURF.CSE.(PG76-28OK)	1,921.000	TON
407 0250	TACK COAT	15,902.000	GAL
411(S3) 5935	(SP)ASPH.CONC.,TYPE S3(PG 76-28 OK)	10,039.000	TON
411(S3) 5945	(SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	20,411.000	TON
411(S5) 5965	(SP)ASPH.CONC.,TYPE S5(PG 76-28 OK)	6,641.000	TON
411(S5) 5975	(SP)ASPH.CONC.,TYPE S5(PG 64-22 OK)	4,048.000	TON
413(A) 4861	RUMBLE STRIP-METHOD AC-CON	37,998.000	LF
417 5267	COLD MILLING PAVEMENT	88,712.000	SY
420(A) 4242	FABRIC REINFORCEMENT	61,219.000	SY
420(B) 4268	BITUMINOUS BINDER	15,305.000	GAL
613(P) 1091	6" PERFORATED PIPE UNDERDRAIN ROUND	200.000	LF
613(Q) 1096	6" NON-PERF.PIPE UNDERDRAIN RND.	50.000	LF
613(R) 1100	PIPE UNDERDRAIN COVER MAT'L.	21.000	CY
613(S) 1180	TRENCH EXCAVATION	44.000	CY
641 1552	MOBILIZATION	1.000	LSUM
643 0087	(SP)CONTRACTORS QUALITY CONTROL	1.000	LSUM
SECTION NO. 0002 Y002-TRAFFIC			
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	55,500.000	LF
856(A) 8839	CONSTRUCTION TRAFF.STR.(PAINT)(4" WIDE)	42,000.000	LF
856(C) 8851	REMOVABLE PAVEMENT MARKING TAPE(4" WIDE)	2,000.000	LF
856(G) 8887	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-1	1,688.000	EA
857(A) 8947	PAVE.MARKERS CLASS C TYPE 2-C	231.000	EA
859(A) 8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	1,000.000	LF
876(C) 8482	(PL)TRUCK MOUNTED ATTENUATOR	384.000	SD
880(A) 8812	ARROW DISPLAY(TYPE C)	384.000	SD
880(B) 8818	CONSTRUCTION SIGNS 0 TO 6.25 SF	768.000	SD
880(B) 8821	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	3,072.000	SD
880(B) 8824	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	4,608.000	SD
880(B) 8827	CONSTRUCTION SIGNS 33.0 SF & OVER	192.000	SD
880(C) 8836	BARRICADES(TYPE II)	384.000	SD

CALL ORDER : 100  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : CUSTER

CONTRACT ID : 030017  
 PCN : 1268705  
 PROJECTS : IMY-40-3(63)76  
 DBE GOALS : 6.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 4.34  
 CALENDAR DAYS : 150  
 RES. ENG. :  
 LIQ. DAM. : \$ 800

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0002	Y002-TRAFFIC		
880(C) 8842	BARRICADES(TYPE III)	768.000	SD
880(C) 8848	WING BARRICADES	768.000	SD
880(D) 8854	VERTICAL PANELS	1,152.000	SD
880(E) 8860	WARNING LIGHTS(TYPE A)	6,144.000	SD
880(E) 8872	WARNING LIGHTS(TYPE C)	71,040.000	SD
880(F) 8878	DRUMS	71,040.000	SD
882(B) 8306	PORT.CHANGEABLE MESSAGE SIGN	384.000	SD

CALL ORDER : 110  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : CUSTER

CONTRACT ID : 030335  
 PCN : 2069804  
 PROJECTS : CMAY-120C(83)3R  
 DBE GOALS : 0.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 CALENDAR DAYS : 20  
 RES. ENG. :  
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:

RESURFACE(ASPHALT) SH-73; BEGIN AT THE JCT. OF SH-73/SH-44  
 NORTH OF FOSS, EXTEND EAST. PROJECT LENGTH = 5.0 MILES  
 FLEXIBLE ESALS =1.06 MILLION ASPHALT GRADE = PG 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY CMAY-129C(83)3R		
411(S4) 5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	11,858.000	TON
855(A) 8815	TRAFFIC STR.(PLAST.)(THIN-LINE)(4" WIDE)	104,544.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

CALL ORDER : 120  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : CUSTER

CONTRACT ID : 030336  
 PCN : 2069904  
 PROJECTS : CMAY-120C(84)3R  
 DBE GOALS : 0.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 CALENDAR DAYS : 20  
 RES. ENG. :  
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:

RESURFACE(ASPHALT) SH-73; BEGIN 5.0 MILES EAST OF JCT.  
 SH-73/SH-44, EXTEND EAST. PROJECT LENGTH = 4.91 MILES  
 FLEXIBLE ESALS = 1.6 MILLION ASPHALT GRADE = PG 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY CMAY-120C(84)3R		
411(S4) 5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	11,872.000	TON
417 4267	COLD MILLING BITUMINOUS PAVEMENT	807.000	SY
855(A) 8815	TRAFFIC STR.(PLAST.)(THIN-LINE)(4" WIDE)	102,662.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM



CALL ORDER : 130  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : CUSTER

CONTRACT ID : 030337  
 PCN : 2070004  
 PROJECTS : CMAY-120B(85)3R  
 DBE GOALS : 0.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 CALENDAR DAYS : 5  
 RES. ENG. :  
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:

RESURFACE(ASPHALT) SH-73;BEGIN 9.91 MILES EAST OF JCT.  
 SH-73/SH-44, EXTEND EAST. PROJECT LENGTH = 0.25 MILES  
 FLEXIBLE ESALS = 1.06 MILLION ASPHALT GRADE = PG 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY CMAY-120C(85)3R		
411(S4) 5950	(SP)ASPH.CONC.,TYPE S4(PG 76-28 OK)	1,040.000	TON
417 4267	COLD MILLING BITUMINOUS PAVEMENT	5,547.000	SY
855(A) 8815	TRAFFIC STR.(PLAST.)(THIN-LINE)(4" WIDE)	5,984.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

CALL ORDER : 140  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 030338  
 PCN : 2069804C  
 PROJECTS : CMAY-120C(83) 3R  
 CMAY-120C(84)3R  
 CMAY-120B(85)3R

COUNTIES : CUSTER

DBE GOALS : 0.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 CALENDAR DAYS : 45  
 RES. ENG.:  
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:  
 RESURFACE(ASPHALT) SH-73; BEGIN AT JCT. SH-73/SH-44 NORTH  
 OF FOSS, EXTEND EAST. PROJECT LENGTH = 10.16 MILES FLEXIBLE  
 ESALS = 1.06 MILLION ASPHALT GRADE = PG 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY CMAY-120C(83)3R		
411(S4) 5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	11,858.000	TON
855(A) 8815	TRAFFIC STR.(PLAST.)(THIN-LINE)(4" WIDE)	104,544.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0002	I000-ROADWAY CMAY-120C(84)3R		
411(S4) 5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	11,872.000	TON
417 4267	COLD MILLING BITUMINOUS PAVEMENT	807.000	SY
855(A) 8815	TRAFFIC STR.(PLAST.)(THIN-LINE)(4" WIDE)	102,662.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003	I000-ROADWAY CMAY-120C(85)3R		
411(S4) 5950	(SP)ASPH.CONC.,TYPE S4(PG 76-28 OK)	1,040.000	TON
417 4267	COLD MILLING BITUMINOUS PAVEMENT	5,547.000	SY
855(A) 8815	TRAFFIC STR.(PLAST.)(THIN-LINE)(4" WIDE)	5,984.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

CALL ORDER : 160  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : GARFIELD

CONTRACT ID : 030327  
 PCN : 1995604  
 PROJECTS : BRO-124D(38) CO  
 DBE GOALS : 7.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 5.96  
 CALENDAR DAYS : 130  
 RES. ENG.:  
 LIQ. DAM.: \$ 500

## CONTRACT DESCRIPTION:

BRIDGE AND APPROACHES COUNTY ROAD; OVER SKELTON CREEK, 5.0  
 MILES SOUTH AND 5.3 MILES EAST OF JCT. US-81/US-60 IN ENID.  
 PROJECT LENGTH = 0.207 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 E000 - ROADWAY			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(G)	0185 EARTHWORK	1.000	LSUM
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	430.000	LF
227	0100 TEMPORARY SILT DIKE	350.000	LF
230(A)	2806 SOLID SLAB SODDING	4,674.000	SY
233(A)	2817 VEGETATIVE MULCHING	0.970	AC
403(E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	539.000	TON
509(D)	0325 CLASS C CONCRETE	32.000	CY
613(CC)	7187 TYPE B4 CULVERT END TREATMENT	6.000	EA
613(D)	0690 24" CORR. GALV. STEEL PIPE	162.000	LF
SECTION NO. 0002 X081 - BRIDGE 'A'			
501(B)	1307 SUBSTRUCTURE EXCAVATION COMMON	80.000	CY
501(D)	6353 UNCLASSIFIED BACKFILL	65.000	CY
503(A)	1312 PRESTRESSED CONCRETE BEAMS (TYPE III)	770.000	LF
504(E)	1380 CONCRETE RAIL (TR1)	447.000	LF
506(A)	1322 STRUCTURAL STEEL	4,420.000	LB
509(A)	1326 CLASS AA CONCRETE	148.000	CY
509(B)	1328 CLASS A CONCRETE	109.200	CY
511(A)	1332 REINFORCING STEEL	47,760.000	LB
514(A)	6010 PILES, FURNISHED (HP 10X42)	418.000	LF
514(B)	6292 PILES, DRIVEN (HP 10X42)	418.000	LF
516(A)	6094 DRILLED SHAFTS 48" DIAMETER	64.200	LF
601(A-1)	1353 TYPE I-A PLAIN RIPRAP	1,056.000	TON
601(A-2)	1355 TYPE I-A FILTER BLANKET	279.000	TON
619(D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F)	6033 GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
641	1399 MOBILIZATION	1.000	LSUM
880(J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAK-STAKING			
642	0098 STAKING	1.000	LSUM

CALL ORDER : 180  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : GREER

CONTRACT ID : 030320  
 PCN : 1502304  
 PROJECTS : STPY-28B(134)  
 DBE GOALS : 15.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 19.51  
 CALENDAR DAYS : 150  
 RES. ENG. :  
 LIQ. DAM. : \$ 500

CONTRACT DESCRIPTION:  
 GRADE, DRAIN AND EROSION CONTROL SH-6; FROM 3.0 MILES NORTH  
 OF THE US-283 JCT., EXTEND NORTH. PROJECT LENGTH = 3.049  
 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 C000-ROADWAY			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(A)	0183 UNCLASSIFIED EXCAVATION	69,016.000	CY
202(C)	0184 UNCLASSIFIED BORROW	6,776.000	CY
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
222	2801 TEMPORARY BALE BARRIER	500.000	LF
224	2803 TEMPORARY SEDIMENT FILTER	12.000	EA
227	0100 TEMPORARY SILT DIKE	800.000	LF
229	4318 DITCH LINER PROTECTION	261.000	LF
230(A)	2806 SOLID SLAB SODDING	1,020.000	SY
230(B)	2807 MULCH SODDING	203,893.000	SY
230(F)	2812 WATERING	15,140.000	MGAL
232(B)	2814 SEEDING METHOD B	21.000	AC
233(A)	2817 VEGETATIVE MULCHING	21.000	AC
241	2832 MOWING	125.000	AC
403(E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	919.000	TON
408	5774 PRIME COAT	15,760.000	GAL
501(A)	0313 STRUCTURAL EXCAVATION UNCLASSIFIED	83.000	CY
509(B)	0321 CLASS A CONCRETE	230.000	CY
509(C)	0322 CLASS A CONCRETE FOR SMALL STRUCTURES	11.000	CY
509(D)	0325 CLASS C CONCRETE	50.000	CY
511(A)	0332 REINFORCING STEEL	40,908.000	LB
611(E)	6002 INLET (SMD-TYPE 2)	12.000	EA
613(B)	0492 24" R.C.PIPE CLASS III	1,048.000	LF
613(CC)	7197 TYPE B6 CULVERT END TREATMENT	12.000	EA
619(A)	0920 REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619(B)	0291 REMOVAL OF HEADWALL	5.000	EA
624(B)	4466 GATES-STYLE WWF (4.5'HIGH X 16'LONG)	4.000	EA
624(C)	4459 (SP)FENCE-STYLE SWF (5 BARBED WIRE)	5,210.000	LF
640	1426 FIELD OFFICE	1.000	EA
641	1552 MOBILIZATION	1.000	LSUM
SECTION NO. 0002 Y000-TRAFFIC			
800	4005 (PL)CEDAR SIGN POST	72.000	EA
850(A)	8110 SHEET ALUMINUM SIGNS	26.000	SF
851(C)	8327 2 1/4" SQUARE TUBE POST	70.000	LF
880(C)	8845 BARRICADES(TYPE III)	12.000	EA

CALL ORDER : 180  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : GREER

CONTRACT ID : 030320  
 PCN : 1502304  
 PROJECTS : STPY-28B(134)  
 DBE GOALS : 15.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 19.51  
 CALENDAR DAYS : 150  
 RES. ENG. :  
 LIQ. DAM.: \$ 500

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0002	Y000-TRAFFIC		
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003	STAK-STAKING		
642 0098	STAKING	1.000	LSUM

CALL ORDER : 200  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : HARPER

CONTRACT ID : 030339  
 PCN : 2070104  
 PROJECTS : NHY-17N(160) 3R  
 DBE GOALS : 0.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 CALENDAR DAYS : 127  
 RES. ENG.:  
 LIQ. DAM.: \$ 1000

CONTRACT DESCRIPTION:

RESURFACE(ASPHALT) US-270/412; BEGIN 1.0 MILES EAST OF HARPER/BEAVER COUNTY LINE, EXTEND EAST. PROJECT LENGTH = 7.0 MILES FLEXIBLE ESALS = 2.6 MILLION ASPHALT GRADE = PG 76-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 I000-ROADWAY(BASE BID)			
202(G) 6181	EARTHWORK	1.000	LSUM
407 0250	TACK COAT	25,132.000	GAL
411(S4) 5950	(SP)ASPH.CONC.,TYPE S4(PG 76-28 OK)	33,369.000	TON
417 5267	COLD MILLING PAVEMENT	182,500.000	SY
420(A) 4244	(PL)PRECOATED FABRIC MEMBRANE(STRIP)	35,000.000	LF
420(B) 4268	BITUMINOUS BINDER	2,987.000	GAL
426(A) 5095	CORED HOLES	4,200.000	EA
426(B) 5096	PORTLAND CEMENT	187.000	TON
426(C) 5097	FLY ASH	373.000	TON
855(A) 8820	(PL)4" RECESSED THERMOPLASTIC STRIPING	138,156.000	LF
855(B) 8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	4.000	EA
855(B) 8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	2.000	EA
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0002 I000-ROADWAY(ADD ALTERNATE)			
202(G) 6181	EARTHWORK	1.000	LSUM
407 0250	TACK COAT	1,548.000	GAL
411(S4) 5950	(SP)ASPH.CONC.,TYPE S4(PG 76-28 OK)	2,168.000	TON
417 5267	COLD MILLING PAVEMENT	12,907.000	SY
420(A) 4244	(PL)PRECOATED FABRIC MEMBRANE(STRIP)	2,500.000	LF
420(B) 4268	BITUMINOUS BINDER	213.000	GAL
426(A) 5095	CORED HOLES	300.000	EA
426(B) 5096	PORTLAND CEMENT	13.000	TON
426(C) 5097	FLY ASH	27.000	TON
855(A) 8820	(PL)4" RECESSED THERMOPLASTIC STRIPING	10,560.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 Y000-TRAFFIC(BASE BID)			
413(A) 4861	RUMBLE STRIP-METHOD AC-CON	73,920.000	LF
619(B) 4780	REMOVAL OF GUARD RAIL	650.000	LF
623(A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	350.000	LF
623(F) 5686	GUARD RAIL ANCHOR UNIT (TYPE D-BF)	4.000	EA
623(H) 8571	(SP)G.E.T. GUARD RAIL END SECTION	4.000	EA
853 9066	GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	12.000	EA

CALL ORDER : 200  
LETTING DATE : September 25, 2003  
LETTING TIME : 10:30 A.M.  
COUNTIES : HARPER

CONTRACT ID : 030339  
PCN : 2070104  
PROJECTS : NHY-17N(160) 3R  
DBE GOALS : 0.00  
GUARANTY : 5% OF BID TOTAL  
PLAN PRICE : 0.00  
CALENDAR DAYS : 127  
RES. ENG. :  
LIQ. DAM.: \$ 1000

SECTION NO. 0004	Y000-TRAFFIC(ADD ALTERNATE)		
413(A) 4861	RUMBLE STRIP-METHOD AC-CON	5,280.000	LF

CALL ORDER : 220  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : JACKSON

CONTRACT ID : 030340  
 PCN : 2069604  
 PROJECTS : CMAY-133C(52)3R  
 DBE GOALS : 0.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 CALENDAR DAYS : 30  
 RES. ENG. :  
 LIQ. DAM. : \$ 500

CONTRACT DESCRIPTION:

RESURFACE(ASPHALT) SH-34; BEGIN AT JCT. SH-34/SH-6 SOUTH OF  
 DUKE, EXTEND NORTH. PROJECT LENGTH = 5.0 MILES FLEXIBLE  
 ESALS = 1.84 MILLION ASPHALT GRADE = PG 76-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-RAODWAY CMAY-133C(52)3R		
411(S4) 5950	(SP)ASPH.CONC.,TYPE S4(PG 76-28 OK)	12,194.000	TON
411(S5) 5965	(SP)ASPH.CONC.,TYPE S5(PG 76-28 OK)	8,556.000	TON
417 4267	COLD MILLING BITUMINOUS PAVEMENT	5,633.000	SY
855(A) 8815	TRAFFIC STR.(PLAST.)(THIN-LINE)(4" WIDE)	95,040.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM



CALL ORDER : 230  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : JACKSON

CONTRACT ID : 030341  
 PCN : 2069704  
 PROJECTS : CMAY-133C(53)3R  
 DBE GOALS : 0.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 CALENDAR DAYS : 30  
 RES. ENG. :  
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:

RESURFACE(ASPHALT) SH-34; BEGIN 5.0 MILES NORTH OF JCT.  
 SH-34/SH-6, EXTEND NORTH. PROJECT LENGTH = 5.29 MILES  
 FLEXIBLE ESALS = 1.84 MILLION ASPHALT GRADE = PG 76-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY CMAY-133C(53)3R		
411(S4) 5950	(SP)ASPH.CONC.,TYPE S4(PG 76-28 OK)	12,843.000	TON
411(S5) 5965	(SP)ASPH.CONC.,TYPE S5(PG 76-28 OK)	9,338.000	TON
417 4267	COLD MILLING BITUMINOUS PAVEMENT	8,612.000	SY
855(A) 8815	TRAFFIC STR.(PLAST.)(THIN-LINE)(4" WIDE)	100,553.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

CALL ORDER : 240  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : JACKSON

CONTRACT ID : 030342  
 PCN : 2069604C  
 PROJECTS : CMAY-133C(52)3R  
 CMAY-133C(53)3R  
 DBE GOALS : 0.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 CALENDAR DAYS : 60  
 RES. ENG.:  
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:  
 RESURFACE(ASPHALT) SH-34; BEGIN AT JCT. SH-34/SH-6 SOUTH OF  
 DUKE, EXTEND NORTH. PROJECT LENGTH = 10.29 MILES FLEXIBLE  
 ESALS = 1.84 MILLION ASPHALT GRADE = PG 76-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-RAODWAY CMAY-133C(52)3R		
411(S4) 5950	(SP)ASPH.CONC.,TYPE S4(PG 76-28 OK)	12,194.000	TON
411(S5) 5965	(SP)ASPH.CONC.,TYPE S5(PG 76-28 OK)	8,556.000	TON
417 4267	COLD MILLING BITUMINOUS PAVEMENT	5,633.000	SY
855(A) 8815	TRAFFIC STR.(PLAST.)(THIN-LINE)(4" WIDE)	95,040.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0002	I000-ROADWAY CMAY-133C(53)3R		
411(S4) 5950	(SP)ASPH.CONC.,TYPE S4(PG 76-28 OK)	12,843.000	TON
411(S5) 5965	(SP)ASPH.CONC.,TYPE S5(PG 76-28 OK)	9,338.000	TON
417 4267	COLD MILLING BITUMINOUS PAVEMENT	8,612.000	SY
855(A) 8815	TRAFFIC STR.(PLAST.)(THIN-LINE)(4" WIDE)	100,553.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

CALL ORDER : 260  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : KAY

CONTRACT ID : 030343  
 PCN : 2069304  
 PROJECTS : CMAY-136B(79)3R  
 DBE GOALS : 10.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 CALENDAR DAYS : 60  
 RES. ENG. :  
 LIQ. DAM. : \$ 500

CONTRACT DESCRIPTION:

RESURFACE(ASPHALT) SH-11; BEGIN AT THE WEST SIDE OF JCT.  
 SH-11/US-177 IN BLACKWELL, EXTEND EAST. PROJECT LENGTH = 3.  
 205 MILES FLEXIBLE ESALS = 4.6 MILLION ASPHALT GRADE = PG  
 64-22 OK, PG 70-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY(BASE BID)		
202(A) 4349	(PL)UNCLASSIFIED EXCAVATION	1.000	LSUM
303 5912	AGGREGATE BASE	50.000	TON
411(S3) 6210	(SP)ASPH.CONC.,TYPE S3(PATCH)(PG64-22OK)	200.000	TON
411(S4) 5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	4,950.000	TON
411(S4) 5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	2,600.000	TON
417 5267	COLD MILLING PAVEMENT	32,600.000	SY
509(B) 0321	CLASS A CONCRETE	6.000	CY
612(A) 0641	MANHOLES ADJUST TO GRADE	7.000	EA
619(B) 4915	REMOVAL OF CONCRETE MEDIAN BARRIER	60.000	LF
619(B) 8305	REMOVAL OF SIGNS	8.000	EA
850(A) 8110	SHEET ALUMINUM SIGNS	125.000	SF
851(C) 8324	2" SQUARE TUBE POST	288.000	LF
851(C) 8327	2 1/4" SQUARE TUBE POST	80.000	LF
851(C) 8330	2 1/2" SQUARE TUBE POST	48.000	LF
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	41,000.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0002	I000-ROADWAY(ADD ALTERNATE 1)		
411(S4) 5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	1,200.000	TON
411(S4) 5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	520.000	TON
417 5267	COLD MILLING PAVEMENT	7,040.000	SY
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	8,200.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003	I000-ROADWAY(ADD ALTERNATE 2)		
411(S4) 5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	1,200.000	TON
411(S4) 5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	520.000	TON
417 5267	COLD MILLING PAVEMENT	7,040.000	SY
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	6,000.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0004	BASE BID (TRAFFIC ITEMS)		
619(B) 4780	REMOVAL OF GUARD RAIL	6,478.000	LF

CALL ORDER : 260  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : KAY

CONTRACT ID : 030343  
 PCN : 2069304  
 PROJECTS : CMAY-136B(79)3R  
 DBE GOALS : 10.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 CALENDAR DAYS : 60  
 RES. ENG. :  
 LIQ. DAM.: \$ 500

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0004	BASE BID (TRAFFIC ITEMS)		
623(A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	4,389.000	LF
623(F) 5686	GUARD RAIL ANCHOR UNIT (TYPE D-BF)	24.000	EA
623(H) 8571	(SP)G.E.T. GUARD RAIL END SECTION	18.000	EA
853 9066	GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	252.000	EA

CALL ORDER : 261  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : KAY

CONTRACT ID : 030368  
 PCN : 2071404  
 PROJECTS : STPY-136C(80)TR  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 1.63  
 CALENDAR DAYS : 30  
 RES. ENG. :  
 LIQ. DAM. : \$ 300

CONTRACT DESCRIPTION:  
 SCHOOL ZONE WARNING FLASHER SIGN US-177: AT BROADWAY,  
 US-177 AT 4TH ST. IN THE TOWN OF BRAMAN. PROJECT LENGTH = 0.  
 00 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	Y031 - TRAFFIC		
641	1552 MOBILIZATION	1.000	LSUM
802(B)	8334 1" PVC SCH.40 PLASTIC CONDUIT TRENCHED	50.000	LF
802(B)	8338 1 1/2" PVC SCH.40 PLASTIC CONDUIT TRENCH	20.000	LF
803	8067 PULL BOX(SIZE III)	2.000	EA
804(A)	2915 STRUCTURAL CONCRETE	0.800	CY
804(B)	2916 REINFORCING STEEL	52.600	LB
810(A)	3118 SERVICE POLE	2.000	EA
811	8044 1/C NO.10 ELECT.COND.	270.000	LF
827	8623 SOLID STATE FLASHER CONTROLLER(TYPE II)	2.000	EA
831	8301 1WAY1SEC.ADJ.SIG.HD.S-22	4.000	EA
850(A)	8110 SHEET ALUMINUM SIGNS	46.440	SF
851(B)	3220 4"@10.79 GALV.STL.PIPE POST	24.000	LF
851(C)	8327 2 1/4" SQUARE TUBE POST	70.000	LF
880(J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
890(A)	8724 (PL)REMOVAL OF EXISTING SIGNS	5.000	EA

CALL ORDER : 280  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : KINGFISHER

CONTRACT ID : 030344  
 PCN : 2069404  
 PROJECTS : NHY-17N(158)3R  
 DBE GOALS : 5.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 CALENDAR DAYS : 240  
 RES. ENG. :  
 LIQ. DAM. : \$ 700

CONTRACT DESCRIPTION:

RESURFACE(ASPHALT) SH-3; BEGIN AT KINGFISHER/BLAINE COUNTY  
 LINE, EXTEND EAST. PROJECT LENGTH = 4.24 MILES FLEXIBLE  
 ESALS = 4.22 MILLION ASPHALT GRADE = PG 64-22 OK, PG 76-28  
 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY(BASE BID) NHY-17N(158)3R		
202(C) 0184	UNCLASSIFIED BORROW	28,000.000	CY
209 0120	MACHINE GRADING	220.910	STA
223 2801	TEMPORARY SILT FENCE	1,000.000	LF
230(A) 2806	SOLID SLAB SODDING	7,900.000	SY
230(F) 2812	WATERING	316.000	MGAL
233(A) 2817	VEGETATIVE MULCHING	60.000	AC
411(S3) 5945	(SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	3,540.000	TON
411(S3) 6210	(SP)ASPH.CONC.,TYPE S3(PATCH)(PG64-22OK)	500.000	TON
411(S4) 5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	4,210.000	TON
417 5267	COLD MILLING PAVEMENT	28,911.000	SY
509(B) 0321	CLASS A CONCRETE	68.000	CY
511(A) 0332	REINFORCING STEEL	8,204.000	LB
613(B) 0492	24" R.C.PIPE CLASS III	28.000	LF
613(B) 0493	30" R.C.PIPE CLASS III	136.000	LF
613(C) 4375	SP. END SECTION OF 24" RCP ROUND	2.000	EA
613(C) 4377	SP. END SECTION OF 30" RCP ROUND	10.000	EA
613(D) 4528	28" X 20" CORR. GALV. STEEL PIPE ARCH	50.000	LF
613(G) 4571	28" X 20" GALV. STEEL CULV. END SEC.ARCH	2.000	EA
619(B) 0291	REMOVAL OF HEADWALL	18.000	EA
619(B) 8305	REMOVAL OF SIGNS	18.000	EA
641 1552	MOBILIZATION	1.000	LSUM
850(A) 8110	SHEET ALUMINUM SIGNS	43.750	SF
851(C) 8324	2" SQUARE TUBE POST	228.000	LF
851(C) 8327	2 1/4" SQUARE TUBE POST	47.500	LF
851(C) 8330	2 1/2" SQUARE TUBE POST	28.500	LF
853 9039	DELINEATORS(TYPE 2, CODE 3)	18.000	EA
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	43,800.000	LF
859(A) 8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	5,500.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0002	I000-ROADWAY(ADD ALTERNATIVE # 1) NHY-17N(158)3R		
230(A) 2806	SOLID SLAB SODDING	1,800.000	SY
230(F) 2812	WATERING	72.000	MGAL
411(S3) 5945	(SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	790.000	TON
411(S3) 6210	(SP)ASPH.CONC.,TYPE S3(PATCH)(PG64-22OK)	200.000	TON

CALL ORDER : 280  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : KINGFISHER

CONTRACT ID : 030344  
 PCN : 2069404  
 PROJECTS : NHY-17N(158)3R  
 DBE GOALS : 5.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 CALENDAR DAYS : 240  
 RES. ENG. :  
 LIQ. DAM. : \$ 700

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0002	I000-ROADWAY(ADD ALTERNATIVE # 1) NHY-17N(158)3R		
411(S4) 5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	1,080.000	TON
417 5267	COLD MILLING PAVEMENT	6,454.000	SY
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	9,760.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003	I000-ROADWAY(ADD ALTERNATIVE # 2) NHY-17N(158)3R		
230(A) 2806	SOLID SLAB SODDING	1,800.000	SY
230(F) 2812	WATERING	72.000	MGAL
411(S3) 5945	(SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	790.000	TON
411(S3) 6210	(SP)ASPH.CONC.,TYPE S3(PATCH)(PG64-22OK)	100.000	TON
411(S4) 5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	950.000	TON
417 5267	COLD MILLING PAVEMENT	6,454.000	SY
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	9,060.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0004	I000-ROADWAY(ADD ALTERNATIVE # 3) NHY-17N(158)3R		
230(A) 2806	SOLID SLAB SODDING	1,800.000	SY
230(F) 2812	WATERING	72.000	MGAL
411(S3) 5945	(SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	790.000	TON
411(S3) 6210	(SP)ASPH.CONC.,TYPE S3(PATCH)(PG64-22OK)	100.000	TON
411(S4) 5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	950.000	TON
417 5267	COLD MILLING PAVEMENT	6,454.000	SY
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	8,160.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0005	I000-ROADWAY(ADD ALTERNATIVE # 4) NHY-17N(158)3R		
230(A) 2806	SOLID SLAB SODDING	1,600.000	SY
230(F) 2812	WATERING	72.000	MGAL
411(S3) 5945	(SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	720.000	TON
411(S3) 6210	(SP)ASPH.CONC.,TYPE S3(PATCH)(PG64-22OK)	100.000	TON
411(S4) 5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	1,010.000	TON
417 5267	COLD MILLING PAVEMENT	7,245.000	SY
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	10,100.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0006	Y000-GUARDRAIL(BASE BID) NHY-17N(158)3R		
619(B) 4780	REMOVAL OF GUARD RAIL	600.000	LF
623(A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	30.000	LF
623(H) 8571	(SP)G.E.T. GUARD RAIL END SECTION	8.000	EA

CALL ORDER : 280  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : KINGFISHER

CONTRACT ID : 030344  
 PCN : 2069404  
 PROJECTS : NHY-17N(158)3R  
 DBE GOALS : 5.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 CALENDAR DAYS : 240  
 RES. ENG. :  
 LIQ. DAM.: \$ 700

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0006	Y000-GUARDRAIL(BASE BID) NHY-17N(158)3R		
853 9066	GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	4.000	EA
SECTION NO. 0007	STAK-STAKING NHY-17N(158)3R		
642 0098	STAKING	1.000	LSUM



CALL ORDER : 290  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : KINGFISHER

CONTRACT ID : 030345  
 PCN : 2069504  
 PROJECTS : NHY-17N(159) 3R  
 DBE GOALS : 3.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 CALENDAR DAYS : 240  
 RES. ENG. :  
 LIQ. DAM. : \$ 700

CONTRACT DESCRIPTION:

RESURFACE(ASPHALT) SH-3; BEGIN 4.72 MILES EAST OF  
 KINGFISHER/BLAINE COUNTY LINE, EXTEND EAST. PROJECT LENGTH  
 = 5.00 MILES FLEXIBLE ESALS = 4.22 MILLION ASPHALT GRADE =  
 PG 64-22 OK, PG 70-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY NHY-17N(159)3R		
202(C) 0184	UNCLASSIFIED BORROW	33,000.000	CY
209 0120	MACHINE GRADING	260.230	STA
223 2801	TEMPORARY SILT FENCE	2,500.000	LF
230(A) 2806	SOLID SLAB SODDING	17,200.000	SY
230(F) 2812	WATERING	688.000	MGAL
233(A) 2817	VEGETATIVE MULCHING	60.000	AC
411(S3) 5945	(SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	7,780.000	TON
411(S3) 6210	(SP)ASPH.CONC.,TYPE S3(PATCH)(PG64-22OK)	1,000.000	TON
411(S4) 5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	9,720.000	TON
417 5267	COLD MILLING PAVEMENT	65,538.000	SY
504(F) 1381	CONCRETE PARAPET	113.000	LF
509(B) 0321	CLASS A CONCRETE	395.000	CY
511(A) 0332	REINFORCING STEEL	34,147.000	LB
613(D) 4528	28" X 20" CORR. GALV. STEEL PIPE ARCH	50.000	LF
613(G) 4571	28" X 20" GALV. STEEL CULV. END SEC.ARCH	2.000	EA
619(B) 0291	REMOVAL OF HEADWALL	28.000	EA
619(B) 6252	REMOVAL OF EXISTING PARAPET	113.000	LF
619(B) 8305	REMOVAL OF SIGNS	9.000	EA
641 1552	MOBILIZATION	1.000	LSUM
850(A) 8110	SHEET ALUMINUM SIGNS	34.500	SF
851(C) 8324	2" SQUARE TUBE POST	152.000	LF
851(C) 8327	2 1/4" SQUARE TUBE POST	35.000	LF
851(C) 8330	2 1/2" SQUARE TUBE POST	21.000	LF
853 9039	DELINEATORS(TYPE 2, CODE 3)	28.000	EA
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	73,400.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0002	Y000-GUARDRAIL NHY-17N(159)		
623(A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	350.000	LF
623(F) 5686	GUARD RAIL ANCHOR UNIT (TYPE D-BF)	4.000	EA
623(H) 8571	(SP)G.E.T. GUARD RAIL END SECTION	4.000	EA
853 9066	GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	12.000	EA
SECTION NO. 0003	STAK-STAKING NHY-17N(159)3R		

CALL ORDER : 290  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : KINGFISHER

CONTRACT ID : 030345  
 PCN : 2069504  
 PROJECTS : NHY-17N(159) 3R  
 DBE GOALS : 3.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 CALENDAR DAYS : 240  
 RES. ENG. :  
 LIQ. DAM.: \$ 700

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003	STAK-STAKING NHY-17N(159)3R		
642 0098	STAKING	1.000	LSUM

CALL ORDER : 300  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : KINGFISHER

CONTRACT ID : 030346  
 PCN : 2069404C  
 PROJECTS : NHY-17N(158)3R  
 NHY-17N(159) 3R  
 DBE GOALS : 4.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 CALENDAR DAYS : 300  
 RES. ENG.:  
 LIQ. DAM.: \$ 1000

CONTRACT DESCRIPTION:  
 RESURFACE(ASPHALT) SH-3; BEGIN AT KING FISHER/BLAINE COUNTY  
 LINE, EXTEND EAST. PROJECT LENGTH = 9.72 MILES FLEXIBLE  
 ESALS = 4.22 MILLION ASPHALT GRADE = PG 64-22 OK, PG 70-28  
 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 I000-ROADWAY(BASE BID) NHY-17N(158)3R			
202(C) 0184	UNCLASSIFIED BORROW	28,000.000	CY
209 0120	MACHINE GRADING	220.910	STA
223 2801	TEMPORARY SILT FENCE	1,000.000	LF
230(A) 2806	SOLID SLAB SODDING	7,900.000	SY
230(F) 2812	WATERING	316.000	MGAL
233(A) 2817	VEGETATIVE MULCHING	60.000	AC
411(S3) 5945	(SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	3,540.000	TON
411(S3) 6210	(SP)ASPH.CONC.,TYPE S3(PATCH)(PG64-22OK)	500.000	TON
411(S4) 5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	4,210.000	TON
417 5267	COLD MILLING PAVEMENT	28,911.000	SY
509(B) 0321	CLASS A CONCRETE	68.000	CY
511(A) 0332	REINFORCING STEEL	8,204.000	LB
613(B) 0492	24" R.C.PIPE CLASS III	28.000	LF
613(B) 0493	30" R.C.PIPE CLASS III	136.000	LF
613(C) 4375	SP. END SECTION OF 24" RCP ROUND	2.000	EA
613(C) 4377	SP. END SECTION OF 30" RCP ROUND	10.000	EA
613(D) 4528	28" X 20" CORR. GALV. STEEL PIPE ARCH	50.000	LF
613(G) 4571	28" X 20" GALV. STEEL CULV. END SEC.ARCH	2.000	EA
619(B) 0291	REMOVAL OF HEADWALL	18.000	EA
619(B) 8305	REMOVAL OF SIGNS	18.000	EA
641 1552	MOBILIZATION	1.000	LSUM
850(A) 8110	SHEET ALUMINUM SIGNS	43.750	SF
851(C) 8324	2" SQUARE TUBE POST	228.000	LF
851(C) 8327	2 1/4" SQUARE TUBE POST	47.500	LF
851(C) 8330	2 1/2" SQUARE TUBE POST	28.500	LF
853 9039	DELINEATORS(TYPE 2, CODE 3)	18.000	EA
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	43,800.000	LF
859(A) 8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	5,500.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0002 I000-ROADWAY(ADD ALTERNATIVE # 1) NHY-17N(158)3R			
230(A) 2806	SOLID SLAB SODDING	1,800.000	SY
230(F) 2812	WATERING	72.000	MGAL
411(S3) 5945	(SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	790.000	TON

CALL ORDER : 300  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : KINGFISHER

CONTRACT ID : 030346  
 PCN : 2069404C  
 PROJECTS : NHY-17N(158)3R  
 NHY-17N(159) 3R  
 DBE GOALS : 4.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 CALENDAR DAYS : 300  
 RES. ENG.:  
 LIQ. DAM.: \$ 1000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0002	I000-ROADWAY(ADD ALTERNATIVE # 1) NHY-17N(158)3R		
411(S3) 6210	(SP)ASPH.CONC.,TYPE S3(PATCH)(PG64-22OK)	200.000	TON
411(S4) 5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	1,080.000	TON
417 5267	COLD MILLING PAVEMENT	6,454.000	SY
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	9,760.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003	I000-ROADWAY(ADD ALTERNATIVE # 2) NHY-17N(158)3R		
230(A) 2806	SOLID SLAB SODDING	1,800.000	SY
230(F) 2812	WATERING	72.000	MGAL
411(S3) 5945	(SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	790.000	TON
411(S3) 6210	(SP)ASPH.CONC.,TYPE S3(PATCH)(PG64-22OK)	100.000	TON
411(S4) 5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	950.000	TON
417 5267	COLD MILLING PAVEMENT	6,454.000	SY
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	9,060.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0004	I000-ROADWAY(ADD ALTERNATIVE # 3) NHY-17N(158)3R		
230(A) 2806	SOLID SLAB SODDING	1,800.000	SY
230(F) 2812	WATERING	72.000	MGAL
411(S3) 5945	(SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	790.000	TON
411(S3) 6210	(SP)ASPH.CONC.,TYPE S3(PATCH)(PG64-22OK)	100.000	TON
411(S4) 5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	950.000	TON
417 5267	COLD MILLING PAVEMENT	6,454.000	SY
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	8,160.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0005	I000-ROADWAY(ADD ALTERNATIVE # 4) NHY-17N(158)3R		
230(A) 2806	SOLID SLAB SODDING	1,600.000	SY
230(F) 2812	WATERING	72.000	MGAL
411(S3) 5945	(SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	720.000	TON
411(S3) 6210	(SP)ASPH.CONC.,TYPE S3(PATCH)(PG64-22OK)	100.000	TON
411(S4) 5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	1,010.000	TON
417 5267	COLD MILLING PAVEMENT	7,245.000	SY
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	10,100.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0006	Y000-GUARDRAIL(BASE BID) NHY-17N(158)3R		
619(B) 4780	REMOVAL OF GUARD RAIL	600.000	LF

CALL ORDER : 300  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : KINGFISHER

CONTRACT ID : 030346  
 PCN : 2069404C  
 PROJECTS : NHY-17N(158)3R  
           NHY-17N(159) 3R  
 DBE GOALS : 4.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 CALENDAR DAYS : 300  
 RES. ENG.:  
 LIQ. DAM.: \$ 1000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0006	Y000-GUARDRAIL(BASE BID) NHY-17N(158)3R		
623(A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	30.000	LF
623(H) 8571	(SP)G.E.T. GUARD RAIL END SECTION	8.000	EA
853 9066	GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	4.000	EA
SECTION NO. 0007	STAK-STAKING NHY-17N(158)3R		
642 0098	STAKING	1.000	LSUM
SECTION NO. 0008	I000-ROADWAY NHY-17N(159)3R		
202(C) 0184	UNCLASSIFIED BORROW	33,000.000	CY
209 0120	MACHINE GRADING	260.230	STA
223 2801	TEMPORARY SILT FENCE	2,500.000	LF
230(A) 2806	SOLID SLAB SODDING	17,200.000	SY
230(F) 2812	WATERING	688.000	MGAL
233(A) 2817	VEGETATIVE MULCHING	60.000	AC
411(S3) 5945	(SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	7,780.000	TON
411(S3) 6210	(SP)ASPH.CONC.,TYPE S3(PATCH)(PG64-22OK)	1,000.000	TON
411(S4) 5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	9,720.000	TON
417 5267	COLD MILLING PAVEMENT	65,538.000	SY
504(F) 1381	CONCRETE PARAPET	113.000	LF
509(B) 0321	CLASS A CONCRETE	395.000	CY
511(A) 0332	REINFORCING STEEL	34,147.000	LB
613(D) 4528	28" X 20" CORR. GALV. STEEL PIPE ARCH	50.000	LF
613(G) 4571	28" X 20" GALV. STEEL CULV. END SEC.ARCH	2.000	EA
619(B) 0291	REMOVAL OF HEADWALL	28.000	EA
619(B) 6252	REMOVAL OF EXISTING PARAPET	113.000	LF
619(B) 8305	REMOVAL OF SIGNS	9.000	EA
641 1552	MOBILIZATION	1.000	LSUM
850(A) 8110	SHEET ALUMINUM SIGNS	34.500	SF
851(C) 8324	2" SQUARE TUBE POST	152.000	LF
851(C) 8327	2 1/4" SQUARE TUBE POST	35.000	LF
851(C) 8330	2 1/2" SQUARE TUBE POST	21.000	LF
853 9039	DELINEATORS(TYPE 2, CODE 3)	28.000	EA
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	73,400.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0009	Y000-GUARDRAIL NHY-17N(159)		
623(A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	350.000	LF
623(F) 5686	GUARD RAIL ANCHOR UNIT (TYPE D-BF)	4.000	EA
623(H) 8571	(SP)G.E.T. GUARD RAIL END SECTION	4.000	EA

CALL ORDER : 300  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.

COUNTIES : KINGFISHER

CONTRACT ID : 030346  
 PCN : 2069404C  
 PROJECTS : NHY-17N(158)3R  
           NHY-17N(159) 3R  
 DBE GOALS : 4.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 CALENDAR DAYS : 300  
 RES. ENG.:  
 LIQ. DAM.: \$ 1000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0009	Y000-GUARDRAIL NHY-17N(159)		
853 9066	GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	12.000	EA
SECTION NO. 0010	STAK-STAKING NHY-17N(159)3R		
642 0098	STAKING	1.000	LSUM

CALL ORDER : 320  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : LATIMER

CONTRACT ID : 030347  
 PCN : 2068604  
 PROJECTS : CMAY-139B(46) 3R  
 DBE GOALS : 3.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 CALENDAR DAYS : 20  
 RES. ENG. :  
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:

RESURFACE(ASPHALT) US-270; BEGIN 3.9 MILES WEST OF  
 LATIMER/LEFLORE COUNTY LINE, EXTEND EAST. PROJECT LENGTH =  
 3.9 MILES FLEXIBLE ESALS = 3 MILLION ASPHALT GRADE = PG  
 64-22 OK, PG 76-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY CMAY-139B(49)3R		
403(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	618.000	TON
407 0250	TACK COAT	4,668.000	GAL
411(S4) 5950	(SP)ASPH.CONC.,TYPE S4(PG 76-28 OK)	6,400.000	TON
411(S4) 5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	3,200.000	TON
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	76,750.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

CALL ORDER : 330  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : LEFLORE

CONTRACT ID : 030348  
 PCN : 2068704  
 PROJECTS : CMAY-140B(108) 3R  
 DBE GOALS : 3.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 CALENDAR DAYS : 20  
 RES. ENG. :  
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:  
 RESURFACE(ASPHALT) US-270; BEGIN AT LATIMER/LEFLORE COUNTY  
 LINE, EXTEND EAST. PROJECT LENGTH = 5.4 MILES FLEXIBLE  
 ESALS = 3.0 MILLION ASPHALT GRADE = PG 64-22 OK, PG 76-28

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY CMAY-140B(108)3R		
403(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	875.000	TON
407 0250	TACK COAT	6,571.000	GAL
411(S4) 5950	(SP)ASPH.CONC.,TYPE S4(PG 76-28 OK)	8,800.000	TON
411(S4) 5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	4,400.000	TON
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	106,270.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM



CALL ORDER : 340  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : LEFLORE

CONTRACT ID : 030349  
 PCN : 2068804  
 PROJECTS : STPY-140B(109) 3R  
 DBE GOALS : 3.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 CALENDAR DAYS : 20  
 RES. ENG. :  
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:

RESURFACE(ASPHALT) US-270; BEGIN AT THE JCT. US-270/US-271,  
 EXTEND EAST. PROJECT LENGTH = 5.7 MILES FLEXIBLE ESALS = 3  
 MILLION ASPHALT GRADE = PG 64-22 OK, PG 76-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY CMAY-140B(109)3R		
403(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	903.000	TON
407 0250	TACK COAT	10,835.000	GAL
411(S4) 5950	(SP)ASPH.CONC.,TYPE S4(PG 76-28 OK)	18,200.000	TON
411(S4) 5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	9,100.000	TON
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	112,170.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

CALL ORDER : 350  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 030350  
 PCN : 2068604C  
 PROJECTS : CMAY-139B(46) 3R  
 CMAY-140B(108) 3R  
 STPY-140B(109) 3R

COUNTIES : LATIMER LEFLORE

DBE GOALS : 3.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 CALENDAR DAYS : 60  
 RES. ENG.:  
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:  
 RESURFACE(ASPHALT) US-270; BEGIN 3.9 MILES WEST OF  
 LATIMER/LEFLORE COUNTY LINE, EXTEND EAST. PROJECT LENGTH =  
 15.0 MILES FLEXIBLE ESALS = 3.0 MILLION ASPHALT GRADE = PG  
 64-22 OK, PG 76-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
-----			
SECTION NO. 0001	I000-ROADWAY CMAY-139B(46)3R		
403(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	618.000	TON
407 0250	TACK COAT	4,668.000	GAL
411(S4) 5950	(SP)ASPH.CONC.,TYPE S4(PG 76-28 OK)	6,400.000	TON
411(S4) 5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	3,200.000	TON
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	76,750.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0002	I000-ROADWAY CMAY-140B(108)3R		
403(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	875.000	TON
407 0250	TACK COAT	6,571.000	GAL
411(S4) 5950	(SP)ASPH.CONC.,TYPE S4(PG 76-28 OK)	8,800.000	TON
411(S4) 5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	4,400.000	TON
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	106,270.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003	I000-ROADWAY CMAY-140B(109)3R		
403(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	903.000	TON
407 0250	TACK COAT	10,835.000	GAL
411(S4) 5950	(SP)ASPH.CONC.,TYPE S4(PG 76-28 OK)	18,200.000	TON
411(S4) 5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	9,100.000	TON
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	112,170.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

CALL ORDER : 360  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : LINCOLN

CONTRACT ID : 030351  
 PCN : 2069104  
 PROJECTS : CMAY-141B(115) 3R  
 DBE GOALS : 5.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 CALENDAR DAYS : 60  
 RES. ENG. :  
 LIQ. DAM.: \$ 600

CONTRACT DESCRIPTION:

RESURFACE US-177: FROM POTTAWATOMIE COUNTY LINE, EXTEND  
 NORTH. PROJECT LENGTH = 8.00 MILES FLEXIBLE ESALS = < 1  
 MILLION ASPHALT GRADE = PG 64-22 OK, PG 70-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY-CMAY-141B(115)3R		
402	5205 (PL)ARMOR COAT	70,400.000	SY
407	0250 TACK COAT	16,782.000	GAL
411	4510 (PL)ASPHALT CONCRETE (3")	38.000	SY
411(S4)	5955 (SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	16,070.000	TON
411(S4)	5960 (SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	10,514.000	TON
504(F)	1381 CONCRETE PARAPET	302.000	LF
505	6139 (PL)MEMBRANE	470.000	SY
505(B)	6019 CLASS B BRIDGE DECK REPAIR	25.000	SY
855(A)	8812 TRAFFIC STRIPE(PLASTIC)(4" WIDE)	156,288.000	LF
880(J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
884(B)	8421 (PL)CONC.BRIDGE PARAPET RETROFIT	300.000	LF
884(C)	8427 REMOVE BRIDGE RAIL & POSTS(STEEL)	300.000	LF
SECTION NO. 0002	Y000-TRAFFIC-CMAY-141B(115)3R		
619(B)	4780 REMOVAL OF GUARD RAIL	212.000	LF
623(A)	0932 BEAM GUARD RAIL-W-BEAM-SINGLE	2,110.000	LF
623(F)	5686 GUARD RAIL ANCHOR UNIT (TYPE D-BF)	12.000	EA
623(H)	8571 (SP)G.E.T. GUARD RAIL END SECTION	12.000	EA
853	9066 GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	56.000	EA

CALL ORDER : 370  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : LINCOLN

CONTRACT ID : 030352  
 PCN : 2069204  
 PROJECTS : STPY-141B(116) 3R  
 DBE GOALS : 8.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 CALENDAR DAYS : 60  
 RES. ENG. :  
 LIQ. DAM.: \$ 600

CONTRACT DESCRIPTION:

RESURFACE US-177: FROM 8.0 MILES NORTH OF POTTAWATOMIE C/L,  
 EXTEND NORTH. PROJECT LENGTH = 7.24 MILES FLEXIBLE ESALS =  
 < 1 MILLION ASPHALT GRADE = PG 64-22 OK, PG 70-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY-STPY-141B(116)3R		
402	5205 (PL)ARMOR COAT	91,746.000	SY
407	0250 TACK COAT	18,689.000	GAL
411(S4)	5955 (SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	14,572.000	TON
411(S4)	5960 (SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	9,514.000	TON
855(A)	3250 TRAFFIC STRIPE(PLASTIC)(4" WIDE)(YELLOW)	141,441.000	LF
880(J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0002	GUARDRAIL-STPY-141B(116)3R		
619(B)	4780 REMOVAL OF GUARD RAIL	2,537.500	LF
623(A)	0932 BEAM GUARD RAIL-W-BEAM-SINGLE	3,262.500	LF
623(F)	4447 GUARD RAIL ANCHOR UNIT (TYPE B)	4.000	EA
623(F)	5686 GUARD RAIL ANCHOR UNIT (TYPE D-BF)	4.000	EA
623(H)	8571 (SP)G.E.T. GUARD RAIL END SECTION	8.000	EA
853	9066 GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	68.000	EA

CALL ORDER : 380  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 030353  
 PCN : 2069104C  
 PROJECTS : CMAY-141B(115) 3R  
           STPY-141B(116) 3R  
 DBE GOALS : 6.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 CALENDAR DAYS : 120  
 RES. ENG.:  
 LIQ. DAM.: \$ 800

CONTRACT DESCRIPTION:

RESURFACE US-177: FROM POTTAWATOMIE COUNTY LINE, EXTEND  
 NORTH. PROJECT LENGTH = 15.24 MILES FLEXIBLE ESALS = < 1  
 MILLION ASPHALT GRADE = PG 64-22 OK, PG 70-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 I000-ROADWAY-CMAY-141B(115)3R			
402	5205 (PL)ARMOR COAT	70,400.000	SY
407	0250 TACK COAT	16,782.000	GAL
411	4510 (PL)ASPHALT CONCRETE (3")	38.000	SY
411(S4)	5955 (SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	16,070.000	TON
411(S4)	5960 (SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	10,514.000	TON
504(F)	1381 CONCRETE PARAPET	302.000	LF
505	6139 (PL)MEMBRANE	470.000	SY
505(B)	6019 CLASS B BRIDGE DECK REPAIR	25.000	SY
855(A)	8812 TRAFFIC STRIPE(PLASTIC)(4" WIDE)	156,288.000	LF
880(J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
884(B)	8421 (PL)CONC.BRIDGE PARAPET RETROFIT	300.000	LF
884(C)	8427 REMOVE BRIDGE RAIL & POSTS(STEEL)	300.000	LF
SECTION NO. 0002 Y000-TRAFFIC-CMAY-141B(115)3R			
619(B)	4780 REMOVAL OF GUARD RAIL	212.000	LF
623(A)	0932 BEAM GUARD RAIL-W-BEAM-SINGLE	2,110.000	LF
623(F)	5686 GUARD RAIL ANCHOR UNIT (TYPE D-BF)	12.000	EA
623(H)	8571 (SP)G.E.T. GUARD RAIL END SECTION	12.000	EA
853	9066 GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	56.000	EA
SECTION NO. 0003 I000-ROADWAY-STPY-141B(116)3R			
402	5205 (PL)ARMOR COAT	91,746.000	SY
407	0250 TACK COAT	18,689.000	GAL
411(S4)	5955 (SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	14,572.000	TON
411(S4)	5960 (SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	9,514.000	TON
855(A)	3250 TRAFFIC STRIPE(PLASTIC)(4" WIDE)(YELLOW)	141,441.000	LF
880(J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0004 GUARDRAIL-STPY-141B(116)3R			
619(B)	4780 REMOVAL OF GUARD RAIL	2,537.500	LF
623(A)	0932 BEAM GUARD RAIL-W-BEAM-SINGLE	3,262.500	LF
623(F)	4447 GUARD RAIL ANCHOR UNIT (TYPE B)	4.000	EA
623(F)	5686 GUARD RAIL ANCHOR UNIT (TYPE D-BF)	4.000	EA

CALL ORDER : 380  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 030353  
 PCN : 2069104C  
 PROJECTS : CMAY-141B(115) 3R  
           STPY-141B(116) 3R  
 DBE GOALS : 6.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 CALENDAR DAYS : 120  
 RES. ENG.:  
 LIQ. DAM.: \$ 800

COUNTIES : LINCOLN

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0004	GUARDRAIL-STPY-141B(116)3R		
623(H) 8571	(SP)G.E.T. GUARD RAIL END SECTION	8.000	EA
853 9066	GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	68.000	EA

CALL ORDER : 410  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : MCCURTAIN

CONTRACT ID : 030332  
 PCN : 2058704  
 PROJECTS : STP-145A(115)UR  
 DBE GOALS : 0.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 4.88  
 CALENDAR DAYS : 45  
 RES. ENG. :  
 LIQ. DAM. : \$ 500

CONTRACT DESCRIPTION:  
 INTERSECTION MODIFICATION AND TRAFFIC SIGNALS WASHINGTON  
 STREET; AT WAL-MART DRIVE IN IDABEL. PROJECT LENGTH = 0.121  
 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
-----			
SECTION NO. 0001	J000-ROADWAY		
202(A) 0183	UNCLASSIFIED EXCAVATION	157.000	CY
310(B) 0149	SUBGRADE, METHOD B	1,321.000	SY
414(B) 0290	8" H.E.S. CONCRETE PAVEMENT	882.000	SY
609(A) 0300	CONC.CURB(6" BARRIER-INTEGRAL)	879.000	LF
610(A) 0602	4" CONCRETE SIDEWALK	13.000	SY
610(B) 0399	6" CONCRETE DRIVEWAY (H.E.S.)	245.000	SY
619(B) 4726	REMOVAL OF CURB AND GUTTER	875.000	LF
619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	441.000	SY
619(B) 4766	REMOVAL OF CONCRETE DRIVEWAY	250.000	SY
619(C) 0924	SAWING PAVEMENT	1,112.000	LF
SECTION NO. 0002	Y031-TRAFFIC ITEMS		
641 1552	MOBILIZATION	1.000	LSUM
802(B) 8332	1" PVC SCH.40 PLASTIC CONDUIT BORED	190.000	LF
802(B) 8336	1 1/2" PVC SCH.40 PLASTIC CONDUIT BORED	125.000	LF
802(B) 8338	1 1/2" PVC SCH.40 PLASTIC CONDUIT TRENCH	485.000	LF
802(B) 8342	2" PVC SCH.40 PLASTIC CONDUIT TRENCH	95.000	LF
802(B) 8344	3" PVC SCH.40 PLASTIC CONDUIT BORED	265.000	LF
802(B) 8346	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	100.000	LF
803 8065	PULL BOX(SIZE I)	3.000	EA
803 8066	PULL BOX(SIZE II)	1.000	EA
803 8067	PULL BOX(SIZE III)	4.000	EA
804(A) 2915	STRUCTURAL CONCRETE	10.500	CY
804(B) 2916	REINFORCING STEEL	1,583.800	LB
806(A) 8311	32'MH POLE 35'TS & 10'LMA(G.STL.)	1.000	EA
806(A) 8312	32'MH POLE 40'TS & 10'LMA(G.STL.)	1.000	EA
806(A) 8351	32'MH POLE 25',TS & 10'LMA(G.STL.)	1.000	EA
806(A) 8352	32'MH POLE,20'TS & 10'LMA(G.STL.)	1.000	EA
809(A) 8090	(PL)ROADWAY LUMINAIRE	4.000	EA
810(A) 3118	SERVICE POLE	1.000	EA
811 8040	1/C NO.6 ELECT.COND.	200.000	LF
811 8044	1/C NO.10 ELECT.COND.	1,430.000	LF
825 8550	VEH.ACT.SOL.ST.TRAF.SIG.CON.ASM	1.000	EA
828(A) 8135	SOL.STE.DIGITAL IND.VEH.LP.DET.	9.000	EA
828(B) 8138	LOOP DETECTOR WIRE	3,680.000	LF
830 8000	PEDESTRIAN PUSH BUTTON	6.000	EA

CALL ORDER : 410  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : MCCURTAIN

CONTRACT ID : 030332  
 PCN : 2058704  
 PROJECTS : STP-145A(115)UR  
 DBE GOALS : 0.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 4.88  
 CALENDAR DAYS : 45  
 RES. ENG. :  
 LIQ. DAM.: \$ 500

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0002 Y031-TRAFFIC ITEMS			
831	8231 1WAY3SEC.ADJ.SIG.HD.S-6	7.000	EA
831	8286 1WAY5SEC.ADJ.SIG.HD.S-19	3.000	EA
831	8295 1WAY2SEC.ADJ.PED.SIG.HD.S-20	3.000	EA
833	3030 BACKPLATE	10.000	EA
834(A)	8207 5/C TRAF.SIG.EL.CABLE	1,085.000	LF
834(A)	8208 7/C TRAF.SIG.EL.CABLE	135.000	LF
834(A)	8209 9/C TRAF.SIG.EL.CABLE	345.000	LF
834(A)	8210 12/C TRAF.SIG.EL.CABLE	85.000	LF
834(A)	8211 15/C TRAF.SIG.EL.CABLE	255.000	LF
834(B)	8220 2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	1,875.000	LF
850(C)	8118 MAST ARM MOUNTED SIGNS(ALUM.)	66.000	SF
855(A)	8812 TRAFFIC STRIPE(PLASTIC)(4" WIDE)	5,285.000	LF
855(B)	8818 TRAFFIC STRIPE(PLASTIC)(ARROWS)	8.000	EA
855(B)	8821 TRAFFIC STRIPE(PLASTIC)(WORDS)	3.000	EA
859(A)	8006 PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	500.000	LF
880(J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAK-STAKING			
642	0098 STAKING	1.000	LSUM



CALL ORDER : 420  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : MCCURTAIN

CONTRACT ID : 030354  
 PCN : 2068904  
 PROJECTS : CMAY-145C(119) 3R  
 DBE GOALS : 3.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 CALENDAR DAYS : 20  
 RES. ENG. :  
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:  
 RESURFACE SH-98: BEG. AT JCT. SH-98 / US-70, EXT. NORTH TO  
 WRIGHT CITY. PROJECT LENGTH = 6.41 MILES FLEX ESALS = .3M  
 ASPHALT GRADE = TYPE S4 (PG-76-28)OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	L000 - ROADWAY		
403(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	1,000.000	TON
407 0250	TACK COAT	7,000.000	GAL
411(S4) 5950	(SP)ASPH.CONC.,TYPE S4(PG 76-28 OK)	20,200.000	TON
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	115,000.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

CALL ORDER : 430  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : MCINTOSH

CONTRACT ID : 030363  
 PCN : 1956304  
 PROJECTS : IMY-40-6(286)253  
 DBE GOALS : 3.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 92.12  
 CALENDAR DAYS : 300  
 RES. ENG. :  
 LIQ. DAM. : \$ 2000

CONTRACT DESCRIPTION:

RESURFACE(CONCRETE) I-40; FROM MILEPOST 254 TO MILEPOST 260.  
 PROJECT LENGTH = 6.417 MILES FLEXIBLE ESALS = 86.7 MILLION  
 ASPHALT GRADE = PG 76-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	J000-ROADWAY		
202(A) 0183	UNCLASSIFIED EXCAVATION	44,801.000	CY
202(C) 0184	UNCLASSIFIED BORROW	56,607.000	CY
209 0120	MACHINE GRADING	89.920	STA
223 2801	TEMPORARY SILT FENCE	10,977.000	LF
226 2805	TEMPORARY SEDIMENT REMOVAL	100.000	CY
227 0100	TEMPORARY SILT DIKE	1,000.000	LF
230(A) 2806	SOLID SLAB SODDING	66,070.000	SY
233(A) 2817	VEGETATIVE MULCHING	12.470	AC
241 2832	MOWING	13.650	AC
407 0250	TACK COAT	20,054.000	GAL
408 5774	PRIME COAT	3,110.000	GAL
411(S2) 5920	(SP)ASPH.CONC.,TYPE S2(PG 76-28 OK)	4,985.000	TON
411(S3) 5935	(SP)ASPH.CONC.,TYPE S3(PG 76-28 OK)	3,689.000	TON
411(S4) 5950	(SP)ASPH.CONC.,TYPE S4(PG 76-28 OK)	3,016.000	TON
411(S6) 5980	(SP)ASPH.CONC.,TYPE S6(PG 76-28 OK)	8,508.000	TON
413(D) 4868	(SP)RUMBLE STRIP-METHOD PCC-CON	133,132.000	LF
414(A1) 6855	10.5" P.C. DOWEL JOINTED CONCRETE PAVE.	19,212.000	SY
414(L) 5600	(SP)P.C.C. FOR PAVE. OVERLAY-WHITETOPPIN	85,150.000	CY
414(M) 5700	(SP)P.C.C.PAVE.,O/L-WHTTPNG.,PLACE ONLY	281,057.000	SY
417 5267	COLD MILLING PAVEMENT	117,390.000	SY
509(D) 0325	CLASS C CONCRETE	5.000	CY
613(D) 0689	18" CORR. GALV. STEEL PIPE	2,360.000	LF
613(D) 0690	24" CORR. GALV. STEEL PIPE	410.000	LF
619(A) 0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	14,119.000	SY
619(B) 4780	REMOVAL OF GUARD RAIL	1,900.000	LF
619(B) 4791	REMOVAL OF CURB	3,900.000	LF
619(C) 0924	SAWING PAVEMENT	4,663.000	LF
623(A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	5,600.000	LF
623(E) 7114	THRIE BEAM BRIDGE CONNECTION-TYPE A	11.000	EA
623(F) 4447	GUARD RAIL ANCHOR UNIT (TYPE B)	9.000	EA
623(H) 8571	(SP)G.E.T. GUARD RAIL END SECTION	20.000	EA
641 1552	MOBILIZATION	1.000	LSUM
643 0087	(SP)CONTRACTORS QUALITY CONTROL	1.000	LSUM
SECTION NO. 0002	X020-BRIDGE 'A'		

CALL ORDER : 430  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : MCINTOSH

CONTRACT ID : 030363  
 PCN : 1956304  
 PROJECTS : IMY-40-6(286)253  
 DBE GOALS : 3.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 92.12  
 CALENDAR DAYS : 300  
 RES. ENG. :  
 LIQ. DAM. : \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
-----			
SECTION NO. 0002	X020-BRIDGE 'A'		
504(F) 1381	CONCRETE PARAPET	204.800	LF
504(H) 6390	RAPID CURE JOINT SEALANT	80.000	LF
505(B) 6019	CLASS B BRIDGE DECK REPAIR	15.000	SY
505(D) 6071	HIGH DENSITY BRIDGE DECK OVERLAY	598.000	SY
619(B) 4727	REMOVAL OF CONCRETE PAVEMENT	598.000	SY
619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	456.000	SY
SECTION NO. 0003 X020-BRIDGE 'B'			
504(F) 1381	CONCRETE PARAPET	204.800	LF
504(H) 6390	RAPID CURE JOINT SEALANT	80.000	LF
505(B) 6019	CLASS B BRIDGE DECK REPAIR	15.000	SY
505(D) 6071	HIGH DENSITY BRIDGE DECK OVERLAY	598.000	SY
619(B) 4727	REMOVAL OF CONCRETE PAVEMENT	598.000	SY
619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	456.000	SY
SECTION NO. 0004 X020-BRIDGE 'C'			
504(F) 1381	CONCRETE PARAPET	220.600	LF
504(H) 6390	RAPID CURE JOINT SEALANT	81.000	LF
505(B) 6019	CLASS B BRIDGE DECK REPAIR	15.000	SY
505(D) 6071	HIGH DENSITY BRIDGE DECK OVERLAY	632.000	SY
619(B) 4727	REMOVAL OF CONCRETE PAVEMENT	632.000	SY
619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	466.000	SY
SECTION NO. 0005 X020-BRIDGE 'D'			
504(F) 1381	CONCRETE PARAPET	220.600	LF
504(H) 6390	RAPID CURE JOINT SEALANT	81.000	LF
505(B) 6019	CLASS B BRIDGE DECK REPAIR	15.000	SY
505(D) 6071	HIGH DENSITY BRIDGE DECK OVERLAY	632.000	SY
619(B) 4727	REMOVAL OF CONCRETE PAVEMENT	632.000	SY
619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	466.000	SY
SECTION NO. 0006 Y008-TRAFFIC CONTROL			
627(G) 4316	RELOC.PORT.TYPE PRECAST CONC.MEDIAN BARR	41,800.000	LF
627(H) 5856	DEL.PORT.TYPE PREC. CONCRETE MEDIAN BARR	83,600.000	LF
856(A) 8839	CONSTRUCTION TRAFF.STR.(PAINT)(4" WIDE)	390,400.000	LF
856(C) 8851	REMOVABLE PAVEMENT MARKING TAPE(4" WIDE)	2,000.000	LF
856(G) 8887	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-1	3,000.000	EA
859(A) 8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	169,000.000	LF
878(C) 8487	MODULAR GLARE SCREEN	79,092.000	SD

CALL ORDER : 430  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : MCINTOSH

CONTRACT ID : 030363  
 PCN : 1956304  
 PROJECTS : IMY-40-6(286)253  
 DBE GOALS : 3.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 92.12  
 CALENDAR DAYS : 300  
 RES. ENG. :  
 LIQ. DAM. : \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0006	Y008-TRAFFIC CONTROL		
880(A) 8812	ARROW DISPLAY(TYPE C)	676.000	SD
880(B) 8818	CONSTRUCTION SIGNS 0 TO 6.25 SF	9,126.000	SD
880(B) 8821	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	8,788.000	SD
880(B) 8824	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	10,478.000	SD
880(B) 8827	CONSTRUCTION SIGNS 33.0 SF & OVER	2,028.000	SD
880(C) 8842	BARRICADES(TYPE III)	12,844.000	SD
880(C) 8848	WING BARRICADES	2,704.000	SD
880(D) 8854	VERTICAL PANELS	35,940.000	SD
880(E) 8860	WARNING LIGHTS(TYPE A)	36,166.000	SD
880(E) 8872	WARNING LIGHTS(TYPE C)	59,488.000	SD
880(F) 8878	DRUMS	23,998.000	SD
880(L) 8911	TRAFFIC SURVEILLANCE, POLICE	150.000	HOURL
882(B) 8306	PORT.CHANGEABLE MESSAGE SIGN	676.000	SD
SECTION NO. 0007	Y002-TRAFFIC SIGNING & STRIPING		
804(A) 2915	STRUCTURAL CONCRETE	7.280	CY
804(B) 2916	REINFORCING STEEL	1,672.000	LB
850(B) 8112	EXTRUDED ALUMINUM PANEL SIGNS	1,227.250	SF
851(A) 3206	4"@13 GALV.STL.WD.FLANGE BM.POST	374.350	LF
851(A) 3207	6"@15 GALV.STL.WD.FLANGE BM.POST	281.700	LF
851(A) 3210	8"@31 GALV.STL.WD.FLANGE BM.POST	152.190	LF
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	221,357.000	LF
857(A) 8947	PAVE.MARKERS CLASS C TYPE 2-C	864.000	EA
890(A) 8720	(PL)REMOVAL OF GROUND MOUNTED SIGNS	1.000	LSUM
890(A) 8722	(PL)REMOVAL OF EXISTING SIGNS	1.000	LSUM
890A/B 8756	(PL)REMOVE & RESET EXISTING SIGNS	42.000	EA
890A/B 8760	(PL)REMOVE & RESET GROUND MOUNTED SIGN	15.000	EA
SECTION NO. 0008	STAK-STAKING		
642 0098	STAKING	1.000	LSUM

CALL ORDER : 440  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : MAJOR

CONTRACT ID : 030369  
 PCN : 1735804  
 PROJECTS : NHY-019N(78)  
 DBE GOALS : 6.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 26.55  
 CALENDAR DAYS : 180  
 RES. ENG. :  
 LIQ. DAM. : \$ 1000

CONTRACT DESCRIPTION:

GRADE, DRAIN & SURFACE US-412: INTERSECTION OF US-281.  
 PROJECT LENGTH = 0.825 MILES FLEXIBLE ESALS = 5.24 MILLION  
 ASPHALT GRADE = PG 64-22 OK & PG 76-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY		
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(A)	0183 UNCLASSIFIED EXCAVATION	173,643.000	CY
202(C)	0184 UNCLASSIFIED BORROW	46,993.000	CY
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
222	2801 TEMPORARY BALE BARRIER	4,920.000	LF
222	2810 REMOVE & RESET TEMPORARY BALE BARRIERS	4,920.000	LF
223	2801 TEMPORARY SILT FENCE	2,590.000	LF
224	2803 TEMPORARY SEDIMENT FILTER	3.000	EA
226	2805 TEMPORARY SEDIMENT REMOVAL	117.000	CY
230(A)	2806 SOLID SLAB SODDING	30,334.000	SY
230(F)	2812 WATERING	8,070.000	MGAL
232(B)	2814 SEEDING METHOD B	12.460	AC
233(A)	2817 VEGETATIVE MULCHING	1.900	AC
233(C)	2819 ASPHALT MULCHING	8,070.000	GAL
234(A)	2824 FERTILIZING (10-20-10)	5.080	TON
234(A)	4406 FERTILIZING (0-46-0)	1.170	TON
241	2832 MOWING	67.530	AC
326(B)	4210 (SP)LIME	898.000	TON
326(F)	4250 (SP)LIME STABILIZED SUBGRADE	44,339.000	SY
403(A)	0217 TRAFFIC BOUND SURFACE COURSE TYPE A	56.000	TON
407	0250 TACK COAT	6,272.000	GAL
408	5774 PRIME COAT	6,651.000	GAL
411(S2)	5930 (SP)ASPH.CONC.,TYPE S2(PG 64-22 OK)	11,110.000	TON
411(S3)	5935 (SP)ASPH.CONC.,TYPE S3(PG 76-28 OK)	5,208.000	TON
411(S3)	5945 (SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	2,607.000	TON
411(S4)	5950 (SP)ASPH.CONC.,TYPE S4(PG 76-28 OK)	3,449.000	TON
411(S4)	5960 (SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	1,420.000	TON
417	5267 COLD MILLING PAVEMENT	1,083.000	SY
509(C)	0322 CLASS A CONCRETE FOR SMALL STRUCTURES	4.950	CY
509(D)	0325 CLASS C CONCRETE	10.000	CY
511(A)	0332 REINFORCING STEEL	650.000	LB
611(E)	6002 INLET (SMD-TYPE 2)	2.000	EA
613(B)	0492 24" R.C.PIPE CLASS III	1,056.000	LF
613(B)	0493 30" R.C.PIPE CLASS III	160.000	LF
613(D)	0689 18" CORR. GALV. STEEL PIPE	40.000	LF
613(M)	5726 18" PREFAB. CULVERT END SEC., ROUND	2.000	EA
613(M)	5730 24" PREFAB. CULVERT END SEC., ROUND	7.000	EA

CALL ORDER : 440  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : MAJOR

CONTRACT ID : 030369  
 PCN : 1735804  
 PROJECTS : NHY-019N(78)  
 DBE GOALS : 6.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 26.55  
 CALENDAR DAYS : 180  
 RES. ENG. :  
 LIQ. DAM. : \$ 1000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 I000-ROADWAY			
613(M) 5732	30" PREFAB. CULVERT END SEC., ROUND	1.000	EA
613(S) 1180	TRENCH EXCAVATION	849.000	CY
613(T) 1181	STANDARD BEDDING MATERIAL	495.000	CY
619(A) 0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619(B) 0291	REMOVAL OF HEADWALL	3.000	EA
619(B) 4725	REMOVAL OF FENCE	7,253.000	LF
619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	15,211.000	SY
619(B) 5918	REMOVAL OF EXISTING PIPE	165.000	LF
619(C) 0924	SAWING PAVEMENT	698.000	LF
624(B) 4466	GATES-STYLE WWF (4.5'HIGH X 16'LONG)	3.000	EA
624(C) 4459	(SP)FENCE-STYLE SWF (5 BARBED WIRE)	5,570.000	LF
640 1426	FIELD OFFICE	1.000	EA
641 1552	MOBILIZATION	1.000	LSUM
643 0087	(SP)CONTRACTORS QUALITY CONTROL	1.000	LSUM
653(A) 5915	EDGE DRAIN CONDUIT-PERFORATED	1,000.000	LF
653(B) 5916	EDGE DRAIN OUTLET LATERAL-NONPERFORATED	10.000	LF
653(C) 5946	OUTLET LATERAL HEADWALL	1.000	EA
SECTION NO. 0002 Y008-TRAFFIC			
802(A) 8314	2" GALV.STEEL ELECT.COND. TRENCHED	500.000	LF
802(B) 8342	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	1,400.000	LF
803 8066	PULL BOX(SIZE II)	4.000	EA
804(A) 2915	STRUCTURAL CONCRETE	13.200	CY
804(B) 2916	REINFORCING STEEL	564.500	LB
806(C) 8968	50' MTG & 15' HLMA(G.STL.)	10.000	EA
807 8093	BREAKAWAY BASE (DES. C)	10.000	EA
809(A) 8090	(PL)ROADWAY LUMINAIRE	10.000	EA
810(A) 3118	SERVICE POLE	1.000	EA
811 8046	1/C NO.12 ELECT.COND.	1,900.000	LF
850(A) 8110	SHEET ALUMINUM SIGNS	411.000	SF
851(C) 8324	2" SQUARE TUBE POST	171.000	LF
851(C) 8327	2 1/4" SQUARE TUBE POST	602.000	LF
853 9024	DELINEATORS(TYPE 1, CODE 1)	60.000	EA
853 9027	DELINEATORS(TYPE 1, CODE 2)	2.000	EA
853 9036	DELINEATORS(TYPE 2, CODE 2)	6.000	EA
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	26,653.000	LF
855(B) 8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	4.000	EA
855(B) 8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	2.000	EA
856(A) 8839	CONSTRUCTION TRAFF.STR.(PAINT)(4" WIDE)	65,456.000	LF
859(A) 8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	26,200.000	LF
880(A) 8800	ARROW DISPLAY(TYPE A)	180.000	SD
880(B) 8818	CONSTRUCTION SIGNS 0 TO 6.25 SF	2,430.000	SD

CALL ORDER : 440  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : MAJOR

CONTRACT ID : 030369  
 PCN : 1735804  
 PROJECTS : NHY-019N(78)  
 DBE GOALS : 6.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 26.55  
 CALENDAR DAYS : 180  
 RES. ENG. :  
 LIQ. DAM.: \$ 1000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0002 Y008-TRAFFIC			
880(B) 8821	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	3,240.000	SD
880(B) 8824	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	4,095.000	SD
880(C) 8842	BARRICADES(TYPE III)	2,205.000	SD
880(C) 8848	WING BARRICADES	900.000	SD
880(E) 8860	WARNING LIGHTS(TYPE A)	11,970.000	SD
880(E) 8872	WARNING LIGHTS(TYPE C)	19,980.000	SD
880(F) 8878	DRUMS	19,980.000	SD
890(A) 8724	(PL)REMOVAL OF EXISTING SIGNS	48.000	EA
SECTION NO. 0003 STAK-STAKING			
642 0098	STAKING	1.000	LSUM

CALL ORDER : 450  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : MAYES

CONTRACT ID : 030366  
 PCN : 1872804  
 PROJECTS : STP-149C(44) CO  
 DBE GOALS : 10.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 19.51  
 CALENDAR DAYS : 200  
 RES. ENG.:  
 LIQ. DAM.: \$ 1000

CONTRACT DESCRIPTION:

GRADE, DRAIN AND SURFACE COUNTY ROAD; BEG. 0.4 MI. N. & 0.1 MI. W. OF LOCUST GROVE, EXT. W. 3.0 MI. ON EW-56 THEN N. 2.2 MI. ON NS-437. PROJECT LENGTH = 4.416 MILES FLEXIBLE ESALS = 9.1 MILLION ASPHALT GRADE = PG 70-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY		
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(A)	0183 UNCLASSIFIED EXCAVATION	60,123.000	CY
202(B)	0182 ROCK EXCAVATION	11,355.000	CY
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
210	0121 OBLITERATING ABANDONED ROAD	9.000	STA
223	2801 TEMPORARY SILT FENCE	4,664.000	LF
230(A)	2806 SOLID SLAB SODDING	80,851.000	SY
232(A)	2813 SEEDING METHOD A	10.000	AC
303	0192 AGGREGATE BASE	30,334.000	CY
407	0250 TACK COAT	21,504.000	GAL
408	5774 PRIME COAT	42,367.000	GAL
411(S3)	5940 (SP)ASPH.CONC.,TYPE S3(PG 70-28 OK)	11,625.000	TON
411(S4)	5955 (SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	8,305.000	TON
501(A)	0313 STRUCTURAL EXCAVATION UNCLASSIFIED	114.000	CY
508	7100 (PL)PRECAST RCB	195.000	LF
509(C)	0322 CLASS A CONCRETE FOR SMALL STRUCTURES	58.000	CY
509(D)	0325 CLASS C CONCRETE	50.000	CY
511(A)	0332 REINFORCING STEEL	4,446.000	LB
613(B)	0491 18" R.C.PIPE CLASS III	139.000	LF
613(B)	0492 24" R.C.PIPE CLASS III	48.000	LF
613(B)	0585 36" R.C.PIPE CLASS IV	209.000	LF
613(B)	0589 60" R.C.PIPE CLASS IV	57.000	LF
613(B)	4515 51" X 31" R.C.PIPE ARCH CLASS A-IV	49.000	LF
613(D)	0689 18" CORR. GALV. STEEL PIPE	2,379.000	LF
613(D)	0690 24" CORR. GALV. STEEL PIPE	241.000	LF
613(M)	4540 51" X 31" PREFAB. CULVERT END SEC., ARCH	2.000	EA
613(M)	5726 18" PREFAB. CULVERT END SEC., ROUND	156.000	EA
613(M)	5730 24" PREFAB. CULVERT END SEC., ROUND	24.000	EA
613(M)	5734 36" PREFAB. CULVERT END SEC., ROUND	5.000	EA
613(S)	1180 TRENCH EXCAVATION	325.000	CY
613(T)	1181 STANDARD BEDDING MATERIAL	280.000	CY
619(A)	0920 REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619(C)	0924 SAWING PAVEMENT	180.000	LF
629(A)	4958 MAILBOX INSTALLATION-SINGLE	17.000	EA
629(B)	4959 MAILBOX INSTALLATION-MULTIPLE	9.000	EA
629(C)	4960 MAILBOX	40.000	EA



CALL ORDER : 450  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : MAYES

CONTRACT ID : 030366  
 PCN : 1872804  
 PROJECTS : STP-149C(44) CO  
 DBE GOALS : 10.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 19.51  
 CALENDAR DAYS : 200  
 RES. ENG. :  
 LIQ. DAM.: \$ 1000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 I000-ROADWAY			
640 1426	FIELD OFFICE	1.000	EA
641 1552	MOBILIZATION	1.000	LSUM
850(A) 8218	SHEET ALUMINUM SIGNS (0.100" THICK)	249.000	SF
851(C) 8327	2 1/4" SQUARE TUBE POST	456.000	LF
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	98,873.000	LF
855(B) 8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	3.000	EA
855(B) 8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	2.000	EA
880(B) 8818	CONSTRUCTION SIGNS 0 TO 6.25 SF	16,800.000	SD
880(B) 8821	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	9,840.000	SD
880(B) 8824	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	8,520.000	SD
880(C) 8842	BARRICADES(TYPE III)	7,200.000	SD
880(E) 8860	WARNING LIGHTS(TYPE A)	58,200.000	SD
880(E) 8872	WARNING LIGHTS(TYPE C)	58,200.000	SD
880(F) 8878	DRUMS	15,840.000	SD
SECTION NO. 0002 STAK-STAKING			
642 0098	STAKING	1.000	LSUM

CALL ORDER : 460  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : MURRAY

CONTRACT ID : 030325  
 PCN : 1770604  
 PROJECTS : STPY-21N(17)TR  
 DBE GOALS : 0.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 4.88  
 CALENDAR DAYS : 45  
 RES. ENG. :  
 LIQ. DAM. : \$ 500

## CONTRACT DESCRIPTION:

TRAFFIC SIGNALS SH-7; AT THE INTERSECTION OF SH-7/W. 9TH  
 STREET IN SULPHUR. PROJECT LENGTH = 0.00 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	Y031-SIGNALS		
414(A) M0260	200MM P.C. CONCRETE PAVEMENT	15.000	M2
609(B) M0395	800MM COMB.CRB.& GUT.(150MM BAR.-NOTCH)	218.000	M
610(A) M0602	100MM CONCRETE SIDEWALK	475.000	M2
610(B) M0604	150MM CONCRETE DRIVEWAY	194.000	M2
619(B) M4726	REMOVAL OF CURB AND GUTTER	180.000	M
619(B) M4727	REMOVAL OF CONCRETE PAVEMENT	292.000	M2
619(B) M4728	REMOVAL OF ASPHALT PAVEMENT	280.000	M2
619(C) M0924	SAWING PAVEMENT	343.000	M
641 M1552	MOBILIZATION	1.000	LSUM
802(B) M8332	25MM PVC SCH.40 P.C.BORED	48.000	M
802(B) M8336	38MM PVC SCH.40 P.C.BORED	15.000	M
802(B) M8338	38MM PVC SCH.40 P.C.TR.	100.000	M
802(B) M8342	50MM PVC SCH.40 P.C.TR.	20.000	M
802(B) M8344	75MM PVC SCH.40 P.C.BORED	66.000	M
802(B) M8346	75MM PVC SCH.40 P.C.TR.	15.000	M
803 M8065	PULL BOX(SIZE I)	3.000	EA
803 M8066	PULL BOX(SIZE II)	2.000	EA
803 M8067	PULL BOX(SIZE III)	3.000	EA
804(A) M2915	STRUCTURAL CONCRETE	8.100	M3
804(B) M2916	REINFORCING STEEL	727.800	KG
806(A) M8724	POLE & 6.1M TS MST.ARM(G.STL.)	1.000	EA
806(A) M8726	POLE & 7.6M TS MST.ARM(G.STL.)	1.000	EA
806(A) M8732	POLE & 12.2M TS MST.ARM(G.STL.)	2.000	EA
811 M8040	1/C NO.6 ELECT.COND.	25.000	M
825 M8550	VEH.ACT.SOL.ST.TRAF.SIG.CON.ASM	1.000	EA
828(A) M8135	SOL.STE.DIGITAL IND.VEH.LP.DET.	8.000	EA
828(B) M8138	LOOP DETECTOR WIRE	1,025.000	M
830 M8000	PEDESTRIAN PUSH BUTTON	8.000	EA
831 M8231	1WAY3SEC.ADJ.SIG.HD.S-6	8.000	EA
831 M8252	1WAY3SEC.ADJ.SIG.HD.S-9	2.000	EA
831 M8295	1WAY2SEC.ADJ.SIG.HD.S-20	8.000	EA
833 M3030	BACKPLATE	10.000	EA
834(A) M8207	5/C TRAF.SIG.EL.CABLE	402.000	M
834(A) M8209	9/C TRAF.SIG.EL.CABLE	74.000	M
834(A) M8210	12/C TRAF.SIG.EL.CABLE	85.000	M
834(B) M8220	2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	340.000	M
850(A) M8110	SHEET ALUMINUM SIGNS	5.310	M2
850(C) M8118	MAST ARM MOUNTED SIGNS(ALUM.)	6.470	M2

CALL ORDER : 460  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : MURRAY

CONTRACT ID : 030325  
 PCN : 1770604  
 PROJECTS : STPY-21N(17)TR  
 DBE GOALS : 0.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 4.88  
 CALENDAR DAYS : 45  
 RES. ENG. :  
 LIQ. DAM.: \$ 500

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
-----			
SECTION NO. 0001	Y031-SIGNALS		
851(C) M8327	57MM SQUARE TUBE POST	34.900	M
855(A) M8812	TRAFFIC STRIPE(PLASTIC)(100MM WIDE)	2,500.000	M
855(B) M8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	9.000	EA
855(B) M8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	5.000	EA
859(A) M8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	150.000	M
880(J) M8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
890(A) M8724	(PL)REMOVAL OF EXISTING SIGNS	1.000	EA
SECTION NO. 0002	STAK-STAKING		
642 M0098	STAKING	1.000	LSUM

CALL ORDER : 470  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : NOBLE

CONTRACT ID : 030321  
 PCN : 0947804  
 PROJECTS : BRFY-52C(159)  
 DBE GOALS : 6.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 28.18  
 CALENDAR DAYS : 200  
 RES. ENG. :  
 LIQ. DAM. : \$ 800

CONTRACT DESCRIPTION:

BRIDGE AND APPROACHES SH-164; AT WARREN CREEK, 0.1 MILE  
 EAST OF GARFIELD COUNTY LINE. PROJECT LENGTH = 0.480 KM.  
 FLEXIBLE ESALS = 0.91 MILLION ASPHALT GRADE = PG 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY		
201	M0102 CLEARING AND GRUBBING	1.000	LSUM
202(A)	M0183 UNCLASSIFIED EXCAVATION	14,600.000	M3
202(C)	M0184 UNCLASSIFIED BORROW	13,096.000	M3
205	M4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
222	M2801 TEMPORARY BALE BARRIER	50.000	M
223	M2802 TEMPORARY SILT FENCE	327.000	M
226	M2805 TEMPORARY SEDIMENT REMOVAL	30.000	M3
227	M0100 TEMPORARY SILT DIKE	60.000	M
229	M4318 DITCH LINER PROTECTION	30.000	M
230(A)	M2806 SOLID SLAB SODDING	21,000.000	M2
232(B)	M2814 SEEDING METHOD B	2.100	HA
233(A)	M2817 VEGETATIVE MULCHING	2.100	HA
241	M2832 MOWING	2.100	HA
326(A)	M4200 (SP)FLY ASH	340.000	T
326(E)	M4240 (SP)CEMENTITIOUS STABILIZED SUBGRADE	5,888.000	M2
403(A)	M0217 TRAFFIC BOUND SURFACE COURSE TYPE A	400.000	T
407	M0250 TACK COAT	5,381.000	L
408	M5774 PRIME COAT	11,450.000	L
411(S2)	M5930 (SP)ASPH.CONC.,TYPE S2(PG 64-22 OK)	1,427.000	T
411(S3)	M5945 (SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	2,492.000	T
411(S4)	M5960 (SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	1,377.000	T
509(D)	M0325 CLASS C CONCRETE	34.000	M3
613(B)	M0409 600MM R.C.PIPE CLASS III	30.480	M
613(CC)	M7187 TYPE B4 CULVERT END TREATMENT	2.000	EA
613(CC)	M7196 TYPE A6 CULVERT END TREATMENT	12.000	EA
613(D)	M0689 450MM CORR. GALV. STEEL PIPE	242.612	M
613(D)	M5739 2100MM CORR. GALV. STEEL PIPE	193.851	M
613(P)	M1092 200MM PERFORATED PIPE UNDERDRAIN ROUND	360.000	M
613(Q)	M1097 200MM NON-PERF.PIPE UNDERDRAIN RND.	120.000	M
613(R)	M1100 PIPE UNDERDRAIN COVER MAT'L.	105.000	M3
613(S)	M1180 TRENCH EXCAVATION	281.000	M3
613(T)	M1181 STANDARD BEDDING MATERIAL	29.000	M3
619(A)	M0920 REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619(B)	M4728 REMOVAL OF ASPHALT PAVEMENT	5,590.000	M2
619(B)	M4763 REMOVAL OF CONC.PAV.W/ASPH.OVERLAY	1,512.000	M2
619(B)	M4780 REMOVAL OF GUARD RAIL	187.000	M
623(A)	M0932 BEAM GUARD RAIL-W-BEAM-SINGLE	255.270	M

CALL ORDER : 470  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : NOBLE

CONTRACT ID : 030321  
 PCN : 0947804  
 PROJECTS : BRFY-52C(159)  
 DBE GOALS : 6.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 28.18  
 CALENDAR DAYS : 200  
 RES. ENG. :  
 LIQ. DAM. : \$ 800

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY		
623(E) M7114	THRIE BEAM BRIDGE CONNECTION-TYPE A	4.000	EA
623(H) M8571	(SP)G.E.T. GUARD RAIL END SECTION	2.000	EA
624(C) M4459	(SP)FENCE-STYLE SWF (5 BARBED WIRE)	421.000	M
629(A) M4958	MAILBOX INSTALLATION-SINGLE	3.000	EA
629(C) M4960	MAILBOX	3.000	EA
629(D) M4961	REMOVAL OF MAILBOX INSTALLATION	3.000	EA
SECTION NO. 0002	X081-BRIDGE 'A'		
202(A) M1301	UNCLASSIFIED EXCAVATION	490.000	M3
501(B) M1307	SUBSTRUCTURE EXCAVATION COMMON	70.000	M3
501(F) M6352	GRANULAR BACKFILL	74.000	M3
503(A) M1311	PRESTRESSED CONCRETE BEAMS (TYPE II)	55.600	M
503(A) M1312	PRESTRESSED CONCRETE BEAMS (TYPE III)	143.200	M
504(A) M1304	APPROACH SLAB	152.000	M2
504(E) M6239	CONCRETE RAIL (TR3)	124.400	M
506(A) M1322	STRUCTURAL STEEL	485.000	KG
509(A) M1326	CLASS AA CONCRETE	164.000	M3
509(B) M1328	CLASS A CONCRETE	71.500	M3
509(D) M1331	CLASS C CONCRETE	16.000	M3
511(A) M1332	REINFORCING STEEL	2,460.000	KG
511(B) M6010	EPOXY COATED REINFORCING STEEL	23,335.000	KG
514(A) M6011	PILES, FURNISHED (HP 250X62)	130.000	M
514(B) M6292	PILES, DRIVEN (HP 250X62)	130.000	M
514(F) M6354	PILE LOAD TEST (DYNAMIC)	12.000	EA
515(A) M6013	WATER REPELLENT (VISUALLY INSPECTED)	476.000	M2
516(A) M6094	DRILLED SHAFTS 1200MM DIAMETER	46.000	M
535 M6164	(PL)FIXED BEARING ASSEMBLY	8.000	EA
535 M6165	(PL)EXPANSION BEARING ASSEMBLY	16.000	EA
535 M6282	(PL)ELASTOMERIC BEARING PADS	16.000	EA
601A-1 M1353	TYPE I-A PLAIN RIPRAP	1,260.000	T
601A-2 M1355	TYPE I-A FILTER BLANKET	190.000	T
609(D) M0398	BITUMINOUS CURBING	388.620	M
613(P) M6204	150MM PERFORATED PIPE UNDERDRAIN ROUND	25.600	M
613(Q) M6207	150MM NON-PERF.PIPE UNDERDRAIN RND.	10.200	M
619(D) M1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
641 M1399	MOBILIZATION	1.000	LSUM
643 M0087	(SP)CONTRACTORS QUALITY CONTROL	1.000	LSUM
SECTION NO. 0003	Y008TRAFFIC CONTROL		
850(A) M8110	SHEET ALUMINUM SIGNS	2.120	M2
851(C) M8327	57MM SQUARE TUBE POST	16.760	M

CALL ORDER : 470  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : NOBLE

CONTRACT ID : 030321  
 PCN : 0947804  
 PROJECTS : BRFY-52C(159)  
 DBE GOALS : 6.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 28.18  
 CALENDAR DAYS : 200  
 RES. ENG. :  
 LIQ. DAM.: \$ 800

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003	Y008TRAFFIC CONTROL		
855(A) M8815	TRAF.STR.(PLAST.)(THIN-LINE)(100MM WIDE)	3,650.000	M
876(C) M8482	(PL)TRUCK MOUNTED ATTENUATOR	185.000	SD
880(J) M8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0004	STAK-STAKING		
642 M0098	STAKING	1.000	LSUM

CALL ORDER : 490  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : NOWATA

CONTRACT ID : 030329  
 PCN : 2015404  
 PROJECTS : BRF-153C(22) CO  
 DBE GOALS : 6.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 4.88  
 CALENDAR DAYS : 150  
 RES. ENG. :  
 LIQ. DAM. : \$ 500

## CONTRACT DESCRIPTION:

BRIDGE AND APPROACHES COUNTY ROAD; OVER CALIFORNIA CREEK, 0.  
 5 MILE NORTH AND 3.8 MILES WEST OF LENAPAH. PROJECT LENGTH  
 = 0.420 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	E000-ROADWAY BRF-153C(22)CO		
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(A)	0183 UNCLASSIFIED EXCAVATION	17,310.000	CY
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	600.000	LF
227	0100 TEMPORARY SILT DIKE	450.000	LF
230(A)	2806 SOLID SLAB SODDING	13,610.000	SY
233(A)	2817 VEGETATIVE MULCHING	5.600	AC
403(E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	2,343.000	TON
509(D)	0325 CLASS C CONCRETE	45.000	CY
613(D)	0689 18" CORR. GALV. STEEL PIPE	46.000	LF
613(D)	0692 36" CORR. GALV. STEEL PIPE	84.000	LF
613(D)	0696 60" CORR. GALV. STEEL PIPE	35.000	LF
613(M)	5726 18" PREFAB. CULVERT END SEC., ROUND	4.000	EA
613(M)	5734 36" PREFAB. CULVERT END SEC., ROUND	4.000	EA
SECTION NO. 0002	X081-BRIDGE 'A' BRF-153C(22)CO		
501(B)	1307 SUBSTRUCTURE EXCAVATION COMMON	96.000	CY
501(F)	6352 GRANULAR BACKFILL	114.000	CY
503(A)	1313 PRESTRESSED CONCRETE BEAMS (TYPE IV)	376.170	LF
504(E)	1380 CONCRETE RAIL (TR1)	263.180	LF
506(A)	1322 STRUCTURAL STEEL	2,020.000	LB
509(A)	1326 CLASS AA CONCRETE	73.600	CY
509(B)	1328 CLASS A CONCRETE	64.490	CY
511(A)	1332 REINFORCING STEEL	25,729.000	LB
514(A)	6010 PILES, FURNISHED (HP 10X42)	380.000	LF
514(B)	6292 PILES, DRIVEN (HP 10X42)	380.000	LF
601(A-1)	1353 TYPE I-A PLAIN RIPRAP	1,760.000	TON
601(A-2)	1355 TYPE I-A FILTER BLANKET	317.000	TON
613(P)	6204 6" PERFORATED PIPE UNDERDRAIN ROUND	60.000	LF
613(Q)	6207 6" NON-PERF. PIPE UNDERDRAIN RND.	50.000	LF
619(D)	M1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F)	6033 GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
640	1398 FIELD OFFICE	1.000	EA
641	1399 MOBILIZATION	1.000	LSUM
880(J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003	X028-BRIDGE 'B' BRF-153C(22)CO		

CALL ORDER : 490  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : NOWATA

CONTRACT ID : 030329  
 PCN : 2015404  
 PROJECTS : BRF-153C(22) CO  
 DBE GOALS : 6.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 4.88  
 CALENDAR DAYS : 150  
 RES. ENG. :  
 LIQ. DAM.: \$ 500

202(A)	1301	UNCLASSIFIED EXCAVATION	390.000	CY
501(A)	1306	STRUCTURAL EXCAVATION UNCLASSIFIED	100.000	CY
509(B)	1328	CLASS A CONCRETE	128.000	CY
511(A)	1332	REINFORCING STEEL	17,170.000	LB
SECTION NO. 0004 STAK-STAKING BRF-153C(22)CO				
642	0098	STAKING	1.000	LSUM



CALL ORDER : 500  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : WASHINGTON

CONTRACT ID : 030330  
 PCN : 1940104  
 PROJECTS : BRO-174D(20) CO  
 DBE GOALS : 0.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 4.88  
 CALENDAR DAYS : 130  
 RES. ENG. :  
 LIQ. DAM. : \$ 500

## CONTRACT DESCRIPTION:

BRIDGE AND APPROACHES COUNTY ROAD; OVER COTTON CREEK,  
 APPROX. 3.3 MILES NORTH AND 6.1 MILES EAST OF US-75/SH-10E  
 JCT. PROJECT LENGTH = 0.254 MILE FLEXIBLE ESALS = 0.1  
 MILLION ASPHALT GRADE = PG 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY BRO-174D(20)CO		
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(G)	0185 EARTHWORK	1.000	LSUM
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
210	0121 OBLITERATING ABANDONED ROAD	6.900	STA
227	0100 TEMPORARY SILT DIKE	3,048.000	LF
230(A)	2806 SOLID SLAB SODDING	9,034.000	SY
233(A)	2817 VEGETATIVE MULCHING	3.000	AC
303	0192 AGGREGATE BASE	847.000	CY
408	5774 PRIME COAT	1,631.000	GAL
411(S4)	5960 (SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	619.000	TON
509(D)	0325 CLASS C CONCRETE	10.000	CY
613(B)	0494 36" R.C.PIPE CLASS III	94.000	LF
613(C)	4379 SP. END SECTION OF 36" RCP ROUND	4.000	EA
613(D)	4528 28" X 20" CORR. GALV. STEEL PIPE ARCH	106.000	LF
613(G)	4571 28" X 20" GALV. STEEL CULV. END SEC.ARCH	6.000	EA
SECTION NO. 0002	X081-BRIDGE 'A' BRO-174D(20)CO		
501(B)	1307 SUBSTRUCTURE EXCAVATION COMMON	94.000	CY
501(D)	6353 UNCLASSIFIED BACKFILL	90.000	CY
503(A)	1312 PRESTRESSED CONCRETE BEAMS (TYPE III)	296.170	LF
504(E)	1380 CONCRETE RAIL (TR1)	215.170	LF
506(A)	1322 STRUCTURAL STEEL	1,800.000	LB
509(A)	1326 CLASS AA CONCRETE	58.500	CY
509(B)	1328 CLASS A CONCRETE	58.400	CY
511(A)	1332 REINFORCING STEEL	21,410.000	LB
514(A)	6010 PILES, FURNISHED (HP 10X42)	60.000	LF
514(A)	6011 PILES, FURNISHED (HP 12X53)	155.000	LF
514(B)	6292 PILES, DRIVEN (HP 10X42)	60.000	LF
514(B)	6294 PILES, DRIVEN (HP 12X53)	155.000	LF
601(A-1)	1353 TYPE I-A PLAIN RIPRAP	700.000	TON
601(A-2)	1355 TYPE I-A FILTER BLANKET	180.000	TON
619(D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F)	6033 GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
641	1399 MOBILIZATION	1.000	LSUM
880(J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

CALL ORDER : 500  
LETTING DATE : September 25, 2003  
LETTING TIME : 10:30 A.M.  
COUNTIES : WASHINGTON

CONTRACT ID : 030330  
PCN : 1940104  
PROJECTS : BRO-174D(20) CO  
DBE GOALS : 0.00  
GUARANTY : 5% OF BID TOTAL  
PLAN PRICE : 4.88  
CALENDAR DAYS : 130  
RES. ENG. :  
LIQ. DAM.: \$ 500

SECTION NO. 0003 STAK-STAKING BRO-174D(20)CO  
642 0098 STAKING

1.000 LSUM

CALL ORDER : 510  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 030331  
 PCN : 1940104C  
 PROJECTS : BRO-174D(20) CO  
 BRF-153C(22) CO  
 DBE GOALS : 3.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 9.76  
 CALENDAR DAYS : 240  
 RES. ENG.:  
 LIQ. DAM.: \$ 500

COUNTIES : NOWATA WASHINGTON

CONTRACT DESCRIPTION:  
 BRIDGES AND APPROACHES COUNTY ROAD; OVER CALIFORNIA CREEK,  
 0.5 MILE NORTH AND 3.8 MILES WEST OF LENAPAH/COUNTY ROAD;  
 OVER COTTON CREEK, 3.3 MI. NORTH AND 6.1 MI. EAST OF  
 US-75/SH-10E JCT. PROJECT LENGTH = 0.674 MILE FLEXIBLE  
 ESALS = 0.1 MILLION ASPHALT GRADE = PG 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 I000-ROADWAY BRO-174D(20)CO			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(G)	0185 EARTHWORK	1.000	LSUM
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
210	0121 OBLITERATING ABANDONED ROAD	6.900	STA
227	0100 TEMPORARY SILT DIKE	3,048.000	LF
230(A)	2806 SOLID SLAB SODDING	9,034.000	SY
233(A)	2817 VEGETATIVE MULCHING	3.000	AC
303	0192 AGGREGATE BASE	847.000	CY
408	5774 PRIME COAT	1,631.000	GAL
411(S4)	5960 (SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	619.000	TON
509(D)	0325 CLASS C CONCRETE	10.000	CY
613(B)	0494 36" R.C.PIPE CLASS III	94.000	LF
613(C)	4379 SP. END SECTION OF 36" RCP ROUND	4.000	EA
613(D)	4528 28" X 20" CORR. GALV. STEEL PIPE ARCH	106.000	LF
613(G)	4571 28" X 20" GALV. STEEL CULV. END SEC.ARCH	6.000	EA
SECTION NO. 0002 X081-BRIDGE 'A' BRO-174D(20)CO			
501(B)	1307 SUBSTRUCTURE EXCAVATION COMMON	94.000	CY
501(D)	6353 UNCLASSIFIED BACKFILL	90.000	CY
503(A)	1312 PRESTRESSED CONCRETE BEAMS (TYPE III)	296.170	LF
504(E)	1380 CONCRETE RAIL (TR1)	215.170	LF
506(A)	1322 STRUCTURAL STEEL	1,800.000	LB
509(A)	1326 CLASS AA CONCRETE	58.500	CY
509(B)	1328 CLASS A CONCRETE	58.400	CY
511(A)	1332 REINFORCING STEEL	21,410.000	LB
514(A)	6010 PILES, FURNISHED (HP 10X42)	60.000	LF
514(A)	6011 PILES, FURNISHED (HP 12X53)	155.000	LF
514(B)	6292 PILES, DRIVEN (HP 10X42)	60.000	LF
514(B)	6294 PILES, DRIVEN (HP 12X53)	155.000	LF
601(A-1)	1353 TYPE I-A PLAIN RIPRAP	700.000	TON
601(A-2)	1355 TYPE I-A FILTER BLANKET	180.000	TON
619(D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F)	6033 GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA

CALL ORDER : 510  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 030331  
 PCN : 1940104C  
 PROJECTS : BRO-174D(20) CO  
 BRF-153C(22) CO  
 DBE GOALS : 3.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 9.76  
 CALENDAR DAYS : 240  
 RES. ENG.:  
 LIQ. DAM.: \$ 500

COUNTIES : NOWATA WASHINGTON

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0002	X081-BRIDGE 'A' BRO-174D(20)CO		
641 1399	MOBILIZATION	1.000	LSUM
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003	STAK-STAKING BRO-174D(20)CO		
642 0098	STAKING	1.000	LSUM
SECTION NO. 0004	E000-ROADWAY BRF-153C(22)CO		
201 0102	CLEARING AND GRUBBING	1.000	LSUM
202(A) 0183	UNCLASSIFIED EXCAVATION	17,310.000	CY
205 4229	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
223 2801	TEMPORARY SILT FENCE	600.000	LF
227 0100	TEMPORARY SILT DIKE	450.000	LF
230(A) 2806	SOLID SLAB SODDING	13,610.000	SY
233(A) 2817	VEGETATIVE MULCHING	5.600	AC
403(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	2,343.000	TON
509(D) 0325	CLASS C CONCRETE	45.000	CY
613(D) 0689	18" CORR. GALV. STEEL PIPE	46.000	LF
613(D) 0692	36" CORR. GALV. STEEL PIPE	84.000	LF
613(D) 0696	60" CORR. GALV. STEEL PIPE	35.000	LF
613(M) 5726	18" PREFAB. CULVERT END SEC., ROUND	4.000	EA
613(M) 5734	36" PREFAB. CULVERT END SEC., ROUND	4.000	EA
SECTION NO. 0005	X081-BRIDGE 'A' BRF-153C(22)CO		
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	96.000	CY
501(F) 6352	GRANULAR BACKFILL	114.000	CY
503(A) 1313	PRESTRESSED CONCRETE BEAMS (TYPE IV)	376.170	LF
504(E) 1380	CONCRETE RAIL (TR1)	263.180	LF
506(A) 1322	STRUCTURAL STEEL	2,020.000	LB
509(A) 1326	CLASS AA CONCRETE	73.600	CY
509(B) 1328	CLASS A CONCRETE	64.490	CY
511(A) 1332	REINFORCING STEEL	25,729.000	LB
514(A) 6010	PILES, FURNISHED (HP 10X42)	380.000	LF
514(B) 6292	PILES, DRIVEN (HP 10X42)	380.000	LF
601(A-1)1353	TYPE I-A PLAIN RIPRAP	1,760.000	TON
601(A-2)1355	TYPE I-A FILTER BLANKET	317.000	TON
613(P) 6204	6" PERFORATED PIPE UNDERDRAIN ROUND	60.000	LF
613(Q) 6207	6" NON-PERF.PIPE UNDERDRAIN RND.	50.000	LF
619(D) M1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F) 6033	GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA

CALL ORDER : 510  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 030331  
 PCN : 1940104C  
 PROJECTS : BRO-174D(20) CO  
 BRF-153C(22) CO  
 DBE GOALS : 3.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 9.76  
 CALENDAR DAYS : 240  
 RES. ENG.:  
 LIQ. DAM.: \$ 500

COUNTIES : NOWATA WASHINGTON

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0005	X081-BRIDGE 'A' BRF-153C(22)CO		
640 1398	FIELD OFFICE	1.000	EA
641 1399	MOBILIZATION	1.000	LSUM
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0006	X028-BRIDGE 'B' BRF-153C(22)CO		
202(A) 1301	UNCLASSIFIED EXCAVATION	390.000	CY
501(A) 1306	STRUCTURAL EXCAVATION UNCLASSIFIED	100.000	CY
509(B) 1328	CLASS A CONCRETE	128.000	CY
511(A) 1332	REINFORCING STEEL	17,170.000	LB
SECTION NO. 0007	STAK-STAKING BRF-153C(22)CO		
642 0098	STAKING	1.000	LSUM

CALL ORDER : 530  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : OKLAHOMA

CONTRACT ID : 030322  
 PCN : 0009508  
 PROJECTS : MGSY-155A(002)  
 DBE GOALS : 10.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 29.80  
 CALENDAR DAYS : 500  
 RES. ENG. :  
 LIQ. DAM. : \$ 2000

## CONTRACT DESCRIPTION:

GRADE AND DRAIN SH-152; FROM COUNCIL ROAD, EXTEND EAST TO  
 MACARTHUR BLVD. IN OKLAHOMA CITY. PROJECT LENGTH = 3.018  
 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	C000-ROADWAY MGSY-155A(002)		
201	M0102 CLEARING AND GRUBBING	1.000	LSUM
202(A)	M0183 UNCLASSIFIED EXCAVATION	170,183.000	M3
202(C)	M0184 UNCLASSIFIED BORROW	1,178,483.000	M3
205	M4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
222	M2801 TEMPORARY BALE BARRIER	5,433.000	M
223	M2802 TEMPORARY SILT FENCE	5,491.000	M
224	M2803 TEMPORARY SEDIMENT FILTER	27.000	EA
226	M2805 TEMPORARY SEDIMENT REMOVAL	150.000	M3
227	M0100 TEMPORARY SILT DIKE	3,958.000	M
230(A)	M2806 SOLID SLAB SODDING	347,591.000	M2
232(B)	M2814 SEEDING METHOD B	30.000	HA
233(A)	M2817 VEGETATIVE MULCHING	28.000	HA
326(A)	M4200 (SP)FLY ASH	5,970.000	T
326(B)	M4210 (SP)LIME	205.000	T
326(E)	M4240 (SP)CEMENTITIOUS STABILIZED SUBGRADE	103,518.000	M2
326(G)	M4260 (SP)LIME PRETREATMENT	10,347.000	M2
403(E)	M0225 TRAFFIC BOUND SURFACE COURSE TYPE E	283.000	T
407	M0250 TACK COAT	11,073.000	L
408	M5774 PRIME COAT	98,472.000	L
411(S2)	M5930 (SP)ASPH.CONC.,TYPE S2(PG 64-22 OK)	6,331.000	T
411(S3)	M5940 (SP)ASPH.CONC.,TYPE S3(PG 70-28 OK)	5,071.000	T
411(S4)	M5955 (SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	2,536.000	T
411(S4)	M5960 (SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	409.000	T
414(A1)	M5755 250MM P.C. DOWEL JOINTED CONCRETE PAVE.	1,672.000	M2
501(A)	M0313 STRUCTURAL EXCAVATION UNCLASSIFIED	664.000	M3
509(B)	M0321 CLASS A CONCRETE	1,777.000	M3
509(D)	M0325 CLASS C CONCRETE	554.000	M3
511(A)	M0332 REINFORCING STEEL	205,508.000	KG
601(A)	M0297 TYPE I PLAIN RIPRAP	3,682.000	T
609(A)	M0287 CONC.CURB(100MM MNTBLE-INTEGRAL)	491.000	M
609(B)	M1513 500MM COMB.CRB.& GUT.(150MM BAR.)	1,919.000	M
609(B)	M1526 800MM COMB.CRB.& GUT.(200MM BAR.)	2,091.000	M
610(B)	M0399 150MM CONCRETE DRIVEWAY (H.E.S.)	668.000	M2
610(G)	M4475 BITUMINOUS DRIVEWAY (150MM)	1,318.000	M2
611(A)	M2657 MANHOLE (1200MM DIA.)	4.000	EA
611(D)	M4215 MANHOLE FRAME & COVER	4.000	EA
611(E)	M5113 INLET CICI DES. 2 (B)	7.000	EA

CALL ORDER : 530  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : OKLAHOMA

CONTRACT ID : 030322  
 PCN : 0009508  
 PROJECTS : MGSY-155A(002)  
 DBE GOALS : 10.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 29.80  
 CALENDAR DAYS : 500  
 RES. ENG.:  
 LIQ. DAM.: \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	C000-ROADWAY MGSY-155A(002)		
611(E) M5114	INLET CICI DES. 2 (C)	1.000	EA
611(E) M5115	INLET CICI DES. 2 (D)	1.000	EA
611(E) M5117	INLET CICI DES. 2 (2B)	2.000	EA
611(E) M5327	INLET GPI TYPE 1 (DES. 1)	12.000	EA
611(E) M5335	INLET GPI TYPE 2 (DES. 9)	2.000	EA
611(E) M6002	INLET (SMD-TYPE 2)	1.000	EA
611(G) M4488	INLET FRM&GRT (SSIF-FRM,CIG-GRT-VG-F)	22.000	EA
611(K) M4488	CAST IRON CURB INLETS	51.000	EA
613(B) M0405	450MM R.C.PIPE CLASS III	227.000	M
613(B) M0409	600MM R.C.PIPE CLASS III	393.000	M
613(B) M0413	750MM R.C.PIPE CLASS III	72.000	M
613(B) M0417	1050MM R.C.PIPE CLASS III	14.000	M
613(B) M0595	600MM R.C.PIPE CLASS V	41.000	M
613(B) M0596	750MM R.C.PIPE CLASS V	139.000	M
613(B) M4411	725MM X 460MM R.C.PIPE ARCH CLASS A-III	10.000	M
613(CC) 7194	TYPE DD4 CULVERT END TREATMENT	1.000	EA
613(M) M0898	600MM PREFAB. CULVERT END SEC., ROUND	13.000	EA
613(M) M0899	750MM PREFAB. CULVERT END SEC., ROUND	5.000	EA
613(M) M4518	725MM X 460MM PREFAB.CULV.END SEC., ARCH	2.000	EA
613(P) M1092	200MM PERFORATED PIPE UNDERDRAIN ROUND	302.000	M
613(Q) M1097	200MM NON-PERF.PIPE UNDERDRAIN RND.	76.000	M
619(A) M0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619(B) M4725	REMOVAL OF FENCE	3,563.000	M
619(B) M4727	REMOVAL OF CONCRETE PAVEMENT	2,264.000	M2
619(B) M4728	REMOVAL OF ASPHALT PAVEMENT	14,072.000	M2
619(B) M4780	REMOVAL OF GUARD RAIL	16.000	M
619(C) M0924	SAWING PAVEMENT	332.000	M
624(A) M4281	FENCE-STYLE WWF	1,653.000	M
624(C) M4458	(SP)FENCE-STYLE SWF (4 BARBED WIRE)	3,559.000	M
624(C) M4459	(SP)FENCE-STYLE SWF (5 BARBED WIRE)	1,912.000	M
624(D) M4292	FENCE-STYLE CLF (1800MM HIGH, CLASS A)	241.000	M
624(E) M5960	GATES-STYLE CLF(1800MM HI X 3600MM LONG)	2.000	EA
629(E) M5048	REMOVE AND RESET MAILBOX	2.000	EA
640 M1426	FIELD OFFICE	1.000	EA
641 M1552	MOBILIZATION	1.000	LSUM
880(C) M8845	BARRICADES(TYPE III)	9.000	EA
SECTION NO. 0002	Y000-TRAFFIC MGSY-155A(002)		
850(A) M8110	SHEET ALUMINUM SIGNS	14.480	M2
851(C) M8327	57MM SQUARE TUBE POST	99.900	M
855(A) M8812	TRAFFIC STRIPE(PLASTIC)(100MM WIDE)	7,142.700	M
855(B) M8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	14.000	EA

CALL ORDER : 530  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : OKLAHOMA

CONTRACT ID : 030322  
 PCN : 0009508  
 PROJECTS : MGSY-155A(002)  
 DBE GOALS : 10.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 29.80  
 CALENDAR DAYS : 500  
 RES. ENG. :  
 LIQ. DAM. : \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0002	Y000-TRAFFIC MGSY-155A(002)		
855(B) M8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	7.000	EA
SECTION NO. 0003	Y000-TRAFFIC SIGNALS MGSY-155A(002)		
802(B) M8332	25MM PVC SCH.40 P.C.BORED	220.000	M
802(B) M8336	38MM PVC SCH.40 P.C.BORED	15.000	M
802(B) M8338	38MM PVC SCH.40 P.C.TR.	390.000	M
802(B) M8342	50MM PVC SCH.40 P.C.TR.	20.000	M
802(B) M8344	75MM PVC SCH.40 P.C.BORED	95.000	M
802(B) M8346	75MM PVC SCH.40 P.C.TR.	10.000	M
803 M8065	PULL BOX(SIZE I)	3.000	EA
803 M8066	PULL BOX(SIZE II)	1.000	EA
803 M8067	PULL BOX(SIZE III)	11.000	EA
804(A) M2915	STRUCTURAL CONCRETE	9.300	M3
804(B) M2916	REINFORCING STEEL	838.700	KG
806(A) M8734	POLE & 13.7M TS MST.ARM(G.STL.)	1.000	EA
806(A) M8780	9.7M MHP 10.7M TS & 3.0M LMA(G.STL.)	1.000	EA
806(A) M8804	9.7M MHP 13.7M TS & 3.0M LMA(G.STL.)	2.000	EA
809(A) M8090	(PL)ROADWAY LUMINAIRE	3.000	EA
810(A) M3118	SERVICE POLE	1.000	EA
811 M8040	1/C NO.6 ELECT.COND.	90.000	M
811 M8044	1/C NO.10 ELECT.COND.	280.000	M
825 M8550	VEH.ACT.SOL.ST.TRAF.SIG.CON.ASM	1.000	EA
828(A) M8135	SOL.STE.DIGITAL IND.VEH.LP.DET.	10.000	EA
828(B) M8138	LOOP DETECTOR WIRE	1,452.000	M
831 M8231	1WAY3SEC.ADJ.SIG.HD.S-6	7.000	EA
831 M8252	1WAY3SEC.ADJ.SIG.HD.S-9	4.000	EA
831 M8262	1WAY3SEC.ADJ.SIG.HD.S-10	1.000	EA
831 M8286	1WAY5SEC.ADJ.SIG.HD.S-19	1.000	EA
833 M3030	BACKPLATE	13.000	EA
834(A) M8207	5/C TRAF.SIG.EL.CABLE	195.000	M
834(A) M8208	7/C TRAF.SIG.EL.CABLE	18.000	M
834(A) M8209	9/C TRAF.SIG.EL.CABLE	61.000	M
834(A) M8210	12/C TRAF.SIG.EL.CABLE	132.000	M
834(B) M8220	2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	970.000	M
850(A) M8110	SHEET ALUMINUM SIGNS	8.620	M2
880(J) M8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
890(A) M8724	(PL)REMOVAL OF EXISTING SIGNS	2.000	EA
SECTION NO. 0004	STAK-STAKING MGSY-155A(002)		
642 M0098	STAKING	1.000	LSUM



CALL ORDER : 540  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : OKLAHOMA

CONTRACT ID : 030323  
 PCN : 0009509  
 PROJECTS : MGSY-155A(171)  
 DBE GOALS : 5.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 67.19  
 CALENDAR DAYS : 360  
 RES. ENG. :  
 LIQ. DAM. : \$ 1000

CONTRACT DESCRIPTION:  
 BRIDGES AND APPROACHES SH-152; BRIDGE AT S.W. 44TH STREET  
 AND AT RAILROAD SPUR AND AT COUNCIL ROAD IN OKLAHOMA CITY.  
 PROJECT LENGTH = 0.143 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
-----			
SECTION NO. 0001	X251-BRIDGE 'A' MGSY-155A(171)		
202(D) M1303	SELECT BORROW	1,365.000	M3
501(B) M1307	SUBSTRUCTURE EXCAVATION COMMON	26.000	M3
501(F) M6352	GRANULAR BACKFILL	160.000	M3
503(A) M6281	PRESTRESSED CONCRETE BEAMS (72 BT)	348.560	M
504(A) M1304	APPROACH SLAB	318.280	M2
504(C) M6276	(PL)SEALED EXPANSION JOINTS	16.114	M
504(F) M6190	1067MM F-SHAPED PARAPET	128.000	M
506(A) M1322	STRUCTURAL STEEL	600.000	KG
509(A) M1326	CLASS AA CONCRETE	177.400	M3
509(B) M1328	CLASS A CONCRETE	106.000	M3
510(C) M6134	SLOPE WALL (100MM)	489.000	M2
511(A) M1332	REINFORCING STEEL	1,095.000	KG
511(B) M6010	EPOXY COATED REINFORCING STEEL	31,055.000	KG
514(A) M6011	PILES, FURNISHED (HP 250X62)	68.000	M
514(A) M6013	PILES, FURNISHED (HP 310X79)	336.000	M
514(B) M6292	PILES, DRIVEN (HP 250X62)	68.000	M
514(B) M6294	PILES, DRIVEN (HP 310X79)	336.000	M
514(F) 6354	PILE LOAD TEST (DYNAMIC)	26.000	EA
515(A) M6013	WATER REPELLENT (VISUALLY INSPECTED)	722.000	M2
535 M6164	(PL)FIXED BEARING ASSEMBLY	8.000	EA
535 M6165	(PL)EXPANSION BEARING ASSEMBLY	8.000	EA
613(P) M6204	150MM PERFORATED PIPE UNDERDRAIN ROUND	42.800	M
613(Q) M6207	150MM NON-PERF.PIPE UNDERDRAIN RND.	31.000	M
641 M1399	MOBILIZATION	1.000	LSUM
643 M0087	(SP)CONTRACTORS QUALITY CONTROL	1.000	LSUM
SECTION NO. 0002	X251-BRIDGE 'B' MGSY-155A(171)		
202(D) M1303	SELECT BORROW	1,377.000	M3
501(B) M1307	SUBSTRUCTURE EXCAVATION COMMON	26.000	M3
501(F) M6352	GRANULAR BACKFILL	160.000	M3
503(A) M6281	PRESTRESSED CONCRETE BEAMS (72 BT)	348.560	M
504(A) M1304	APPROACH SLAB	318.280	M2
504(C) M6276	(PL)SEALED EXPANSION JOINTS	16.114	M
504(F) M6190	1067MM F-SHAPED PARAPET	128.000	M
506(A) M1322	STRUCTURAL STEEL	600.000	KG
509(A) M1326	CLASS AA CONCRETE	177.400	M3

CALL ORDER : 540  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : OKLAHOMA

CONTRACT ID : 030323  
 PCN : 0009509  
 PROJECTS : MGSY-155A(171)  
 DBE GOALS : 5.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 67.19  
 CALENDAR DAYS : 360  
 RES. ENG. :  
 LIQ. DAM. : \$ 1000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0002	X251-BRIDGE 'B' MGSY-155A(171)		
509(B) M1328	CLASS A CONCRETE	106.000	M3
510(C) M6134	SLOPE WALL (100MM)	489.000	M2
511(A) M1332	REINFORCING STEEL	1,095.000	KG
511(B) M6010	EPOXY COATED REINFORCING STEEL	31,055.000	KG
514(A) M6011	PILES, FURNISHED (HP 250X62)	68.000	M
514(A) M6013	PILES, FURNISHED (HP 310X79)	336.000	M
514(B) M6292	PILES, DRIVEN (HP 250X62)	68.000	M
514(B) M6294	PILES, DRIVEN (HP 310X79)	336.000	M
514(F) M6354	PILE LOAD TEST (DYNAMIC)	26.000	EA
515(A) M6013	WATER REPELLENT (VISUALLY INSPECTED)	722.000	M2
535 M6164	(PL)FIXED BEARING ASSEMBLY	8.000	EA
535 M6165	(PL)EXPANSION BEARING ASSEMBLY	8.000	EA
613(P) M6204	150MM PERFORATED PIPE UNDERDRAIN ROUND	42.800	M
613(Q) M6207	150MM NON-PERF.PIPE UNDERDRAIN RND.	31.000	M
SECTION NO. 0003	X181-BRIDGE 'C' MGSY-155A(171)		
202(D) M1303	SELECT BORROW	974.000	M3
501(B) M1307	SUBSTRUCTURE EXCAVATION COMMON	22.200	M3
501(F) M6352	GRANULAR BACKFILL	119.200	M3
503(A) M6281	PRESTRESSED CONCRETE BEAMS (72 BT)	261.420	M
504(A) M1304	APPROACH SLAB	246.280	M2
504(C) M6276	(PL)SEALED EXPANSION JOINTS	12.514	M
504(F) M6190	1067MM F-SHAPED PARAPET	128.000	M
506(A) M1322	STRUCTURAL STEEL	400.000	KG
509(A) M1326	CLASS AA CONCRETE	136.500	M3
509(B) M1328	CLASS A CONCRETE	88.250	M3
510(C) M6134	SLOPE WALL (100MM)	687.000	M2
511(A) M1332	REINFORCING STEEL	785.000	KG
511(B) M6010	EPOXY COATED REINFORCING STEEL	25,564.000	KG
514(A) M6011	PILES, FURNISHED (HP 250X62)	92.000	M
514(A) M6013	PILES, FURNISHED (HP 310X79)	383.000	M
514(B) M6292	PILES, DRIVEN (HP 250X62)	92.000	M
514(B) M6294	PILES, DRIVEN (HP 310X79)	383.000	M
514(F) M6354	PILE LOAD TEST (DYNAMIC)	22.000	EA
515(A) M6013	WATER REPELLENT (VISUALLY INSPECTED)	678.800	M2
535 M6164	(PL)FIXED BEARING ASSEMBLY	6.000	EA
535 M6165	(PL)EXPANSION BEARING ASSEMBLY	6.000	EA
613(D) M5226	1030MM X 740MM CORR. GALV. ST. PIPE ARCH	91.440	M
613(G) M7046	1030MM X 740MM GALV.STL.CULV.END SEC.ARC	4.000	EA
613(P) M6204	150MM PERFORATED PIPE UNDERDRAIN ROUND	33.600	M
613(Q) M6207	150MM NON-PERF.PIPE UNDERDRAIN RND.	39.000	M
SECTION NO. 0004	X181-BRIDGE 'D' MGSY-155A(171)		

CALL ORDER : 540  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : OKLAHOMA

CONTRACT ID : 030323  
 PCN : 0009509  
 PROJECTS : MGSY-155A(171)  
 DBE GOALS : 5.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 67.19  
 CALENDAR DAYS : 360  
 RES. ENG. :  
 LIQ. DAM. : \$ 1000

202(D)	M1303	SELECT BORROW	974.000	M3
501(B)	M1307	SUBSTRUCTURE EXCAVATION COMMON	22.200	M3
501(F)	M6352	GRANULAR BACKFILL	119.200	M3
503(A)	M6281	PRESTRESSED CONCRETE BEAMS (72 BT)	261.420	M
504(A)	M1304	APPROACH SLAB	246.280	M2
504(C)	M6276	(PL)SEALED EXPANSION JOINTS	12.514	M
504(F)	M6190	1067MM F-SHAPED PARAPET	128.000	M
506(A)	M1322	STRUCTURAL STEEL	400.000	KG
509(A)	M1326	CLASS AA CONCRETE	136.500	M3
509(B)	M1328	CLASS A CONCRETE	88.250	M3
510(C)	M6134	SLOPE WALL (100MM)	687.000	M2
511(A)	M1332	REINFORCING STEEL	785.000	KG
511(B)	M6010	EPOXY COATED REINFORCING STEEL	25,564.000	KG
514(A)	M6011	PILES, FURNISHED (HP 250X62)	92.000	M
514(A)	M6013	PILES, FURNISHED (HP 310X79)	383.000	M
514(B)	M6292	PILES, DRIVEN (HP 250X62)	92.000	M
514(B)	M6294	PILES, DRIVEN (HP 310X79)	383.000	M
514(F)	M6354	PILE LOAD TEST (DYNAMIC)	22.000	EA
515(A)	M6013	WATER REPELLENT (VISUALLY INSPECTED)	678.800	M2
535	M6164	(PL)FIXED BEARING ASSEMBLY	6.000	EA
535	M6165	(PL)EXPANSION BEARING ASSEMBLY	6.000	EA
613(P)	M6204	150MM PERFORATED PIPE UNDERDRAIN ROUND	33.600	M
613(Q)	M6207	150MM NON-PERF.PIPE UNDERDRAIN RND.	39.000	M

## SECTION NO. 0005 X251-BRIDGE 'E' MGSY-155A(171)

202(D)	M1303	SELECT BORROW	508.000	M3
501(B)	M1307	SUBSTRUCTURE EXCAVATION COMMON	28.000	M3
501(F)	M6352	GRANULAR BACKFILL	63.400	M3
503(A)	M1311	PRESTRESSED CONCRETE BEAMS (TYPE II)	134.000	M
503(A)	M1313	PRESTRESSED CONCRETE BEAMS (TYPE IV)	136.250	M
504(A)	M1304	APPROACH SLAB	326.200	M2
504(C)	M6276	(PL)SEALED EXPANSION JOINTS	27.541	M
504(F)	M6190	1067MM F-SHAPED PARAPET	163.460	M
506(A)	M1322	STRUCTURAL STEEL	245.000	KG
509(A)	M1326	CLASS AA CONCRETE	162.900	M3
509(B)	M1328	CLASS A CONCRETE	131.600	M3
510(C)	M6134	SLOPE WALL (100MM)	698.000	M2
511(A)	M1332	REINFORCING STEEL	2,290.000	KG
511(B)	M6010	EPOXY COATED REINFORCING STEEL	31,696.000	KG
514(A)	M6011	PILES, FURNISHED (HP 250X62)	344.600	M
514(B)	M6292	PILES, DRIVEN (HP 250X62)	344.600	M
514(F)	M6354	PILE LOAD TEST (DYNAMIC)	18.000	EA
515(A)	M6013	WATER REPELLENT (VISUALLY INSPECTED)	609.300	M2
516(A)	M6094	DRILLED SHAFTS 1200MM DIAMETER	60.000	M
535	M6164	(PL)FIXED BEARING ASSEMBLY	15.000	EA
535	M6165	(PL)EXPANSION BEARING ASSEMBLY	15.000	EA
613(P)	M6204	150MM PERFORATED PIPE UNDERDRAIN ROUND	37.000	M

CALL ORDER : 540  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : OKLAHOMA

CONTRACT ID : 030323  
 PCN : 0009509  
 PROJECTS : MGSY-155A(171)  
 DBE GOALS : 5.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 67.19  
 CALENDAR DAYS : 360  
 RES. ENG. :  
 LIQ. DAM. : \$ 1000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0005	X251-BRIDGE 'E' MGSY-155A(171)		
613(Q) M6207	150MM NON-PERF.PIPE UNDERDRAIN RND.	30.000	M
SECTION NO. 0006	X251-BRIDGE 'F' MGSY-155A(171)		
202(D) M1303	SELECT BORROW	508.000	M3
501(B) M1307	SUBSTRUCTURE EXCAVATION COMMON	28.000	M3
501(F) M6352	GRANULAR BACKFILL	63.400	M3
503(A) M1311	PRESTRESSED CONCRETE BEAMS (TYPE II)	134.000	M
503(A) M1313	PRESTRESSED CONCRETE BEAMS (TYPE IV)	136.250	M
504(A) M1304	APPROACH SLAB	326.200	M2
504(C) M6276	(PL)SEALED EXPANSION JOINTS	27.541	M
504(F) M6190	1067MM F-SHAPED PARAPET	163.460	M
506(A) M1322	STRUCTURAL STEEL	245.000	KG
509(A) M1326	CLASS AA CONCRETE	162.900	M3
509(B) M1328	CLASS A CONCRETE	133.800	M3
510(C) M6134	SLOPE WALL (100MM)	698.000	M2
511(A) M1332	REINFORCING STEEL	2,240.000	KG
511(B) M6010	EPOXY COATED REINFORCING STEEL	31,767.000	KG
514(A) M6011	PILES, FURNISHED (HP 250X62)	344.600	M
514(B) M6292	PILES, DRIVEN (HP 250X62)	344.600	M
514(F) M6354	PILE LOAD TEST (DYNAMIC)	18.000	EA
515(A) M6013	WATER REPELLENT (VISUALLY INSPECTED)	608.200	M2
516(A) M6094	DRILLED SHAFTS 1200MM DIAMETER	60.000	M
535 M6164	(PL)FIXED BEARING ASSEMBLY	15.000	EA
535 M6165	(PL)EXPANSION BEARING ASSEMBLY	15.000	EA
613(P) M6204	150MM PERFORATED PIPE UNDERDRAIN ROUND	37.000	M
613(Q) M6207	150MM NON-PERF.PIPE UNDERDRAIN RND.	30.000	M
SECTION NO. 0007	STAK-STAKING MGSY-155A(171)		
642 M0098	STAKING	1.000	LSUM

CALL ORDER : 550  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : OKLAHOMA

CONTRACT ID : 030324  
 PCN : 0009508C  
 PROJECTS : MGSY-155A(002)  
 MGSY-155A(171)  
 DBE GOALS : 8.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 96.99  
 CALENDAR DAYS : 500  
 RES. ENG. :  
 LIQ. DAM. : \$ 2000

CONTRACT DESCRIPTION:  
 GRADE, DRAIN AND BRIDGE SH-152; FROM COUNCIL ROAD, EXTEND  
 EAST TO MACARTHUR BLVD. IN OKLAHOMA CITY. PROJECT LENGTH =  
 3.161 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	C000-ROADWAY MGSY-155A(002)		
201	M0102 CLEARING AND GRUBBING	1.000	LSUM
202(A)	M0183 UNCLASSIFIED EXCAVATION	170,183.000	M3
202(C)	M0184 UNCLASSIFIED BORROW	1,178,483.000	M3
205	M4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
222	M2801 TEMPORARY BALE BARRIER	5,433.000	M
223	M2802 TEMPORARY SILT FENCE	5,491.000	M
224	M2803 TEMPORARY SEDIMENT FILTER	27.000	EA
226	M2805 TEMPORARY SEDIMENT REMOVAL	150.000	M3
227	M0100 TEMPORARY SILT DIKE	3,958.000	M
230(A)	M2806 SOLID SLAB SODDING	347,591.000	M2
232(B)	M2814 SEEDING METHOD B	30.000	HA
233(A)	M2817 VEGETATIVE MULCHING	28.000	HA
326(A)	M4200 (SP)FLY ASH	5,970.000	T
326(B)	M4210 (SP)LIME	205.000	T
326(E)	M4240 (SP)CEMENTITIOUS STABILIZED SUBGRADE	103,518.000	M2
326(G)	M4260 (SP)LIME PRETREATMENT	10,347.000	M2
403(E)	M0225 TRAFFIC BOUND SURFACE COURSE TYPE E	283.000	T
407	M0250 TACK COAT	11,073.000	L
408	M5774 PRIME COAT	98,472.000	L
411(S2)	M5930 (SP)ASPH.CONC.,TYPE S2(PG 64-22 OK)	6,331.000	T
411(S3)	M5940 (SP)ASPH.CONC.,TYPE S3(PG 70-28 OK)	5,071.000	T
411(S4)	M5955 (SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	2,536.000	T
411(S4)	M5960 (SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	409.000	T
414(A1)	M5755 250MM P.C. DOWEL JOINTED CONCRETE PAVE.	1,672.000	M2
501(A)	M0313 STRUCTURAL EXCAVATION UNCLASSIFIED	664.000	M3
509(B)	M0321 CLASS A CONCRETE	1,777.000	M3
509(D)	M0325 CLASS C CONCRETE	554.000	M3
511(A)	M0332 REINFORCING STEEL	205,508.000	KG
601(A)	M0297 TYPE I PLAIN RIPRAP	3,682.000	T
609(A)	M0287 CONC.CURB(100MM MNTBLE-INTEGRAL)	491.000	M
609(B)	M1513 500MM COMB.CRB.& GUT.(150MM BAR.)	1,919.000	M
609(B)	M1526 800MM COMB.CRB.& GUT.(200MM BAR.)	2,091.000	M
610(B)	M0399 150MM CONCRETE DRIVEWAY (H.E.S.)	668.000	M2
610(G)	M4475 BITUMINOUS DRIVEWAY (150MM)	1,318.000	M2
611(A)	M2657 MANHOLE (1200MM DIA.)	4.000	EA
611(D)	M4215 MANHOLE FRAME & COVER	4.000	EA

CALL ORDER : 550  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : OKLAHOMA

CONTRACT ID : 030324  
 PCN : 0009508C  
 PROJECTS : MGSY-155A(002)  
 MGSY-155A(171)  
 DBE GOALS : 8.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 96.99  
 CALENDAR DAYS : 500  
 RES. ENG.:  
 LIQ. DAM.: \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	C000-ROADWAY MGSY-155A(002)		
611(E) M5113	INLET CICI DES. 2 (B)	7.000	EA
611(E) M5114	INLET CICI DES. 2 (C)	1.000	EA
611(E) M5115	INLET CICI DES. 2 (D)	1.000	EA
611(E) M5117	INLET CICI DES. 2 (2B)	2.000	EA
611(E) M5327	INLET GPI TYPE 1 (DES. 1)	12.000	EA
611(E) M5335	INLET GPI TYPE 2 (DES. 9)	2.000	EA
611(E) M6002	INLET (SMD-TYPE 2)	1.000	EA
611(G) M4488	INLET FRM&GRT (SSIF-FRM,CIG-GRT-VG-F)	22.000	EA
611(K) M4488	CAST IRON CURB INLETS	51.000	EA
613(B) M0405	450MM R.C.PIPE CLASS III	227.000	M
613(B) M0409	600MM R.C.PIPE CLASS III	393.000	M
613(B) M0413	750MM R.C.PIPE CLASS III	72.000	M
613(B) M0417	1050MM R.C.PIPE CLASS III	14.000	M
613(B) M0595	600MM R.C.PIPE CLASS V	41.000	M
613(B) M0596	750MM R.C.PIPE CLASS V	139.000	M
613(B) M4411	725MM X 460MM R.C.PIPE ARCH CLASS A-III	10.000	M
613(CC) 7194	TYPE DD4 CULVERT END TREATMENT	1.000	EA
613(M) M0898	600MM PREFAB. CULVERT END SEC., ROUND	13.000	EA
613(M) M0899	750MM PREFAB. CULVERT END SEC., ROUND	5.000	EA
613(M) M4518	725MM X 460MM PREFAB.CULV.END SEC., ARCH	2.000	EA
613(P) M1092	200MM PERFORATED PIPE UNDERDRAIN ROUND	302.000	M
613(Q) M1097	200MM NON-PERF.PIPE UNDERDRAIN RND.	76.000	M
619(A) M0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619(B) M4725	REMOVAL OF FENCE	3,563.000	M
619(B) M4727	REMOVAL OF CONCRETE PAVEMENT	2,264.000	M2
619(B) M4728	REMOVAL OF ASPHALT PAVEMENT	14,072.000	M2
619(B) M4780	REMOVAL OF GUARD RAIL	16.000	M
619(C) M0924	SAWING PAVEMENT	332.000	M
624(A) M4281	FENCE-STYLE WWF	1,653.000	M
624(C) M4458	(SP)FENCE-STYLE SWF (4 BARBED WIRE)	3,559.000	M
624(C) M4459	(SP)FENCE-STYLE SWF (5 BARBED WIRE)	1,912.000	M
624(D) M4292	FENCE-STYLE CLF (1800MM HIGH, CLASS A)	241.000	M
624(E) M5960	GATES-STYLE CLF(1800MM HI X 3600MM LONG)	2.000	EA
629(E) M5048	REMOVE AND RESET MAILBOX	2.000	EA
640 M1426	FIELD OFFICE	1.000	EA
641 M1552	MOBILIZATION	1.000	LSUM
880(C) M8845	BARRICADES(TYPE III)	9.000	EA
SECTION NO. 0002	Y000-TRAFFIC MGSY-155A(002)		
850(A) M8110	SHEET ALUMINUM SIGNS	14.480	M2
851(C) M8327	57MM SQUARE TUBE POST	99.900	M

CALL ORDER : 550  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 030324  
 PCN : 0009508C  
 PROJECTS : MGSY-155A(002)  
 MGSY-155A(171)  
 DBE GOALS : 8.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 96.99  
 CALENDAR DAYS : 500  
 RES. ENG.:  
 LIQ. DAM.: \$ 2000

COUNTIES : OKLAHOMA

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0002	Y000-TRAFFIC MGSY-155A(002)		
855(A) M8812	TRAFFIC STRIPE(PLASTIC)(100MM WIDE)	7,142.700	M
855(B) M8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	14.000	EA
855(B) M8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	7.000	EA
SECTION NO. 0003	Y000-TRAFFIC SIGNALS MGSY-155A(002)		
802(B) M8332	25MM PVC SCH.40 P.C.BORED	220.000	M
802(B) M8336	38MM PVC SCH.40 P.C.BORED	15.000	M
802(B) M8338	38MM PVC SCH.40 P.C.TR.	390.000	M
802(B) M8342	50MM PVC SCH.40 P.C.TR.	20.000	M
802(B) M8344	75MM PVC SCH.40 P.C.BORED	95.000	M
802(B) M8346	75MM PVC SCH.40 P.C.TR.	10.000	M
803 M8065	PULL BOX(SIZE I)	3.000	EA
803 M8066	PULL BOX(SIZE II)	1.000	EA
803 M8067	PULL BOX(SIZE III)	11.000	EA
804(A) M2915	STRUCTURAL CONCRETE	9.300	M3
804(B) M2916	REINFORCING STEEL	838.700	KG
806(A) M8734	POLE & 13.7M TS MST.ARM(G.STL.)	1.000	EA
806(A) M8780	9.7M MHP 10.7M TS & 3.0M LMA(G.STL.)	1.000	EA
806(A) M8804	9.7M MHP 13.7M TS & 3.0M LMA(G.STL.)	2.000	EA
809(A) M8090	(PL)ROADWAY LUMINAIRE	3.000	EA
810(A) M3118	SERVICE POLE	1.000	EA
811 M8040	1/C NO.6 ELECT.COND.	90.000	M
811 M8044	1/C NO.10 ELECT.COND.	280.000	M
825 M8550	VEH.ACT.SOL.ST.TRAF.SIG.CON.ASM	1.000	EA
828(A) M8135	SOL.STE.DIGITAL IND.VEH.LP.DET.	10.000	EA
828(B) M8138	LOOP DETECTOR WIRE	1,452.000	M
831 M8231	1WAY3SEC.ADJ.SIG.HD.S-6	7.000	EA
831 M8252	1WAY3SEC.ADJ.SIG.HD.S-9	4.000	EA
831 M8262	1WAY3SEC.ADJ.SIG.HD.S-10	1.000	EA
831 M8286	1WAY5SEC.ADJ.SIG.HD.S-19	1.000	EA
833 M3030	BACKPLATE	13.000	EA
834(A) M8207	5/C TRAF.SIG.EL.CABLE	195.000	M
834(A) M8208	7/C TRAF.SIG.EL.CABLE	18.000	M
834(A) M8209	9/C TRAF.SIG.EL.CABLE	61.000	M
834(A) M8210	12/C TRAF.SIG.EL.CABLE	132.000	M
834(B) M8220	2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	970.000	M
850(A) M8110	SHEET ALUMINUM SIGNS	8.620	M2
880(J) M8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
890(A) M8724	(PL)REMOVAL OF EXISTING SIGNS	2.000	EA
SECTION NO. 0004	STAK-STAKING MGSY-155A(002)		

CALL ORDER : 550  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 030324  
 PCN : 0009508C  
 PROJECTS : MGSY-155A(002)  
 MGSY-155A(171)  
 DBE GOALS : 8.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 96.99  
 CALENDAR DAYS : 500  
 RES. ENG.:  
 LIQ. DAM.: \$ 2000

COUNTIES : OKLAHOMA

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
-----			
SECTION NO. 0004	STAK-STAKING MGSY-155A(002)		
642 M0098	STAKING	1.000	LSUM
-----			
SECTION NO. 0005	X251-BRIDGE 'A' MGSY-155A(171)		
202(D) M1303	SELECT BORROW	1,365.000	M3
501(B) M1307	SUBSTRUCTURE EXCAVATION COMMON	26.000	M3
501(F) M6352	GRANULAR BACKFILL	160.000	M3
503(A) M6281	PRESTRESSED CONCRETE BEAMS (72 BT)	348.560	M
504(A) M1304	APPROACH SLAB	318.280	M2
504(C) M6276	(PL)SEALED EXPANSION JOINTS	16.114	M
504(F) M6190	1067MM F-SHAPED PARAPET	128.000	M
506(A) M1322	STRUCTURAL STEEL	600.000	KG
509(A) M1326	CLASS AA CONCRETE	177.400	M3
509(B) M1328	CLASS A CONCRETE	106.000	M3
510(C) M6134	SLOPE WALL (100MM)	489.000	M2
511(A) M1332	REINFORCING STEEL	1,095.000	KG
511(B) M6010	EPOXY COATED REINFORCING STEEL	31,055.000	KG
514(A) M6011	PILES, FURNISHED (HP 250X62)	68.000	M
514(A) M6013	PILES, FURNISHED (HP 310X79)	336.000	M
514(B) M6292	PILES, DRIVEN (HP 250X62)	68.000	M
514(B) M6294	PILES, DRIVEN (HP 310X79)	336.000	M
514(F) M6354	PILE LOAD TEST (DYNAMIC)	26.000	EA
515(A) M6013	WATER REPELLENT (VISUALLY INSPECTED)	722.000	M2
535 M6164	(PL)FIXED BEARING ASSEMBLY	8.000	EA
535 M6165	(PL)EXPANSION BEARING ASSEMBLY	8.000	EA
613(P) M6204	150MM PERFORATED PIPE UNDERDRAIN ROUND	42.800	M
613(Q) M6207	150MM NON-PERF.PIPE UNDERDRAIN RND.	31.000	M
641 M1399	MOBILIZATION	1.000	LSUM
643 M0087	(SP)CONTRACTORS QUALITY CONTROL	1.000	LSUM
-----			
SECTION NO. 0006	X251-BRIDGE 'B' MGSY-155A(171)		
202(D) M1303	SELECT BORROW	1,377.000	M3
501(B) M1307	SUBSTRUCTURE EXCAVATION COMMON	26.000	M3
501(F) M6352	GRANULAR BACKFILL	160.000	M3
503(A) M6281	PRESTRESSED CONCRETE BEAMS (72 BT)	348.560	M
504(A) M1304	APPROACH SLAB	318.280	M2
504(C) M6276	(PL)SEALED EXPANSION JOINTS	16.114	M
504(F) M6190	1067MM F-SHAPED PARAPET	128.000	M
506(A) M1322	STRUCTURAL STEEL	600.000	KG
509(A) M1326	CLASS AA CONCRETE	177.400	M3
509(B) M1328	CLASS A CONCRETE	106.000	M3



CALL ORDER : 550  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : OKLAHOMA

CONTRACT ID : 030324  
 PCN : 0009508C  
 PROJECTS : MGSY-155A(002)  
 MGSY-155A(171)  
 DBE GOALS : 8.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 96.99  
 CALENDAR DAYS : 500  
 RES. ENG.:  
 LIQ. DAM.: \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0006	X251-BRIDGE 'B' MGSY-155A(171)		
510(C) M6134	SLOPE WALL (100MM)	489.000	M2
511(A) M1332	REINFORCING STEEL	1,095.000	KG
511(B) M6010	EPOXY COATED REINFORCING STEEL	31,055.000	KG
514(A) M6011	PILES, FURNISHED (HP 250X62)	68.000	M
514(A) M6013	PILES, FURNISHED (HP 310X79)	336.000	M
514(B) M6292	PILES, DRIVEN (HP 250X62)	68.000	M
514(B) M6294	PILES, DRIVEN (HP 310X79)	336.000	M
514(F) M6354	PILE LOAD TEST (DYNAMIC)	26.000	EA
515(A) M6013	WATER REPELLENT (VISUALLY INSPECTED)	722.000	M2
535 M6164	(PL)FIXED BEARING ASSEMBLY	8.000	EA
535 M6165	(PL)EXPANSION BEARING ASSEMBLY	8.000	EA
613(P) M6204	150MM PERFORATED PIPE UNDERDRAIN ROUND	42.800	M
613(Q) M6207	150MM NON-PERF.PIPE UNDERDRAIN RND.	31.000	M
SECTION NO. 0007	X181-BRIDGE 'C' MGSY-155A(171)		
202(D) M1303	SELECT BORROW	974.000	M3
501(B) M1307	SUBSTRUCTURE EXCAVATION COMMON	22.200	M3
501(F) M6352	GRANULAR BACKFILL	119.200	M3
503(A) M6281	PRESTRESSED CONCRETE BEAMS (72 BT)	261.420	M
504(A) M1304	APPROACH SLAB	246.280	M2
504(C) M6276	(PL)SEALED EXPANSION JOINTS	12.514	M
504(F) M6190	1067MM F-SHAPED PARAPET	128.000	M
506(A) M1322	STRUCTURAL STEEL	400.000	KG
509(A) M1326	CLASS AA CONCRETE	136.500	M3
509(B) M1328	CLASS A CONCRETE	88.250	M3
510(C) M6134	SLOPE WALL (100MM)	687.000	M2
511(A) M1332	REINFORCING STEEL	785.000	KG
511(B) M6010	EPOXY COATED REINFORCING STEEL	25,564.000	KG
514(A) M6011	PILES, FURNISHED (HP 250X62)	92.000	M
514(A) M6013	PILES, FURNISHED (HP 310X79)	383.000	M
514(B) M6292	PILES, DRIVEN (HP 250X62)	92.000	M
514(B) M6294	PILES, DRIVEN (HP 310X79)	383.000	M
514(F) M6354	PILE LOAD TEST (DYNAMIC)	22.000	EA
515(A) M6013	WATER REPELLENT (VISUALLY INSPECTED)	678.800	M2
535 M6164	(PL)FIXED BEARING ASSEMBLY	6.000	EA
535 M6165	(PL)EXPANSION BEARING ASSEMBLY	6.000	EA
613(D) M5226	1030MM X 740MM CORR. GALV. ST. PIPE ARCH	91.440	M
613(G) M7046	1030MM X 740MM GALV.STL.CULV.END SEC.ARC	4.000	EA
613(P) M6204	150MM PERFORATED PIPE UNDERDRAIN ROUND	33.600	M
613(Q) M6207	150MM NON-PERF.PIPE UNDERDRAIN RND.	39.000	M
SECTION NO. 0008	X181-BRIDGE 'D' MGSY-155A(171)		

CALL ORDER : 550  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 030324  
 PCN : 0009508C  
 PROJECTS : MGSY-155A(002)  
 MGSY-155A(171)  
 DBE GOALS : 8.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 96.99  
 CALENDAR DAYS : 500  
 RES. ENG.:  
 LIQ. DAM.: \$ 2000

COUNTIES : OKLAHOMA

202(D)	M1303	SELECT BORROW	974.000	M3
501(B)	M1307	SUBSTRUCTURE EXCAVATION COMMON	22.200	M3
501(F)	M6352	GRANULAR BACKFILL	119.200	M3
503(A)	M6281	PRESTRESSED CONCRETE BEAMS (72 BT)	261.420	M
504(A)	M1304	APPROACH SLAB	246.280	M2
504(C)	M6276	(PL)SEALED EXPANSION JOINTS	12.514	M
504(F)	M6190	1067MM F-SHAPED PARAPET	128.000	M
506(A)	M1322	STRUCTURAL STEEL	400.000	KG
509(A)	M1326	CLASS AA CONCRETE	136.500	M3
509(B)	M1328	CLASS A CONCRETE	88.250	M3
510(C)	M6134	SLOPE WALL (100MM)	687.000	M2
511(A)	M1332	REINFORCING STEEL	785.000	KG
511(B)	M6010	EPOXY COATED REINFORCING STEEL	25,564.000	KG
514(A)	M6011	PILES, FURNISHED (HP 250X62)	92.000	M
514(A)	M6013	PILES, FURNISHED (HP 310X79)	383.000	M
514(B)	M6292	PILES, DRIVEN (HP 250X62)	92.000	M
514(B)	M6294	PILES, DRIVEN (HP 310X79)	383.000	M
514(F)	M6354	PILE LOAD TEST (DYNAMIC)	22.000	EA
515(A)	M6013	WATER REPELLENT (VISUALLY INSPECTED)	678.800	M2
535	M6164	(PL)FIXED BEARING ASSEMBLY	6.000	EA
535	M6165	(PL)EXPANSION BEARING ASSEMBLY	6.000	EA
613(P)	M6204	150MM PERFORATED PIPE UNDERDRAIN ROUND	33.600	M
613(Q)	M6207	150MM NON-PERF.PIPE UNDERDRAIN RND.	39.000	M

SECTION NO. 0009 X251-BRIDGE 'E' MGSY-155A(171)

202(D)	M1303	SELECT BORROW	508.000	M3
501(B)	M1307	SUBSTRUCTURE EXCAVATION COMMON	28.000	M3
501(F)	M6352	GRANULAR BACKFILL	63.400	M3
503(A)	M1311	PRESTRESSED CONCRETE BEAMS (TYPE II)	134.000	M
503(A)	M1313	PRESTRESSED CONCRETE BEAMS (TYPE IV)	136.250	M
504(A)	M1304	APPROACH SLAB	326.200	M2
504(C)	M6276	(PL)SEALED EXPANSION JOINTS	27.541	M
504(F)	M6190	1067MM F-SHAPED PARAPET	163.460	M
506(A)	M1322	STRUCTURAL STEEL	245.000	KG
509(A)	M1326	CLASS AA CONCRETE	162.900	M3
509(B)	M1328	CLASS A CONCRETE	131.600	M3
510(C)	M6134	SLOPE WALL (100MM)	698.000	M2
511(A)	M1332	REINFORCING STEEL	2,290.000	KG
511(B)	M6010	EPOXY COATED REINFORCING STEEL	31,696.000	KG
514(A)	M6011	PILES, FURNISHED (HP 250X62)	344.600	M
514(B)	M6292	PILES, DRIVEN (HP 250X62)	344.600	M
514(F)	M6354	PILE LOAD TEST (DYNAMIC)	18.000	EA
515(A)	M6013	WATER REPELLENT (VISUALLY INSPECTED)	609.300	M2
516(A)	M6094	DRILLED SHAFTS 1200MM DIAMETER	60.000	M
535	M6164	(PL)FIXED BEARING ASSEMBLY	15.000	EA
535	M6165	(PL)EXPANSION BEARING ASSEMBLY	15.000	EA

CALL ORDER : 550  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 030324  
 PCN : 0009508C  
 PROJECTS : MGSY-155A(002)  
 MGSY-155A(171)  
 DBE GOALS : 8.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 96.99  
 CALENDAR DAYS : 500  
 RES. ENG.:  
 LIQ. DAM.: \$ 2000

COUNTIES : OKLAHOMA

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0009	X251-BRIDGE 'E' MGSY-155A(171)		
613(P) M6204	150MM PERFORATED PIPE UNDERDRAIN ROUND	37.000	M
613(Q) M6207	150MM NON-PERF.PIPE UNDERDRAIN RND.	30.000	M
SECTION NO. 0010	X251-BRIDGE 'F' MGSY-155A(171)		
202(D) M1303	SELECT BORROW	508.000	M3
501(B) M1307	SUBSTRUCTURE EXCAVATION COMMON	28.000	M3
501(F) M6352	GRANULAR BACKFILL	63.400	M3
503(A) M1311	PRESTRESSED CONCRETE BEAMS (TYPE II)	134.000	M
503(A) M1313	PRESTRESSED CONCRETE BEAMS (TYPE IV)	136.250	M
504(A) M1304	APPROACH SLAB	326.200	M2
504(C) M6276	(PL)SEALED EXPANSION JOINTS	27.541	M
504(F) M6190	1067MM F-SHAPED PARAPET	163.460	M
506(A) M1322	STRUCTURAL STEEL	245.000	KG
509(A) M1326	CLASS AA CONCRETE	162.900	M3
509(B) M1328	CLASS A CONCRETE	133.800	M3
510(C) M6134	SLOPE WALL (100MM)	698.000	M2
511(A) M1332	REINFORCING STEEL	2,240.000	KG
511(B) M6010	EPOXY COATED REINFORCING STEEL	31,767.000	KG
514(A) M6011	PILES, FURNISHED (HP 250X62)	344.600	M
514(B) M6292	PILES, DRIVEN (HP 250X62)	344.600	M
514(F) M6354	PILE LOAD TEST (DYNAMIC)	18.000	EA
515(A) M6013	WATER REPELLENT (VISUALLY INSPECTED)	608.200	M2
516(A) M6094	DRILLED SHAFTS 1200MM DIAMETER	60.000	M
535 M6164	(PL)FIXED BEARING ASSEMBLY	15.000	EA
535 M6165	(PL)EXPANSION BEARING ASSEMBLY	15.000	EA
613(P) M6204	150MM PERFORATED PIPE UNDERDRAIN ROUND	37.000	M
613(Q) M6207	150MM NON-PERF.PIPE UNDERDRAIN RND.	30.000	M
SECTION NO. 0011	STAK-STAKING MGSY-155A(171)		
642 M0098	STAKING	1.000	LSUM

CALL ORDER : 560  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 030249  
 PCN : 1899306  
 PROJECTS : ITSU-0QT8(22) DC  
 ITSU-0QT8(18) DC  
 ITSU-0QT8(19) DC

COUNTIES : OKLAHOMA

DBE GOALS : 0.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 98.62  
 CALENDAR DAYS : 150  
 RES. ENG.:  
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:  
 SAFETY IMPROVEMENT I-40/I-44/I-235; VARIOUS LOCATIONS IN  
 OKLAHOMA CITY. PROJECT LENGTH = 0.00 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SFTY-TRAFFIC ITEMS ITSU-0QT8(22)DC		
509(B) 0321	CLASS A CONCRETE	0.240	CY
802(B) 8336	1 1/2" PVC SCH.40 PLASTIC CONDUIT BORED	800.000	LF
802(B) 8338	1 1/2" PVC SCH.40 PLASTIC CONDUIT TRENCH	2,900.000	LF
803 8075	(SP)GROUNG BOX, R1	2.000	EA
804(B) 2916	REINFORCING STEEL	25.200	LB
810(A) 3118	SERVICE POLE	1.000	EA
811 8046	1/C NO.12 ELECT.COND.	1,200.000	LF
818 8715	(PL)FIBER OPTIC CABLE, 24, SMF-28	900.000	LF
818 8720	(PL)FIBER OPTIC CABLE, 48, SMF-28	2,600.000	LF
818 8735	(PL)FIBER OPTIC CABLE SPLICE	336.000	EA
818 8740	(PL)FIBER OPTIC CABLE TERMINATION	336.000	EA
818 8745	(PL)FIBER OPTIC PATCH PANEL, 24 PORT	2.000	EA
818 8750	(PL)FIBER OPTIC PATCH PANEL, 48 PORT	1.000	EA
818 8755	(PL)FIBER OPTIC PATCH PANEL, 96 PORT	5.000	EA
877 5515	(PL)COMMUNICATION HUT, TYPE B	1.000	EA
877 5530	(PL)COMM. HUT POPULATION PACKAGE A	2.000	EA
877 5546	(PL)NETWORK EQUIPMENT PACKAGE B	2.000	EA
890(A) 8704	(PL)REMOVAL OF PULL BOX	1.000	EA
SECTION NO. 0002	SFTY-TRAFFIC ITEMS ITSU-0QT8(018)DC		
509(D) 0325	CLASS C CONCRETE	3.940	CY
641 1552	MOBILIZATION	1.000	LSUM
802(A) 8310	2" GALV.STEEL ELECT.COND. EXPOSED	400.000	LF
802(B) 8336	1 1/2" PVC SCH.40 PLASTIC CONDUIT BORED	1,220.000	LF
802(B) 8338	1 1/2" PVC SCH.40 PLASTIC CONDUIT TRENCH	6,160.000	LF
803 8066	PULL BOX(SIZE II)	5.000	EA
804(B) 2916	REINFORCING STEEL	63.000	LB
810(A) 3118	SERVICE POLE	1.000	EA
811 8046	1/C NO.12 ELECT.COND.	1,050.000	LF
818 8715	(PL)FIBER OPTIC CABLE, 24, SMF-28	8,600.000	LF
818 8720	(PL)FIBER OPTIC CABLE, 48, SMF-28	26,000.000	LF
818 8735	(PL)FIBER OPTIC CABLE SPLICE	344.000	EA
818 8740	(PL)FIBER OPTIC CABLE TERMINATION	704.000	EA
818 8745	(PL)FIBER OPTIC PATCH PANEL, 24 PORT	15.000	EA
818 8750	(PL)FIBER OPTIC PATCH PANEL, 48 PORT	6.000	EA

CALL ORDER : 560  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 030249  
 PCN : 1899306  
 PROJECTS : ITSU-0QT8(22) DC  
 ITSU-0QT8(18) DC  
 ITSU-0QT8(19) DC

COUNTIES : OKLAHOMA

DBE GOALS : 0.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 98.62  
 CALENDAR DAYS : 150  
 RES. ENG.:  
 LIQ. DAM.: \$ 500

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0002	SFTY-TRAFFIC ITEMS ITSU-0QT8(018)DC		
818	8755 (PL)FIBER OPTIC PATCH PANEL, 96 PORT	4.000	EA
818	8760 (PL)FIBER OPTIC PATCH PANEL CABEL, 5'	30.000	EA
818	8780 (PL)FIBER OPTIC & COMMUNICATION EQUIP.	1.000	LSUM
834	8358 (PL)UNDERGROUND COMMUNICATION CABLE	6,000.000	LF
877	5510 (PL)COMMUNICATION HUT, TYPE A	1.000	EA
877	5530 (PL)COMM. HUT POPULATION PACKAGE A	1.000	EA
877	5545 (PL)NETWORK EQUIPMENT PACKAGE A	1.000	EA
880(J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
895	6551 CABINET	2.000	EA
SECTION NO. 0003	SFTY-TRAFFIC ITEMS ITSU-0Q8(19)DC		
509(B)	0321 CLASS A CONCRETE	0.120	CY
641	1552 MOBILIZATION	1.000	LSUM
802(B)	8336 1 1/2" PVC SCH.40 PLASTIC CONDUIT BORED	300.000	LF
802(B)	8338 1 1/2" PVC SCH.40 PLASTIC CONDUIT TRENCH	1,600.000	LF
803	8075 (SP)GROUNG BOX, R1	1.000	EA
804(B)	2916 REINFORCING STEEL	12.600	LB
810(A)	3118 SERVICE POLE	1.000	EA
811	8046 1/C NO.12 ELECT.COND.	800.000	LF
818	8715 (PL)FIBER OPTIC CABLE, 24, SMF-28	900.000	LF
818	8735 (PL)FIBER OPTIC CABLE SPLICE	324.000	EA
818	8740 (PL)FIBER OPTIC CABLE TERMINATION	512.000	EA
818	8745 (PL)FIBER OPTIC PATCH PANEL, 24 PORT	3.000	EA
818	8750 (PL)FIBER OPTIC PATCH PANEL, 48 PORT	1.000	EA
818	8755 (PL)FIBER OPTIC PATCH PANEL, 96 PORT	4.000	EA
877	5515 (PL)COMMUNICATION HUT, TYPE B	1.000	EA
877	5530 (PL)COMM. HUT POPULATION PACKAGE A	1.000	EA
877	5531 (PL)COMM. HUT POPULATION PACKAGE B	1.000	EA
877	5546 (PL)NETWORK EQUIPMENT PACKAGE B	2.000	EA
880(J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
890(A)	8704 (PL)REMOVAL OF PULL BOX	1.000	EA

CALL ORDER : 580  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : OSAGE

CONTRACT ID : 030355  
 PCN : 2070304  
 PROJECTS : NHY-18N(34)3R  
 DBE GOALS : 5.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 CALENDAR DAYS : 60  
 RES. ENG. :  
 LIQ. DAM. : \$ 500

CONTRACT DESCRIPTION:

RESURFACE(ASPHALT) US-60; BEGIN AT JCT. US-60/SH-99 EAST OF  
 PAWHUSKA, EXTEND NORTH. PROJECT LENGTH = 3.25 MILES  
 FLEXIBLE ESALS = 1.0 MILLION ASPHALT GRADE = PG 70-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY(BASE BID) NHY-18N(34)3R		
202(C) 0184	UNCLASSIFIED BORROW	1,385.000	CY
411(S4) 5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	8,862.000	TON
417 5267	COLD MILLING PAVEMENT	58,154.000	SY
420(A) 4242	FABRIC REINFORCEMENT	34,615.000	SY
420(A) 4244	(PL)PRECOATED FABRIC MEMBRANE(STRIP)	346.000	LF
420(B) 4268	BITUMINOUS BINDER	8,654.000	GAL
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	47,520.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0002	I000-ROADWAY(ADD ALT.) NHY-18N(34)3R		
202(C) 0184	UNCLASSIFIED BORROW	615.000	CY
411(S4) 5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	3,938.000	TON
417 5267	COLD MILLING PAVEMENT	25,846.000	SY
420(A) 4242	FABRIC REINFORCEMENT	15,385.000	SY
420(A) 4244	(PL)PRECOATED FABRIC MEMBRANE(STRIP)	154.000	LF
420(B) 4268	BITUMINOUS BINDER	3,846.000	GAL
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	21,120.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

CALL ORDER : 590  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : OSAGE

CONTRACT ID : 030356  
 PCN : 2070404  
 PROJECTS : STPY-157B(52) 3R  
 DBE GOALS : 10.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 CALENDAR DAYS : 60  
 RES. ENG. :  
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:

RESURFACE(ASPHALT) SH-99; BEGIN AT JCT. SH-99/SH-11 NORTH  
 OF WYNONA, EXTEND NORTH. PROJECT LENGTH = 5.32 MILES  
 FLEXIBLE ESALS = 1.0 MILLION ASPHALT GRADE = PG 70-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY(BASE BID) STPY-157B(52)3R		
202(C) 0184	UNCLASSIFIED BORROW	2,842.000	CY
411(S4) 5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	18,670.000	TON
417 5267	COLD MILLING PAVEMENT	111,573.000	SY
420(A) 4242	FABRIC REINFORCEMENT	82,000.000	SY
420(A) 4244	(PL)PRECOATED FABRIC MEMBRANE(STRIP)	975.000	LF
420(B) 4268	BITUMINOUS BINDER	16,647.000	GAL
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	91,240.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0002	I0009ROADWAY(ADD ALT.) STPY-157B(52)3R		
202(C) 0184	UNCLASSIFIED BORROW	658.000	CY
411(S4) 5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	4,323.000	TON
417 5267	COLD MILLING PAVEMENT	25,828.000	SY
420(A) 4244	(PL)PRECOATED FABRIC MEMBRANE(STRIP)	225.000	LF
420(B) 4268	BITUMINOUS BINDER	3,854.000	GAL
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	21,120.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003	Y000-GUARDRAIL(BASE BID) STPY-157B(52)3R		
619(B) 4780	REMOVAL OF GUARD RAIL	500.000	LF
623(A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	300.000	LF
623(H) 8571	(SP)G.E.T. GUARD RAIL END SECTION	4.000	EA
853 9069	GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	10.000	EA

CALL ORDER : 600  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : OSAGE

CONTRACT ID : 030357  
 PCN : 2070304C  
 PROJECTS : NHY-18N(34)3R  
 STPY-157B(52) 3R  
 DBE GOALS : 6.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 CALENDAR DAYS : 120  
 RES. ENG.:  
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:  
 RESURFACE(ASPHALT) US-60/SH-99; BEGIN AT JCT. SH-99/SH-11  
 NORTH OF WYNONA, EXTEND NORTH. PROJECT LENGTH = 8.57 MILES  
 FLEXIBLE ESALS = 1.0 MILLION ASPHALT GRADE = PG 70-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY(BASE BID) NHY-18N(34)3R		
202(C) 0184	UNCLASSIFIED BORROW	1,385.000	CY
411(S4) 5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	8,862.000	TON
417 5267	COLD MILLING PAVEMENT	58,154.000	SY
420(A) 4242	FABRIC REINFORCEMENT	34,615.000	SY
420(A) 4244	(PL)PRECOATED FABRIC MEMBRANE(STRIP)	346.000	LF
420(B) 4268	BITUMINOUS BINDER	8,654.000	GAL
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	47,520.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0002	I000-ROADWAY(ADD ALT.) NHY-18N(34)3R		
202(C) 0184	UNCLASSIFIED BORROW	615.000	CY
411(S4) 5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	3,938.000	TON
417 5267	COLD MILLING PAVEMENT	25,846.000	SY
420(A) 4242	FABRIC REINFORCEMENT	15,385.000	SY
420(A) 4244	(PL)PRECOATED FABRIC MEMBRANE(STRIP)	154.000	LF
420(B) 4268	BITUMINOUS BINDER	3,846.000	GAL
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	21,120.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003	I000-ROADWAY(BASE BID) STPY-157B(52)3R		
202(C) 0184	UNCLASSIFIED BORROW	2,842.000	CY
411(S4) 5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	18,670.000	TON
417 5267	COLD MILLING PAVEMENT	111,573.000	SY
420(A) 4242	FABRIC REINFORCEMENT	82,000.000	SY
420(A) 4244	(PL)PRECOATED FABRIC MEMBRANE(STRIP)	975.000	LF
420(B) 4268	BITUMINOUS BINDER	16,647.000	GAL
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	91,240.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0004	I0009ROADWAY(ADD ALT.) STPY-157B(52)3R		
202(C) 0184	UNCLASSIFIED BORROW	658.000	CY
411(S4) 5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	4,323.000	TON
417 5267	COLD MILLING PAVEMENT	25,828.000	SY



CALL ORDER : 600  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : OSAGE

CONTRACT ID : 030357  
 PCN : 2070304C  
 PROJECTS : NHY-18N(34)3R  
 STPY-157B(52) 3R  
 DBE GOALS : 6.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 CALENDAR DAYS : 120  
 RES. ENG.:  
 LIQ. DAM.: \$ 500

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0004	I0009ROADWAY(ADD ALT.) STPY-157B(52)3R		
420(A) 4244	(PL)PRECOATED FABRIC MEMBRANE(STRIP)	225.000	LF
420(B) 4268	BITUMINOUS BINDER	3,854.000	GAL
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	21,120.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0005	Y000-GUARDRAIL(BASE BID) STPY-157B(52)3R		
619(B) 4780	REMOVAL OF GUARD RAIL	500.000	LF
623(A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	300.000	LF
623(H) 8571	(SP)G.E.T. GUARD RAIL END SECTION	4.000	EA
853 9069	GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	10.000	EA

CALL ORDER : 640  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : PUSHMATAHA

CONTRACT ID : 030370  
 PCN : 2071104  
 PROJECTS : STPY-164A(53)TR  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 2.17  
 CALENDAR DAYS : 30  
 RES. ENG.:  
 LIQ. DAM.: \$ 300

CONTRACT DESCRIPTION:  
 SCHOOL ZONE FLASHERS SH-3 IN RATTAN IN PUSHMATAHA COUNTY.  
 PROJECT LENGTH = 0.00 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	Y002 - SCHOOL ZONE FLASHERS		
641	1552 MOBILIZATION	1.000	LSUM
802(B)	8334 1" PVC SCH.40 PLASTIC CONDUIT TRENCHED	170.000	LF
803	8067 PULL BOX(SIZE III)	1.000	EA
804(A)	2915 STRUCTURAL CONCRETE	0.800	CY
804(B)	2916 REINFORCING STEEL	52.600	LB
810(A)	3118 SERVICE POLE	2.000	EA
811	8044 1/C NO.10 ELECT.COND.	600.000	LF
827	8623 SOLID STATE FLASHER CONTROLLER(TYPE II)	2.000	EA
831	8301 1WAY1SEC.ADJ.SIG.HD.S-22	4.000	EA
850(A)	8110 SHEET ALUMINUM SIGNS	62.100	SF
851(B)	3220 4"@10.79 GALV.STL.PIPE POST	24.000	LF
851(C)	8327 2 1/4" SQUARE TUBE POST	135.000	LF
880(J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
890(A)	8724 (PL)REMOVAL OF EXISTING SIGNS	6.000	EA

CALL ORDER : 660  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : TULSA

CONTRACT ID : 030371  
 PCN : 2057504  
 PROJECTS : NHY-30N(40)  
 DBE GOALS : 2.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 5.96  
 CALENDAR DAYS : 45  
 RES. ENG. :  
 LIQ. DAM. : \$ 500

## CONTRACT DESCRIPTION:

BRIDGE REPAIR US-169; NORTHBOUND RAMP TO I-244 WESTBOUND.  
 PROJECT LENGTH = 0.00 MILE ASPHALT GRADE = PG 76-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	X220-BRIDGE 'A'		
411(S4) 5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	132.000	TON
417 5267	COLD MILLING PAVEMENT	3,089.000	SY
504(H) 6390	RAPID CURE JOINT SEALANT	345.000	LF
505(B) 6019	CLASS B BRIDGE DECK REPAIR	810.000	SY
505(C) 6020	CLASS C BRIDGE DECK REPAIR	70.000	SY
505(D) 6087	LATEX MODIFIED BRIDGE DECK OVERLAY	2,156.000	SY
509(B) 1328	CLASS A CONCRETE	31.000	CY
511(B) 6010	EPOXY COATED REINFORCING STEEL	4,890.000	LB
515(A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	136.000	SY
520(A) 6058	PREPARATION OF CRACKS ABOVE WATER	50.000	LF
520(C) 6060	EPOXY RESIN ABOVE WATER	1.000	GAL
535 6130	(SP)CORROSION INHIBITOR(SURFACE APPLIED)	112.000	SY
540 4515	(PL)REPAIR BRIDGE ITEM (TYPE A)	1.000	EA
641 1399	MOBILIZATION	1.000	LSUM
SECTION NO. 0002	Y000-TRAFFIC		
619(B) 4780	REMOVAL OF GUARD RAIL	150.000	LF
627(G) 4316	RELOC.PORT.TYPE PRECAST CONC.MEDIAN BARR	1,300.000	LF
627(H) 5856	DEL.PORT.TYPE PREC. CONCRETE MEDIAN BARR	1,850.000	LF
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	2,270.000	LF
870(A) 8485	SAND FILLED IMPACT ATTEN.MODULE	30.000	SD
876(C) 8482	(PL)TRUCK MOUNTED ATTENUATOR	10.000	SD
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
880(L) 8911	TRAFFIC SURVEILLANCE, POLICE	50.000	HOURL
882(B) 8306	PORT.CHANGEABLE MESSAGE SIGN	60.000	SD

CALL ORDER : 661  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : TULSA

CONTRACT ID : 030078  
 PCN : 2102104  
 PROJECTS : SAP-172N(243)  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 2.71  
 CALENDAR DAYS : 25  
 RES. ENG.:  
 LIQ. DAM.: \$ 300

## CONTRACT DESCRIPTION:

OVERHEAD SIGN STRUCTURE AND SIGN REPLACEMENT US-169: AT  
 SH-266 IN TULSA, TULSA COUNTY. PROJECT LENGTH = 0.00 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	Y000 - TRAFFIC		
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
880(L) 8911	TRAFFIC SURVEILLANCE, POLICE	4.000	HOURL
SECTION NO. 0002	Y002 - SIGNING		
641 1399	MOBILIZATION	1.000	LSUM
802(A) 8300	3/4" GALV.STEEL ELECT.COND. EXPOSED	100.000	LF
802(B) 8342	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	200.000	LF
803 8065	PULL BOX(SIZE I)	2.000	EA
804(A) 2915	STRUCTURAL CONCRETE	27.880	CY
804(B) 2916	REINFORCING STEEL	742.000	LB
809(D) 8453	OVERHEAD SIGN LUMINAIRE	4.000	EA
811 8038	1/C NO.4 ELECT.COND.	300.000	LF
811 8044	1/C NO.10 ELECT.COND.	855.000	LF
850(A) 8110	SHEET ALUMINUM SIGNS	20.000	SF
850(B) 8114	EXTR.ALUM.PAN.SGN.(OVRHD SIGNS)	404.500	SF
852 8603	(PL)OVHD.SN.STR.WLKWAY&HANDRAIL-INTERNAL	90.000	LF
852 8604	(PL)OVHD.SN.STR.WLKWAY&HANDRAIL-EXTERNAL	55.000	LF
852A/B 8970	OVHD.SN.STR.TYPE C-1 ALUM./G.STL.90'	1.000	EA
870 8011	SAND FILLED IMPACT ATTEN.MODULE REMOVAL	1.000	LSUM
870(A) 8011	SAND FILLED IMPACT ATTEN.MODULE	38.000	EA
890(A) 8700	(PL)REMOVAL OF SIGN FOOTING	2.000	EA

CALL ORDER : 680  
 LETTING DATE : September 25, 2003  
 LETTING TIME : 10:30 A.M.  
 COUNTIES : WAGONER MUSKOGEE

CONTRACT ID : 030358  
 PCN : 2068504  
 PROJECTS : CMAY-173C(80) 3R  
 DBE GOALS : 3.00  
 GUARANTY : 5% OF BID TOTAL  
 PLAN PRICE : 0.00  
 CALENDAR DAYS : 90  
 RES. ENG. :  
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:  
 RESURFACE US-64: BEG. 0.56 MILES EAST OF THE TULSA /  
 WAGONER C/L EXTEND EAST TO HASKELL CITY LIMITS. PROJECT  
 LENGTH = 7.18 MILES FLEX ESALS = 3.0+ MILLION ASPHALT GRADE  
 = PG 70-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 I000-ROADWAY			
209 0120	MACHINE GRADING	56.000	STA
403(F) 7047	TRAFFIC BOUND SURFACE COURSE TYPE F	3,500.000	TON
407 0250	TACK COAT	12,100.000	GAL
411(S4) 5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	9,750.000	TON
411(S5) 5970	(SP)ASPH.CONC.,TYPE S5(PG 70-28 OK)	8,500.000	TON
417 5267	COLD MILLING PAVEMENT	4,380.000	SY
420(A) 4246	(PL)SELF ADH. STRES RELIEF FAB. INTRLYR.	270.000	SY
504(F) 1381	CONCRETE PARAPET	65.000	LF
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	124,500.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0002 Y000 - TRAFFIC			
619(B) 4780	REMOVAL OF GUARD RAIL	1,212.500	LF
623 8572	(PL)CURVED APPROACH GUARD RAIL	1.000	EA
623(A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	2,912.500	LF
623(F) 4447	GUARD RAIL ANCHOR UNIT (TYPE B)	2.000	EA
623(F) 5686	GUARD RAIL ANCHOR UNIT (TYPE D-BF)	11.000	EA
623(H) 8571	(SP)G.E.T. GUARD RAIL END SECTION	14.000	EA
853 9066	GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	78.000	EA