

Notice

Electronic bid packages are available for the [October 23, 2003](#) Letting. Instructions for using the electronic bidding system (EBS) are available from the Office Engineer's office. The printed bid sheets created from the EBS system must be placed in front of the bid item pages in the bidding proposal and will be turned in with the bid documents along with the proper disk. They should be placed and attached there without detaching the original proposal. (The paper copy of the bid items is the official bid document.) Please remember that you must use the electronic bidding system (EBS) when bidding projects in the highway Letting. Failure to use the EBS system could mean possible rejection of bids. Plans and proposals should be ready for sale on [September 29, 2003](#).

The direct line to the ODOT order desk is 522-3474. Please use this number when ordering plans and proposals. If ordering plans only please call the Reproduction Branch at 521-2586.

A Pre-Bid Conference will be held at [10:00 a.m.](#) on [October 10](#), 2003 concerning this [October](#) Bid Opening at the Oklahoma Department of Transportation (ODOT) Commission Room. Please review plans and proposals and send your comments and questions to the Office Engineer Division (attn: Masoud Pajoh or Jack Stewart) as early as possible at Fax: (405) 522-0972 or phone: (405) 521-2625. This will help both ODOT and Contractor.

All proposals not mailed must be turned into the Reproduction office off the main lobby of the ODOT building until 30 minutes before the Opening. From 30 minutes before the Bid Opening until the time of the Bid Opening, bid proposals must be turned in directly to the ODOT Commission Room on the east side of the lobby.

Please write the call order number of the jobs you are bidding electronically on the disk label of the original disk. Be sure to save your work and any revisions you receive to your original disk and submit that disk with your bid.

Mandatory Pre-Bid Conference

At 1:30 p.m. to 4:30 p.m. on Wednesday, October 15, 2003, a mandatory Pre-bid Conference will be held at the Oklahoma Department of Transportation Training Center, located at 1025 S.E. 59th Street (Northeast corner of I-35 and S.E. 59th) in Oklahoma City. The purpose of the Conference is to familiarize prospective bidders and ODOT Field personnel with the new Percent Within Limits QC-QA Specifications for asphalt concrete pavements.

Contractors bidding on any of the following October Letting Projects must attend the conference.

- IMY-0035-4(196)177; J/P 20247(04); Noble; I-35 from milepost 179.5 to 185.
- STPY-125C(069); J/P 18774(04); Garvin; SH- from 2 miles east of Lindsay extending east 2 miles.

Note:

NESHAP report for the following project is available upon request from the Office Engineer Division:
Muskogee County STPY-051C(404)RW

Note:

“As-Planned” utility location sheets for the following project are available upon request from the Office Engineer Division:
Tulsa County, NHY-14N(37)

Until further notice all projects which include a pay item for Contractors Quality Control (Item 643) will require the bidder to bid a minimum amount for that item.

This minimum will be specified at the end of the Special Provision 648-1QA(a)99, Payment for Contractor's Quality Control. You may increase this amount as necessary to cover the estimated Quality Control expenses.

Failure to include at least this amount will be considered grounds for rejection of Contractor's bid as nonresponsive.

Note:

ODOT will no longer allow DBE credit towards project DBE goals for the supplying of liquid asphalt cement or other bituminous materials.

**These Long Form and Short Form Notices and those in the future can be accessed on ODOT's Web site
<http://www.okladot.state.ok.us/>**

Reminder

The low bidder must submit to the Office Engineer Division written confirmation from the DBE that it is participating in the contract as provided in the prime contractor's commitment. This may be submitted with the bid or not later than the Department's close of business on the Wednesday following the bid opening. Otherwise the bid shall be considered nonresponsive and shall be rejected by the Department.

Reminder

*Please be sure that bid bonds are stapled to the **back** of the proposal as instructed on the cover sheet of all proposals.*

Note:

The **Order Form** included in this Short Form Notice may be used to order plans and proposals for this letting.

Please check off the proposal(s) in which you are interested and fax to:

405-522-0972 attention Linda Stoltz.

The Bid Opening can be heard from the AGC website which is:

<http://www.okagehwy.com/>

DATE : September 24, 2003
AHOMA DEPARTMENT OF TRANSPORTATION
NOTICE TO CONTRACTORS -- October 23, 2003

LNTCNCA
LETTING

LNTCNCA-D

SEALED PROPOSALS SENT BY REGISTERED MAIL WILL BE RECEIVED THROUGH THE ODOT REPRODUCTION BRANCH UNTIL 30 MINUTES PRIOR TO THE SCHEDULED BID OPENING. FROM 30 MINUTES PRIOR TO THE BID OPENING UNTIL THE TIME OF THE BID OPENING, BID PROPOSALS MUST BE TURNED IN DIRECTLY TO THE ODOT COMMISSION ROOM LOCATED ON THE EAST SIDE OF THE LOBBY. THE SCHEDULED BID OPENING OF 10:30 A.M. October 23, 2003 , FOR THE WORK LISTED BELOW.

NO PROPOSAL FOR CONSTRUCTION OR MAINTENANCE WORK OF THE DEPARTMENT WILL BE ISSUED TO ANY CONTRACTOR AFTER 10:30 A.M. ON THE WORKING DAY PRECEDING OPENING OF BIDS FOR ANY CONTRACT.

EACH SEPARATE PROPOSAL SHALL BE ACCOMPANIED BY A CERTIFIED OR CASHIER'S CHECK OR BID BOND EQUAL TO 5% OF THE BID MADE PAYABLE TO THE STATE OF OKLAHOMA, DEPARTMENT OF TRANSPORTATION, AS A PROPOSAL GUARANTY. PROPOSAL CHECKS WILL BE HELD OR RETURNED BY THE DEPARTMENT AS PER SECTION 103.04 OF THE STATE STANDARD SPECIFICATIONS.

THIS WORK WILL BE DONE UNDER THE OKLAHOMA DEPARTMENT OF TRANSPORTATION COMMISSION'S APPLICABLE SPECIFICATIONS FOR HIGHWAY CONSTRUCTION.

THE MINIMUM WAGE TO BE PAID LABORERS AND MECHANICS EMPLOYED ON THIS PROJECT WILL BE INCLUDED IN THE PROPOSAL.

PROPOSALS MUST BE PREPARED AS DIRECTED BY THE STATE STANDARD SPECIFICATIONS.

THIS WORK WILL BE DONE UNDER THE OKLAHOMA DEPARTMENT OF TRANSPORTATION COMMISSION'S APPLICABLE SPECIFICATIONS FOR HIGHWAY CONSTRUCTION AS DEPICTED ON THE LOWER LEFT CORNER OF THE PLAN'S TITLE SHEET.

PLANS, FORMS OF PROPOSALS, CONTRACTS AND SPECIFICATIONS MAY BE EXAMINED AT THE DIVISION HEADQUARTERS IN THE DIVISION THE WORK IS TO BE PERFORMED OR AT THE OKLAHOMA DEPARTMENT OF TRANSPORTATION OFFICE ENGINEER'S DIVISION IN OKLAHOMA CITY, OKLAHOMA.

PLANS AND PROPOSAL FORMS MAY BE ORDERED FROM JACK STEWART, DIVISION ENGINEER, OKLAHOMA DEPARTMENT OF TRANSPORTATION BUILDING, 200 N.E. 21ST STREET, OKLAHOMA CITY, OKLAHOMA 73105. COST OF BIDDING DOCUMENTS ARE \$25.00 + tax FOR EACH BIDDING PROPOSAL. STATE STANDARD SPECIFICATION 1988 EDITION (RED BOOK) AND 1991 SUPPLEMENT MAY BE PURCHASED FOR \$8.00 + tax, OR 1996 METRIC STANDARD SPECIFICATION \$27.00 + TAX, OR 1999 METRIC AND ENGLISH STANDARD SPECIFICATION \$55.00 + TAX. (OKLAHOMA TAX IS 8.375%). MAKE CHECKS PAYABLE TO OKLAHOMA DEPARTMENT OF TRANSPORTATION.

NO REFUNDS WILL BE MADE FOR BIDDING DOCUMENTS OR SPECIFICATION BOOKS PURCHASED BY PROSPECTIVE BIDDERS.

UPON AWARD OF CONTRACT TO A SUCCESSFUL BIDDER, THE CONTRACT WILL BE COMPLETELY AND CORRECTLY EXECUTED BY THE CONTRACTOR AND RETURNED TO THE DEPARTMENT WITHIN TEN (10) WORKING DAYS FROM THE DATE OF AWARD. THE DEPARTMENT WILL HAVE FOURTEEN (14) WORKING DAYS FROM THE DATE OF AWARD TO COMPLETE ITS EXECUTION OF THE CONTRACT.

THE OKLAHOMA DEPARTMENT OF TRANSPORTATION HEREBY NOTIFIES ALL BIDDERS THAT IT WILL AFFIRMATIVELY INSURE THAT IN ANY CONTRACT ENTERED INTO PURSUANT TO THIS ADVERTISEMENT, DISADVANTAGED BUSINESS ENTERPRISES WILL BE AFFORDED FULL OPPORTUNITY TO SUBMIT BIDS IN RESPONSE TO THIS INVITATION AND WILL NOT BE DISCRIMINATED AGAINST ON THE GROUNDS OF RACE, COLOR, SEX, RELIGION, NATIONAL ORIGIN, OR DISABILITY IN CONSIDERATION FOR AN AWARD.

BIDDERS ARE HEREBY NOTIFIED THAT ALL BIDS ARE LIKELY TO BE REJECTED IF THE LOWEST RESPONSIVE BID RECEIVED EXCEEDS THE ENGINEER'S ESTIMATE BY MORE THAN SEVEN (7) PERCENT. IN THE EVENT ALL BIDS ARE REJECTED FOR THIS REASON, THIS PROJECT MAY BE DEFERRED FOR READVERTISING FOR BIDS UNTIL A MORE COMPETITIVE SITUATION EXISTS.

DESCRIPTION OF WORK AND LOCATION OF PROJECT:

CALL ORDER : 040
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : CHEROKEE

CONTRACT ID : 030374
 PCN : 2046504
 PROJECTS : STPY-111A(59) TR
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 6.50
 CALENDAR DAYS : 30
 RES. ENG.:
 LIQ. DAM.: \$ 300

CONTRACT DESCRIPTION:
 TRAFFIC SIGNALS US-62: AT THE JUNCTION OF US-62 - SH-10
 / 51 / 82 (BERTHA PARKER BYPASS) AND 4TH STREET IN
 TAHLEQUAH. PROJECT LENGTH 0.00 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 Y000 - TRAFFIC			
641	1552	MOBILIZATION	1.000 LSUM
802(B)	8332	1" PVC SCH.40 PLASTIC CONDUIT BORED	210.000 LF
802(B)	8338	1 1/2" PVC SCH.40 PLASTIC CONDUIT TRENCH	800.000 LF
802(B)	8342	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	120.000 LF
802(B)	8344	3" PVC SCH.40 PLASTIC CONDUIT BORED	385.000 LF
802(B)	8346	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	80.000 LF
803	8065	PULL BOX(SIZE I)	3.000 EA
803	8066	PULL BOX(SIZE II)	1.000 EA
803	8067	PULL BOX(SIZE III)	4.000 EA
804(A)	2915	STRUCTURAL CONCRETE	11.200 CY
804(B)	2916	REINFORCING STEEL	1,705.400 LB
806(A)	8312	32'MH POLE 40'TS & 10'LMA(G.STL.)	1.000 EA
806(A)	8314	32'MH POLE 50'TS & 10'LMA(G.STL.)	1.000 EA
806(A)	8351	32'MH POLE 25',TS & 10'LMA(G.STL.)	1.000 EA
806(A)	8730	POLE & 35' TS MST.ARM(G.STL.)	1.000 EA
809(A)	8090	(PL)ROADWAY LUMINAIRE	3.000 EA
810(A)	3118	SERVICE POLE	1.000 EA
811	8040	1/C NO.6 ELECT.COND.	180.000 LF
811	8044	1/C NO.10 ELECT.COND.	1,640.000 LF
825	8550	VEH.ACT.SOL.ST.TRAF.SIG.CON.ASM	1.000 EA
828(A)	8135	SOL.STE.DIGITAL IND.VEH.LP.DET.	10.000 EA
828(B)	8138	LOOP DETECTOR WIRE	4,050.000 LF
831	8231	1WAY3SEC.ADJ.SIG.HD.S-6	6.000 EA
831	8252	1WAY3SEC.ADJ.SIG.HD.S-9	2.000 EA
831	8286	1WAY5SEC.ADJ.SIG.HD.S-19	2.000 EA
833	3030	BACKPLATE	10.000 EA
834(A)	8207	5/C TRAF.SIG.EL.CABLE	395.000 LF
834(A)	8208	7/C TRAF.SIG.EL.CABLE	445.000 LF
834(A)	8209	9/C TRAF.SIG.EL.CABLE	435.000 LF
834(B)	8220	2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	2,800.000 LF
840(A)	8592	(PL)E.P.S. OPTICAL EMITTER	5.000 EA
840(B)	8593	(PL)E.P.S. OPTICAL DETECTOR	4.000 EA
840(C)	8594	(PL)E.P.S. OPTICAL DETECTOR CABLE	1,115.000 LF
840(D)	8595	(PL)E.P.S. 2 CHANNEL PHASE SELECTOR	2.000 EA
850(C)	8118	MAST ARM MOUNTED SIGNS(ALUM.)	61.500 SF
855(A)	8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	2,285.000 LF
855(B)	8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	3.000 EA

CALL ORDER : 040
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : CHEROKEE

CONTRACT ID : 030374
 PCN : 2046504
 PROJECTS : STPY-111A(59) TR
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 6.50
 CALENDAR DAYS : 30
 RES. ENG. :
 LIQ. DAM. : \$ 300

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	Y000 - TRAFFIC		
855(B) 8821	TRAFFIC STRIPE (PLASTIC) (WORDS)	2.000	EA
859(A) 8006	PAVEMENT MRKNG.REMOVAL (TRAF.STRP)	500.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
890(A) 8724	(PL)REMOVAL OF EXISTING SIGNS	2.000	EA
SECTION NO. 0002	STAK - STAKING		
642 0098	STAKING	1.000	LSUM

CALL ORDER : 060
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : CLEVELAND

CONTRACT ID : 030373
 PCN : 1821104
 PROJECTS : STP-114B(48) AG
 DBE GOALS : 3.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 34.68
 CALENDAR DAYS : 200
 RES. ENG.:
 LIQ. DAM.: \$ 1000

CONTRACT DESCRIPTION:
 GRADE, DRAIN AND SURFACE (CONCRETE) PORTER AVENUE; FROM
 ROBINSON TO ROCK CREEK ROAD IN NORMAN. PROJECT LENGTH = 0.
 852 MILE FLEXIBLE ESALS = 0.1 MILLION ASPHALT GRADE = PG
 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 J000-ROADWAY			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202 (A)	0183 UNCLASSIFIED EXCAVATION	16,524.000	CY
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	6,200.000	LF
224	2803 TEMPORARY SEDIMENT FILTER	18.000	EA
227	0100 TEMPORARY SILT DIKE	120.000	LF
230 (A)	2806 SOLID SLAB SODDING	9,988.000	SY
232 (B)	2814 SEEDING METHOD B	2.000	AC
233 (A)	2817 VEGETATIVE MULCHING	2.000	AC
241	2832 MOWING	2.000	AC
326 (B)	4210 (SP)LIME	386.000	TON
326 (F)	4250 (SP)LIME STABILIZED SUBGRADE	34,262.000	SY
403 (E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	500.000	TON
407	0250 TACK COAT	18.000	GAL
408	5774 PRIME COAT	5,140.000	GAL
411 (S2)	5930 (SP)ASPH.CONC.,TYPE S2 (PG 64-22 OK)	7,770.000	TON
414 (A1)	5754 9" P.C. DOWEL JOINTED CONCRETE PAVEMENT	27,487.300	SY
414 (B1)	5758 9" H.E.S. DOWEL JOINTED CONCRETE PAV	4,208.800	SY
509 (D)	0325 CLASS C CONCRETE	1.800	CY
609 (A)	0380 CONC.CURB (8" BARRIER-INTEGRAL)	8,021.000	LF
610 (A)	0602 4" CONCRETE SIDEWALK	3,991.000	SY
610 (B)	0399 6" CONCRETE DRIVEWAY (H.E.S.)	1,310.000	SY
611 (A)	2657 MANHOLE (4' DIA.)	7.000	EA
611 (A)	2658 MANHOLE (5' DIA.)	9.000	EA
611 (B)	2680 ADD'L.DEPTH IN MANHOLE (4' DIA.)	1.600	VF
611 (B)	2681 ADD'L.DEPTH IN MANHOLE (5' DIA.)	15.200	VF
611 (D)	4215 MANHOLE FRAME & COVER	16.000	EA
611 (E)	5103 INLET CICI DES. 1 (C)	2.000	EA
611 (E)	5104 INLET CICI DES. 1 (D)	9.000	EA
611 (E)	5115 INLET CICI DES. 2 (D)	4.000	EA
611 (E)	5118 INLET CICI DES. 2 (B-D)	2.000	EA
611 (F)	5320 INLET CICI DES. 1 (ADD'L DEPTH)	8.200	VF
611 (F)	5325 INLET CICI DES. 2 (ADD'L DEPTH)	5.700	VF
611 (G)	4488 INLET FRM&GRT (SSIF-FRM,CIG-GRT-VG-F)	21.000	EA
611 (K)	4488 CAST IRON CURB INLETS	84.000	EA
612 (B)	0642 MANHOLES REBUILT	1.000	EA

CALL ORDER : 060
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : CLEVELAND

CONTRACT ID : 030373
 PCN : 1821104
 PROJECTS : STP-114B(48) AG
 DBE GOALS : 3.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 34.68
 CALENDAR DAYS : 200
 RES. ENG.:
 LIQ. DAM.: \$ 1000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 J000-ROADWAY			
612 (F) 0646	INLETS REBUILT	1.000	EA
613 (B) 0491	18" R.C.PIPE CLASS III	1,143.000	LF
613 (B) 0492	24" R.C.PIPE CLASS III	808.000	LF
613 (B) 0493	30" R.C.PIPE CLASS III	1,227.000	LF
613 (B) 0494	36" R.C.PIPE CLASS III	353.000	LF
613 (B) 0495	42" R.C.PIPE CLASS III	178.000	LF
613 (P) 1091	6" PERFORATED PIPE UNDERDRAIN ROUND	500.000	LF
613 (Q) 1096	6" NON-PERF.PIPE UNDERDRAIN RND.	200.000	LF
619 (A) 0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619 (B) 4726	REMOVAL OF CURB AND GUTTER	2,383.000	LF
619 (B) 4727	REMOVAL OF CONCRETE PAVEMENT	3,923.000	SY
619 (B) 4728	REMOVAL OF ASPHALT PAVEMENT	16,795.000	SY
619 (B) 4766	REMOVAL OF CONCRETE DRIVEWAY	1,530.000	SY
619 (B) 4792	REMOVAL OF SIDEWALK	474.000	SY
619 (C) 0924	SAWING PAVEMENT	1,125.000	LF
629 (A) 4958	MAILBOX INSTALLATION-SINGLE	4.000	EA
629 (B) 4959	MAILBOX INSTALLATION-MULTIPLE	1.000	EA
629 (C) 4960	MAILBOX	6.000	EA
629 (D) 4961	REMOVAL OF MAILBOX INSTALLATION	5.000	EA
640 1426	FIELD OFFICE	1.000	EA
641 1552	MOBILIZATION	1.000	LSUM
SECTION NO. 0002 Y000-TRAFFIC			
804 (A) 2915	STRUCTURAL CONCRETE	1.500	CY
828 (B) 8138	LOOP DETECTOR WIRE	230.000	LF
850 (A) 8110	SHEET ALUMINUM SIGNS	136.500	SF
851 (B) 3216	2"@3.65 GALV.STL.PIPE POST	391.500	LF
855 (A) 8812	TRAFFIC STRIPE (PLASTIC) (4" WIDE)	16,536.000	LF
855 (B) 8818	TRAFFIC STRIPE (PLASTIC) (ARROWS)	23.000	EA
855 (B) 8821	TRAFFIC STRIPE (PLASTIC) (WORDS)	2.000	EA
857 (A) 8935	PAVE.MARKERS CLASS C TYPE 1-B	92.000	EA
857 (A) 8947	PAVE.MARKERS CLASS C TYPE 2-C	110.000	EA
857 (A) 8950	PAVE.MARKERS CLASS C TYPE 2-D	161.000	EA
859 (A) 8006	PAVEMENT MRKNG.REMOVAL (TRAF.STRP)	10,000.000	LF
880 (J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
890A/B 8756	(PL)REMOVE & RESET EXISTING SIGNS	2.000	EA
SECTION NO. 0003 STAK-STAKING			
642 0098	STAKING	1.000	LSUM
SECTION NO. 0004 Y060-NON-PARTICIPATING			
612 (A) 0641	MANHOLES ADJUST TO GRADE	2.000	EA

CALL ORDER : 080
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : COMANCHE

CONTRACT ID : 030406
 PCN : 1016707
 PROJECTS : STPY-116C(001)
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 57.44
 CALENDAR DAYS : 300
 RES. ENG.:
 LIQ. DAM.: \$ 1000

CONTRACT DESCRIPTION:
 GRADE, DRAIN AND SURFACE(RECONSTRUCT EXISTING LANES) SH-49;
 BEGIN AT JCT. SH-58, EXTEND EAST. PROJECT LENGTH = 5.224 KM.
 FLEXIBLE ESALS = 5.5 MILLION ASPHALT GRADE = PG 64-22 OK,
 PG 70-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 I000-ROADWAY			
202 (E) M0110	EMBANKMENTS	82,188.000	M3
202 (G) M0185	EARTHWORK	1.000	LSUM
205 4229	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
221 M2800	TEMPORARY SLOPE DRAINS	200.000	M
222 M2801	TEMPORARY BALE BARRIER	100.000	M
223 M2802	TEMPORARY SILT FENCE	100.000	M
224 M2803	TEMPORARY SEDIMENT FILTER	10.000	EA
225 M2804	TEMPORARY SEDIMENT BASIN	10.000	EA
226 M2805	TEMPORARY SEDIMENT REMOVAL	500.000	M3
227 M0100	TEMPORARY SILT DIKE	1,940.000	M
229 M4318	DITCH LINER PROTECTION	2,026.000	M
230 (A) M2806	SOLID SLAB SODDING	68,345.000	M2
230 (F) M2812	WATERING	4,806.800	KL
232 (B) M2814	SEEDING METHOD B	35.300	HA
233 (A) M2817	VEGETATIVE MULCHING	35.300	HA
234 (A) M2824	FERTILIZING (10-20-10)	7.400	T
235 (A) M0100	(PL)ROCK FILTER DAM, TYPE 1	20.000	M3
241 M2832	MOWING	17.700	HA
303 M0192	AGGREGATE BASE	15,393.000	M3
310 (B) M0149	SUBGRADE, METHOD B	3,612.000	M2
325 M5271	SEPARATOR FABRIC	76,966.000	M2
326 (B) M4210	(SP)LIME	3,137.000	T
326 (F) M4250	(SP)LIME STABILIZED SUBGRADE	102,675.000	M2
403 (E) M0225	TRAFFIC BOUND SURFACE COURSE TYPE E	22,827.000	T
407 M0250	TACK COAT	35,930.000	L
408 M5774	PRIME COAT	109,617.000	L
411 (S2)M5930	(SP)ASPH.CONC.,TYPE S2 (PG 64-22 OK)	17,831.000	T
411 (S3)M5940	(SP)ASPH.CONC.,TYPE S3 (PG 70-28 OK)	7,455.000	T
411 (S3)M5945	(SP)ASPH.CONC.,TYPE S3 (PG 64-22 OK)	4,261.000	T
411 (S4)M5955	(SP)ASPH.CONC.,TYPE S4 (PG 70-28 OK)	5,052.000	T
411 (S4)M5960	(SP)ASPH.CONC.,TYPE S4 (PG 64-22 OK)	5,844.000	T
413 (A) M4861	RUMBLE STRIP-METHOD AC-CON	10,246.000	M
414 (A1)M5754	225MM P.C. DOWEL JOINTED CONCRETE PAVE.	5,319.000	M2
501 (A) M0313	STRUCTURAL EXCAVATION UNCLASSIFIED	107.900	M3
509 (B) M0321	CLASS A CONCRETE	133.500	M3
509 (D) M0325	CLASS C CONCRETE	736.000	M3

CALL ORDER : 080
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : COMANCHE

CONTRACT ID : 030406
 PCN : 1016707
 PROJECTS : STPY-116C(001)
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 57.44
 CALENDAR DAYS : 300
 RES. ENG. :
 LIQ. DAM. : \$ 1000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY		
511 (A) M0332	REINFORCING STEEL	13,075.000	KG
601 (A) M0297	TYPE I PLAIN RIPRAP	219.400	T
601A-2 M0538	TYPE I-A FILTER BLANKET	68.400	T
609 (B) M1500	500MM COMB.CRB.& GUT.(100MM MNTBLE)	664.000	M
610 (B) M0604	150MM CONCRETE DRIVEWAY	864.800	M2
610 (C) M0608	100MM CONCRETE DIVIDING STRIP	478.100	M2
611 (E) M6002	INLET (SMD-TYPE 2)	11.000	EA
613 (B) M0405	450MM R.C.PIPE CLASS III	267.700	M
613 (B) M0415	900MM R.C.PIPE CLASS III	11.500	M
613 (B) M0417	1050MM R.C.PIPE CLASS III	24.300	M
613 (B) M0419	1200MM R.C.PIPE CLASS III	7.800	M
613 (B) M4427	1485MM X 915MM R.C.PIPE ARCH CLASS A-III	12.300	M
613 (CC)M7186	TYPE A4 CULVERT END TREATMENT	29.000	EA
613 (CC)M7196	TYPE A6 CULVERT END TREATMENT	29.000	EA
613 (D) M0689	450MM CORR. GALV. STEEL PIPE	742.500	M
613 (D) M0690	600MM CORR. GALV. STEEL PIPE	8.500	M
613 (M) M0897	450MM PREFAB. CULVERT END SEC., ROUND	5.000	EA
613 (M) M0980	1050MM PREFAB. CULVERT END SEC., ROUND	1.000	EA
613 (MM)M7500	TYPE A4 SLOPED CONCRETE END SECTION	2.000	EA
613 (MM)M7503	TYPE D4 SLOPED CONCRETE END SECTION	1.000	EA
613 (MM)M7505	TYPE F4 SLOPED CONCRETE END SECTION	3.000	EA
613 (MM)M7520	TYPE A6 SLOPED CONCRETE END SECTION	2.000	EA
613 (MM)M7523	TYPE D6 SLOPED CONCRETE END SECTOPM	1.000	EA
613 (MM)M7525	TYPE F6 SLOPED CONCRETE END SECTION	1.000	EA
613 (P) M1092	200MM PERFORATED PIPE UNDERDRAIN ROUND	150.000	M
613 (Q) M1097	200MM NON-PERF.PIPE UNDERDRAIN RND.	430.000	M
619 (A) M0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619 (B) M4727	REMOVAL OF CONCRETE PAVEMENT	5,265.000	M2
619 (B) M4728	REMOVAL OF ASPHALT PAVEMENT	48,152.000	M2
619 (C) M0924	SAWING PAVEMENT	325.000	M
623 (A) M0932	BEAM GUARD RAIL-W-BEAM-SINGLE	124.100	M
623 (H) M8571	(SP)G.E.T. GUARD RAIL END SECTION	6.000	EA
624 (A) M4281	FENCE-STYLE WWF	98.000	M
629 (A) M4958	MAILBOX INSTALLATION-SINGLE	16.000	EA
629 (B) M4959	MAILBOX INSTALLATION-MULTIPLE	2.000	EA
629 (C) M4960	MAILBOX	24.000	EA
629 (D) M4961	REMOVAL OF MAILBOX INSTALLATION	24.000	EA
640 M1398	FIELD OFFICE	1.000	EA
641 M1399	MOBILIZATION	1.000	LSUM
643 M0087	(SP) CONTRACTORS QUALITY CONTROL	1.000	LSUM
653 (A) M5915	EDGE DRAIN CONDUIT-PERFORATED	4,952.000	M
653 (B) M5916	EDGE DRAIN OUTLET LATERAL-NONPERFORATED	49.300	M
653 (C) M5946	OUTLET LATERAL HEADWALL	17.000	EA

CALL ORDER : 080
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : COMANCHE

CONTRACT ID : 030406
 PCN : 1016707
 PROJECTS : STPY-116C(001)
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 57.44
 CALENDAR DAYS : 300
 RES. ENG.:
 LIQ. DAM.: \$ 1000

SECTION NO. 0002		Y002-TRAFFIC ITEMS		
850(A)	M8110	SHEET ALUMINUM SIGNS	6.700	M2
851(C)	M8327	57MM SQUARE TUBE POST	26.800	M
851(C)	M8330	64MM SQUARE TUBE POST	3.400	M
853	M9024	DELINEATORS (TYPE 1, CODE 1)	2.000	EA
853	M9039	DELINEATORS (TYPE 2, CODE 3)	4.000	EA
855(A)	M8812	TRAFFIC STRIPE (PLASTIC) (100MM WIDE)	16,597.000	M
855(B)	M8818	TRAFFIC STRIPE (PLASTIC) (ARROWS)	22.000	EA
855(B)	M8821	TRAFFIC STRIPE (PLASTIC) (WORDS)	11.000	EA
857(A)	M8947	PAVE.MARKERS CLASS C TYPE 2-C	30.000	EA
880(I)	M8902	FLAGGER	90.000	SD
880(J)	M8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
890A/B	M8760	(PL)REMOVE & RESET GROUND MOUNTED SIGN	87.000	EA
SECTION NO. 0003		STAK-STAKING		
642	M0098	STAKING	1.000	LSUM

CALL ORDER : 090
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : COMANCHE

CONTRACT ID : 030375
 PCN : 1953604
 PROJECTS : BRO-116D(70)CO
 DBE GOALS : 9.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 7.59
 CALENDAR DAYS : 90
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:
 BRIDGE AND APPROACHES COUNTY ROAD; OVER UNNAMED TRIBUTARY
 TO COTTONWOOD CREEK, 4.0 MILES EAST AND 0.7 MILE SOUTH OF
 SH-65/SH-17 JCT. PROJECT LENGTH = 0.265 MILE FLEXIBLE ESALS
 = 0.2 MILLION ASPHALT GRADE = PG 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 I000-ROADWAY BRO-116D(70)CO			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202 (G)	0185 EARTHWORK	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	554.000	LF
227	0100 TEMPORARY SILT DIKE	180.000	LF
229	4318 DITCH LINER PROTECTION	2,423.000	LF
230 (A)	2806 SOLID SLAB SODDING	7,000.000	SY
233 (A)	2817 VEGETATIVE MULCHING	4.200	AC
311 (B)	0152 PROCESS EXISTING BASE & SURFACE, METHOD B	12.000	STA
411 (S3)	5945 (SP) ASPH. CONC., TYPE S3 (PG 64-22 OK)	809.000	TON
411 (S4)	5960 (SP) ASPH. CONC., TYPE S4 (PG 64-22 OK)	380.000	TON
509 (D)	0325 CLASS C CONCRETE	199.000	CY
850 (A)	8110 SHEET ALUMINUM SIGNS	10.000	SF
851 (C)	8327 2 1/4" SQUARE TUBE POST	26.000	LF
854 (A)	8800 TRAFFIC STRIPE (PAINT) (4" WIDE)	2,800.000	LF
SECTION NO. 0002 X081-BRIDGE 'A' BRO-116D(70)CO			
501 (B)	1307 SUBSTRUCTURE EXCAVATION COMMON	78.000	CY
501 (D)	6353 UNCLASSIFIED BACKFILL	64.000	CY
503 (A)	1312 PRESTRESSED CONCRETE BEAMS (TYPE III)	296.670	LF
504 (E)	1380 CONCRETE RAIL (TR1)	207.000	LF
506 (A)	1322 STRUCTURAL STEEL	1,620.000	LB
509 (A)	1326 CLASS AA CONCRETE	58.300	CY
509 (B)	1328 CLASS A CONCRETE	48.800	CY
511 (A)	0332 REINFORCING STEEL	20,093.000	LB
514 (A)	6010 PILES, FURNISHED (HP 10X42)	160.000	LF
514 (A)	6011 PILES, FURNISHED (HP 12X53)	470.610	LF
514 (B)	6292 PILES, DRIVEN (HP 10X42)	160.000	LF
514 (B)	6294 PILES, DRIVEN (HP 12X53)	470.610	LF
601 (A-1)	1353 TYPE I-A PLAIN RIPRAP	1,047.000	TON
601 (A-2)	1355 TYPE I-A FILTER BLANKET	333.000	TON
619 (D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623 (F)	6033 GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
641	1399 MOBILIZATION	1.000	LSUM
880 (J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAK-STAKING BRO-116D(70)CO			
642	0098 STAKING	1.000	LSUM

CALL ORDER : 100
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : COMANCHE

CONTRACT ID : 030376
 PCN : 1954404
 PROJECTS : BRO-116D(71)CO
 DBE GOALS : 7.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 5.42
 CALENDAR DAYS : 90
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:
 BRIDGE AND APPROACHES COUNTY ROAD; OVER UNNAMED TRIBUTARY
 TO SANDY CREEK, 2.0 MILES WEST AND 6.2 MILES NORTH OF
 INDIAHOMA. PROJECT LENGTH = 0.175 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 E000-ROADWAY BRO116D(71)CO			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(G)	0185 EARTHWORK	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	1,000.000	LF
227	0100 TEMPORARY SILT DIKE	500.000	LF
230(A)	2806 SOLID SLAB SODDING	2,190.000	SY
233(A)	2817 VEGETATIVE MULCHING	0.450	AC
403(E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	713.000	TON
509(D)	0325 CLASS C CONCRETE	10.000	CY
613(D)	0689 18" CORR. GALV. STEEL PIPE	60.000	LF
613(M)	5726 18" PREFAB. CULVERT END SEC., ROUND	4.000	EA
SECTION NO. 0002 X081-BRIDGE 'A' BRO-116D(71)CO			
501(B)	1307 SUBSTRUCTURE EXCAVATION COMMON	96.000	CY
501(D)	6353 UNCLASSIFIED BACKFILL	114.000	CY
503(A)	1313 PRESTRESSED CONCRETE BEAMS (TYPE IV)	396.170	LF
504(E)	1380 CONCRETE RAIL (TR1)	272.000	LF
506(A)	1322 STRUCTURAL STEEL	2,020.000	LB
509(A)	1326 CLASS AA CONCRETE	77.200	CY
509(B)	1328 CLASS A CONCRETE	63.800	CY
511(A)	1332 REINFORCING STEEL	25,952.000	LB
514	6260 (PL)PILOT HOLES	195.000	LF
514(A)	6010 PILES, FURNISHED (HP 10X42)	82.800	LF
514(A)	6011 PILES, FURNISHED (HP 12X53)	212.800	LF
514(B)	6292 PILES, DRIVEN (HP 10X42)	82.800	LF
514(B)	6294 PILES, DRIVEN (HP 12X53)	212.800	LF
601(A-1)	1353 TYPE I-A PLAIN RIPRAP	455.000	TON
601(A-2)	1355 TYPE I-A FILTER BLANKET	100.000	TON
619(D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F)	6033 GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
641	1399 MOBILIZATION	1.000	LSUM
880(J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAK-STAKING BRO-116D(71)CO			
642	0098 STAKING	1.000	LSUM

CALL ORDER : 110
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : COMANCHE

CONTRACT ID : 030377
 PCN : 1974104
 PROJECTS : BRF-116C(75)CO
 DBE GOALS : 3.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 6.50
 CALENDAR DAYS : 150
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:
 BRIDGE AND APPROACHES COUNTY ROAD; OVER WEST CACHE CREEK, 4.
 0 MILES SOUTH AND 1.6 MILES EAST OF CACHE. PROJECT LENGTH =
 0.171 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 E000-ROADWAY BRF-116C(75)CO			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202 (G)	0185 EARTHWORK	1.000	LSUM
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	1,000.000	LF
227	0100 TEMPORARY SILT DIKE	500.000	LF
230 (A)	2806 SOLID SLAB SODDING	800.000	SY
233 (A)	2817 VEGETATIVE MULCHING	0.320	AC
403 (E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	617.000	TON
509 (D)	0325 CLASS C CONCRETE	10.000	CY
613 (D)	0689 18" CORR. GALV. STEEL PIPE	60.000	LF
613 (M)	5726 18" PREFAB. CULVERT END SEC., ROUND	4.000	EA
SECTION NO. 0002 X081-BRIDGE BRF-116C(75)CO			
501 (B)	1307 SUBSTRUCTURE EXCAVATION COMMON	96.000	CY
501 (D)	6353 UNCLASSIFIED BACKFILL	114.000	CY
503 (A)	1313 PRESTRESSED CONCRETE BEAMS (TYPE IV)	1,028.510	LF
504 (E)	1380 CONCRETE RAIL (TR1)	592.000	LF
506 (A)	1322 STRUCTURAL STEEL	5,570.000	LB
509 (A)	1326 CLASS AA CONCRETE	197.800	CY
509 (B)	1328 CLASS A CONCRETE	103.100	CY
511 (A)	1332 REINFORCING STEEL	60,216.000	LB
514	6260 (PL)PILOT HOLES	67.000	LF
514 (A)	6010 PILES, FURNISHED (HP 10X42)	412.200	LF
514 (B)	6292 PILES, DRIVEN (HP 10X42)	412.200	LF
516 (A)	6094 DRILLED SHAFTS 48" DIAMETER	104.000	LF
601 (A-1)	1353 TYPE I-A PLAIN RIPRAP	1,474.000	TON
601 (A-2)	1355 TYPE I-A FILTER BLANKET	341.000	TON
619 (D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623 (F)	6033 GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
641	1399 MOBILIZATION	1.000	LSUM
880 (J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAK-STAKING BRF-116C(75)CO			
642	0098 STAKING	1.000	LSUM

CALL ORDER : 120
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : COMANCHE

CONTRACT ID : 030378
 PCN : 1953604C
 PROJECTS: BRO-116D(70) (71)CO/BRF-116C(75)
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 19.51
 CALENDAR DAYS : 230
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:
 BRIDGES AND APPROACHES COUNTY ROAD; OVER UNNAMED TRIBUTARY TO COTTONWOOD CREEK, 4.0 MILES EAST AND 0.7 MILE SOUTH OF SH-65/SH-17 JCT./ COUNTY ROAD; OVER UNNAMED TRIBUTARY TO SANDY CREEK, 2.0 MILES WEST AND 6.2 MILES NORTH OF INDIAHOMA/ COUNTY ROAD; OVER WEST CACHE CREEK, 4.0 MILES SOUTH AND 1.6 MILES EAST OF CACHE. PROJECT LENGTH = 0.611 MILE FLEXIBLE ESALS = 0.2 MILLION ASPHALT GRADE = PG 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 I000-ROADWAY BRO-116D(70)CO			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202 (G)	0185 EARTHWORK	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	554.000	LF
227	0100 TEMPORARY SILT DIKE	180.000	LF
229	4318 DITCH LINER PROTECTION	2,423.000	LF
230 (A)	2806 SOLID SLAB SODDING	7,000.000	SY
233 (A)	2817 VEGETATIVE MULCHING	4.200	AC
311 (B)	0152 PROCESS EXISTING BASE & SURFACE,METHOD B	12.000	STA
411 (S3)	5945 (SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	809.000	TON
411 (S4)	5960 (SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	380.000	TON
509 (D)	0325 CLASS C CONCRETE	199.000	CY
850 (A)	8110 SHEET ALUMINUM SIGNS	10.000	SF
851 (C)	8327 2 1/4" SQUARE TUBE POST	26.000	LF
854 (A)	8800 TRAFFIC STRIPE(PAINT) (4" WIDE)	2,800.000	LF
SECTION NO. 0002 E000-ROADWAY BRO116D(71)CO			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202 (G)	0185 EARTHWORK	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	1,000.000	LF
227	0100 TEMPORARY SILT DIKE	500.000	LF
230 (A)	2806 SOLID SLAB SODDING	2,190.000	SY
233 (A)	2817 VEGETATIVE MULCHING	0.450	AC
403 (E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	713.000	TON
509 (D)	0325 CLASS C CONCRETE	10.000	CY
613 (D)	0689 18" CORR. GALV. STEEL PIPE	60.000	LF
613 (M)	5726 18" PREFAB. CULVERT END SEC., ROUND	4.000	EA
SECTION NO. 0003 E000-ROADWAY BRF-116C(75)CO			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202 (G)	0185 EARTHWORK	1.000	LSUM

CALL ORDER : 120
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : COMANCHE

CONTRACT ID : 030378
 PCN : 1953604C
 PROJECTS : BRO-116D(70) (71)CO/BRF-116C(75)
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 19.51
 CALENDAR DAYS : 230
 RES. ENG.:
 LIQ. DAM.: \$ 500

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003 E000-ROADWAY BRF-116C(75)CO			
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	1,000.000	LF
227	0100 TEMPORARY SILT DIKE	500.000	LF
230(A)	2806 SOLID SLAB SODDING	800.000	SY
233(A)	2817 VEGETATIVE MULCHING	0.320	AC
403(E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	617.000	TON
509(D)	0325 CLASS C CONCRETE	10.000	CY
613(D)	0689 18" CORR. GALV. STEEL PIPE	60.000	LF
613(M)	5726 18" PREFAB. CULVERT END SEC., ROUND	4.000	EA
SECTION NO. 0004 X081-BRIDGE 'A' BRO-116D(70)CO			
501(B)	1307 SUBSTRUCTURE EXCAVATION COMMON	78.000	CY
501(D)	6353 UNCLASSIFIED BACKFILL	64.000	CY
503(A)	1312 PRESTRESSED CONCRETE BEAMS (TYPE III)	296.670	LF
504(E)	1380 CONCRETE RAIL (TR1)	207.000	LF
506(A)	1322 STRUCTURAL STEEL	1,620.000	LB
509(A)	1326 CLASS AA CONCRETE	58.300	CY
509(B)	1328 CLASS A CONCRETE	48.800	CY
511(A)	0332 REINFORCING STEEL	20,093.000	LB
514(A)	6010 PILES, FURNISHED (HP 10X42)	160.000	LF
514(A)	6011 PILES, FURNISHED (HP 12X53)	470.610	LF
514(B)	6292 PILES, DRIVEN (HP 10X42)	160.000	LF
514(B)	6294 PILES, DRIVEN (HP 12X53)	470.610	LF
601(A-1)	1353 TYPE I-A PLAIN RIPRAP	1,047.000	TON
601(A-2)	1355 TYPE I-A FILTER BLANKET	333.000	TON
619(D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F)	6033 GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
641	1399 MOBILIZATION	1.000	LSUM
880(J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0005 X081-BRIDGE 'A' BRO-116D(71)CO			
501(B)	1307 SUBSTRUCTURE EXCAVATION COMMON	96.000	CY
501(D)	6353 UNCLASSIFIED BACKFILL	114.000	CY
503(A)	1313 PRESTRESSED CONCRETE BEAMS (TYPE IV)	396.170	LF
504(E)	1380 CONCRETE RAIL (TR1)	272.000	LF
506(A)	1322 STRUCTURAL STEEL	2,020.000	LB
509(A)	1326 CLASS AA CONCRETE	77.200	CY
509(B)	1328 CLASS A CONCRETE	63.800	CY
511(A)	1332 REINFORCING STEEL	25,952.000	LB
514	6260 (PL)PILOT HOLES	195.000	LF
514(A)	6010 PILES, FURNISHED (HP 10X42)	82.800	LF

CALL ORDER : 120
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : COMANCHE

CONTRACT ID : 030378
 PCN : 1953604C
 PROJECTS : BRO-116D(70) (71)CO/BRF-116C(75)
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 19.51
 CALENDAR DAYS : 230
 RES. ENG.:
 LIQ. DAM.: \$ 500

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0005	X081-BRIDGE 'A' BRO-116D(71)CO		
514 (A) 6011	PILES, FURNISHED (HP 12X53)	212.800	LF
514 (B) 6292	PILES, DRIVEN (HP 10X42)	82.800	LF
514 (B) 6294	PILES, DRIVEN (HP 12X53)	212.800	LF
601 (A-1) 1353	TYPE I-A PLAIN RIPRAP	455.000	TON
601 (A-2) 1355	TYPE I-A FILTER BLANKET	100.000	TON
619 (D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623 (F) 6033	GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
641 1399	MOBILIZATION	1.000	LSUM
880 (J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0006	X081-BRIDGE 'A' BRF-116C(75)CO		
501 (B) 1307	SUBSTRUCTURE EXCAVATION COMMON	96.000	CY
501 (D) 6353	UNCLASSIFIED BACKFILL	114.000	CY
503 (A) 1313	PRESTRESSED CONCRETE BEAMS (TYPE IV)	1,028.510	LF
504 (E) 1380	CONCRETE RAIL (TR1)	592.000	LF
506 (A) 1322	STRUCTURAL STEEL	5,570.000	LB
509 (A) 1326	CLASS AA CONCRETE	197.800	CY
509 (B) 1328	CLASS A CONCRETE	103.100	CY
511 (A) 1332	REINFORCING STEEL	60,216.000	LB
514 6260	(PL)PILOT HOLES	67.000	LF
514 (A) 6010	PILES, FURNISHED (HP 10X42)	412.200	LF
514 (B) 6292	PILES, DRIVEN (HP 10X42)	412.200	LF
516 (A) 6094	DRILLED SHAFTS 48" DIAMETER	104.000	LF
601 (A-1) 1353	TYPE I-A PLAIN RIPRAP	1,474.000	TON
601 (A-2) 1355	TYPE I-A FILTER BLANKET	341.000	TON
619 (D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623 (F) 6033	GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
641 1399	MOBILIZATION	1.000	LSUM
880 (J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0007	STAK-STAKING BRO-116D(70)CO		
642 0098	STAKING	1.000	LSUM
SECTION NO. 0008	STAK-STAKING BRO-116D(71)CO		
642 0098	STAKING	1.000	LSUM
SECTION NO. 0009	STAK-STAKING BRF-116C(75)CO		
642 0098	STAKING	1.000	LSUM

CALL ORDER : 130
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : COMANCHE

CONTRACT ID : 030079
 PCN : 1979304
 PROJECTS : SAP-116D(76)
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 14.09
 CALENDAR DAYS : 75
 RES. ENG. :
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:
 SURFACE(ASPHALT) INDUSTRIAL ACCESS; FOR FT. SILL NATIONAL
 CEMETERY, ON JAKE DUNN ROAD, BEGIN 1.443 MILES SOUTH OF
 US-277, EXTEND NORTH. PROJECT LENGTH = 1.443 MILES FLEXIBLE
 ESALS = 0.17 MILLION ASPHALT GRADE = PG 64-22 OK (FAST
 CONTRACT TURN-AROUND)

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 I000-ROADWAY			
209	0120 MACHINE GRADING	76.210	STA
230 (A)	2806 SOLID SLAB SODDING	34,043.000	SY
241	2832 MOWING	7.100	AC
326 (A)	4200 (SP) FLY ASH	1,257.000	TON
326 (B)	4210 (SP) LIME	210.000	TON
326 (E)	4240 (SP) CEMENTITIOUS STABILIZED SUBGRADE	23,150.000	SY
326 (F)	4250 (SP) LIME STABILIZED SUBGRADE	11,575.000	SY
403 (E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	100.000	TON
407	0250 TACK COAT	2,286.000	GAL
408	5774 PRIME COAT	3,531.000	GAL
411 (S3)	5945 (SP) ASPH.CONC., TYPE S3 (PG 64-22 OK)	6,464.000	TON
411 (S4)	5960 (SP) ASPH.CONC., TYPE S4 (PG 64-22 OK)	2,530.000	TON
641	1552 MOBILIZATION	1.000	LSUM
855 (A)	3250 TRAFFIC STRIPE (PLASTIC) (4" WIDE) (YELLOW)	30,154.000	LF
880 (J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0002 STAK-STAKING			
642	0098 STAKING	1.000	LSUM

CALL ORDER : 150
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : CRAIG

CONTRACT ID : 030379
 PCN : 1992904
 PROJECTS : BRO-118D(31) CO
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 7.59
 CALENDAR DAYS : 100
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:
 BRIDGE AND APPROACHES COUNTY ROAD; OVER COW CREEK ON THE
 OTTAWA COUNTY LINE, 0.9 MILE NORTH OF SH-10. PROJECT LENGTH
 = 0.283 MILE (FAST CONTRACT TURN-AROUND)

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 E000-ROADWAY BRO-118D(31)CO			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202 (A)	0183 UNCLASSIFIED EXCAVATION	1,681.000	CY
202 (C)	0184 UNCLASSIFIED BORROW	6,750.000	CY
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	2,400.000	LF
227	0100 TEMPORARY SILT DIKE	160.000	LF
230 (A)	2806 SOLID SLAB SODDING	5,988.000	SY
233 (A)	2817 VEGETATIVE MULCHING	2.500	AC
403 (E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	940.000	TON
613 (B)	0491 18" R.C.PIPE CLASS III	40.000	LF
613 (B)	4505 24" X 38" R.C.PIPE ELL. CLASS HE-III	39.000	LF
613 (C)	4373 SP. END SECTION OF 18" RCP ROUND	2.000	EA
613 (C)	5100 SP. END SECTION OF 24" X 38" RCP ELL.	2.000	EA
613 (H)	0782 30" CORR. ALUMINUM PIPE	34.000	LF
613 (M)	5732 30" PREFAB. CULVERT END SEC., ROUND	2.000	EA
850 (A)	8110 SHEET ALUMINUM SIGNS	10.000	SF
SECTION NO. 0002 X081-BRIDGE 'A' BRO-118D(31)CO			
501 (B)	1307 SUBSTRUCTURE EXCAVATION COMMON	60.000	CY
501 (F)	6352 GRANULAR BACKFILL	40.000	CY
503 (B)	6144 PRESTRESSED CONCRETE DOUBLE TEE	275.500	LF
504 (E)	1380 CONCRETE RAIL (TR1)	155.000	LF
509 (A)	1326 CLASS AA CONCRETE	38.000	CY
509 (B)	1328 CLASS A CONCRETE	29.000	CY
511 (A)	1332 REINFORCING STEEL	10,698.000	LB
514 (A)	6010 PILES, FURNISHED (HP 10X42)	234.000	LF
514 (B)	6292 PILES, DRIVEN (HP 10X42)	234.000	LF
601 (A-1)	1353 TYPE I-A PLAIN RIPRAP	900.000	TON
601 (A-2)	1355 TYPE I-A FILTER BLANKET	154.000	TON
613 (P)	6204 6" PERFORATED PIPE UNDERDRAIN ROUND	54.000	LF
613 (Q)	6207 6" NON-PERF.PIPE UNDERDRAIN RND.	50.000	LF
619 (D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623 (F)	6033 GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
640	1398 FIELD OFFICE	1.000	EA
641	1399 MOBILIZATION	1.000	LSUM
880 (J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAK-STAKING BRO-118D(31)CO			
642	0098 STAKING	1.000	LSUM

CALL ORDER : 160
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : CRAIG

CONTRACT ID : 030380
 PCN : 1993004
 PROJECTS : BRF-118C(32)CO
 DBE GOALS : 3.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 7.59
 CALENDAR DAYS : 90
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:
 BRIDGE AND APPROACHES COUNTY ROAD; OVER BOGGS CREEK, 3.0
 MILES EAST OF NOWATA COUNTY LINE AND 3.0 MILES SOUTH OF
 KANSAS BORDER. PROJECT LENGTH = 0.248 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001	E000-ROADWAY BRF-118C(32)CO		
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202 (A)	0103 COMMON EXCAVATION	6,010.000	CY
202 (C)	0184 UNCLASSIFIED BORROW	1,900.000	CY
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	1,500.000	LF
227	0100 TEMPORARY SILT DIKE	250.000	LF
230 (A)	2806 SOLID SLAB SODDING	700.000	SY
232 (A)	2813 SEEDING METHOD A	1.000	AC
233 (A)	2817 VEGETATIVE MULCHING	2.300	AC
403 (E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	775.000	TON
601A-1	0536 TYPE I-A PLAIN RIPRAP	1,950.000	TON
613 (H)	0781 24" CORR. ALUMINUM PIPE	86.000	LF
613 (M)	5730 24" PREFAB. CULVERT END SEC., ROUND	6.000	EA
850 (A)	8110 SHEET ALUMINUM SIGNS	40.000	SF
SECTION NO. 0002	X081-BRIDGE 'A' BRF-118C(32)CO		
501 (B)	1307 SUBSTRUCTURE EXCAVATION COMMON	84.000	CY
501 (F)	6352 GRANULAR BACKFILL	82.000	CY
503 (A)	1313 PRESTRESSED CONCRETE BEAMS (TYPE IV)	356.670	LF
504 (E)	1380 CONCRETE RAIL (TR1)	245.000	LF
506 (A)	1322 STRUCTURAL STEEL	2,150.000	LB
509 (A)	1326 CLASS AA CONCRETE	69.800	CY
509 (B)	1328 CLASS A CONCRETE	54.400	CY
511 (A)	1332 REINFORCING STEEL	23,796.000	LB
514 (A)	6010 PILES, FURNISHED (HP 10X42)	428.900	LF
514 (B)	6292 PILES, DRIVEN (HP 10X42)	428.900	LF
601 (A-1)	1353 TYPE I-A PLAIN RIPRAP	1,400.000	TON
601 (A-2)	1355 TYPE I-A FILTER BLANKET	260.000	TON
613 (P)	6204 6" PERFORATED PIPE UNDERDRAIN ROUND	52.000	LF
613 (Q)	6207 6" NON-PERF. PIPE UNDERDRAIN RND.	50.000	LF
619 (D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623 (F)	6034 GUARD RAIL ANCHOR UNIT (TYPE III)	4.000	EA
641	1399 MOBILIZATION	1.000	LSUM
880 (J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003	STAK-STAKING BRF-118C(32)CO		
642	0098 STAKING	1.000	LSUM

CALL ORDER : 170
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : CRAIG

CONTRACT ID : 030381
 PCN : 1992904C
 PROJECTS : BRO-118D(31)CO/BRF-118C(32)CO
 DBE GOALS : 4.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 15.17
 CALENDAR DAYS : 150
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:
 BRIDGES AND APPROACHES COUNTY ROAD; OVER COW CREEK, ON THE
 OTTAWA COUNTY LINE, 0.9 MILE NORTH OF SH-10/COUNTY ROAD;
 OVER BOGGS CREEK, 3.0 MILES EAST OF NOWATA COUNTY LINE AND
 3.0 MILES SOUTH OF KANSAS BORDER. PROJECT LENGTH = 0.531
 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 E000-ROADWAY BRO-118D(31)CO			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(A)	0183 UNCLASSIFIED EXCAVATION	1,681.000	CY
202(C)	0184 UNCLASSIFIED BORROW	6,750.000	CY
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	2,400.000	LF
227	0100 TEMPORARY SILT DIKE	160.000	LF
230(A)	2806 SOLID SLAB SODDING	5,988.000	SY
233(A)	2817 VEGETATIVE MULCHING	2.500	AC
403(E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	940.000	TON
613(B)	0491 18" R.C.PIPE CLASS III	40.000	LF
613(B)	4505 24" X 38" R.C.PIPE ELL. CLASS HE-III	39.000	LF
613(C)	4373 SP. END SECTION OF 18" RCP ROUND	2.000	EA
613(C)	5100 SP. END SECTION OF 24" X 38" RCP ELL.	2.000	EA
613(H)	0782 30" CORR. ALUMINUM PIPE	34.000	LF
613(M)	5732 30" PREFAB. CULVERT END SEC., ROUND	2.000	EA
850(A)	8110 SHEET ALUMINUM SIGNS	10.000	SF
SECTION NO. 0002 E000-ROADWAY BRF-118C(32)CO			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(A)	0103 COMMON EXCAVATION	6,010.000	CY
202(C)	0184 UNCLASSIFIED BORROW	1,900.000	CY
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	1,500.000	LF
227	0100 TEMPORARY SILT DIKE	250.000	LF
230(A)	2806 SOLID SLAB SODDING	700.000	SY
232(A)	2813 SEEDING METHOD A	1.000	AC
233(A)	2817 VEGETATIVE MULCHING	2.300	AC
403(E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	775.000	TON
601A-1	0536 TYPE I-A PLAIN RIPRAP	1,950.000	TON
613(H)	0781 24" CORR. ALUMINUM PIPE	86.000	LF
613(M)	5730 24" PREFAB. CULVERT END SEC., ROUND	6.000	EA
850(A)	8110 SHEET ALUMINUM SIGNS	40.000	SF

CALL ORDER : 170
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : CRAIG

CONTRACT ID : 030381
 PCN : 1992904C
 PROJECTS : BRO-118D(31)CO/BRF-118C(32)CO
 DBE GOALS : 4.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 15.17
 CALENDAR DAYS : 150
 RES. ENG.:
 LIQ. DAM.: \$ 500

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003	X081-BRIDGE 'A' BRO-118D(31)CO		
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	60.000	CY
501(F) 6352	GRANULAR BACKFILL	40.000	CY
503(B) 6144	PRESTRESSED CONCRETE DOUBLE TEE	275.500	LF
504(E) 1380	CONCRETE RAIL (TR1)	155.000	LF
509(A) 1326	CLASS AA CONCRETE	38.000	CY
509(B) 1328	CLASS A CONCRETE	29.000	CY
511(A) 1332	REINFORCING STEEL	10,698.000	LB
514(A) 6010	PILES, FURNISHED (HP 10X42)	234.000	LF
514(B) 6292	PILES, DRIVEN (HP 10X42)	234.000	LF
601(A-1) 1353	TYPE I-A PLAIN RIPRAP	900.000	TON
601(A-2) 1355	TYPE I-A FILTER BLANKET	154.000	TON
613(P) 6204	6" PERFORATED PIPE UNDERDRAIN ROUND	54.000	LF
613(Q) 6207	6" NON-PERF.PIPE UNDERDRAIN RND.	50.000	LF
619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F) 6033	GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
640 1398	FIELD OFFICE	1.000	EA
641 1399	MOBILIZATION	1.000	LSUM
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0004	X081-BRIDGE 'A' BRF-118C(32)CO		
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	84.000	CY
501(F) 6352	GRANULAR BACKFILL	82.000	CY
503(A) 1313	PRESTRESSED CONCRETE BEAMS (TYPE IV)	356.670	LF
504(E) 1380	CONCRETE RAIL (TR1)	245.000	LF
506(A) 1322	STRUCTURAL STEEL	2,150.000	LB
509(A) 1326	CLASS AA CONCRETE	69.800	CY
509(B) 1328	CLASS A CONCRETE	54.400	CY
511(A) 1332	REINFORCING STEEL	23,796.000	LB
514(A) 6010	PILES, FURNISHED (HP 10X42)	428.900	LF
514(B) 6292	PILES, DRIVEN (HP 10X42)	428.900	LF
601(A-1) 1353	TYPE I-A PLAIN RIPRAP	1,400.000	TON
601(A-2) 1355	TYPE I-A FILTER BLANKET	260.000	TON
613(P) 6204	6" PERFORATED PIPE UNDERDRAIN ROUND	52.000	LF
613(Q) 6207	6" NON-PERF.PIPE UNDERDRAIN RND.	50.000	LF
619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F) 6034	GUARD RAIL ANCHOR UNIT (TYPE III)	4.000	EA
641 1399	MOBILIZATION	1.000	LSUM
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0005	STAK-STAKING BRO-118D(31)CO		
642 0098	STAKING	1.000	LSUM
SECTION NO. 0006	STAK-STAKING BRF-118C(32)CO		
642 0098	STAKING	1.000	LSUM

CALL ORDER : 210
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : GARVIN

CONTRACT ID : 030383
 PCN : 1877404
 PROJECTS : STPY-125C(069)
 DBE GOALS : 9.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 33.60
 CALENDAR DAYS : 210
 RES. ENG.:
 LIQ. DAM.: \$ 1000

CONTRACT DESCRIPTION:
 GRADE, DRAIN AND SURFACE SH-19: FROM 2 MILES EAST OF
 LINDSAY EXTENDING EAST. PROJECT LENGTH = 3.784 MILES
 FLEXIBLE ESALS = 7.0 MILLION ASPHALT GRADE = PG 64-22 OK,
 PG 70-28 OK (PERCENT WITHIN LIMITS SPECIAL PROVISION)

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 I000-ROADWAY			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(A)	0183 UNCLASSIFIED EXCAVATION	39,361.000	CY
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
222	2801 TEMPORARY BALE BARRIER	2,166.000	LF
223	2801 TEMPORARY SILT FENCE	1,774.000	LF
224	2803 TEMPORARY SEDIMENT FILTER	4.000	EA
225	2804 TEMPORARY SEDIMENT BASIN	4.000	EA
230(A)	2806 SOLID SLAB SODDING	124,120.000	SY
233(A)	2817 VEGETATIVE MULCHING	70.600	AC
326(A)	4200 (SP)FLY ASH	2,570.000	TON
326(B)	4210 (SP)LIME	133.000	TON
326(E)	4240 (SP)CEMENTITIOUS STABILIZED SUBGRADE	46,660.000	SY
326(G)	4260 (SP)LIME PRETREATMENT	46,660.000	SY
403(E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	1,381.000	TON
407	0250 TACK COAT	11,770.000	GAL
408	5774 PRIME COAT	6,702.000	GAL
411(S3)	5940 (SP)ASPH.CONC.,TYPE S3(PG 70-28 OK)	9,456.000	TON
411(S3)	5945 (SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	20,299.000	TON
411(S4)	5955 (SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	6,305.000	TON
411(S4)	5960 (SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	4,191.000	TON
417	5267 COLD MILLING PAVEMENT	320.000	SY
420(A)	4242 FABRIC REINFORCEMENT	8,880.000	SY
420(B)	4268 BITUMINOUS BINDER	2,137.000	GAL
509(B)	0321 CLASS A CONCRETE	53.600	CY
509(D)	0325 CLASS C CONCRETE	10.000	CY
511(A)	0332 REINFORCING STEEL	8,854.000	LB
613(B)	0492 24" R.C.PIPE CLASS III	96.000	LF
613(D)	0689 18" CORR. GALV. STEEL PIPE	552.000	LF
613(D)	0690 24" CORR. GALV. STEEL PIPE	122.000	LF
613(D)	0691 30" CORR. GALV. STEEL PIPE	148.000	LF
613(D)	0692 36" CORR. GALV. STEEL PIPE	282.000	LF
613(D)	4528 28" X 20" CORR. GALV. STEEL PIPE ARCH	222.000	LF
613(M)	4516 28" X 20" PREFAB. CULVERT END SEC., ARCH	10.000	EA
613(M)	5726 18" PREFAB. CULVERT END SEC., ROUND	22.000	EA
613(M)	5730 24" PREFAB. CULVERT END SEC., ROUND	10.000	EA
613(M)	5732 30" PREFAB. CULVERT END SEC., ROUND	6.000	EA

CALL ORDER : 210
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : GARVIN

CONTRACT ID : 030383
 PCN : 1877404
 PROJECTS : STPY-125C(069)
 DBE GOALS : 9.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 33.60
 CALENDAR DAYS : 210
 RES. ENG. :
 LIQ. DAM. : \$ 1000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 I000-ROADWAY			
613 (M) 5734	36" PREFAB. CULVERT END SEC., ROUND	10.000	EA
613 (P) 6204	6" PERFORATED PIPE UNDERDRAIN ROUND	1,000.000	LF
613 (Q) 1096	6" NON-PERF. PIPE UNDERDRAIN RND.	500.000	LF
619 (B) 0291	REMOVAL OF HEADWALL	10.000	EA
619 (B) 5918	REMOVAL OF EXISTING PIPE	168.000	LF
624 (C) 4459	(SP) FENCE-STYLE SWF (5 BARBED WIRE)	35,592.000	LF
640 1398	FIELD OFFICE	1.000	EA
641 1552	MOBILIZATION	1.000	LSUM
643 0087	(SP) CONTRACTORS QUALITY CONTROL	1.000	LSUM
SECTION NO. 0002 Y002-TRAFFIC			
850 (A) 8110	SHEET ALUMINUM SIGNS	85.830	SF
851 (C) 8324	2" SQUARE TUBE POST	45.180	LF
851 (C) 8327	2 1/4" SQUARE TUBE POST	134.100	LF
855 (A) 8812	TRAFFIC STRIPE (PLASTIC) (4" WIDE)	44,902.000	LF
856 (A) 8839	CONSTRUCTION TRAFF. STR. (PAINT) (4" WIDE)	39,965.000	LF
856 (C) 8851	REMOVABLE PAVEMENT MARKING TAPE (4" WIDE)	1,000.000	LF
856 (G) 8887	(PL) CONST. ZONE PAV. MKRS (FLEX TAB) TYP. 2-1	16,000.000	EA
859 (A) 8006	PAVEMENT MRKNG. REMOVAL (TRAF. STRP)	39,965.000	LF
880 (B) 8818	CONSTRUCTION SIGNS 0 TO 6.25 SF	3,444.000	SD
880 (B) 8821	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	756.000	SD
880 (B) 8824	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	2,352.000	SD
880 (C) 8836	BARRICADES (TYPE II)	840.000	SD
880 (C) 8842	BARRICADES (TYPE III)	840.000	SD
880 (C) 8848	WING BARRICADES	840.000	SD
880 (D) 8854	VERTICAL PANELS	42,210.000	SD
880 (E) 8860	WARNING LIGHTS (TYPE A)	2,520.000	SD
880 (E) 8872	WARNING LIGHTS (TYPE C)	42,210.000	SD
880 (F) 8878	DRUMS	42,210.000	SD
880 (I) 8902	FLAGGER	168.000	SD
SECTION NO. 0003 STAK-STAKING			
642 0098	STAKING	1.000	LSUM

CALL ORDER : 240
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : GREER

CONTRACT ID : 030384
 PCN : 2019704
 PROJECTS : BRO-128D(51) CO
 DBE GOALS : 7.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 9.75
 CALENDAR DAYS : 90
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:
 BRIDGE AND APPROACHES COUNTY ROAD; OVER HAYSTACK CREEK, 3.5
 MILES NORTH AND 9.2 MILES WEST OF JCT. SH-34/SH-34A AT
 WILLOW. PROJECT LENGTH = 0.207 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 E000 - ROADWAY			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202 (A)	0183 UNCLASSIFIED EXCAVATION	2,072.000	CY
202 (C)	0184 UNCLASSIFIED BORROW	4,275.000	CY
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
222	2801 TEMPORARY BALE BARRIER	200.000	LF
223	2801 TEMPORARY SILT FENCE	2,000.000	LF
230 (A)	2806 SOLID SLAB SODDING	5,720.000	SY
233 (A)	2817 VEGETATIVE MULCHING	1.200	AC
403 (E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	531.000	TON
509 (D)	0325 CLASS C CONCRETE	10.000	CY
850 (A)	8110 SHEET ALUMINUM SIGNS	10.000	SF
851 (D)	8597 FLANGE CHANNEL POSTS (4 LB/FT)	28.000	LF
SECTION NO. 0002 X081 - BRIDGE 'A'			
501 (B)	1307 SUBSTRUCTURE EXCAVATION COMMON	84.000	CY
501 (D)	6353 UNCLASSIFIED BACKFILL	82.000	CY
503 (A)	1313 PRESTRESSED CONCRETE BEAMS (TYPE IV)	396.670	LF
504 (E)	1380 CONCRETE RAIL (TR1)	265.000	LF
506 (A)	1322 STRUCTURAL STEEL	1,810.000	LB
509 (A)	1326 CLASS AA CONCRETE	77.000	CY
509 (B)	1328 CLASS A CONCRETE	53.800	CY
511 (A)	1332 REINFORCING STEEL	24,566.000	LB
514 (A)	6010 PILES, FURNISHED (HP 10X42)	523.000	LF
514 (B)	6292 PILES, DRIVEN (HP 10X42)	523.000	LF
601 (A-1)	1353 TYPE I-A PLAIN RIPRAP	650.000	TON
601 (A-2)	1355 TYPE I-A FILTER BLANKET	175.000	TON
619 (D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623 (F)	6033 GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
641	1399 MOBILIZATION	1.000	LSUM
880 (J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAK-STAKING			
642	0098 STAKING	1.000	LSUM

CALL ORDER : 280
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : KAY

CONTRACT ID : 030402
 PCN : 1267104
 PROJECTS : IMY-35-4(151)209
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 59.61
 CALENDAR DAYS : 250
 RES. ENG.:
 LIQ. DAM.: \$ 2000

CONTRACT DESCRIPTION:
 RESURFACING (CONCRETE OVERLAY) I-35: FROM 2 MILES NORTH OF
 THE KAY/NOBLE COUNTY LINE EXTEND NORTH. PROJECT LENGTH = 4.
 015 MILE FLEXIBLE ESALS = 45.8 MILLION ASPHALT GRADE = PG
 64-22 OK, PG 70-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 L000-ROADWAY			
202 (A)	0183 UNCLASSIFIED EXCAVATION	24,549.000	CY
202 (C)	0184 UNCLASSIFIED BORROW	11,704.000	CY
223	2801 TEMPORARY SILT FENCE	11,550.000	LF
224	2803 TEMPORARY SEDIMENT FILTER	16.000	EA
226	2805 TEMPORARY SEDIMENT REMOVAL	30.000	CY
227	0100 TEMPORARY SILT DIKE	196.000	LF
230 (A)	2806 SOLID SLAB SODDING	77,935.000	SY
232 (B)	2814 SEEDING METHOD B	23.000	AC
233 (A)	2817 VEGETATIVE MULCHING	23.000	AC
241	2832 MOWING	23.000	AC
325	5271 SEPARATOR FABRIC	5,500.000	SY
326 (A)	4200 (SP) FLY ASH	6,859.000	TON
326 (B)	4210 (SP) LIME	2,286.000	TON
326 (E)	4240 (SP) CEMENTITIOUS STABILIZED SUBGRADE	126,540.000	SY
326 (G)	4260 (SP) LIME PRETREATMENT	126,540.000	SY
407	0250 TACK COAT	12,847.000	GAL
408	5774 PRIME COAT	20,900.000	GAL
411 (S3)	5945 (SP) ASPH.CONC., TYPE S3 (PG 64-22 OK)	7,375.000	TON
411 (S4)	5955 (SP) ASPH.CONC., TYPE S4 (PG 70-28 OK)	1,813.000	TON
411 (S4)	5960 (SP) ASPH.CONC., TYPE S4 (PG 64-22 OK)	40,261.000	TON
413 (D)	4868 (SP) RUMBLE STRIP-METHOD PCC-CON	81,556.000	LF
414 (A1)	6857 12.5" P.C. DOWEL JOINTED CONCRETE PAVE.	109,686.000	SY
414 (B1)	5759 10" H.E.S. DOWEL JOINTED CONCRETE PAV	11,336.000	SY
414 (B1)	5770 12.5" H.E.S. DOWEL JOINTED CONCRETE PAVE	4,048.000	SY
414 (H)	5200 (SP) UNBONDED PCC OVERLAY	14,018.000	CY
414 (J)	5400 P.C. CONCRETE PAVEMENT (PLACEMENT ONLY)	61,800.000	SY
417	5267 COLD MILLING PAVEMENT	4,659.000	SY
501 (A)	0313 STRUCTURAL EXCAVATION UNCLASSIFIED	34.000	CY
509 (B)	0321 CLASS A CONCRETE	77.000	CY
509 (C)	0322 CLASS A CONCRETE FOR SMALL STRUCTURES	53.000	CY
509 (D)	1331 CLASS C CONCRETE	20.000	CY
511 (A)	0332 REINFORCING STEEL	11,826.000	LB
601 (A)	0297 TYPE I PLAIN RIPRAP	200.000	TON
613 (D)	4527 21" X 15" CORR. GALV. STEEL PIPE ARCH	2,800.000	LF
619 (B)	0291 REMOVAL OF HEADWALL	14.000	EA
619 (B)	4725 REMOVAL OF FENCE	431.000	LF

CALL ORDER : 280
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : KAY

CONTRACT ID : 030402
 PCN : 1267104
 PROJECTS : IMY-35-4(151)209
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 59.61
 CALENDAR DAYS : 250
 RES. ENG.:
 LIQ. DAM.: \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	L000-ROADWAY		
619 (B) 4728	REMOVAL OF ASPHALT PAVEMENT	11,556.000	SY
619 (B) 4763	REMOVAL OF CONC.PAV.W/ASPH.OVERLAY	113,734.000	SY
619 (B) 4780	REMOVAL OF GUARD RAIL	10,775.000	LF
623 (A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	9,825.000	LF
623 (D) 5203	BEAM GUARD RAIL-THRIE-BEAM-DOUBLE	100.000	LF
623 (E) 7113	BEAM GUARD RAIL-THRIE-BEAM TRANS. SECT.	16.000	EA
623 (F) 4447	GUARD RAIL ANCHOR UNIT (TYPE B)	12.000	EA
623 (F) 6028	GUARD RAIL ANCHOR UNIT	10.000	EA
623 (H) 8571	(SP)G.E.T. GUARD RAIL END SECTION	22.000	EA
624 (C) 4459	(SP)FENCE-STYLE SWF (5 BARBED WIRE)	337.000	LF
640 1398	FIELD OFFICE	1.000	EA
641 1399	MOBILIZATION	1.000	LSUM
653 (A) 5915	EDGE DRAIN CONDUIT-PERFORATED	9,000.000	LF
653 (B) 5916	EDGE DRAIN OUTLET LATERAL-NONPERFORATED	1,000.000	LF
653 (C) 5946	OUTLET LATERAL HEADWALL	31.000	EA
SECTION NO. 0002	X171-BRIDGE 'A'		
619 (D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
SECTION NO. 0003	X171-BRIDGE 'B'		
619 (D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
SECTION NO. 0004	X020-BRIDGE 'C'		
417 5267	COLD MILLING PAVEMENT	679.200	SY
504 (A) 1304	APPROACH SLAB	180.800	SY
504 (H) 6390	RAPID CURE JOINT SEALANT	340.300	LF
505 (B) 6019	CLASS B BRIDGE DECK REPAIR	20.000	SY
505 (D) 6071	HIGH DENSITY BRIDGE DECK OVERLAY	679.200	SY
510 (C) 6134	SLOPE WALL (4")	5.000	SY
619 (B) 2505	(PL)REMOVAL OF BRIDGE ITEMS	2.000	EA
SECTION NO. 0005	X020-BRIDGE 'D'		
417 5267	COLD MILLING PAVEMENT	679.200	SY
504 (A) 1304	APPROACH SLAB	180.800	SY
504 (H) 6390	RAPID CURE JOINT SEALANT	340.300	LF
505 (B) 6019	CLASS B BRIDGE DECK REPAIR	20.000	SY
505 (D) 6071	HIGH DENSITY BRIDGE DECK OVERLAY	679.200	SY
510 (C) 6134	SLOPE WALL (4")	5.000	SY
619 (B) 2505	(PL)REMOVAL OF BRIDGE ITEMS	2.000	EA

CALL ORDER : 280
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : KAY

CONTRACT ID : 030402
 PCN : 1267104
 PROJECTS : IMY-35-4(151)209
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 59.61
 CALENDAR DAYS : 250
 RES. ENG.:
 LIQ. DAM.: \$ 2000

SECTION NO. 0006	X071-BRIDGE 'E'		
504 (A)	1304	APPROACH SLAB	137.200 SY
504 (F)	1381	CONCRETE PARAPET	60.300 LF
504 (H)	6390	RAPID CURE JOINT SEALANT	92.900 LF
505 (B)	6019	CLASS B BRIDGE DECK REPAIR	5.000 SY
510 (C)	6134	SLOPE WALL (4")	5.000 SY
515 (A)	6013	WATER REPELLENT (VISUALLY INSPECTED)	49.000 SY
619 (B)	2505	(PL)REMOVAL OF BRIDGE ITEMS	2.000 EA
SECTION NO. 0007	X071-BRIDGE 'F'		
504 (A)	1304	APPROACH SLAB	137.200 SY
504 (F)	1381	CONCRETE PARAPET	60.300 LF
504 (H)	6390	RAPID CURE JOINT SEALANT	92.900 LF
505 (B)	6019	CLASS B BRIDGE DECK REPAIR	5.000 SY
510 (C)	6134	SLOPE WALL (4")	5.000 SY
515 (A)	6013	WATER REPELLENT (VISUALLY INSPECTED)	49.000 SY
619 (B)	2505	(PL)REMOVAL OF BRIDGE ITEMS	2.000 EA
SECTION NO. 0008	Y000-TRAFFIC		
627 (O)	4410	REL.OF RENTED PORT.PREC.CONC.MED.BARRIER	28,350.000 LF
627 (P)	4425	RENTED PORT.TYPE PREC.CONC.MED. BARR.	25,750.000 LF
804 (A)	2915	STRUCTURAL CONCRETE	18.700 CY
804 (B)	2916	REINFORCING STEEL	3,192.000 LB
850 (A)	8110	SHEET ALUMINUM SIGNS	364.200 SF
850 (B)	8112	EXTRUDED ALUMINUM PANEL SIGNS	1,153.600 SF
851 (A)	3206	4"@13 GALV.STL.WD.FLANGE BM.POST	203.100 LF
851 (A)	3207	6"@15 GALV.STL.WD.FLANGE BM.POST	229.900 LF
851 (A)	3209	6"@25 GALV.STL.WD.FLANGE BM.POST	49.800 LF
851 (B)	3217	2 1/2"@5.79 GALV.STL.PIPE POST	56.000 LF
851 (B)	3218	3"@7.58 GALV.STL.PIPE POST	28.000 LF
851 (B)	3219	3 1/2"@9.11 GALV.STL.PIPE POST	120.000 LF
851 (C)	8321	1 3/4" SQUARE TUBE POST	451.500 LF
851 (C)	8324	2" SQUARE TUBE POST	60.000 LF
851 (C)	8327	2 1/4" SQUARE TUBE POST	14.000 LF
855 (A)	8812	TRAFFIC STRIPE (PLASTIC) (4" WIDE)	136,000.000 LF
856 (A)	8839	CONSTRUCTION TRAFF.STR. (PAINT) (4" WIDE)	160,000.000 LF
856 (G)	8887	(PL)CONST.ZONE PAV.MKRS (FLEX TAB) TYP.2-1	2,500.000 EA
857 (A)	8911	PAVE.MARKERS CLASS A TYPE 2-C	14.000 EA
857 (A)	8947	PAVE.MARKERS CLASS C TYPE 2-C	520.000 EA
859 (A)	8006	PAVEMENT MRKNG.REMOVAL (TRAF.STRP)	126,500.000 LF
870 (A)	8485	SAND FILLED IMPACT ATTEN.MODULE	500.000 SD
876 (C)	8482	(PL)TRUCK MOUNTED ATTENUATOR	500.000 SD
878 (C)	8487	MODULAR GLARE SCREEN	1,570,000.000 SD
880 (A)	8812	ARROW DISPLAY (TYPE C)	500.000 SD
880 (B)	8818	CONSTRUCTION SIGNS 0 TO 6.25 SF	12,000.000 SD
880 (B)	8821	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	19,500.000 SD

CALL ORDER : 280
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : KAY

CONTRACT ID : 030402
 PCN : 1267104
 PROJECTS : IMY-35-4(151)209
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 59.61
 CALENDAR DAYS : 250
 RES. ENG. :
 LIQ. DAM. : \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0008 Y000-TRAFFIC			
880 (B) 8824	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	5,000.000	SD
880 (C) 8842	BARRICADES (TYPE III)	8,500.000	SD
880 (C) 8848	WING BARRICADES	1,000.000	SD
880 (D) 8854	VERTICAL PANELS	23,000.000	SD
880 (E) 8860	WARNING LIGHTS (TYPE A)	53,000.000	SD
880 (E) 8872	WARNING LIGHTS (TYPE C)	123,000.000	SD
880 (F) 8878	DRUMS	100,000.000	SD
880 (L) 8911	TRAFFIC SURVEILLANCE, POLICE	50.000	HOUR
882 (B) 8306	PORT.CHANGEABLE MESSAGE SIGN	500.000	SD
SECTION NO. 0009 STAK-STAKING			
642 0098	STAKING	1.000	LSUM

CALL ORDER : 300
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : KIOWA

CONTRACT ID : 030385
 PCN : 1960904
 PROJECTS : BRO-138D(51) CO
 DBE GOALS : 9.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 9.75
 CALENDAR DAYS : 130
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:
 BRIDGE AND APPROACHES COUNTY ROAD; OVER ELK CREEK, 5.0
 MILES NORTH AND 4.4 MILES WEST OF HOBART. PROJECT LENGTH =
 0.217 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 E000 - ROADWAY			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202 (A)	0183 UNCLASSIFIED EXCAVATION	554.000	CY
202 (C)	0184 UNCLASSIFIED BORROW	3,191.000	CY
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
222	2801 TEMPORARY BALE BARRIER	2,035.000	LF
223	2801 TEMPORARY SILT FENCE	2,035.000	LF
230 (A)	2806 SOLID SLAB SODDING	9,845.000	SY
233 (A)	2817 VEGETATIVE MULCHING	2.030	AC
509 (D)	0325 CLASS C CONCRETE	10.000	CY
850 (A)	8110 SHEET ALUMINUM SIGNS	24.000	SF
851 (A)	3206 4"@13 GALV.STL.WD.FLANGE BM.POST	30.000	LF
SECTION NO. 0002 X081 - BRIDGE 'A'			
501 (B)	1307 SUBSTRUCTURE EXCAVATION COMMON	86.000	CY
501 (D)	6353 UNCLASSIFIED BACKFILL	68.000	CY
503 (A)	1311 PRESTRESSED CONCRETE BEAMS (TYPE II)	508.510	LF
504 (C)	6250 SEALED EXPANSION JOINT	67.110	LF
504 (E)	1380 CONCRETE RAIL (TR1)	325.160	LF
506 (A)	1322 STRUCTURAL STEEL	4,220.000	LB
509 (A)	1326 CLASS AA CONCRETE	99.000	CY
509 (B)	1328 CLASS A CONCRETE	102.600	CY
511 (A)	1332 REINFORCING STEEL	37,120.000	LB
514 (A)	6010 PILES, FURNISHED (HP 10X42)	854.250	LF
514 (B)	6292 PILES, DRIVEN (HP 10X42)	854.250	LF
516 (A)	6093 DRILLED SHAFTS 42" DIAMETER	202.000	LF
601 (A-1)	1353 TYPE I-A PLAIN RIPRAP	1,080.000	TON
601 (A-2)	1355 TYPE I-A FILTER BLANKET	300.000	TON
619 (D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623 (F)	6033 GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
641	1399 MOBILIZATION	1.000	LSUM
880 (J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAK-STAKING			
642	0098 STAKING	1.000	LSUM

CALL ORDER : 320
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : LOVE

CONTRACT ID : 030386
 PCN : 1957704
 PROJECTS : NHIY-0035-1(126)007
 DBE GOALS : 10.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 17.34
 CALENDAR DAYS : 215
 RES. ENG.:
 LIQ. DAM.: \$ 2000

CONTRACT DESCRIPTION:
 RESURFACE (UNBONDED OVERLAY) I-35: 7 MI. NORTH OF TEXAS
 STATE LINE EXTENDING NORTH . PROJECT LENGTH = 3.484 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	J000- ROADWAY		
202 (A) 0183	UNCLASSIFIED EXCAVATION	42,126.000	CY
202 (C) 0184	UNCLASSIFIED BORROW	7,982.000	CY
205 4229	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
223 2801	TEMPORARY SILT FENCE	1,500.000	LF
227 0100	TEMPORARY SILT DIKE	800.000	LF
230 (A) 2806	SOLID SLAB SODDING	85,214.000	SY
232 (B) 2814	SEEDING METHOD B	17.600	AC
233 (A) 2817	VEGETATIVE MULCHING	17.600	AC
241 2832	MOWING	17.600	AC
303 0192	AGGREGATE BASE	16,097.000	CY
310 (B) 0149	SUBGRADE, METHOD B	48,842.000	SY
407 0250	TACK COAT	4,895.000	GAL
408 5774	PRIME COAT	12,072.000	GAL
411 (S2) 5930	(SP) ASPH.CONC., TYPE S2 (PG 64-22 OK)	1,204.000	TON
411 (S3) 5935	(SP) ASPH.CONC., TYPE S3 (PG 76-28 OK)	1,279.000	TON
411 (S3) 5940	(SP) ASPH.CONC., TYPE S3 (PG 70-28 OK)	711.000	TON
411 (S4) 5950	(SP) ASPH.CONC., TYPE S4 (PG 76-28 OK)	1,033.000	TON
411 (S4) 5955	(SP) ASPH.CONC., TYPE S4 (PG 70-28 OK)	469.000	TON
411 (S4) 5960	(SP) ASPH.CONC., TYPE S4 (PG 64-22 OK)	16,757.000	TON
413 (D) 4868	(SP) RUMBLE STRIP-METHOD PCC-CON	73,594.000	LF
414 (A1) 5760	11" P.C. DOWEL JOINTED CONCRETE PAVEMENT	36,719.000	SY
414 (B) 5913	H.E.S. CONCRETE (FULL DEPTH PATCHING)	50.000	SY
414 (H) 5200	(SP) UNBONDED PCC OVERLAY	36,121.000	CY
414 (H) 5250	(SP) P.C.C. PAVEMENT (PLACEMENT ONLY)	155,364.000	SY
417 5267	COLD MILLING PAVEMENT	147,807.000	SY
613 (D) 4527	21" X 15" CORR. GALV. STEEL PIPE ARCH	500.000	LF
619 (B) 4728	REMOVAL OF ASPHALT PAVEMENT	4,171.000	SY
619 (B) 4763	REMOVAL OF CONC.PAV.W/ASPH.OVERLAY	21,145.000	SY
619 (C) 0924	SAWING PAVEMENT	24,857.000	LF
623 (A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	400.000	LF
623 (E) 7113	BEAM GUARD RAIL-THRIE-BEAM TRANS. SECT.	4.000	EA
625 (D) 1254	REMOVE AND RECONSTRUCT GUARD RAIL	4,738.000	LF
640 1426	FIELD OFFICE	1.000	EA
641 1399	MOBILIZATION	1.000	LSUM
643 0087	(SP) CONTRACTORS QUALITY CONTROL	1.000	LSUM
653 (A) 5915	EDGE DRAIN CONDUIT-PERFORATED	6,000.000	LF
653 (B) 5916	EDGE DRAIN OUTLET LATERAL-NONPERFORATED	500.000	LF
653 (C) 5946	OUTLET LATERAL HEADWALL	20.000	EA

CALL ORDER : 320
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : LOVE

CONTRACT ID : 030386
 PCN : 1957704
 PROJECTS : NHIY-0035-1(126)007
 DBE GOALS : 10.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 17.34
 CALENDAR DAYS : 215
 RES. ENG.:
 LIQ. DAM.: \$ 2000

SECTION NO. 0002		Y008-TRAFFIC		
627 (G)	4316	RELOC.PORT.TYPE PRECAST CONC.MEDIAN BARR	22,100.000	LF
627 (H)	5856	DEL.PORT.TYPE PREC. CONCRETE MEDIAN BARR	44,200.000	LF
855 (A)	8812	TRAFFIC STRIPE (PLASTIC) (4" WIDE)	103,103.000	LF
856 (A)	8839	CONSTRUCTION TRAFF.STR. (PAINT) (4" WIDE)	90,840.000	LF
856 (C)	8851	REMOVABLE PAVEMENT MARKING TAPE (4" WIDE)	1,000.000	LF
856 (G)	8887	(PL)CONST.ZONE PAV.MKRS (FLEX TAB)TYP.2-1	16,000.000	EA
857 (A)	8947	PAVE.MARKERS CLASS C TYPE 2-C	372.000	EA
859 (A)	8006	PAVEMENT MRKNG.REMOVAL (TRAF.STRP)	100,000.000	LF
870 (A)	8485	SAND FILLED IMPACT ATTEN.MODULE	4,560.000	SD
876 (C)	8482	(PL)TRUCK MOUNTED ATTENUATOR	240.000	SD
878 (C)	8487	MODULAR GLARE SCREEN	398,400.000	SD
880 (A)	8812	ARROW DISPLAY (TYPE C)	480.000	SD
880 (B)	8818	CONSTRUCTION SIGNS 0 TO 6.25 SF	3,360.000	SD
880 (B)	8821	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,440.000	SD
880 (B)	8824	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	4,800.000	SD
880 (B)	8827	CONSTRUCTION SIGNS 33.0 SF & OVER	960.000	SD
880 (C)	8842	BARRICADES (TYPE III)	4,800.000	SD
880 (C)	8848	WING BARRICADES	960.000	SD
880 (E)	8860	WARNING LIGHTS (TYPE A)	14,400.000	SD
880 (E)	8872	WARNING LIGHTS (TYPE C)	21,600.000	SD
880 (F)	8878	DRUMS	21,600.000	SD
882 (B)	8306	PORT.CHANGEABLE MESSAGE SIGN	1,440.000	SD
SECTION NO. 0003		STAK-STAKING		
642	0098	STAKING	1.000	LSUM

CALL ORDER : 340
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : MCCLAIN

CONTRACT ID : 030405
 PCN : 1818004
 PROJECTS : BRO-144D(33) CO
 DBE GOALS : 10.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 9.75
 CALENDAR DAYS : 130
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:

BRIDGE AND APPROACHES COUNTY ROAD: CO. BR. OVER BIG CREEK,
 1.0 MI. SOUTH AND 1.4 MI. EAST OF THE US-177 / SH-59 JCT.
 PROJECT LENGTH = 0.217 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 E000 - ROADWAY			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202 (G)	0185 EARTHWORK	1.000	LSUM
222	2801 TEMPORARY BALE BARRIER	500.000	LF
223	2801 TEMPORARY SILT FENCE	2,300.000	LF
227	0100 TEMPORARY SILT DIKE	500.000	LF
230 (A)	2806 SOLID SLAB SODDING	5,895.000	SY
233 (A)	2817 VEGETATIVE MULCHING	1.200	AC
403 (E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	623.000	TON
509 (D)	0325 CLASS C CONCRETE	10.000	CY
613 (CC)	7187 TYPE B4 CULVERT END TREATMENT	2.000	EA
613 (D)	0690 24" CORR. GALV. STEEL PIPE	42.000	LF
SECTION NO. 0002 X081 - BRIDGE			
501 (B)	1307 SUBSTRUCTURE EXCAVATION COMMON	96.000	CY
501 (D)	6353 UNCLASSIFIED BACKFILL	104.000	CY
503 (A)	1313 PRESTRESSED CONCRETE BEAMS (TYPE IV)	356.170	LF
504 (E)	1380 CONCRETE RAIL (TR1)	253.000	LF
506 (A)	1322 STRUCTURAL STEEL	2,020.000	LB
509 (A)	1326 CLASS AA CONCRETE	70.000	CY
509 (B)	1328 CLASS A CONCRETE	62.400	CY
511 (A)	1332 REINFORCING STEEL	24,620.000	LB
514 (A)	6010 PILES, FURNISHED (HP 10X42)	1,140.000	LF
514 (B)	6292 PILES, DRIVEN (HP 10X42)	1,140.000	LF
601 (A-1)	1353 TYPE I-A PLAIN RIPRAP	772.000	TON
601 (A-2)	1355 TYPE I-A FILTER BLANKET	211.000	TON
619 (D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623 (F)	6033 GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
641	1399 MOBILIZATION	1.000	LSUM
880 (J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAK - STAKING			
642	0098 STAKING	1.000	LSUM

CALL ORDER : 370
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : MARSHALL

CONTRACT ID : 030387
 PCN : 0764504
 PROJECTS : BRO-48D(140) CO
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 6.50
 CALENDAR DAYS : 90
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:
 BRIDGE AND APPROACHES COUNTY ROAD; OVER UNNAMED CREEK, 4.0
 MILES NORTH AND 6.9 MILES WEST OF ANTIOCH. PROJECT LENGTH =
 0.080 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 E000-ROADWAY			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202 (E)	0110 EMBANKMENTS	1,536.000	CY
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	800.000	LF
227	0100 TEMPORARY SILT DIKE	100.000	LF
230 (A)	2806 SOLID SLAB SODDING	2,200.000	SY
233 (A)	2817 VEGETATIVE MULCHING	0.500	AC
403 (E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	430.000	TON
509 (D)	0325 CLASS C CONCRETE	10.000	CY
613 (D)	0696 60" CORR. GALV. STEEL PIPE	100.000	LF
613 (D)	4528 28" X 20" CORR. GALV. STEEL PIPE ARCH	38.000	LF
613 (M)	4516 28" X 20" PREFAB. CULVERT END SEC., ARCH	2.000	EA
SECTION NO. 0002 X028-BRIDGE 'A'			
202 (A)	1301 UNCLASSIFIED EXCAVATION	810.000	CY
501 (A)	1306 STRUCTURAL EXCAVATION UNCLASSIFIED	146.000	CY
509 (B)	1328 CLASS A CONCRETE	295.000	CY
511 (A)	1332 REINFORCING STEEL	46,477.000	LB
601 (A-1)	1353 TYPE I-A PLAIN RIPRAP	40.000	TON
601 (A-2)	1355 TYPE I-A FILTER BLANKET	12.000	TON
619 (D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
641	1399 MOBILIZATION	1.000	LSUM
880 (J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAK-STAKING			
642	0098 STAKING	1.000	LSUM

CALL ORDER : 390
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : MUSKOGEE

CONTRACT ID : 030388
 PCN : 1499404
 PROJECTS : STPY-51C(404)
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 96.45
 CALENDAR DAYS : 365
 RES. ENG.:
 LIQ. DAM.: \$ 2000

CONTRACT DESCRIPTION:
 GRADE, DRAIN, SURFACE AND BRIDGE(RCB) US-64; BEGIN 11.229
 MILES SOUTH OF JCT. SH-165, EXTEND NORTH. PROJECT LENGTH =
 3.229 MILES FLEXIBLE ESALS = 4.01 MILLION ASPHALT GRADE =
 PG 64-22 OK, PG 70-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 I000-ROADWAY			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(A)	0183 UNCLASSIFIED EXCAVATION	128,288.000	CY
202(C)	0184 UNCLASSIFIED BORROW	37,509.000	CY
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
222	2801 TEMPORARY BALE BARRIER	2,000.000	LF
223	2801 TEMPORARY SILT FENCE	1,300.000	LF
226	2805 TEMPORARY SEDIMENT REMOVAL	150.000	CY
227	0100 TEMPORARY SILT DIKE	1,751.000	LF
229	4318 DITCH LINER PROTECTION	1,710.000	LF
230(A)	2806 SOLID SLAB SODDING	141,896.000	SY
232(A)	2813 SEEDING METHOD A	57.780	AC
233(A)	2817 VEGETATIVE MULCHING	57.780	AC
241	2832 MOWING	78.550	AC
246(A)	7041 (SP) GEOGRID EARTH REINFORCEMENT	101,497.000	SY
303	0192 AGGREGATE BASE	43,417.000	CY
325	5271 SEPARATOR FABRIC	22,453.000	SY
326(A)	4200 (SP) FLY ASH	2,487.000	TON
326(B)	4210 (SP) LIME	4,421.000	TON
326(E)	4240 (SP) CEMENTITIOUS STABILIZED SUBGRADE	46,041.000	SY
326(F)	4250 (SP) LIME STABILIZED SUBGRADE	153,436.000	SY
403(E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	5,108.000	TON
407	0250 TACK COAT	15,741.000	GAL
408	5774 PRIME COAT	64,228.000	GAL
411(S2)	5930 (SP) ASPH.CONC., TYPE S2 (PG 64-22 OK)	930.000	TON
411(S3)	5940 (SP) ASPH.CONC., TYPE S3 (PG 70-28 OK)	55,706.000	TON
411(S3)	5945 (SP) ASPH.CONC., TYPE S3 (PG 64-22 OK)	2,777.000	TON
411(S5)	5970 (SP) ASPH.CONC., TYPE S5 (PG 70-28 OK)	14,146.000	TON
413(A)	4861 RUMBLE STRIP-METHOD AC-CON	34,100.000	LF
417	5267 COLD MILLING PAVEMENT	1,484.000	SY
501(A)	0313 STRUCTURAL EXCAVATION UNCLASSIFIED	272.000	CY
509(B)	0321 CLASS A CONCRETE	731.000	CY
509(C)	0322 CLASS A CONCRETE FOR SMALL STRUCTURES	13.000	CY
509(D)	0325 CLASS C CONCRETE	327.000	CY
511(A)	0332 REINFORCING STEEL	110,879.000	LB
601(A)	0297 TYPE I PLAIN RIPRAP	40.000	TON
609(B)	1524 2'-8" COMB.CRB. & GUT. (6" MNTBLE)	13,700.000	LF

CALL ORDER : 390
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : MUSKOGEE

CONTRACT ID : 030388
 PCN : 1499404
 PROJECTS : STPY-51C(404)
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 96.45
 CALENDAR DAYS : 365
 RES. ENG.:
 LIQ. DAM.: \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY		
610 (B) 0399	6" CONCRETE DRIVEWAY (H.E.S.)	1,692.000	SY
611 (D) 4215	MANHOLE FRAME & COVER	19.000	EA
611 (E) 5113	INLET CICI DES. 2 (B)	3.000	EA
611 (E) 5492	INLET CDI RCB(45SK) DES. 2	1.000	EA
611 (E) 5870	INLET W/LRG.JCT.BOX,CICI-JB-1,DES.2	1.000	EA
611 (E) 5872	INLET W/LRG.JCT.BOX,CICI-JB-1,DES.2 (B)	2.000	EA
611 (E) 5970	INLET W/SMALL JCT.BOX,CICI-JB-1,DES.2	2.000	EA
611 (E) 5972	INLET W/SMALL JCT.BOX,CICI-JB-1,DES.2 (B)	5.000	EA
611 (E) 6000	INLET (SMD-TYPE 1)	24.000	EA
611 (F) 5872	INLET W/LJB,CICI-JB-1,DES.2 (B,ADD.DPTH)	6.000	VF
611 (F) 5970	INLET W/SJB,CICI-JB-1,DES.2 (ADD.DPTH)	4.000	VF
611 (F) 5972	INLET W/SJB,CICI-JB-1,DES.2 (B,ADD.DPTH)	2.000	VF
611 (G) 4488	INLET FRM&GRT (SSIF-FRM,CIG-GRT-VG-F)	26.000	EA
611 (J) 0487	JUNCTION BOXES	398.000	CF
611 (K) 4488	CAST IRON CURB INLETS	46.000	EA
613 (B) 0491	18" R.C.PIPE CLASS III	2,735.000	LF
613 (B) 0492	24" R.C.PIPE CLASS III	599.000	LF
613 (B) 0493	30" R.C.PIPE CLASS III	450.000	LF
613 (B) 0494	36" R.C.PIPE CLASS III	125.000	LF
613 (B) 0496	48" R.C.PIPE CLASS III	515.000	LF
613 (D) 0689	18" CORR. GALV. STEEL PIPE	475.000	LF
613 (D) 0690	24" CORR. GALV. STEEL PIPE	266.000	LF
613 (D) 0691	30" CORR. GALV. STEEL PIPE	86.000	LF
613 (D) 0692	36" CORR. GALV. STEEL PIPE	478.000	LF
613 (D) 4532	57" X 38" CORR. GALV. STEEL PIPE ARCH	102.000	LF
613 (M) 4544	57" X 38" PREFAB. CULVERT END SEC., ARCH	8.000	EA
613 (M) 5726	18" PREFAB. CULVERT END SEC., ROUND	22.000	EA
613 (M) 5730	24" PREFAB. CULVERT END SEC., ROUND	13.000	EA
613 (M) 5732	30" PREFAB. CULVERT END SEC., ROUND	4.000	EA
613 (M) 5734	36" PREFAB. CULVERT END SEC., ROUND	12.000	EA
613 (M) 5738	48" PREFAB. CULVERT END SEC., ROUND	1.000	EA
613 (P) 6204	6" PERFORATED PIPE UNDERDRAIN ROUND	3,697.000	LF
613 (Q) 1096	6" NON-PERF.PIPE UNDERDRAIN RND.	1,233.000	LF
619 (A) 0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619 (B) 4728	REMOVAL OF ASPHALT PAVEMENT	4,152.000	SY
619 (B) 4763	REMOVAL OF CONC.PAV.W/ASPH.OVERLAY	45,867.000	SY
624 (A) 4281	FENCE-STYLE WWF	2,956.000	LF
624 (C) 4459	(SP)FENCE-STYLE SWF (5 BARBED WIRE)	17,859.000	LF
629 (A) 4958	MAILBOX INSTALLATION-SINGLE	22.000	EA
629 (C) 4960	MAILBOX	22.000	EA
629 (D) 4961	REMOVAL OF MAILBOX INSTALLATION	22.000	EA
640 1426	FIELD OFFICE	1.000	EA
641 1552	MOBILIZATION	1.000	LSUM

CALL ORDER : 390
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : MUSKOGEE

CONTRACT ID : 030388
 PCN : 1499404
 PROJECTS : STPY-51C(404)
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 96.45
 CALENDAR DAYS : 365
 RES. ENG.:
 LIQ. DAM.: \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 I000-ROADWAY			
643	0087 (SP)CONTRACTORS QUALITY CONTROL	1.000	LSUM
653(A)	5915 EDGE DRAIN CONDUIT-PERFORATED	13,700.000	LF
653(C)	5946 OUTLET LATERAL HEADWALL	10.000	EA
SECTION NO. 0002 X028-BRIDGE 'A'			
202(A)	1301 UNCLASSIFIED EXCAVATION	480.000	CY
202(G)	6181 EARTHWORK	1.000	LSUM
501(A)	1306 STRUCTURAL EXCAVATION UNCLASSIFIED	115.000	CY
509(B)	1328 CLASS A CONCRETE	229.800	CY
511(A)	1332 REINFORCING STEEL	40,580.000	LB
601(B)	1357 TYPE II SP. PLAIN RIPRAP	1,870.000	TON
619(B)	2505 (PL)REMOVAL OF BRIDGE ITEMS	2.000	EA
SECTION NO. 0003 Y008-TRAFFIC			
850(A)	8110 SHEET ALUMINUM SIGNS	226.440	SF
851(C)	8327 2 1/4" SQUARE TUBE POST	517.500	LF
855(A)	8812 TRAFFIC STRIPE (PLASTIC) (4" WIDE)	86,500.000	LF
855(B)	8818 TRAFFIC STRIPE (PLASTIC) (ARROWS)	80.000	EA
856(A)	8839 CONSTRUCTION TRAFF.STR. (PAINT) (4" WIDE)	160,000.000	LF
856(G)	8887 (PL)CONST.ZONE PAV.MKRS (FLEX TAB) TYP.2-1	12,000.000	EA
859(A)	8006 PAVEMENT MRKNG.REMOVAL (TRAF.STRP)	50,000.000	LF
876(C)	8482 (PL)TRUCK MOUNTED ATTENUATOR	100.000	SD
880(B)	8818 CONSTRUCTION SIGNS 0 TO 6.25 SF	13,200.000	SD
880(B)	8821 CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	14,080.000	SD
880(B)	8824 CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	15,400.000	SD
880(C)	8836 BARRICADES (TYPE II)	1,760.000	SD
880(C)	8842 BARRICADES (TYPE III)	13,200.000	SD
880(C)	8848 WING BARRICADES	1,760.000	SD
880(D)	8854 VERTICAL PANELS	44,000.000	SD
880(E)	8860 WARNING LIGHTS (TYPE A)	43,560.000	SD
880(E)	8872 WARNING LIGHTS (TYPE C)	88,000.000	SD
880(F)	8878 DRUMS	44,000.000	SD
SECTION NO. 0004 STAK-STAKING			
642	0098 STAKING	1.000	LSUM

CALL ORDER : 410
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : NOBLE

CONTRACT ID : 030364
 PCN : 2024704
 PROJECTS : NHIY-35-4(196)177
 DBE GOALS : 6.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 42.27
 CALENDAR DAYS : 330
 RES. ENG.:
 LIQ. DAM.: \$ 2000

CONTRACT DESCRIPTION:
 RESURFACE (ASPHALT) I-35; FROM MILE MARKER 177.5 TO MILE MARKER 185. PROJECT LENGTH = 6.159 MILES FLEXIBLE ESALS = 61.31 MILLION ASPHALT GRADE = PG 64-22 OK, PG 76-28 OK. (PERCENT WITHIN LIMITS SPECIAL PROVISION)

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 I000-ROADWAY			
202 (A)	0183 UNCLASSIFIED EXCAVATION	29,035.830	CY
202 (C)	0184 UNCLASSIFIED BORROW	1,000.000	CY
223	2801 TEMPORARY SILT FENCE	5,992.000	LF
227	0100 TEMPORARY SILT DIKE	266.000	LF
230 (A)	2806 SOLID SLAB SODDING	49,626.870	SY
232 (B)	2814 SEEDING METHOD B	29.300	AC
233 (A)	2817 VEGETATIVE MULCHING	29.300	AC
303	0192 AGGREGATE BASE	14,989.540	CY
325	5271 SEPARATOR FABRIC	67,706.990	SY
326 (A)	4200 (SP) FLY ASH	4,064.960	TON
326 (E)	4240 (SP) CEMENTITIOUS STABILIZED SUBGRADE	62,117.670	SY
408	5774 PRIME COAT	17,883.000	GAL
411 (S2)	5930 (SP) ASPH. CONC., TYPE S2 (PG 64-22 OK)	25,024.910	TON
411 (S3)	5935 (SP) ASPH. CONC., TYPE S3 (PG 76-28 OK)	40,213.880	TON
411 (S3)	5945 (SP) ASPH. CONC., TYPE S3 (PG 64-22 OK)	25,184.700	TON
411 (S4)	5950 (SP) ASPH. CONC., TYPE S4 (PG 76-28 OK)	22,193.970	TON
411 (S4)	5960 (SP) ASPH. CONC., TYPE S4 (PG 64-22 OK)	16,551.930	TON
411 (S5)	5965 (SP) ASPH. CONC., TYPE S5 (PG 76-28 OK)	16,220.140	TON
413 (A)	4861 RUMBLE STRIP-METHOD AC-CON	124,063.160	LF
417	5267 COLD MILLING PAVEMENT	7,888.880	SY
613 (P)	1091 6" PERFORATED PIPE UNDERDRAIN ROUND	329.000	LF
613 (Q)	1096 6" NON-PERF. PIPE UNDERDRAIN RND.	109.000	LF
613 (R)	1100 PIPE UNDERDRAIN COVER MAT'L.	1,042.000	CY
613 (S)	1180 TRENCH EXCAVATION	1,389.000	CY
619 (B)	4728 REMOVAL OF ASPHALT PAVEMENT	53,606.660	SY
619 (B)	4915 REMOVAL OF CONCRETE MEDIAN BARRIER	399.350	LF
623 (A)	0932 BEAM GUARD RAIL-W-BEAM-SINGLE	5,212.500	LF
623 (C)	5202 BEAM GUARD RAIL-THRIE-BEAM-SINGLE	387.500	LF
623 (E)	7113 BEAM GUARD RAIL-THRIE-BEAM TRANS. SECT.	1.000	EA
623 (E)	7114 THRIE BEAM BRIDGE CONNECTION-TYPE A	17.000	EA
623 (F)	4447 GUARD RAIL ANCHOR UNIT (TYPE B)	11.000	EA
623 (F)	4453 GUARD RAIL ANCHOR UNIT (TYPE GE)	10.000	EA
623 (H)	8571 (SP) G.E.T. GUARD RAIL END SECTION	21.000	EA
623 (I)	8680 (PL) BRIDGE-GUARD RAIL CONNECTION-TYPE B	3.000	EA
625 (C)	1253 REMOVE AND STORE GUARD RAIL	7,237.500	LF
641	1552 MOBILIZATION	1.000	LSUM

CALL ORDER : 410
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : NOBLE

CONTRACT ID : 030364
 PCN : 2024704
 PROJECTS : NHIY-35-4(196)177
 DBE GOALS : 6.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 42.27
 CALENDAR DAYS : 330
 RES. ENG. :
 LIQ. DAM. : \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 I000-ROADWAY			
643	0087 (SP)CONTRACTORS QUALITY CONTROL	1.000	LSUM
653(A)	5915 EDGE DRAIN CONDUIT-PERFORATED	12,703.000	LF
653(B)	5916 EDGE DRAIN OUTLET LATERAL-NONPERFORATED	816.000	LF
653(C)	5946 OUTLET LATERAL HEADWALL	45.000	EA
SECTION NO. 0002 'X220-BRIDGE 'A'			
417	5267 COLD MILLING PAVEMENT	601.900	SY
504	6179 (PL)BRIDGE TRAFFIC RAIL	203.000	LF
504(H)	6390 RAPID CURE JOINT SEALANT	78.000	LF
505(A)	6018 CLASS A BRIDGE DECK REPAIR	23.000	SY
505(B)	6019 CLASS B BRIDGE DECK REPAIR	20.000	SY
505(D)	6071 HIGH DENSITY BRIDGE DECK OVERLAY	601.900	SY
515(A)	6013 WATER REPELLENT (VISUALLY INSPECTED)	91.000	SY
520(A)	6058 PREPARATION OF CRACKS ABOVE WATER	400.000	LF
520(C)	6060 EPOXY RESIN ABOVE WATER	26.000	GAL
521(A)	6210 PNEUMATICALLY PLACED MORTAR	20.000	SY
535	6130 (SP)CORROSION INHIBITOR(SURFACE APPLIED)	25.000	SY
535	6321 (PL)CLEAN AND SANDBLAST SUBSTRUCTURE	1.000	LSUM
619(B)	2510 (PL)REMOVAL OF BRIDGE ITEM (TYPE A)	1.000	LSUM
SECTION NO. 0003 X220-BRIDGE 'B'			
417	5267 COLD MILLING PAVEMENT	601.900	SY
504	6179 (PL)BRIDGE TRAFFIC RAIL	203.000	LF
504(H)	6390 RAPID CURE JOINT SEALANT	78.000	LF
505(A)	6018 CLASS A BRIDGE DECK REPAIR	23.000	SY
505(B)	6019 CLASS B BRIDGE DECK REPAIR	20.000	SY
505(D)	6071 HIGH DENSITY BRIDGE DECK OVERLAY	601.900	SY
515(A)	6013 WATER REPELLENT (VISUALLY INSPECTED)	91.000	SY
520(A)	6058 PREPARATION OF CRACKS ABOVE WATER	400.000	LF
520(C)	6060 EPOXY RESIN ABOVE WATER	26.000	GAL
521(A)	6210 PNEUMATICALLY PLACED MORTAR	20.000	SY
535	6130 (SP)CORROSION INHIBITOR(SURFACE APPLIED)	25.000	SY
535	6321 (PL)CLEAN AND SANDBLAST SUBSTRUCTURE	1.000	LSUM
619(B)	2510 (PL)REMOVAL OF BRIDGE ITEM (TYPE A)	1.000	LSUM
SECTION NO. 0004 X171-BRIDGE 'C'			
417	5267 COLD MILLING PAVEMENT	1,082.100	SY
504(A)	1304 APPROACH SLAB	472.800	SY
504(C)	6276 (PL)SEALED EXPANSION JOINTS	146.200	LF
504(F)	1381 CONCRETE PARAPET	211.800	LF

CALL ORDER : 410
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : NOBLE

CONTRACT ID : 030364
 PCN : 2024704
 PROJECTS : NHIY-35-4(196)177
 DBE GOALS : 6.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 42.27
 CALENDAR DAYS : 330
 RES. ENG.:
 LIQ. DAM.: \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0004 X171-BRIDGE 'C'			
504 (H) 6390	RAPID CURE JOINT SEALANT	146.200	LF
505 (B) 6019	CLASS B BRIDGE DECK REPAIR	50.000	SY
505 (C) 6020	CLASS C BRIDGE DECK REPAIR	27.000	SY
505 (D) 6071	HIGH DENSITY BRIDGE DECK OVERLAY	1,082.100	SY
510 (C) 6137	SLOPE WALL (4")	10.000	SY
515 (A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	85.000	SY
619 (B) 2505	(PL)REMOVAL OF BRIDGE ITEMS	2.000	EA
SECTION NO. 0005 X171-BRIDGE 'D'			
417 5267	COLD MILLING PAVEMENT	1,082.100	SY
504 (A) 1304	APPROACH SLAB	472.800	SY
504 (C) 6276	(PL)SEALED EXPANSION JOINTS	146.200	LF
504 (F) 1381	CONCRETE PARAPET	211.800	LF
504 (H) 6390	RAPID CURE JOINT SEALANT	146.200	LF
505 (B) 6019	CLASS B BRIDGE DECK REPAIR	50.000	SY
505 (C) 6020	CLASS C BRIDGE DECK REPAIR	27.000	SY
505 (D) 6071	HIGH DENSITY BRIDGE DECK OVERLAY	1,082.100	SY
510 (C) 6137	SLOPE WALL (4")	10.000	SY
515 (A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	85.000	SY
619 (B) 2505	(PL)REMOVAL OF BRIDGE ITEMS	2.000	EA
SECTION NO. 0006 X071-BRIDGE 'E'			
504 (A) 1304	APPROACH SLAB	316.600	SY
504 (C) 6276	(PL)SEALED EXPANSION JOINTS	106.800	LF
504 (F) 1381	CONCRETE PARAPET	15.200	LF
505 (C) 6020	CLASS C BRIDGE DECK REPAIR	20.000	SY
515 (A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	6.000	SY
521 (A) 6210	PNEUMATICALLY PLACED MORTAR	10.000	SY
535 6130	(SP)CORROSION INHIBITOR(SURFACE APPLIED)	12.000	SY
619 (B) 2505	(PL)REMOVAL OF BRIDGE ITEMS	2.000	EA
SECTION NO. 0007 X071-BRIDGE 'F'			
504 (A) 1304	APPROACH SLAB	316.600	SY
504 (C) 6276	(PL)SEALED EXPANSION JOINTS	106.800	LF
504 (F) 1381	CONCRETE PARAPET	27.700	LF
505 (C) 6020	CLASS C BRIDGE DECK REPAIR	20.000	SY
515 (A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	6.000	SY
521 (A) 6210	PNEUMATICALLY PLACED MORTAR	10.000	SY
535 6130	(SP)CORROSION INHIBITOR(SURFACE APPLIED)	12.000	SY
619 (B) 2505	(PL)REMOVAL OF BRIDGE ITEMS	2.000	EA

CALL ORDER : 410
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : NOBLE

CONTRACT ID : 030364
 PCN : 2024704
 PROJECTS : NHIY-35-4(196)177
 DBE GOALS : 6.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 42.27
 CALENDAR DAYS : 330
 RES. ENG. :
 LIQ. DAM. : \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0007 X071-BRIDGE 'F'			
619(B) 4915	REMOVAL OF CONCRETE MEDIAN BARRIER	12.500	LF
SECTION NO. 0008 Y008-TRAFFIC			
627(G) 4316	RELOC.PORT.TYPE PRECAST CONC.MEDIAN BARR	11,880.000	LF
627(H) 5856	DEL.PORT.TYPE PREC. CONCRETE MEDIAN BARR	5,260.000	LF
804(A) 2915	STRUCTURAL CONCRETE	5.690	CY
804(B) 2916	REINFORCING STEEL	824.000	LB
850(A) 8110	SHEET ALUMINUM SIGNS	564.595	SF
850(B) 8112	EXTRUDED ALUMINUM PANEL SIGNS	75.000	SF
851(A) 3206	4"@13 GALV.STL.WD.FLANGE BM.POST	60.000	LF
851(B) 3217	2 1/2"@5.79 GALV.STL.PIPE POST	56.000	LF
851(B) 3218	3"@7.58 GALV.STL.PIPE POST	42.000	LF
851(B) 3219	3 1/2"@9.11 GALV.STL.PIPE POST	120.000	LF
851(C) 8321	1 3/4" SQUARE TUBE POST	138.000	LF
851(C) 8324	2" SQUARE TUBE POST	110.000	LF
851(C) 8327	2 1/4" SQUARE TUBE POST	298.500	LF
851(C) 8330	2 1/2" SQUARE TUBE POST	87.000	LF
855(A) 8812	TRAFFIC STRIPE (PLASTIC) (4" WIDE)	187,130.000	LF
856(A) 8839	CONSTRUCTION TRAFF.STR. (PAINT) (4" WIDE)	65,050.000	LF
856(C) 8851	REMOVABLE PAVEMENT MARKING TAPE (4" WIDE)	500.000	LF
856(G) 8887	(PL)CONST.ZONE PAV.MKRS (FLEX TAB) TYP.2-1	34,000.000	EA
857(A) 8947	PAVE.MARKERS CLASS C TYPE 2-C	972.000	EA
859(A) 8006	PAVEMENT MRKNG.REMOVAL (TRAF.STRP)	500.000	LF
870(A) 8485	SAND FILLED IMPACT ATTEN.MODULE	313.000	SD
876(C) 8482	(PL)TRUCK MOUNTED ATTENUATOR	313.000	SD
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
882(B) 8306	PORT.CHANGEABLE MESSAGE SIGN	758.000	SD
890(A) 8724	(PL)REMOVAL OF EXISTING SIGNS	55.000	EA
SECTION NO. 0009 STAK-STAKING			
642 0098	STAKING	1.000	LSUM

CALL ORDER : 430
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : OTTAWA

CONTRACT ID : 030389
 PCN : 1671704
 PROJECTS : BRO-158D(006) CO
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 9.75
 CALENDAR DAYS : 150
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:
 BRIDGE AND APPROACHES COUNTY ROAD: BRIDGE AT FIVE MILE
 CREEK, 2.0 MILES NORTH AND 5.1 MILES EAST OF QUAPAW.
 PROJECT LENGTH = 0.209 KM FLEXIBLE ESALS = 0.64 MILLION
 ASPHALT GRADE = PG 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 I000-ROADWAY			
201	M0102 CLEARING AND GRUBBING	1.000	LSUM
202 (G)	M0185 EARTHWORK	1.000	LSUM
205	M4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
210	M0121 OBLITERATING ABANDONED ROAD	0.150	STA
222	M2801 TEMPORARY BALE BARRIER	500.000	M
223	M2802 TEMPORARY SILT FENCE	500.000	M
230 (A)	M2806 SOLID SLAB SODDING	2,403.000	M2
233 (A)	M2817 VEGETATIVE MULCHING	0.240	HA
303	M0192 AGGREGATE BASE	361.000	M3
403 (E)	M0225 TRAFFIC BOUND SURFACE COURSE TYPE E	48.000	T
407	M0250 TACK COAT	398.000	L
408	M5774 PRIME COAT	1,710.000	L
411 (S3)	M5945 (SP) ASPH. CONC., TYPE S3 (PG 64-22 OK)	425.000	T
411 (S4)	M5960 (SP) ASPH. CONC., TYPE S4 (PG 64-22 OK)	209.000	T
509 (D)	M0325 CLASS C CONCRETE	20.000	M3
613 (D)	M0692 90MM CORR. GALV. STEEL PIPE	26.000	M
613 (MM)	M7503 TYPE D4 SLOPED CONCRETE END SECTION	2.000	EA
854 (A)	M8800 TRAFFIC STRIPE (PAINT) (100MM WIDE)	936.000	M
SECTION NO. 0002 X081-BRIDGE 'A'			
501 (B)	M1307 SUBSTRUCTURE EXCAVATION COMMON	110.000	M3
501 (C)	M1308 SUBSTRUCTURE EXCAVATION ROCK	17.200	M3
501 (D)	M6353 UNCLASSIFIED BACKFILL	32.000	M3
503 (B)	M6144 PRESTRESSED CONCRETE DOUBLE TEE	240.800	M
504 (E)	M1380 CONCRETE RAIL (TR1)	112.300	M
509 (A)	M1326 CLASS AA CONCRETE	83.600	M3
509 (B)	M1328 CLASS A CONCRETE	73.200	M3
511 (A)	M1332 REINFORCING STEEL	14,655.000	KG
516 (A)	M6091 DRILLED SHAFTS 750MM DIAMETER	12.600	M
601A-1	M1353 TYPE I-A PLAIN RIPRAP	20.000	T
601A-2	M1355 TYPE I-A FILTER BLANKET	67.000	T
619 (D)	M1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623 (F)	6033 GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
640	M1398 FIELD OFFICE	1.000	EA
641	M1399 MOBILIZATION	1.000	LSUM
880 (J)	M8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAK-STAKING			
642	M0098 STAKING	1.000	LSUM

CALL ORDER : 450
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : PAYNE

CONTRACT ID : 030390
 PCN : 1699812
 PROJECTS : STPY-160B(59)
 DBE GOALS : 8.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 45.52
 CALENDAR DAYS : 250
 RES. ENG.:
 LIQ. DAM.: \$ 1000

CONTRACT DESCRIPTION:
 GRADE, DRAIN AND SURFACE (ASPHALT) SH-51; FROM LITTLE
 STILLWATER CREEK EAST OF STILLWATER, EXTEND EAST. PROJECT
 LENGTH = 1.17 MILES FLEXIBLE ESALS = 10.5 MILLION ASPHALT
 GRADE = PG 64-22 OK, PG 76-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 I000-ROADWAY			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202 (A)	0183 UNCLASSIFIED EXCAVATION	44,120.000	CY
202 (C)	0184 UNCLASSIFIED BORROW	9,343.000	CY
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
222	2801 TEMPORARY BALE BARRIER	1,020.000	LF
223	2801 TEMPORARY SILT FENCE	2,900.000	LF
224	2803 TEMPORARY SEDIMENT FILTER	1.000	EA
226	2805 TEMPORARY SEDIMENT REMOVAL	30.000	CY
227	0100 TEMPORARY SILT DIKE	800.000	LF
229	4318 DITCH LINER PROTECTION	5,650.000	LF
230 (A)	2806 SOLID SLAB SODDING	12,338.000	SY
230 (B)	2807 MULCH SODDING	40,795.000	SY
230 (F)	2812 WATERING	2,126.000	MGAL
233 (A)	2817 VEGETATIVE MULCHING	11.000	AC
234 (A)	2824 FERTILIZING (10-20-10)	5.330	TON
234 (A)	4406 FERTILIZING (0-46-0)	5.220	TON
241	2832 MOWING	22.000	AC
243	0450 (PL) TEMPORARY INLET SEDIMENT FILTER	1.000	EA
326 (B)	4210 (SP) LIME	760.000	TON
326 (F)	4250 (SP) LIME STABILIZED SUBGRADE	42,529.000	SY
403 (E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	144.000	TON
407	0250 TACK COAT	6,759.000	GAL
408	5774 PRIME COAT	7,415.000	GAL
411 (S2)	5930 (SP) ASPH.CONC., TYPE S2 (PG 64-22 OK)	11,942.000	TON
411 (S3)	5935 (SP) ASPH.CONC., TYPE S3 (PG 76-28 OK)	6,896.000	TON
411 (S3)	5940 (SP) ASPH.CONC., TYPE S3 (PG 70-28 OK)	526.000	TON
411 (S3)	5945 (SP) ASPH.CONC., TYPE S3 (PG 64-22 OK)	4,483.000	TON
411 (S4)	5950 (SP) ASPH.CONC., TYPE S4 (PG 76-28 OK)	4,601.000	TON
411 (S4)	5955 (SP) ASPH.CONC., TYPE S4 (PG 70-28 OK)	348.000	TON
411 (S4)	5960 (SP) ASPH.CONC., TYPE S4 (PG 64-22 OK)	2,745.000	TON
413 (A)	4861 RUMBLE STRIP-METHOD AC-CON	21,054.000	LF
414 (B)	5072 9" H.E.S. CONCRETE (PATCHING)	61.000	SY
417	5267 COLD MILLING PAVEMENT	16,453.000	SY
417	5268 COLD MILLING PAVEMENT (2")	7,750.000	SY
420 (A)	4242 FABRIC REINFORCEMENT	17,987.000	SY
420 (B)	4268 BITUMINOUS BINDER	4,497.000	GAL

CALL ORDER : 450
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : PAYNE

CONTRACT ID : 030390
 PCN : 1699812
 PROJECTS : STPY-160B(59)
 DBE GOALS : 8.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 45.52
 CALENDAR DAYS : 250
 RES. ENG.:
 LIQ. DAM.: \$ 1000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001	I000-ROADWAY		
501 (A) 0313	STRUCTURAL EXCAVATION UNCLASSIFIED	88.000	CY
509 (B) 0321	CLASS A CONCRETE	292.000	CY
509 (D) 0325	CLASS C CONCRETE	1,054.000	CY
511 (A) 0332	REINFORCING STEEL	41,314.000	LB
601 (A) 0297	TYPE I PLAIN RIPRAP	252.000	TON
601 (E) 6312	FILTER FABRIC (RIPRAP)	308.000	SY
611 (E) 5337	INLET GPI TYPE 2 (DES. 11)	1.000	EA
611 (L) 4207	DROP INLET GRATE (GPI-TYPE A)	2.000	EA
611 (L) 4208	DROP INLET GRATE (GPI-TYPE B)	1.000	EA
611 (N) 3640	WELDED STEEL GRATE (56" SQ.)	4.000	EA
613 (B) 0492	24" R.C.PIPES CLASS III	192.000	LF
613 (B) 0495	42" R.C.PIPES CLASS III	151.000	LF
613 (CC) 7187	TYPE B4 CULVERT END TREATMENT	2.000	EA
613 (CC) 7188	TYPE C4 CULVERT END TREATMENT	1.000	EA
613 (CC) 7189	TYPE D4 CULVERT END TREATMENT	1.000	EA
613 (CC) 7197	TYPE B6 CULVERT END TREATMENT	16.000	EA
613 (CC) 7198	TYPE C6 CULVERT END TREATMENT	1.000	EA
613 (D) 4528	28" X 20" CORR. GALV. STEEL PIPE ARCH	471.000	LF
613 (D) 4530	42" X 29" CORR. GALV. STEEL PIPE ARCH	74.000	LF
613 (P) 1092	8" PERFORATED PIPE UNDERDRAIN ROUND	400.000	LF
613 (Q) 1097	8" NON-PERF. PIPE UNDERDRAIN RND.	200.000	LF
613 (S) 1180	TRENCH EXCAVATION	257.000	CY
613 (T) 1181	STANDARD BEDDING MATERIAL	206.000	CY
619 (A) 0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619 (B) 4728	REMOVAL OF ASPHALT PAVEMENT	22,488.000	SY
619 (C) 0924	SAWING PAVEMENT	12,600.000	LF
624 (A) 4281	FENCE-STYLE WWF	768.000	LF
624 (C) 4459	(SP) FENCE-STYLE SWF (5 BARBED WIRE)	170.000	LF
629 (A) 4958	MAILBOX INSTALLATION-SINGLE	2.000	EA
629 (B) 4959	MAILBOX INSTALLATION-MULTIPLE	3.000	EA
629 (C) 4960	MAILBOX	10.000	EA
629 (D) 4961	REMOVAL OF MAILBOX INSTALLATION	5.000	EA
640 1426	FIELD OFFICE	1.000	EA
641 1552	MOBILIZATION	1.000	LSUM

SECTION NO. 0002	Y002-TRAFFIC SIGNING		
850 (A) 8110	SHEET ALUMINUM SIGNS	199.000	SF
851 (C) 8327	2 1/4" SQUARE TUBE POST	480.000	LF
855 (A) 8812	TRAFFIC STRIPE (PLASTIC) (4" WIDE)	39,000.000	LF
855 (B) 8818	TRAFFIC STRIPE (PLASTIC) (ARROWS)	46.000	EA
855 (B) 8821	TRAFFIC STRIPE (PLASTIC) (WORDS)	3.000	EA

CALL ORDER : 450
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : PAYNE

CONTRACT ID : 030390
 PCN : 1699812
 PROJECTS : STPY-160B(59)
 DBE GOALS : 8.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 45.52
 CALENDAR DAYS : 250
 RES. ENG.:
 LIQ. DAM.: \$ 1000

SECTION NO. 0003 Y000-TRAFFIC OPERATIONS

627 (E)	4314	PRECAST CONC. MEDIAN BARRIER, PORT. TYPE	380.000	LF
627 (G)	4316	RELOC.PORT.TYPE PRECAST CONC.MEDIAN BARR	380.000	LF
627 (H)	5856	DEL.PORT.TYPE PREC. CONCRETE MEDIAN BARR	380.000	LF
856 (A)	8839	CONSTRUCTION TRAFF.STR. (PAINT) (4" WIDE)	4,000.000	LF
856 (C)	8851	REMOVABLE PAVEMENT MARKING TAPE (4" WIDE)	33,600.000	LF
856 (G)	8881	(PL)CONSTRUCTION ZONE PAVEMENT MARKERS	9,400.000	EA
859 (A)	8006	PAVEMENT MRKNG.REMOVAL (TRAF.STRP)	13,000.000	LF
870 (A)	8011	SAND FILLED IMPACT ATTEN.MODULE	30.000	EA
880 (B)	8818	CONSTRUCTION SIGNS 0 TO 6.25 SF	6,600.000	SD
880 (B)	8821	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	3,300.000	SD
880 (B)	8824	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	3,300.000	SD
880 (C)	8842	BARRICADES (TYPE III)	7,200.000	SD
880 (C)	8848	WING BARRICADES	1,200.000	SD
880 (D)	8854	VERTICAL PANELS	3,000.000	SD
880 (E)	8860	WARNING LIGHTS (TYPE A)	1,200.000	SD
880 (E)	8872	WARNING LIGHTS (TYPE C)	83,100.000	SD
880 (F)	8878	DRUMS	83,100.000	SD
880 (L)	8911	TRAFFIC SURVEILLANCE, POLICE	48.000	HOURL
882 (B)	8306	PORT.CHANGEABLE MESSAGE SIGN	600.000	SD

SECTION NO. 0004 STAK-STAKING

642	0098	STAKING	1.000	LSUM
-----	------	---------	-------	------

CALL ORDER : 458
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : PAYNE

CONTRACT ID : 030437
 PCN : 1897604
 PROJECTS : RABA-0Q16(001)RA
 DBE GOALS : 7.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 185.32
 CALENDAR DAYS : 410
 RES. ENG.:
 LIQ. DAM.: \$ 2000

CONTRACT DESCRIPTION:
 GRADE, DRAIN, & SURFACE US-177; FROM SH-33, EXTEND NORTH TO
 WEST 32ND AVE. IN STILLWATER. PROJECT LENGTH 6.532 MILES
 FLEXIBLE ESALS = 6.7 MILLION ASPHALT GRADE = PG 64-22OK,
 PG-70-28

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 I000-ROADWAY RABA-0Q16(001)HP			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202 (A)	0183 UNCLASSIFIED EXCAVATION	213,140.000	CY
202 (C)	0184 UNCLASSIFIED BORROW	21,058.000	CY
202 (D)	0186 SELECT BORROW	390.000	CY
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	15,894.000	LF
224	2803 TEMPORARY SEDIMENT FILTER	11.000	EA
226	2805 TEMPORARY SEDIMENT REMOVAL	170.000	CY
227	0100 TEMPORARY SILT DIKE	4,420.000	LF
229	4318 DITCH LINER PROTECTION	7,933.000	LF
230 (A)	2806 SOLID SLAB SODDING	25,473.000	SY
230 (B)	2807 MULCH SODDING	161,674.000	SY
230 (F)	2812 WATERING	13,535.000	MGAL
232 (A)	2813 SEEDING METHOD A	101.000	AC
233 (A)	2817 VEGETATIVE MULCHING	139.800	AC
234 (A)	2824 FERTILIZING (10-20-10)	34.300	TON
234 (A)	4406 FERTILIZING (0-46-0)	3.600	TON
241	2832 MOWING	139.800	AC
243	0450 (PL) TEMPORARY INLET SEDIMENT FILTER	1.000	EA
326 (B)	4210 (SP) LIME	5,708.000	TON
326 (F)	4250 (SP) LIME STABILIZED SUBGRADE	244,901.000	SY
403 (E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	4,657.000	TON
407	0250 TACK COAT	51,422.000	GAL
408	5774 PRIME COAT	37,249.000	GAL
411 (S2)	5930 (SP) ASPH.CONC., TYPE S2 (PG 64-22 OK)	102,429.000	TON
411 (S3)	5940 (SP) ASPH.CONC., TYPE S3 (PG 70-28 OK)	41,820.000	TON
411 (S4)	5955 (SP) ASPH.CONC., TYPE S4 (PG 70-28 OK)	27,880.000	TON
411 (S4)	5960 (SP) ASPH.CONC., TYPE S4 (PG 64-22 OK)	14,191.000	TON
413 (B)	4862 RUMBLE STRIP-METHOD AC-CYC (GROUP)	2,351.000	EAGP
417	4267 COLD MILLING BITUMINOUS PAVEMENT	29,238.000	SY
417	4659 (PL) FOG SEAL	26,645.000	GAL
420 (A)	4244 (PL) PRECOATED FABRIC MEMBRANE (STRIP)	24,552.000	LF
501 (A)	0313 STRUCTURAL EXCAVATION UNCLASSIFIED	299.460	CY
509 (B)	0321 CLASS A CONCRETE	806.800	CY
509 (D)	0325 CLASS C CONCRETE	913.410	CY
511 (A)	0332 REINFORCING STEEL	135,913.000	LB

CALL ORDER : 458
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : PAYNE

CONTRACT ID : 030437
 PCN : 1897604
 PROJECTS : RABA-0Q16(001)RA
 DBE GOALS : 7.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 185.32
 CALENDAR DAYS : 410
 RES. ENG.:
 LIQ. DAM.: \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY RABA-0Q16(001)HP		
601 (A-1) 1353	TYPE I-A PLAIN RIPRAP	838.000	TON
601 (A-2) 1355	TYPE I-A FILTER BLANKET	188.000	TON
609 (B) 1523	2'-8" COMB.CRB.& GUT.(4" MNTBLE)	190.420	LF
609 (B) 1524	2'-8" COMB.CRB.& GUT.(6" MNTBLE)	883.300	LF
610 (B) 0400	8" CONCRETE DRIVEWAY (H.E.S.)	707.000	SY
610 (C) 0608	4" CONCRETE DIVIDING STRIP	157.560	SY
611 (D) 4215	MANHOLE FRAME & COVER	1.000	EA
611 (E) 6002	INLET (SMD-TYPE 2)	1.000	EA
611 (E) 6006	INLET (SMD-TYPE 2B)	1.000	EA
611 (J) 0487	JUNCTION BOXES	40.650	CF
611 (L) 4479	DROP INLET GRATE (24" SPDI)	9.000	EA
613 (B) 0491	18" R.C.PIPES CLASS III	686.000	LF
613 (B) 0492	24" R.C.PIPES CLASS III	345.000	LF
613 (B) 0494	36" R.C.PIPES CLASS III	298.000	LF
613 (B) 4498	43" X 26" R.C.PIPES ARCH CLASS A-III	118.000	LF
613 (B) 4504	19" X 30" R.C.PIPES ELL. CLASS HE-III	374.000	LF
613 (B) 4505	24" X 38" R.C.PIPES ELL. CLASS HE-III	298.000	LF
613 (B) 4508	38" X 60" R.C.PIPES ELL. CLASS HE-III	124.000	LF
613 (C) 5100	SP. END SECTION OF 24" X 38" RCP ELL.	4.000	EA
613 (C) 5156	SP. END SECTION OF 38" X 60" RCP ELL.	2.000	EA
613 (C) 5157	SP. END SECTION OF 19" X 30" RCP ELL.	2.000	EA
613 (CC) 7186	TYPE A4 CULVERT END TREATMENT	91.000	EA
613 (CC) 7187	TYPE B4 CULVERT END TREATMENT	6.000	EA
613 (CC) 7188	TYPE C4 CULVERT END TREATMENT	4.000	EA
613 (CC) 7189	TYPE D4 CULVERT END TREATMENT	2.000	EA
613 (CC) 7191	TYPE AA4 CULVERT END TREATMENT	21.000	EA
613 (CC) 7192	TYPE BB4 CULVERT END TREATMENT	31.000	EA
613 (CC) 7193	TYPE CC4 CULVERT END TREATMENT	7.000	EA
613 (CC) 7196	TYPE A6 CULVERT END TREATMENT	73.000	EA
613 (CC) 7197	TYPE B6 CULVERT END TREATMENT	11.000	EA
613 (CC) 7199	TYPE D6 CULVERT END TREATMENT	2.000	EA
613 (CC) 7201	TYPE AA6 CULVERT END TREATMENT	22.000	EA
613 (CC) 7202	TYPE BB6 CULVERT END TREATMENT	31.000	EA
613 (CC) 7203	TYPE CC6 CULVERT END TREATMENT	7.000	EA
613 (D) 0688	12" CORR. GALV. STEEL PIPE	500.000	LF
613 (D) 0689	18" CORR. GALV. STEEL PIPE	987.000	LF
613 (D) 0690	24" CORR. GALV. STEEL PIPE	897.000	LF
613 (D) 0692	36" CORR. GALV. STEEL PIPE	238.000	LF
613 (D) 0694	48" CORR. GALV. STEEL PIPE	54.000	LF
613 (D) 4527	21" X 15" CORR. GALV. STEEL PIPE ARCH	5,982.000	LF
613 (D) 4528	28" X 20" CORR. GALV. STEEL PIPE ARCH	1,524.000	LF
613 (D) 4529	35" X 24" CORR. GALV. STEEL PIPE ARCH	2,308.000	LF
613 (D) 4530	42" X 29" CORR. GALV. STEEL PIPE ARCH	1,012.000	LF

CALL ORDER : 458
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : PAYNE

CONTRACT ID : 030437
 PCN : 1897604
 PROJECTS : RABA-0Q16(001)RA
 DBE GOALS : 7.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 185.32
 CALENDAR DAYS : 410
 RES. ENG.:
 LIQ. DAM.: \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY RABA-0Q16(001)HP		
613 (D) 4531	49" X 33" CORR. GALV. STEEL PIPE ARCH	58.000	LF
613 (M) 5730	24" PREFAB. CULVERT END SEC., ROUND	4.000	EA
613 (M) 5734	36" PREFAB. CULVERT END SEC., ROUND	9.000	EA
613 (P) 1092	8" PERFORATED PIPE UNDERDRAIN ROUND	2,500.000	LF
613 (Q) 1097	8" NON-PERF. PIPE UNDERDRAIN RND.	500.000	LF
613 (R) 1100	PIPE UNDERDRAIN COVER MAT'L.	100.000	CY
613 (S) 1180	TRENCH EXCAVATION	1,794.590	CY
613 (T) 1181	STANDARD BEDDING MATERIAL	1,203.170	CY
619 (A) 0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619 (B) 4726	REMOVAL OF CURB AND GUTTER	560.000	LF
619 (B) 4727	REMOVAL OF CONCRETE PAVEMENT	3,026.000	SY
619 (B) 4728	REMOVAL OF ASPHALT PAVEMENT	90,176.000	SY
619 (B) 4763	REMOVAL OF CONC.PAV.W/ASPH.OVERLAY	7,093.000	SY
619 (C) 0924	SAWING PAVEMENT	49,761.000	LF
624 (A) 4281	FENCE-STYLE WWF	1,044.000	LF
624 (B) 4462	GATES-STYLE WWF (4.5'HIGH X 12'LONG)	8.000	EA
624 (B) 4464	GATES-STYLE WWF (4.5'HIGH X 14'LONG)	1.000	EA
624 (B) 4466	GATES-STYLE WWF (4.5'HIGH X 16'LONG)	2.000	EA
624 (C) 4458	(SP) FENCE-STYLE SWF (4 BARBED WIRE)	4,139.000	LF
624 (C) 4459	(SP) FENCE-STYLE SWF (5 BARBED WIRE)	6,155.000	LF
624 (D) 4290	FENCE-STYLE CLF (5'HIGH, CLASS A)	504.000	LF
624 (D) 4292	FENCE-STYLE CLF (6'HIGH, CLASS A)	361.000	LF
624 (E) 5894	GATES-STYLE CLF (5'HIGH X 12'LONG)	1.000	EA
624 (E) 5898	GATES-STYLE CLF (5'HIGH X 16'LONG)	2.000	EA
624 (E) 5964	GATES-STYLE CLF (6'HIGH X 16'LONG)	4.000	EA
629 (A) 4958	MAILBOX INSTALLATION-SINGLE	34.000	EA
629 (B) 4959	MAILBOX INSTALLATION-MULTIPLE	7.000	EA
629 (C) 4960	MAILBOX	66.000	EA
629 (D) 4961	REMOVAL OF MAILBOX INSTALLATION	65.000	EA
629 (E) 5048	REMOVE AND RESET MAILBOX	12.000	EA
640 1426	FIELD OFFICE	1.000	EA
641 1552	MOBILIZATION	1.000	LSUM
SECTION NO. 0002	X028-BRIDGE 'A' RABA-0Q16(001)HP		
202 (A) 1301	UNCLASSIFIED EXCAVATION	8,976.000	CY
501 (A) 1306	STRUCTURAL EXCAVATION UNCLASSIFIED	160.000	CY
508 (A) 6335	REMOVAL OF CULVERT END	1.000	EA
509 (B) 1328	CLASS A CONCRETE	339.400	CY
511 (A) 1332	REINFORCING STEEL	71,910.000	LB
601 (A-1) 1353	TYPE I-A PLAIN RIPRAP	404.000	TON
601 (A-2) 1355	TYPE I-A FILTER BLANKET	93.000	TON

CALL ORDER : 458
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : PAYNE

CONTRACT ID : 030437
 PCN : 1897604
 PROJECTS : RABA-0Q16(001)RA
 DBE GOALS : 7.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 185.32
 CALENDAR DAYS : 410
 RES. ENG.:
 LIQ. DAM.: \$ 2000

SECTION NO. 0003		Y000-TRAFFIC OPERATIONS	RABA-0Q16(001)HP	
627 (G)	4316	RELOC.PORT.TYPE PRECAST CONC.MEDIAN BARR	1,000.000	LF
627 (H)	5856	DEL.PORT.TYPE PREC. CONCRETE MEDIAN BARR	800.000	LF
856 (A)	8839	CONSTRUCTION TRAFF.STR. (PAINT) (4" WIDE)	282,895.000	LF
856 (C)	8851	REMOVABLE PAVEMENT MARKING TAPE (4" WIDE)	194,180.000	LF
856 (G)	8890	(PL)CONST.ZONE PAV.MKRS (FLEX TAB)TYP.2-2	25,000.000	EA
859 (A)	8006	PAVEMENT MRKNG.REMOVAL (TRAF.STRP)	5,000.000	LF
870 (A)	8485	SAND FILLED IMPACT ATTEN.MODULE	29,400.000	SD
880 (B)	8818	CONSTRUCTION SIGNS 0 TO 6.25 SF	1,580.000	SD
880 (B)	8821	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	10,578.000	SD
880 (B)	8824	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	6,600.000	SD
880 (C)	8842	BARRICADES (TYPE III)	3,770.000	SD
880 (C)	8848	WING BARRICADES	3,770.000	SD
880 (D)	8854	VERTICAL PANELS	222,990.000	SD
880 (E)	8860	WARNING LIGHTS (TYPE A)	8,170.000	SD
880 (E)	8872	WARNING LIGHTS (TYPE C)	279,010.000	SD
880 (F)	8878	DRUMS	56,020.000	SD
SECTION NO. 0004		Y002-TRAFFIC SIGNING	RABA-0Q16(001)HP	
850 (A)	8110	SHEET ALUMINUM SIGNS	535.500	SF
851 (C)	8327	2 1/4" SQUARE TUBE POST	1,158.500	LF
855 (A)	8812	TRAFFIC STRIPE (PLASTIC) (4" WIDE)	212,309.000	LF
855 (B)	8818	TRAFFIC STRIPE (PLASTIC) (ARROWS)	283.000	EA
855 (B)	8821	TRAFFIC STRIPE (PLASTIC) (WORDS)	23.000	EA
SECTION NO. 0005		Y002-TRAFFIC SIGNALS	RABA-0Q16(001)HP	
802 (B)	8332	1" PVC SCH.40 PLASTIC CONDUIT BORED	195.000	LF
802 (B)	8336	1 1/2" PVC SCH.40 PLASTIC CONDUIT BORED	60.000	LF
802 (B)	8338	1 1/2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	890.000	LF
802 (B)	8342	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	30.000	LF
802 (B)	8344	3" PVC SCH.40 PLASTIC CONDUIT BORED	290.000	LF
802 (B)	8346	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	35.000	LF
803	8065	PULL BOX (SIZE I)	3.000	EA
803	8066	PULL BOX (SIZE II)	1.000	EA
803	8067	PULL BOX (SIZE III)	7.000	EA
804 (A)	2915	STRUCTURAL CONCRETE	6.400	CY
804 (B)	2916	REINFORCING STEEL	974.400	LB
806 (A)	8313	32'MH POLE 45'TS & 10'LMA (G.STL.)	1.000	EA
806 (A)	8355	(PL)32'MH POLE,TWIN TS & 10'LMA (G.STL.)	1.000	EA
809 (A)	8090	(PL)ROADWAY LUMINAIRE	2.000	EA
810 (A)	3118	SERVICE POLE	1.000	EA
811	8040	1/C NO.6 ELECT.COND.	200.000	LF
811	8044	1/C NO.10 ELECT.COND.	860.000	LF
825	8550	VEH.ACT.SOL.ST.TRAF.SIG.CON.ASM	1.000	EA
828 (A)	8135	SOL.STE.DIGITAL IND.VEH.LP.DET.	7.000	EA
828 (B)	8138	LOOP DETECTOR WIRE	3,610.000	LF
831	8231	1WAY3SEC.ADJ.SIG.HD.S-6	4.000	EA

CALL ORDER : 458
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : PAYNE

CONTRACT ID : 030437
 PCN : 1897604
 PROJECTS : RABA-0Q16(001)RA
 DBE GOALS : 7.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 185.32
 CALENDAR DAYS : 410
 RES. ENG. :
 LIQ. DAM. : \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0005 Y002-TRAFFIC SIGNALS RABA-0Q16(001)HP			
831	8252 1WAY3SEC.ADJ.SIG.HD.S-9	3.000	EA
831	8262 1WAY3SEC.ADJ.SIG.HD.S-10	1.000	EA
833	3030 BACKPLATE	8.000	EA
834 (A)	8207 5/C TRAF.SIG.EL.CABLE	735.000	LF
834 (A)	8211 15/C TRAF.SIG.EL.CABLE	45.000	LF
834 (B)	8220 2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	2,210.000	LF
850 (C)	8118 MAST ARM MOUNTED SIGNS (ALUM.)	39.000	SF
890 (A)	8726 (PL)REMOVAL OF TRAFFIC SIGNAL EQUIPMENT	1.000	LSUM
SECTION NO. 0006 STAK-STAKING RABA-0Q16(001)HP			
642	0098 STAKING	1.000	LSUM

CALL ORDER : 459
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : PAYNE

CONTRACT ID : 030438
 PCN : 1897607
 PROJECTS : RABA-0Q16(008)RA
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 0.00
 CALENDAR DAYS : 30
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:
 RIGHT-OF-WAY CLEARANCE CONTRACT US-177; FROM SH-33 EXTEND,
 NORTH TO WEST 32ND AVE. IN STILLWATER. PROJECT LENGTH = 6.501 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROWA-ROADWAY RABA-016(008)RA		
643 0094	(PL)RIGHT-OF-WAY CLEARANCE	1.000	LSUM

CALL ORDER : 460
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : PAYNE

CONTRACT ID : 030401
 PCN : 1897604C
 PROJECTS : RABA-0Q16(001)RA/RABA-0Q16(008)
 DBE GOALS : 7.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 185.32
 CALENDAR DAYS : 410
 RES. ENG.:
 LIQ. DAM.: \$ 2000

CONTRACT DESCRIPTION:
 GRADE, DRAIN, SURFACE AND RIGHT-OF-WAY CLEARANCE US-177;
 FROM SH-33, EXTEND NORTH TO 32ND AVE. IN STILLWATER.
 PROJECT LENGTH = 6.531 MILES FLEXIBLE ESALS = 6.7 MILLION
 ASPHALT GRADE = PG 64-22 OK, PG 70-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001	I000-ROADWAY RABA-0Q16(001)RA		
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202 (A)	0183 UNCLASSIFIED EXCAVATION	213,140.000	CY
202 (C)	0184 UNCLASSIFIED BORROW	21,058.000	CY
202 (D)	0186 SELECT BORROW	390.000	CY
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	15,894.000	LF
224	2803 TEMPORARY SEDIMENT FILTER	11.000	EA
226	2805 TEMPORARY SEDIMENT REMOVAL	170.000	CY
227	0100 TEMPORARY SILT DIKE	4,420.000	LF
229	4318 DITCH LINER PROTECTION	8,023.000	LF
230 (A)	2806 SOLID SLAB SODDING	25,473.000	SY
230 (B)	2807 MULCH SODDING	161,674.000	SY
230 (F)	2812 WATERING	13,535.000	MGAL
232 (A)	2813 SEEDING METHOD A	101.000	AC
233 (A)	2817 VEGETATIVE MULCHING	139.800	AC
234 (A)	2824 FERTILIZING (10-20-10)	34.300	TON
234 (A)	4406 FERTILIZING (0-46-0)	3.600	TON
241	2832 MOWING	139.800	AC
243	0450 (PL) TEMPORARY INLET SEDIMENT FILTER	1.000	EA
326 (B)	4210 (SP) LIME	5,708.000	TON
326 (F)	4250 (SP) LIME STABILIZED SUBGRADE	244,901.000	SY
403 (E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	4,779.000	TON
407	0250 TACK COAT	51,422.000	GAL
408	5774 PRIME COAT	37,249.000	GAL
411 (S2)	5930 (SP) ASPH.CONC., TYPE S2 (PG 64-22 OK)	102,429.000	TON
411 (S3)	5940 (SP) ASPH.CONC., TYPE S3 (PG 70-28 OK)	41,820.000	TON
411 (S4)	5955 (SP) ASPH.CONC., TYPE S4 (PG 70-28 OK)	27,880.000	TON
411 (S4)	5960 (SP) ASPH.CONC., TYPE S4 (PG 64-22 OK)	14,191.000	TON
413 (B)	4862 RUMBLE STRIP-METHOD AC-CYC (GROUP)	2,351.000	EAGP
417	4267 COLD MILLING BITUMINOUS PAVEMENT	29,238.000	SY
417	4659 (PL) FOG SEAL	26,645.000	GAL
420 (A)	4244 (PL) PRECOATED FABRIC MEMBRANE (STRIP)	24,552.000	LF
501 (A)	0313 STRUCTURAL EXCAVATION UNCLASSIFIED	299.460	CY
509 (B)	0321 CLASS A CONCRETE	806.800	CY
509 (D)	0325 CLASS C CONCRETE	918.410	CY
511 (A)	0332 REINFORCING STEEL	135,913.000	LB

CALL ORDER : 460
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : PAYNE

CONTRACT ID : 030401
 PCN : 1897604C
 PROJECTS : RABA-0Q16(001)RA/RABA-0Q16(008)
 DBE GOALS : 7.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 185.32
 CALENDAR DAYS : 410
 RES. ENG.:
 LIQ. DAM.: \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY RABA-0Q16(001)RA		
601 (A-1) 1353	TYPE I-A PLAIN RIPRAP	838.000	TON
601 (A-2) 1355	TYPE I-A FILTER BLANKET	188.000	TON
609 (B) 1523	2'-8" COMB.CRB.& GUT.(4" MNTBLE)	190.420	LF
609 (B) 1524	2'-8" COMB.CRB.& GUT.(6" MNTBLE)	883.300	LF
610 (B) 0400	8" CONCRETE DRIVEWAY (H.E.S.)	707.000	SY
610 (C) 0608	4" CONCRETE DIVIDING STRIP	157.560	SY
611 (D) 4215	MANHOLE FRAME & COVER	1.000	EA
611 (E) 6002	INLET (SMD-TYPE 2)	1.000	EA
611 (E) 6006	INLET (SMD-TYPE 2B)	1.000	EA
611 (J) 0487	JUNCTION BOXES	40.650	CF
611 (L) 4479	DROP INLET GRATE (24" SPDI)	9.000	EA
613 (B) 0491	18" R.C.PIPE CLASS III	686.000	LF
613 (B) 0492	24" R.C.PIPE CLASS III	345.000	LF
613 (B) 0494	36" R.C.PIPE CLASS III	298.000	LF
613 (B) 4498	43" X 26" R.C.PIPE ARCH CLASS A-III	118.000	LF
613 (B) 4504	19" X 30" R.C.PIPE ELL. CLASS HE-III	374.000	LF
613 (B) 4505	24" X 38" R.C.PIPE ELL. CLASS HE-III	298.000	LF
613 (B) 4508	38" X 60" R.C.PIPE ELL. CLASS HE-III	124.000	LF
613 (C) 5100	SP. END SECTION OF 24" X 38" RCP ELL.	4.000	EA
613 (C) 5156	SP. END SECTION OF 38" X 60" RCP ELL.	2.000	EA
613 (C) 5157	SP. END SECTION OF 19" X 30" RCP ELL.	2.000	EA
613 (CC) 7186	TYPE A4 CULVERT END TREATMENT	91.000	EA
613 (CC) 7187	TYPE B4 CULVERT END TREATMENT	6.000	EA
613 (CC) 7188	TYPE C4 CULVERT END TREATMENT	4.000	EA
613 (CC) 7189	TYPE D4 CULVERT END TREATMENT	2.000	EA
613 (CC) 7191	TYPE AA4 CULVERT END TREATMENT	21.000	EA
613 (CC) 7192	TYPE BB4 CULVERT END TREATMENT	31.000	EA
613 (CC) 7193	TYPE CC4 CULVERT END TREATMENT	7.000	EA
613 (CC) 7196	TYPE A6 CULVERT END TREATMENT	73.000	EA
613 (CC) 7197	TYPE B6 CULVERT END TREATMENT	11.000	EA
613 (CC) 7199	TYPE D6 CULVERT END TREATMENT	2.000	EA
613 (CC) 7201	TYPE AA6 CULVERT END TREATMENT	22.000	EA
613 (CC) 7202	TYPE BB6 CULVERT END TREATMENT	31.000	EA
613 (CC) 7203	TYPE CC6 CULVERT END TREATMENT	7.000	EA
613 (D) 0688	12" CORR. GALV. STEEL PIPE	500.000	LF
613 (D) 0689	18" CORR. GALV. STEEL PIPE	987.000	LF
613 (D) 0690	24" CORR. GALV. STEEL PIPE	897.000	LF
613 (D) 0692	36" CORR. GALV. STEEL PIPE	238.000	LF
613 (D) 0694	48" CORR. GALV. STEEL PIPE	54.000	LF
613 (D) 4527	21" X 15" CORR. GALV. STEEL PIPE ARCH	6,006.000	LF
613 (D) 4528	28" X 20" CORR. GALV. STEEL PIPE ARCH	1,547.000	LF
613 (D) 4529	35" X 24" CORR. GALV. STEEL PIPE ARCH	2,308.000	LF
613 (D) 4530	42" X 29" CORR. GALV. STEEL PIPE ARCH	1,012.000	LF

CALL ORDER : 460
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : PAYNE

CONTRACT ID : 030401
 PCN : 1897604C
 PROJECTS : RABA-0Q16(001)RA/RABA-0Q16(008)
 DBE GOALS : 7.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 185.32
 CALENDAR DAYS : 410
 RES. ENG.:
 LIQ. DAM.: \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY RABA-0Q16(001)RA		
613(D) 4531	49" X 33" CORR. GALV. STEEL PIPE ARCH	58.000	LF
613(M) 5730	24" PREFAB. CULVERT END SEC., ROUND	4.000	EA
613(M) 5734	36" PREFAB. CULVERT END SEC., ROUND	9.000	EA
613(P) 1092	8" PERFORATED PIPE UNDERDRAIN ROUND	2,500.000	LF
613(Q) 1097	8" NON-PERF. PIPE UNDERDRAIN RND.	500.000	LF
613(R) 1100	PIPE UNDERDRAIN COVER MAT'L.	100.000	CY
613(S) 1180	TRENCH EXCAVATION	1,794.590	CY
613(T) 1181	STANDARD BEDDING MATERIAL	1,203.170	CY
619(A) 0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619(B) 4726	REMOVAL OF CURB AND GUTTER	560.000	LF
619(B) 4727	REMOVAL OF CONCRETE PAVEMENT	3,026.000	SY
619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	90,176.000	SY
619(B) 4763	REMOVAL OF CONC.PAV.W/ASPH.OVERLAY	7,093.000	SY
619(C) 0924	SAWING PAVEMENT	49,761.000	LF
624(A) 4281	FENCE-STYLE WWF	1,044.000	LF
624(B) 4462	GATES-STYLE WWF (4.5'HIGH X 12'LONG)	8.000	EA
624(B) 4464	GATES-STYLE WWF (4.5'HIGH X 14'LONG)	1.000	EA
624(B) 4466	GATES-STYLE WWF (4.5'HIGH X 16'LONG)	2.000	EA
624(C) 4458	(SP)FENCE-STYLE SWF (4 BARBED WIRE)	4,139.000	LF
624(C) 4459	(SP)FENCE-STYLE SWF (5 BARBED WIRE)	6,155.000	LF
624(D) 4290	FENCE-STYLE CLF (5'HIGH, CLASS A)	504.000	LF
624(D) 4292	FENCE-STYLE CLF (6'HIGH, CLASS A)	361.000	LF
624(E) 5894	GATES-STYLE CLF (5'HIGH X 12'LONG)	1.000	EA
624(E) 5898	GATES-STYLE CLF (5'HIGH X 16'LONG)	2.000	EA
624(E) 5964	GATES-STYLE CLF (6'HIGH X 16'LONG)	4.000	EA
629(A) 4958	MAILBOX INSTALLATION-SINGLE	34.000	EA
629(B) 4959	MAILBOX INSTALLATION-MULTIPLE	7.000	EA
629(C) 4960	MAILBOX	66.000	EA
629(D) 4961	REMOVAL OF MAILBOX INSTALLATION	65.000	EA
629(E) 5048	REMOVE AND RESET MAILBOX	12.000	EA
640 1426	FIELD OFFICE	1.000	EA
641 1552	MOBILIZATION	1.000	LSUM
SECTION NO. 0002	ROWA-ROADWAY RABA-016(008)RA		
643 0094	(PL)RIGHT-OF-WAY CLEARANCE	1.000	LSUM
SECTION NO. 0003	X028-BRIDGE 'A' RABA-0Q16(001)RA		
202(A) 1301	UNCLASSIFIED EXCAVATION	8,976.000	CY
501(A) 1306	STRUCTURAL EXCAVATION UNCLASSIFIED	160.000	CY
508(A) 6335	REMOVAL OF CULVERT END	1.000	EA
509(B) 1328	CLASS A CONCRETE	339.400	CY

CALL ORDER : 460
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : PAYNE

CONTRACT ID : 030401
 PCN : 1897604C
 PROJECTS : RABA-0Q16(001)RA/RABA-0Q16(008)
 DBE GOALS : 7.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 185.32
 CALENDAR DAYS : 410
 RES. ENG.:
 LIQ. DAM.: \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003 X028-BRIDGE 'A' RABA-0Q16(001)RA			
511 (A) 1332	REINFORCING STEEL	71,910.000	LB
601 (A-1) 1353	TYPE I-A PLAIN RIPRAP	404.000	TON
601 (A-2) 1355	TYPE I-A FILTER BLANKET	93.000	TON
SECTION NO. 0004 Y000-TRAFFIC OPERATIONS RABA-0Q16(001)RA			
627 (G) 4316	RELOC.PORT.TYPE PRECAST CONC.MEDIAN BARR	1,000.000	LF
627 (H) 5856	DEL.PORT.TYPE PREC. CONCRETE MEDIAN BARR	800.000	LF
856 (A) 8839	CONSTRUCTION TRAFF.STR.(PAINT)(4" WIDE)	282,895.000	LF
856 (C) 8851	REMOVABLE PAVEMENT MARKING TAPE(4" WIDE)	194,180.000	LF
856 (G) 8890	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-2	25,000.000	EA
859 (A) 8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	5,000.000	LF
870 (A) 8485	SAND FILLED IMPACT ATTEN.MODULE	29,400.000	SD
880 (B) 8818	CONSTRUCTION SIGNS 0 TO 6.25 SF	1,580.000	SD
880 (B) 8821	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	10,578.000	SD
880 (B) 8824	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	6,600.000	SD
880 (C) 8842	BARRICADES(TYPE III)	3,770.000	SD
880 (C) 8848	WING BARRICADES	3,770.000	SD
880 (D) 8854	VERTICAL PANELS	222,990.000	SD
880 (E) 8860	WARNING LIGHTS(TYPE A)	8,170.000	SD
880 (E) 8872	WARNING LIGHTS(TYPE C)	279,010.000	SD
880 (F) 8878	DRUMS	56,020.000	SD
SECTION NO. 0005 Y002-TRAFFIC SIGNING RABA-0Q16(001)RA			
850 (A) 8110	SHEET ALUMINUM SIGNS	540.500	SF
851 (C) 8327	2 1/4" SQUARE TUBE POST	1,171.200	LF
855 (A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	212,309.000	LF
855 (B) 8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	283.000	EA
855 (B) 8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	23.000	EA
SECTION NO. 0006 Y002-TRAFFIC SIGNALS RABA-0Q16(001)RA			
802 (B) 8332	1" PVC SCH.40 PLASTIC CONDUIT BORED	195.000	LF
802 (B) 8336	1 1/2" PVC SCH.40 PLASTIC CONDUIT BORED	60.000	LF
802 (B) 8338	1 1/2" PVC SCH.40 PLASTIC CONDUIT TRENCH	890.000	LF
802 (B) 8342	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	30.000	LF
802 (B) 8344	3" PVC SCH.40 PLASTIC CONDUIT BORED	290.000	LF
802 (B) 8346	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	35.000	LF
803 8065	PULL BOX(SIZE I)	3.000	EA
803 8066	PULL BOX(SIZE II)	1.000	EA
803 8067	PULL BOX(SIZE III)	7.000	EA
804 (A) 2915	STRUCTURAL CONCRETE	6.400	CY

CALL ORDER : 460
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : PAYNE

CONTRACT ID : 030401
 PCN : 1897604C
 PROJECTS : RABA-0Q16(001)RA/RABA-0Q16(008)
 DBE GOALS : 7.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 185.32
 CALENDAR DAYS : 410
 RES. ENG. :
 LIQ. DAM. : \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0006	Y002-TRAFFIC SIGNALS RABA-0Q16(001)RA		
804 (B) 2916	REINFORCING STEEL	974.400	LB
806 (A) 8313	32'MH POLE 45'TS & 10'LMA(G.STL.)	1.000	EA
806 (A) 8355	(PL)32'MH POLE,TWIN TS & 10'LMA(G.STL.)	1.000	EA
809 (A) 8090	(PL)ROADWAY LUMINAIRE	2.000	EA
810 (A) 3118	SERVICE POLE	1.000	EA
811 8040	1/C NO.6 ELECT.COND.	200.000	LF
811 8044	1/C NO.10 ELECT.COND.	860.000	LF
825 8550	VEH.ACT.SOL.ST.TRAF.SIG.CON.ASM	1.000	EA
828 (A) 8135	SOL.STE.DIGITAL IND.VEH.LP.DET.	7.000	EA
828 (B) 8138	LOOP DETECTOR WIRE	3,610.000	LF
831 8231	1WAY3SEC.ADJ.SIG.HD.S-6	4.000	EA
831 8252	1WAY3SEC.ADJ.SIG.HD.S-9	3.000	EA
831 8262	1WAY3SEC.ADJ.SIG.HD.S-10	1.000	EA
833 3030	BACKPLATE	8.000	EA
834 (A) 8207	5/C TRAF.SIG.EL.CABLE	735.000	LF
834 (A) 8211	15/C TRAF.SIG.EL.CABLE	45.000	LF
834 (B) 8220	2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	2,210.000	LF
850 (C) 8118	MAST ARM MOUNTED SIGNS (ALUM.)	39.000	SF
890 (A) 8726	(PL)REMOVAL OF TRAFFIC SIGNAL EQUIPMENT	1.000	LSUM
SECTION NO. 0007	STAK-STAKING RABA-0Q16(001)RA		
642 0098	STAKING	1.000	LSUM

CALL ORDER : 490
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : PITTSBURG

CONTRACT ID : 030399
 PCN : 1998104
 PROJECTS : BRO-161D(108) CO
 DBE GOALS : 6.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 8.67
 CALENDAR DAYS : 120
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:
 BRIDGE AND APPROACHES COUNTY ROAD: OVER ANDERSON CREEK
 APPROX. 5.0 MILES EAST OF SAVANNA. PROJECT LENGTH = 0.229
 MILES ASPHALT GRADE = PG 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 F000 - ROADWAY			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202 (G)	0185 EARTHWORK	1.000	LSUM
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
222	2801 TEMPORARY BALE BARRIER	1,000.000	LF
223	2801 TEMPORARY SILT FENCE	2,000.000	LF
230 (A)	2806 SOLID SLAB SODDING	5,590.000	SY
233 (A)	2817 VEGETATIVE MULCHING	2.000	AC
303	0192 AGGREGATE BASE	1,463.000	CY
403 (E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	50.000	TON
407	0250 TACK COAT	175.000	GAL
408	5774 PRIME COAT	1,334.000	GAL
411 (S3)	5945 (SP) ASPH.CONC., TYPE S3 (PG 64-22 OK)	489.000	TON
411 (S4)	5960 (SP) ASPH.CONC., TYPE S4 (PG 64-22 OK)	321.000	TON
509 (B)	0321 CLASS A CONCRETE	44.000	CY
509 (D)	0325 CLASS C CONCRETE	50.000	CY
511 (A)	0332 REINFORCING STEEL	6,440.000	LB
613 (P)	1091 6" PERFORATED PIPE UNDERDRAIN ROUND	500.000	LF
613 (Q)	1096 6" NON-PERF.PIPE UNDERDRAIN RND.	500.000	LF
855 (A)	8812 TRAFFIC STRIPE (PLASTIC) (4" WIDE)	2,425.000	LF
SECTION NO. 0002 X081 - BRIDGE			
501 (B)	1307 SUBSTRUCTURE EXCAVATION COMMON	60.000	CY
501 (D)	6353 UNCLASSIFIED BACKFILL	40.000	CY
503 (B)	6144 PRESTRESSED CONCRETE DOUBLE TEE	550.000	LF
504 (E)	1380 CONCRETE RAIL (TR1)	265.000	LF
509 (A)	1326 CLASS AA CONCRETE	74.000	CY
509 (B)	1328 CLASS A CONCRETE	43.000	CY
511 (A)	1332 REINFORCING STEEL	18,728.000	LB
514 (A)	6010 PILES, FURNISHED (HP 10X42)	425.000	LF
514 (B)	6292 PILES, DRIVEN (HP 10X42)	425.000	LF
516 (A)	6092 DRILLED SHAFTS 36" DIAMETER	84.000	LF
601 (A-1)	1353 TYPE I-A PLAIN RIPRAP	1,240.000	TON
601 (A-2)	1355 TYPE I-A FILTER BLANKET	350.000	TON
619 (D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623 (F)	6033 GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
641	1399 MOBILIZATION	1.000	LSUM
880 (J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAK - STAKING			
642	0098 STAKING	1.000	LSUM

CALL ORDER : 510
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : POTTAWATOMIE

CONTRACT ID : 030391
 PCN : 1858604
 PROJECTS : BRO-163D(66) CO
 DBE GOALS : 8.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 5.42
 CALENDAR DAYS : 150
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:
 BRIDGE AND APPROACHES COUNTY ROAD: CO. BR. OVER ROCK CREEK
 TRIB 1.3 MI. NORTH AND 1.0 MI. EAST OF JCT. I-40 / US 177.
 PROJECT LENGTH = 0.227 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 E000 - ROADWAY			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202 (G)	0185 EARTHWORK	1.000	LSUM
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
222	2801 TEMPORARY BALE BARRIER	240.000	LF
223	2801 TEMPORARY SILT FENCE	2,400.000	LF
230 (A)	2806 SOLID SLAB SODDING	11,593.000	SY
233 (A)	2817 VEGETATIVE MULCHING	2.300	AC
403 (E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	671.000	TON
509 (B)	0321 CLASS A CONCRETE	128.000	CY
509 (D)	0325 CLASS C CONCRETE	250.000	CY
511 (A)	0332 REINFORCING STEEL	18,150.000	LB
601 (A-1)	1353 TYPE I-A PLAIN RIPRAP	150.000	TON
601 (A-2)	1355 TYPE I-A FILTER BLANKET	50.000	TON
613 (CC)	7187 TYPE B4 CULVERT END TREATMENT	2.000	EA
613 (D)	4528 28" X 20" CORR. GALV. STEEL PIPE ARCH	58.000	LF
619 (D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
880 (J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0002 STAK - STAKING			
642	0098 STAKING	1.000	LSUM

CALL ORDER : 530
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : ROGERS

CONTRACT ID : 030434
 PCN : 2080304
 PROJECTS : STPY-166C(127)
 DBE GOALS : 6.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 39.00
 CALENDAR DAYS : 120
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:
 INTERSECTION MODIFICATION & TRAFFIC SIGNALS SH-167/SH-266:
 INTERSECTION AT PORT OF CATOOSA. PROJECT LENGTH = 0.633
 MILES FLEXIBLE ESALS = 9.8 MILLION ASPHALT GRADE = PG 64-22
 OK, PG 76-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 L000-ROADWAY			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202 (G)	0185 EARTHWORK	1.000	LSUM
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
222	2801 TEMPORARY BALE BARRIER	200.000	LF
223	2801 TEMPORARY SILT FENCE	4,500.000	LF
230 (A)	2806 SOLID SLAB SODDING	17,500.000	SY
326 (A)	4200 (SP) FLY ASH	64.000	TON
326 (B)	4210 (SP) LIME	88.000	TON
326 (E)	4240 (SP) CEMENTITIOUS STABILIZED SUBGRADE	1,175.000	SY
326 (F)	4250 (SP) LIME STABILIZED SUBGRADE	4,830.000	SY
326 (G)	4260 (SP) LIME PRETREATMENT	1,175.000	SY
403 (E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	488.000	TON
407	0250 TACK COAT	775.000	GAL
408	5774 PRIME COAT	1,210.000	GAL
411 (S3)	5945 (SP) ASPH.CONC., TYPE S3 (PG 64-22 OK)	1,080.000	TON
411 (S4)	5950 (SP) ASPH.CONC., TYPE S4 (PG 76-28 OK)	2,980.000	TON
414 (A1)	5754 9" P.C. DOWEL JOINTED CONCRETE PAVEMENT	4,466.000	SY
414 (B)	5072 9" H.E.S. CONCRETE (PATCHING)	100.000	SY
417	5267 COLD MILLING PAVEMENT	4,000.000	SY
419	4152 CONCRETE JOINT REHABILITATION	7,150.000	LF
420 (A)	4242 FABRIC REINFORCEMENT	7,950.000	SY
509 (D)	0325 CLASS C CONCRETE	15.000	CY
609 (A)	0288 CONC.CURB (6" MNTBLE-INTEGRAL)	1,351.000	LF
609 (B)	1513 1'-8" COMB.CRB.& GUT.(6" BARRIER)	225.000	LF
609 (B)	1525 2'-8" COMB.CRB.& GUT.(6" BARRIER)	3,810.000	LF
610 (B)	5016 8" CONCRETE DRIVEWAY	662.500	SY
613 (B)	0491 18" R.C.PIPE CLASS III	68.000	LF
613 (M)	5726 18" PREFAB. CULVERT END SEC., ROUND	2.000	EA
619 (A)	0920 REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619 (B)	4727 REMOVAL OF CONCRETE PAVEMENT	250.000	SY
619 (B)	4728 REMOVAL OF ASPHALT PAVEMENT	5,500.000	SY
619 (B)	4763 REMOVAL OF CONC.PAV.W/ASPH.OVERLAY	100.000	SY
619 (B)	4766 REMOVAL OF CONCRETE DRIVEWAY	315.000	SY
619 (B)	4791 REMOVAL OF CURB	1,290.000	LF
619 (B)	4792 REMOVAL OF SIDEWALK	1,190.000	SY
619 (C)	0924 SAWING PAVEMENT	1,128.000	LF

CALL ORDER : 530
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : ROGERS

CONTRACT ID : 030434
 PCN : 2080304
 PROJECTS : STPY-166C(127)
 DBE GOALS : 6.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 39.00
 CALENDAR DAYS : 120
 RES. ENG.:
 LIQ. DAM.: \$ 500

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 L000-ROADWAY			
641	1552 MOBILIZATION	1.000	LSUM
SECTION NO. 0002 Y031-TRAFFIC SIGNAL			
802(B)	8334 1" PVC SCH.40 PLASTIC CONDUIT TRENCHED	70.000	LF
802(B)	8336 1 1/2" PVC SCH.40 PLASTIC CONDUIT BORED	100.000	LF
802(B)	8338 1 1/2" PVC SCH.40 PLASTIC CONDUIT TRENCH	1,200.000	LF
802(B)	8342 2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	30.000	LF
802(B)	8344 3" PVC SCH.40 PLASTIC CONDUIT BORED	470.000	LF
802(B)	8346 3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	30.000	LF
803	8065 PULL BOX(SIZE I)	3.000	EA
803	8066 PULL BOX(SIZE II)	1.000	EA
803	8067 PULL BOX(SIZE III)	7.000	EA
804(A)	2915 STRUCTURAL CONCRETE	20.500	CY
804(B)	2916 REINFORCING STEEL	1,492.000	LB
806(A)	8355 (PL)32'MH POLE,TWIN TS & 10'LMA(G.STL.)	2.000	EA
809(A)	8090 (PL)ROADWAY LUMINAIRE	3.000	EA
810(A)	3118 SERVICE POLE	1.000	EA
811	8044 1/C NO.10 ELECT.COND.	800.000	LF
825	8550 VEH.ACT.SOL.ST.TRAF.SIG.CON.ASM	1.000	EA
828(A)	8135 SOL.STE.DIGITAL IND.VEH.LP.DET.	12.000	EA
828(B)	8138 LOOP DETECTOR WIRE	3,540.000	LF
831	8231 1WAY3SEC.ADJ.SIG.HD.S-6	5.000	EA
831	8286 1WAY5SEC.ADJ.SIG.HD.S-19	8.000	EA
833	3038 5" BACKPLATE(12" HDS)(B-2)	13.000	EA
834(A)	8207 5/C TRAF.SIG.EL.CABLE	350.000	LF
834(A)	8208 7/C TRAF.SIG.EL.CABLE	640.000	LF
834(A)	8213 21/C TRAF.SIG.EL.CABLE	450.000	LF
834(B)	8220 2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	3,400.000	LF
850(C)	8118 MAST ARM MOUNTED SIGNS(ALUM.)	84.000	SF
SECTION NO. 0003 Y000-TRAFFIC SIGNING & STRIPING			
623(M)	6500 (PL)STATIONARY BOLLARD	4.000	EA
850(A)	8110 SHEET ALUMINUM SIGNS	140.480	SF
851(C)	8327 2 1/4" SQUARE TUBE POST	198.000	LF
855(A)	8812 TRAFFIC STRIPE(PLASTIC)(4" WIDE)	13,626.000	LF
855(B)	8818 TRAFFIC STRIPE(PLASTIC)(ARROWS)	17.000	EA
855(B)	8821 TRAFFIC STRIPE(PLASTIC)(WORDS)	8.000	EA
880(J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
882(B)	8306 PORT.CHANGEABLE MESSAGE SIGN	360.000	SD
890(A)	8722 (PL)REMOVAL OF EXISTING SIGNS	1.000	LSUM
SECTION NO. 0004 STAK-STAKING			
642	0098 STAKING	1.000	LSUM

CALL ORDER : 530
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : ROGERS

CONTRACT ID : 030434
 PCN : 2080304
 PROJECTS : STPY-166C(127)
 DBE GOALS : 6.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 39.00
 CALENDAR DAYS : 120
 RES. ENG.:
 LIQ. DAM.: \$ 500

SECTION NO. 0005 J000-ROADWAY - NONPARTICIPATING

201	0102	CLEARING AND GRUBBING	1.000	LSUM
202 (G)	0185	EARTHWORK	1.000	LSUM
230 (A)	2806	SOLID SLAB SODDING	1,200.000	SY
326 (B)	4210	(SP)LIME	60.000	TON
326 (F)	4250	(SP)LIME STABILIZED SUBGRADE	2,400.000	SY
414 (A1)	5754	9" P.C. DOWEL JOINTED CONCRETE PAVEMENT	2,300.000	SY
609 (A)	0300	CONC.CURB (6" BARRIER-INTEGRAL)	1,400.000	LF
611 (A)	2657	MANHOLE (4' DIA.)	2.000	EA
611 (E)	5102	INLET CICI DES. 1 (B)	2.000	EA
611 (G)	4488	INLET FRM&GRT (SSIF-FRM,CIG-GRT-VG-F)	2.000	EA
611 (K)	4488	CAST IRON CURB INLETS	6.000	EA
612 (T)	0706	REMOVE & RESET MANHOLE FRAME & COVER	2.000	EA
613 (B)	0491	18" R.C.PIPE CLASS III	298.000	LF
616 (I)	1100	(PL)REPAIR EXISTING IRRIGATION SYSTEM	1.000	LSUM
619 (A)	0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619 (B)	4727	REMOVAL OF CONCRETE PAVEMENT	1,775.000	SY
619 (B)	4791	REMOVAL OF CURB	1,325.000	LF
619 (C)	0924	SAWING PAVEMENT	350.000	LF
890A/B	8744	(PL)REMOVE & RESET LIGHT POLE	1.000	EA

CALL ORDER : 550
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : STEPHENS

CONTRACT ID : 030392
 PCN : 1960104
 PROJECTS : BRO-169D(77)CO
 DBE GOALS : 11.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 8.67
 CALENDAR DAYS : 100
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:
 BRIDGE AND APPROACHES COUNTY ROAD; OVER EAST COW CREEK, 2.1
 MILES NORTH AND 2.8 MILES EAST OF THE SH-7/US-81 JCT. IN
 DUNCAN. PROJECT LENGTH = 0.239 MILE FLEXIBLE ESALS = 0.2
 MILLION ASPHALT GRADE = PG 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 I000-ROADWAY			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(G)	0185 EARTHWORK	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	1,500.000	LF
227	0100 TEMPORARY SILT DIKE	200.000	LF
230(A)	2806 SOLID SLAB SODDING	18,000.000	SY
233(A)	2817 VEGETATIVE MULCHING	7.000	AC
311(B)	0152 PROCESS EXISTING BASE & SURFACE, METHOD B	11.700	STA
411(S3)	5945 (SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	705.000	TON
411(S4)	5960 (SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	333.000	TON
509(D)	0325 CLASS C CONCRETE	10.000	CY
854(A)	8800 TRAFFIC STRIPE(PAINT)(4" WIDE)	1,606.000	LF
SECTION NO. 0002 X081-BRIDGE 'A'			
501(B)	1307 SUBSTRUCTURE EXCAVATION COMMON	84.000	CY
501(D)	6353 UNCLASSIFIED BACKFILL	82.000	CY
503(A)	1313 PRESTRESSED CONCRETE BEAMS (TYPE IV)	376.670	LF
504(E)	1380 CONCRETE RAIL (TR1)	255.000	LF
506(A)	1322 STRUCTURAL STEEL	1,810.000	LB
509(A)	1326 CLASS AA CONCRETE	73.400	CY
509(B)	1328 CLASS A CONCRETE	53.800	CY
511(A)	1332 REINFORCING STEEL	23,825.000	LB
514(A)	6010 PILES, FURNISHED (HP 10X42)	700.000	LF
514(B)	6292 PILES, DRIVEN (HP 10X42)	700.000	LF
601(A-1)	1353 TYPE I-A PLAIN RIPRAP	1,437.000	TON
601(A-2)	1355 TYPE I-A FILTER BLANKET	335.000	TON
619(D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F)	6033 GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
641	1399 MOBILIZATION	1.000	LSUM
880(J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAK-STAKING			
642	0098 STAKING	1.000	LSUM

CALL ORDER : 570
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : TILLMAN

CONTRACT ID : 030393
 PCN : 1916404
 PROJECTS : BRO-171D(59) CO
 DBE GOALS : 9.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 4.34
 CALENDAR DAYS : 90
 RES. ENG. :
 LIQ. DAM. : \$ 500

CONTRACT DESCRIPTION:
 BRIDGE AND APPROACHES COUNTY ROAD; OVER LITTLE DEEP RED
 CREEK, 0.5 MILE NORTH AND 2.6 MILES EAST OF HOLLISTER.
 PROJECT LENGTH = 0.170 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 E000 - ROADWAY BRO-171D(59)C0			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202 (G)	0185 EARTHWORK	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	1,680.000	LF
227	0100 TEMPORARY SILT DIKE	150.000	LF
230 (A)	2806 SOLID SLAB SODDING	6,665.000	SY
233 (A)	2817 VEGETATIVE MULCHING	1.370	AC
403 (E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	447.000	TON
509 (D)	0325 CLASS C CONCRETE	34.300	CY
613 (CC)	7187 TYPE B4 CULVERT END TREATMENT	2.000	EA
613 (D)	0690 24" CORR. GALV. STEEL PIPE	52.000	LF
SECTION NO. 0002 X028 - BRIDGE 'A' BRO-171D(59)CO			
202 (A)	1301 UNCLASSIFIED EXCAVATION	2,135.000	CY
501 (A)	1306 STRUCTURAL EXCAVATION UNCLASSIFIED	182.000	CY
509 (B)	1328 CLASS A CONCRETE	259.900	CY
511 (A)	1332 REINFORCING STEEL	46,330.000	LB
619 (D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
641	1399 MOBILIZATION	1.000	LSUM
880 (J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAK-STAKING BRO-171D(59)CO			
642	0098 STAKING	1.000	LSUM

CALL ORDER : 580
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : TILLMAN

CONTRACT ID : 030394
 PCN : 1964104
 PROJECTS : BRF-171C(64) CO
 DBE GOALS : 7.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 11.92
 CALENDAR DAYS : 130
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:
 BRIDGE AND APPROACHES COUNTY ROAD; OVER SUTTLE CREEK, 4.0
 MILES SOUTH AND 1.4 MILES WEST OF FREDERICK. PROJECT LENGTH
 = 0.141 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 E000 - ROADWAY BRF-171C(64)CO			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202 (A)	0183 UNCLASSIFIED EXCAVATION	158.000	CY
202 (C)	0184 UNCLASSIFIED BORROW	1,082.000	CY
222	2801 TEMPORARY BALE BARRIER	1,235.000	LF
223	2801 TEMPORARY SILT FENCE	1,235.000	LF
230 (A)	2806 SOLID SLAB SODDING	5,430.000	SY
233 (A)	2817 VEGETATIVE MULCHING	1.200	AC
403 (E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	345.000	TON
509 (D)	0325 CLASS C CONCRETE	10.000	CY
850 (A)	8110 SHEET ALUMINUM SIGNS	24.000	SF
851 (A)	3206 4"@13 GALV.STL.WD.FLANGE BM.POST	30.000	LF
SECTION NO. 0002 X081 - BRIDGE BRF-171C(64)CO			
501 (B)	1307 SUBSTRUCTURE EXCAVATION COMMON	80.000	CY
501 (D)	6353 UNCLASSIFIED BACKFILL	50.000	CY
503 (A)	1311 PRESTRESSED CONCRETE BEAMS (TYPE II)	510.000	LF
504 (C)	6250 SEALED EXPANSION JOINT	58.830	LF
504 (E)	1380 CONCRETE RAIL (TR1)	317.000	LF
506 (A)	1322 STRUCTURAL STEEL	3,830.000	LB
509 (A)	1326 CLASS AA CONCRETE	98.200	CY
509 (B)	1328 CLASS A CONCRETE	77.200	CY
511 (A)	1332 REINFORCING STEEL	32,645.000	LB
514 (A)	6010 PILES, FURNISHED (HP 10X42)	464.000	LF
514 (B)	6292 PILES, DRIVEN (HP 10X42)	464.000	LF
516 (A)	6093 DRILLED SHAFTS 42" DIAMETER	123.000	LF
601 (A-1)	1353 TYPE I-A PLAIN RIPRAP	1,200.000	TON
601 (A-2)	1355 TYPE I-A FILTER BLANKET	310.000	TON
619 (D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623 (F)	6033 GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
641	1399 MOBILIZATION	1.000	LSUM
880 (J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAK-STAKING BRF-171C(64)CO			
642	0098 STAKING	1.000	LSUM

CALL ORDER : 590
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : TILLMAN

CONTRACT ID : 030395
 PCN : 1916404C
 PROJECTS : BRO-171D(59)CO/BRF-171C(64)CO
 DBE GOALS : 8.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 16.26
 CALENDAR DAYS : 170
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:
 BRIDGES AND APPROACHES COUNTY ROAD; OVER LITTLE DEEP RED CREEK, 0.5 MILE NORTH AND 2.6 MILES EAST OF HOLLISTER/COUNTY ROAD; OVER SUTTLE CREEK, 4.0 MILES SOUTH AND 1.4 MILES WEST OF FREDERICK. PROJECT LENGTH = 0.311 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 E000 - ROADWAY BRO-171D(59)CO			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202 (G)	0185 EARTHWORK	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	1,680.000	LF
227	0100 TEMPORARY SILT DIKE	150.000	LF
230 (A)	2806 SOLID SLAB SODDING	6,665.000	SY
233 (A)	2817 VEGETATIVE MULCHING	1.370	AC
403 (E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	447.000	TON
509 (D)	0325 CLASS C CONCRETE	34.300	CY
613 (CC)	7187 TYPE B4 CULVERT END TREATMENT	2.000	EA
613 (D)	0690 24" CORR. GALV. STEEL PIPE	52.000	LF
SECTION NO. 0002 E000 - ROADWAY BRF-171C(64)CO			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202 (A)	0183 UNCLASSIFIED EXCAVATION	158.000	CY
202 (C)	0184 UNCLASSIFIED BORROW	1,082.000	CY
222	2801 TEMPORARY BALE BARRIER	1,235.000	LF
223	2801 TEMPORARY SILT FENCE	1,235.000	LF
230 (A)	2806 SOLID SLAB SODDING	5,430.000	SY
233 (A)	2817 VEGETATIVE MULCHING	1.200	AC
403 (E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	345.000	TON
509 (D)	0325 CLASS C CONCRETE	10.000	CY
850 (A)	8110 SHEET ALUMINUM SIGNS	24.000	SF
851 (A)	3206 4"@13 GALV.STL.WD.FLANGE BM.POST	30.000	LF
SECTION NO. 0003 X028 - BRIDGE 'A' BRO-171D(59)CO			
202 (A)	1301 UNCLASSIFIED EXCAVATION	2,135.000	CY
501 (A)	1306 STRUCTURAL EXCAVATION UNCLASSIFIED	182.000	CY
509 (B)	1328 CLASS A CONCRETE	259.900	CY
511 (A)	1332 REINFORCING STEEL	46,330.000	LB
619 (D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
641	1399 MOBILIZATION	1.000	LSUM
880 (J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

CALL ORDER : 590
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : TILLMAN

CONTRACT ID : 030395
 PCN : 1916404C
 PROJECTS : BRO-171D(59)CO/BRF-171C(64)CO
 DBE GOALS : 8.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 16.26
 CALENDAR DAYS : 170
 RES. ENG.:
 LIQ. DAM.: \$ 500

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0004	X081 - BRIDGE 'A' BRF-171C(64)CO		
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	80.000	CY
501(D) 6353	UNCLASSIFIED BACKFILL	50.000	CY
503(A) 1311	PRESTRESSED CONCRETE BEAMS (TYPE II)	510.000	LF
504(C) 6250	SEALED EXPANSION JOINT	58.830	LF
504(E) 1380	CONCRETE RAIL (TR1)	317.000	LF
506(A) 1322	STRUCTURAL STEEL	3,830.000	LB
509(A) 1326	CLASS AA CONCRETE	98.200	CY
509(B) 1328	CLASS A CONCRETE	77.200	CY
511(A) 1332	REINFORCING STEEL	32,645.000	LB
514(A) 6010	PILES, FURNISHED (HP 10X42)	464.000	LF
514(B) 6292	PILES, DRIVEN (HP 10X42)	464.000	LF
516(A) 6093	DRILLED SHAFTS 42" DIAMETER	123.000	LF
601(A-1) 1353	TYPE I-A PLAIN RIPRAP	1,200.000	TON
601(A-2) 1355	TYPE I-A FILTER BLANKET	310.000	TON
619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F) 6033	GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
641 1399	MOBILIZATION	1.000	LSUM
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0005	STAK-STAKING BRO-171D(59)CO		
642 0098	STAKING	1.000	LSUM
SECTION NO. 0006	STAK-STAKING BRF-171C(64)CO		
642 0098	STAKING	1.000	LSUM

CALL ORDER : 610
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : TULSA

CONTRACT ID : 030409
 PCN : 1103113
 PROJECTS : NHY-30N(42)
 DBE GOALS : 2.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 55.27
 CALENDAR DAYS : 150
 RES. ENG.:
 LIQ. DAM.: \$ 800

CONTRACT DESCRIPTION:
 SOUND BARRIER WALL US-169; FROM I-44 TO I-244 IN TULSA.
 PROJECT LENGTH = 1.4399 KM.

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 Y220-ROADWAY			
201	M0102 CLEARING AND GRUBBING	1.000	LSUM
202 (A)	M0183 UNCLASSIFIED EXCAVATION	783.000	M3
202 (C)	M0184 UNCLASSIFIED BORROW	625.000	M3
205	M4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
223	M2802 TEMPORARY SILT FENCE	2,880.000	M
226	M2805 TEMPORARY SEDIMENT REMOVAL	30.000	M3
227	M0100 TEMPORARY SILT DIKE	90.000	M
230 (A)	M2806 SOLID SLAB SODDING	21,390.000	M2
233 (A)	M2817 VEGETATIVE MULCHING	2.100	HA
235 (C)	M0102 (PL)ROCK FILTER DAM, TYPE 3	16.000	M3
241	M2832 MOWING	2.100	HA
243	M0450 (PL)TEMPORARY INLET SEDIMENT FILTER	7.000	EA
501 (A)	M0313 STRUCTURAL EXCAVATION UNCLASSIFIED	18.000	M3
509 (B)	M0321 CLASS A CONCRETE	50.000	M3
510 (B)	M6334 SOUND BARRIER WALL	8,211.500	M2
511 (A)	M0332 REINFORCING STEEL	5,020.000	KG
516 (A)	M6091 DRILLED SHAFTS 750MM DIAMETER	1,732.100	M
611 (E)	M6002 INLET (SMD-TYPE 2)	1.000	EA
613 (B)	M0405 450MM R.C.PIPE CLASS III	4.400	M
619 (A)	M0920 REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
640	M1426 FIELD OFFICE	1.000	EA
641	M1552 MOBILIZATION	1.000	LSUM
880 (J)	M8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0002 STAK-STAKING			
642	M0098 STAKING	1.000	LSUM

CALL ORDER : 620
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : TULSA

CONTRACT ID : 030396
 PCN : 1293808
 PROJECTS : NHY-14N(37)
 DBE GOALS : 10.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 46.60
 CALENDAR DAYS : 180
 RES. ENG.:
 LIQ. DAM.: \$ 1000

CONTRACT DESCRIPTION:
 GRADING, DRAINAGE, SURFACING US-75: US-75 & 81ST STREET
 INTERCHANGE IN THE CITY OF TULSA. PROJECT LENGTH = 0.75 KM
 FLEXIBLE ESALS = < 3M ASPHALT GRADE = PG 64 - 22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 I000 - ROADWAY			
201	M0102	CLEARING AND GRUBBING	1.000 LSUM
202 (A)	M0183	UNCLASSIFIED EXCAVATION	73,472.000 M3
202 (C)	M0184	UNCLASSIFIED BORROW	500.000 M3
205	M4229	TYPE A-SALVAGED TOPSOIL	1.000 LSUM
223	M2802	TEMPORARY SILT FENCE	1,000.000 M
225	M2804	TEMPORARY SEDIMENT BASIN	1.000 EA
226	M2805	TEMPORARY SEDIMENT REMOVAL	100.000 M3
227	M0100	TEMPORARY SILT DIKE	250.000 M
229	M4318	DITCH LINER PROTECTION	357.000 M
230 (A)	M2806	SOLID SLAB SODDING	78,862.000 M2
232 (B)	M2814	SEEDING METHOD B	7.890 HA
233 (A)	M2817	VEGETATIVE MULCHING	15.770 HA
235 (A)	M0100	(PL)ROCK FILTER DAM, TYPE 1	8.000 M3
238	M0300	(PL)TEMPORARY SEDIMENT TRAP	2.000 EA
326 (A)	M4200	(SP)FLY ASH	839.720 T
326 (E)	M4240	(SP)CEMENTITIOUS STABILIZED SUBGRADE	14,578.460 M2
403 (E)	M0225	TRAFFIC BOUND SURFACE COURSE TYPE E	200.000 T
408	M5774	PRIME COAT	14,291.000 L
411 (S2)	M5930	(SP)ASPH.CONC.,TYPE S2 (PG 64-22 OK)	743.610 T
411 (S3)	M5940	(SP)ASPH.CONC.,TYPE S3 (PG 70-28 OK)	273.090 T
411 (S3)	M5945	(SP)ASPH.CONC.,TYPE S3 (PG 64-22 OK)	375.260 T
411 (S4)	M5955	(SP)ASPH.CONC.,TYPE S4 (PG 70-28 OK)	172.870 T
411 (S4)	M5960	(SP)ASPH.CONC.,TYPE S4 (PG 64-22 OK)	1,904.240 T
414 (A)	M0360	215MM P.C. CONCRETE PAVEMENT	3,503.670 M2
414 (A1)	M5752	175MM P.C. DOWEL JOINTED CONCRETE PAVE.	1,309.150 M2
414 (A1)	M6853	215MM P.C. DOWEL JOINTED CONC. PAVEMENT	6,698.850 M2
414 (B)	M5913	H.E.S. CONCRETE (FULL DEPTH PATCHING)	100.000 M2
509 (D)	M0325	CLASS C CONCRETE	199.000 M3
601 (A)	M0297	TYPE I PLAIN RIPRAP	18.000 T
611 (A)	M2657	MANHOLE (1200MM DIA.)	1.000 EA
611 (A)	M2658	MANHOLE (1500MM DIA.)	1.000 EA
611 (B)	M2680	ADD'L.DEPTH IN MANHOLE (1200MM DIA.)	0.230 VM
611 (B)	M2681	ADD'L.DEPTH IN MANHOLE (1500MM DIA.)	1.030 VM
611 (D)	4215	MANHOLE FRAME & COVER	2.000 EA
613 (B)	M0409	600MM R.C.PIPE CLASS III	18.900 M
613 (B)	M0413	750MM R.C.PIPE CLASS III	131.680 M
613 (B)	M0415	900MM R.C.PIPE CLASS III	18.290 M

CALL ORDER : 620
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : TULSA

CONTRACT ID : 030396
 PCN : 1293808
 PROJECTS : NHY-14N(37)
 DBE GOALS : 10.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 46.60
 CALENDAR DAYS : 180
 RES. ENG.:
 LIQ. DAM.: \$ 1000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000 - ROADWAY		
613 (B) M0417	1050MM R.C.PIPE CLASS III	35.360	M
613 (B) M0419	1200MM R.C.PIPE CLASS III	7.320	M
613 (B) M4427	1485MM X 915MM R.C.PIPE ARCH CLASS A-III	7.920	M
613 (CC)M7186	TYPE A4 CULVERT END TREATMENT	1.000	EA
613 (CC)M7196	TYPE A6 CULVERT END TREATMENT	1.000	EA
613 (D) M0689	450MM CORR. GALV. STEEL PIPE	14.910	M
613 (M) M0899	750MM PREFAB. CULVERT END SEC., ROUND	2.000	EA
613 (M) M0900	900MM PREFAB. CULVERT END SEC., ROUND	2.000	EA
613 (M) M0980	1050MM PREFAB. CULVERT END SEC., ROUND	1.000	EA
613 (M) M0981	1200MM PREFAB. CULVERT END SEC., ROUND	2.000	EA
613 (M) M4548	1485MM X 915MM PREFAB.CULV.END SEC.,ARCH	2.000	EA
613 (MM)M7521	TYPE B6 SLOPED CONCRETE END SECTION	2.000	EA
613 (P) M1091	150MM PERFORATED PIPE UNDERDRAIN ROUND	100.000	M
613 (Q) M1096	150MM NON-PERF.PIPE UNDERDRAIN RND.	30.000	M
619 (A) M0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
624 (C) M4459	(SP)FENCE-STYLE SWF (5 BARBED WIRE)	503.000	M
624 (D) M4293	FENCE-STYLE CLF (1800MM HIGH, CLASS B)	1,625.000	M
624 (E) M5960	GATES-STYLE CLF(1800MM HI X 3600MM LONG)	1.000	EA
627 (I) M4317	CONCRETE MEDIAN BARRIER, DESIGN 1	55.100	M
640 M1426	FIELD OFFICE	1.000	EA
641 M1552	MOBILIZATION	1.000	LSUM
643 M0087	(SP)CONTRACTORS QUALITY CONTROL	1.000	LSUM
871 M8701	(PL)QUADGUARD IMPACT ATTENUATOR	2.000	EA
SECTION NO. 0002	Y008 - TRAFFIC		
627 (H) M5856	DEL.PORT.TYPE PREC. CONCRETE MEDIAN BARR	1,710.000	M
802 (B) M8344	75MM PVC SCH.40 P.C.BORED	126.000	M
803 M8065	PULL BOX(SIZE I)	8.000	EA
804 (A) M2915	STRUCTURAL CONCRETE	8.040	M3
804 (B) M2916	REINFORCING STEEL	460.440	KG
850 (A) M8110	SHEET ALUMINUM SIGNS	14.740	M2
850 (B) M8112	EXTRUDED ALUMINUM PANEL SIGNS	3.070	M2
850 (B) M8114	EXTR.ALUM.PAN.SGN.(OVRHD SIGNS)	5.740	M2
851 (A) M3206	100MM@19.3 GALV.STL.WD.FLANGE BM.POST	7.920	M
851 (B) M3218	75MM@11.28 GALV.STL.PIPE POST	15.840	M
851 (C) M8324	50MM SQUARE TUBE POST	8.220	M
851 (C) M8327	57MM SQUARE TUBE POST	33.980	M
852 M8604	(PL)OVHD.SN.STR.WLKWAY&HANDRAIL-EXTERNAL	22.000	M
852A/B M9015	OVHD.SN.STR.TYPE E-1 ALUM./G.STL.	1.000	EA
853 M9024	DELINEATORS(TYPE 1, CODE 1)	60.000	EA
853 M9027	DELINEATORS(TYPE 1, CODE 2)	20.000	EA
855 (A) M8812	TRAFFIC STRIPE(PLASTIC)(100MM WIDE)	4,982.000	M

CALL ORDER : 620
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : TULSA

CONTRACT ID : 030396
 PCN : 1293808
 PROJECTS : NHY-14N(37)
 DBE GOALS : 10.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 46.60
 CALENDAR DAYS : 180
 RES. ENG. :
 LIQ. DAM. : \$ 1000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0002 Y008 - TRAFFIC			
855 (B) M8818	TRAFFIC STRIPE (PLASTIC) (ARROWS)	11.000	EA
855 (B) M8821	TRAFFIC STRIPE (PLASTIC) (WORDS)	5.000	EA
857 (A) M8947	PAVE.MARKERS CLASS C TYPE 2-C	54.000	EA
870 (A) M8011	SAND FILLED IMPACT ATTEN.MODULE	19.000	EA
870 (A) M8485	SAND FILLED IMPACT ATTEN.MODULE	600.000	SD
876 (C) M8482	(PL) TRUCK MOUNTED ATTENUATOR	300.000	SD
880 (J) M8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
880 (L) M8911	TRAFFIC SURVEILLANCE, POLICE	50.000	HOURL
882 (B) M8306	PORTABLE CHANGEABLE MESSAGE SIGN	1,200.000	SD
SECTION NO. 0003 STAK - STAKING			
642 M0098	STAKING	1.000	LSUM

CALL ORDER : 621
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : TULSA

CONTRACT ID : 030403
 PCN : 2057604
 PROJECTS : BHIY-244-2 (426) 004
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 37.93
 CALENDAR DAYS : 120
 RES. ENG.:
 LIQ. DAM.: \$ 800

CONTRACT DESCRIPTION:
 BRIDGE REPAIR I-244; BRIDGES AT ARKANSAS RIVER. PROJECT
 LENGTH = 0.00 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001	X081-BRIDGE 'A'		
502	6116 (PL)FALSEWORK JACKING	1.000	LSUM
503 (A)	6123 PRESTRESSED CONCRETE BEAMS	186.920	LF
504 (H)	6390 RAPID CURE JOINT SEALANT	150.000	LF
506 (A)	1322 STRUCTURAL STEEL	380.000	LB
509 (A)	1326 CLASS AA CONCRETE	61.800	CY
509 (B)	1328 CLASS A CONCRETE	507.800	CY
511 (B)	6010 EPOXY COATED REINFORCING STEEL	97,920.000	LB
515 (A)	6013 WATER REPELLENT (VISUALLY INSPECTED)	2,111.000	SY
520 (A)	6058 PREPARATION OF CRACKS ABOVE WATER	1,240.000	LF
520 (C)	6060 EPOXY RESIN ABOVE WATER	193.500	GAL
524	6410 (SP)FIBER-REINFORCED EPOXY COMPOSITE MTL	2,862.000	SF
535	6130 (SP)CORROSION INHIBITOR(SURFACE APPLIED)	1,430.000	SY
535	6282 (PL)ELASTOMERIC BEARING PADS	10.000	EA
540	4515 (PL)REPAIR BRIDGE ITEM (TYPE A)	5.000	EA
540	4525 (PL)REPAIR BRIDGE ITEM (TYPE B)	100.000	EA
619 (B)	2510 (PL)REMOVAL OF BRIDGE ITEM (TYPE A)	1.000	LSUM
619 (B)	2520 (PL)REMOVAL OF BRIDGE ITEM (TYPE B)	1.000	LSUM
641	1399 MOBILIZATION	1.000	LSUM
SECTION NO. 0002	X081-BRIDGE 'B'		
502	6116 (PL)FALSEWORK JACKING	1.000	LSUM
503 (A)	6123 PRESTRESSED CONCRETE BEAMS	133.840	LF
504 (H)	6390 RAPID CURE JOINT SEALANT	150.000	LF
506 (A)	1322 STRUCTURAL STEEL	300.000	LB
509 (A)	1326 CLASS AA CONCRETE	55.100	CY
509 (B)	1328 CLASS A CONCRETE	407.800	CY
511 (B)	6010 EPOXY COATED REINFORCING STEEL	77,470.000	LB
515 (A)	6013 WATER REPELLENT (VISUALLY INSPECTED)	1,741.000	SY
520 (A)	6058 PREPARATION OF CRACKS ABOVE WATER	1,240.000	LF
520 (C)	6060 EPOXY RESIN ABOVE WATER	193.500	GAL
524	6410 (SP)FIBER-REINFORCED EPOXY COMPOSITE MTL	3,224.200	SF
535	6130 (SP)CORROSION INHIBITOR(SURFACE APPLIED)	1,157.000	SY
535	6282 (PL)ELASTOMERIC BEARING PADS	6.000	EA
540	4515 (PL)REPAIR BRIDGE ITEM (TYPE A)	9.000	EA
540	4525 (PL)REPAIR BRIDGE ITEM (TYPE B)	82.000	EA
619 (B)	2510 (PL)REMOVAL OF BRIDGE ITEM (TYPE A)	1.000	LSUM
619 (B)	2520 (PL)REMOVAL OF BRIDGE ITEM (TYPE B)	1.000	LSUM

CALL ORDER : 621
LETTING DATE : October 23, 2003
LETTING TIME : 10:30 A.M.
COUNTIES : TULSA

CONTRACT ID : 030403
PCN : 2057604
PROJECTS : BHIY-244-2(426)004
DBE GOALS : 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE : 37.93
CALENDAR DAYS : 120
RES. ENG. :
LIQ. DAM. : \$ 800

SECTION NO. 0003 Y000-TRAFFIC CONTROL

855(A)	8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	500.000	LF
876(C)	8482	(PL)TRUCK MOUNTED ATTENUATOR	300.000	SD
880(J)	8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
882(B)	8306	PORT.CHANGEABLE MESSAGE SIGN	300.000	SD

CALL ORDER : 650
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : WASHITA

CONTRACT ID : 030397
 PCN : 1997904
 PROJECTS : BRO-175D(42) CO
 DBE GOALS : 11.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 8.67
 CALENDAR DAYS : 100
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:

GRADE, DRAIN & BRIDGE COUNTY ROAD: OVER CORN CREEK, 3.0
 MILES WEST AND 2.6 MILES SOUTH OF CORN. PROJECT LENGTH = 0.
 165 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 E000 - ROADWAY			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202 (G)	0185 EARTHWORK	1.000	LSUM
222	2801 TEMPORARY BALE BARRIER	1,475.000	LF
223	2801 TEMPORARY SILT FENCE	1,475.000	LF
230 (A)	2806 SOLID SLAB SODDING	7,940.000	SY
233 (A)	2817 VEGETATIVE MULCHING	1.640	AC
509 (D)	0325 CLASS C CONCRETE	86.200	CY
613 (CC)	7187 TYPE B4 CULVERT END TREATMENT	4.000	EA
613 (D)	0690 24" CORR. GALV. STEEL PIPE	108.000	LF
SECTION NO. 0002 X081 - BRIDGE			
501 (B)	1307 SUBSTRUCTURE EXCAVATION COMMON	84.000	CY
501 (D)	6353 UNCLASSIFIED BACKFILL	82.000	CY
503 (A)	1313 PRESTRESSED CONCRETE BEAMS (TYPE IV)	396.670	LF
504 (E)	1380 CONCRETE RAIL (TR1)	265.000	LF
506 (A)	1322 STRUCTURAL STEEL	1,810.000	LB
509 (A)	1326 CLASS AA CONCRETE	77.000	CY
509 (B)	1328 CLASS A CONCRETE	53.800	CY
511 (A)	1332 REINFORCING STEEL	24,540.000	LB
514 (A)	6010 PILES, FURNISHED (HP 10X42)	1,001.000	LF
514 (B)	6292 PILES, DRIVEN (HP 10X42)	1,001.000	LF
601 (A-1)	1352 TYPE I-A PLAIN RIPRAP	890.000	CY
601 (A-2)	1355 TYPE I-A FILTER BLANKET	300.000	TON
619 (D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623 (F)	6033 GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
641	1399 MOBILIZATION	1.000	LSUM
880 (J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAK - STAKING			
642	0098 STAKING	1.000	LSUM

CALL ORDER : 651
 LETTING DATE : October 23, 2003
 LETTING TIME : 10:30 A.M.
 COUNTIES : WASHITA

CONTRACT ID : 030404
 PCN : 1648604
 PROJECTS : BRO-175D(003) CO
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 9.75
 CALENDAR DAYS : 100
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:
 BRIDGE AND APPROACHES COUNTY ROAD: AT BOGGY CREEK, 0.6
 MI. SOUTH AND 1.5 MI. WEST OF US-183A JCT. AT BESSIE.
 PROJECT LENGTH = 0.280 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 E000 - ROADWAY			
201 M0102	CLEARING AND GRUBBING	1.000	LSUM
202(G) M0185	EARTHWORK	1.000	LSUM
222 M2801	TEMPORARY BALE BARRIER	80.000	M
223 M2802	TEMPORARY SILT FENCE	560.000	M
230(A) M2806	SOLID SLAB SODDING	1,770.000	M2
233(A) M2817	VEGETATIVE MULCHING	0.453	HA
403(E) M0225	TRAFFIC BOUND SURFACE COURSE TYPE E	626.000	T
509(D) M0325	CLASS C CONCRETE	10.000	M3
613(CC)M7186	TYPE A4 CULVERT END TREATMENT	2.000	EA
613(CC)M7193	TYPE CC4 CULVERT END TREATMENT	2.000	EA
613(D) M0689	450MM CORR. GALV. STEEL PIPE	9.900	M
613(D) M5224	910MM X 660MM CORR. GALV. ST. PIPE ARCH	34.800	M
619(A) M0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
850(A) M8110	SHEET ALUMINUM SIGNS	1.220	M2
SECTION NO. 0002 X081 - BRIDGE			
501(B) M1307	SUBSTRUCTURE EXCAVATION COMMON	135.000	M3
501(D) M6353	UNCLASSIFIED BACKFILL	115.000	M3
503(A) M1313	PRESTRESSED CONCRETE BEAMS (TYPE IV)	126.840	M
504(E) M1380	CONCRETE RAIL (TR1)	91.200	M
506(A) M1322	STRUCTURAL STEEL	760.000	KG
509(A) M1326	CLASS AA CONCRETE	58.500	M3
509(B) M1328	CLASS A CONCRETE	75.600	M3
511(A) M1332	REINFORCING STEEL	13,020.000	KG
514(A) M6011	PILES, FURNISHED (HP 250X62)	328.300	M
514(B) M6292	PILES, DRIVEN (HP 250X62)	328.300	M
601(E) M6312	FILTER FABRIC (RIPRAP)	845.000	M2
601A-1 M1353	TYPE I-A PLAIN RIPRAP	1,120.000	T
601A-2 M1355	TYPE I-A FILTER BLANKET	220.000	T
619(D) M1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F) M6033	GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
641 M1399	MOBILIZATION	1.000	LSUM
880(J) M8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAK - STAKING			
642 M0098	STAKING	1.000	LSUM