

REVISIONS		
REV. NO.	DESCRIPTION	DATE

ENVIRONMENTAL MITIGATION NOTES

404 PERMIT AND DEQ STORM WATER PERMIT REQUIREMENTS OVER WATERS:

IF THE CONTRACTOR ELECTS TO BUILD A WORK ROAD(S) WITHIN THE LIMITS OF THE CHANNEL IN ORDER TO PERFORM WORK, THE CONTRACTOR WILL BE RESPONSIBLE FOR EFFECTIVE EROSION AND SEDIMENT CONTROL IN ACCORDANCE WITH THE CORPS OF ENGINEERS 404 PERMIT WHICH IS INCLUDED IN THE CONTRACT.

IF THE AREA OF DISTURBANCE IS (1) OR MORE ACRES AND IS NOT ALREADY COVERED BY A DEQ PERMIT, THE CONTRACTOR WILL BE REQUIRED TO OBTAIN A DEQ STORM WATER CONSTRUCTION PERMIT WHICH WILL INCLUDE AN APPLICATION (NOTICE OF INTENT) TO DEQ PRIOR TO EARTH DISTURBING ACTIVITIES, A STORM WATER POLLUTION PREVENTION PLAN AND THE INSTALLATION AND MAINTENANCE OF EROSION AND SEDIMENT CONTROLS.

ALL TEMPORARY WORK ROADS MUST BE REMOVED IN THEIR ENTIRETY AND THE AFFECTED AREAS RETURNED TO PRECONSTRUCTION CONDITIONS. IN ADDITION, THE CONTRACTOR WILL BE RESPONSIBLE FOR PERMANENT STABILIZATION MEASURES AFTER REMOVAL OF THE WORK ROAD(S). ALL COSTS ASSOCIATED WITH THE CONTRACTORS' WORK ROAD INCLUDING A DEQ PERMIT, EROSION AND SEDIMENT CONTROLS AND PERMANENT STABILIZATION, ETC. WILL BE THE RESPONSIBILITY OF THE CONTRACTOR.

GOOD-HOUSEKEEPING REQUIREMENT:

MATERIAL STORAGE, CHEMICAL STORAGE, TRASH, SANITARY FACILITIES, ETC. SHOULD BE LOCATED NO CLOSER THAN 50 FEET FROM THE BANK OF ANY WATERS IN ORDER TO PROTECT WATER QUALITY.

DEBRIS SHALL NOT BE BURIED WITHIN LIMITS OF RIGHT-OF-WAY.

PAY QUANTITIES					
0200 BRIDGE 'A' - NBI 19361 - SH-2 OVER KIAMICHI RIVER					
ITEM		DESCRIPTION		UNIT	QUANTITY
504(C)	1450	EXPANSION DEVICE (BR-1)	(1)	LF	198.00
504(G)	6390	RAPID CURE JOINT SEALANT (BR-1)	(2)	LF	64.00
504(H)	6389	ELASTOMERIC MORTAR (BR-1)	(1)	CF	30.00

PAY QUANTITIES					
0201 BRIDGE 'B' - NBI 19363 - SH-2 OVER KIAMICHI RIVER					
ITEM		DESCRIPTION		UNIT	QUANTITY
504(C)	1450	EXPANSION DEVICE (BR-1)	(1)	LF	165.00
504(G)	6390	RAPID CURE JOINT SEALANT (BR-1)	(2)	LF	64.00
504(H)	6389	ELASTOMERIC MORTAR (BR-1)	(1)	CF	25.00

PAY QUANTITIES					
0202 BRIDGE 'C' - NBI 13536 - US-271 SB OVER RED RIVER & CO RD					
ITEM		DESCRIPTION		UNIT	QUANTITY
504(C)	1450	EXPANSION DEVICE (BR-1)	(1)	LF	120.00
504(G)	6390	RAPID CURE JOINT SEALANT (BR-1)	(2)	LF	36.00
504(H)	6389	ELASTOMERIC MORTAR (BR-1)	(1)(3)	CF	33.00
513(B)	6019	CLASS B BRIDGE DECK REPAIR	(5)	SY	10.00
523(A)	6550	SEALER CRACK PREPARATION	(4)	LF	80.00
523(B)	6560	SEALER RESIN	(4)	GAL	0.60
535	6130	(SP) CORROSION INHIBITOR (SURFACE APPLIED)	(5)	SY	2.00

PAY QUANTITIES					
0203 BRIDGE 'D' - NBI 17605 - US-271 NB OVER RED RIVER & CO RD					
ITEM		DESCRIPTION		UNIT	QUANTITY
504(C)	1450	EXPANSION DEVICE (BR-1)	(7)	LF	279.20
504(G)	6390	RAPID CURE JOINT SEALANT (BR-1)	(2)(8)	LF	700.00
513(B)	6019	CLASS B BRIDGE DECK REPAIR	(5)	SY	170.00
513(C)	6020	CLASS C BRIDGE DECK REPAIR	(6)	SY	170.00
535	6130	(SP) CORROSION INHIBITOR (SURFACE APPLIED)	(5)(6)	SY	34.00
535	6410	MASTIC ASPHALT JOINT MATERIAL (BR-1)	(9)	CF	11.00

PAY QUANTITIES					
0204 BRIDGE 'E' - NBI 17044 - SH-3 OVER LITTLE RIVER					
ITEM		DESCRIPTION		UNIT	QUANTITY
504(C)	1450	EXPANSION DEVICE (BR-1)	(7)	LF	30.00
504(G)	6390	RAPID CURE JOINT SEALANT (BR-1)	(2)(10)	LF	1,254.00
504(H)	6389	ELASTOMERIC MORTAR (BR-1)	(10)	CF	114.00

PAY QUANTITIES					
0205 BRIDGE 'F' - NBI 19257 - US-70/US-259/SH-3 SB OVER LITTLE RIVER O'FLOW					
ITEM		DESCRIPTION		UNIT	QUANTITY
504(C)	1450	EXPANSION DEVICE (BR-1)	(1)(7)	LF	350.40
504(H)	6389	ELASTOMERIC MORTAR (BR-1)	(1)	CF	24.00
523(C)	6570	DECK AREA SEALED (FLOODCOATS) (BR-1)	(11)	SY	1,380.00
535	6410	MASTIC ASPHALT JOINT MATERIAL (BR-1)	(9)	CF	14.00

PAY QUANTITIES					
0206 BRIDGE 'G' - NBI 19269 - US-70/US-259/SH-3 SB OVER LITTLE RIVER O'FLOW					
ITEM		DESCRIPTION		UNIT	QUANTITY
504(C)	1450	EXPANSION DEVICE (BR-1)	(1)(7)	LF	525.60
504(H)	6389	ELASTOMERIC MORTAR (BR-1)	(1)	CF	34.00
523(C)	6570	DECK AREA SEALED (FLOODCOATS) (BR-1)	(11)	SY	2,064.00
535	6410	MASTIC ASPHALT JOINT MATERIAL (BR-1)	(9)	CF	14.00

BR-1:
PAYMENT FOR THIS ITEM WILL BE BASED ON THE PLAN QUANTITY ONLY.
SEE SECTION 109.01B OF THE STANDARD SPECIFICATIONS.

THIS PROJECT IS MANDATORILY TIED WITH 24333(08). THE PRICE BID FOR 24333(08) SHALL INCLUDE ALL COSTS OF MOBILIZATION REQUIRED FOR 24333(08) AND 31697(04).

MULTIPLE LOCATIONS	DIVISION TWO	Design	N/A	N/A
GENERAL NOTES AND SUMMARY OF PAY QUANTITIES (SHEET 2 OF 2)(BRIDGE)		Detail	TEE	3/16
		Check	N/A	N/A
		Squad	HENSLEY	
		Engr.	DEFRANCO	
STATE OF OKLAHOMA	DEPARTMENT OF TRANSPORTATION	JOB/PIECE NO.	31697(04)	SHEET NO. AB02