

SUMMARY OF MAILBOX INSTALLATIONS								
LOCATION	TYPE OF INSTALLATION	MAILBOX	REMOVAL OF MAILBOX INSTALLATION		TRAFFIC BOUND SURFACE COURSE TYPE E	402(E) TONS		
			629(A)	629(B)			629(C)	629(D)
			SINGLE	MULTIPLE			EA.	EA.
STATION	SIDE							
106+64.00	RT	1		1	1	2		
109+40.00	RT	1		1	1	2		
113+10.00	RT	1		1	1	2		
116+00.00	RT	1		1	1	2		
126+97.00	RT	1		1	1	2		
133+20.00	RT	1		1	1	2		
134+88.00	RT		1	2	2	2		
139+70.00	RT		1	2	2	2		
144+80.00	RT	1		1	1	2		
152+04.00	RT	1		1	1	2		
154+35.00	RT	1		1	1	2		
155+72.00	RT	1		1	1	2		
157+10.00	RT	1		1	1	2		
158+77.00	RT	1		1	1	2		
172+68.00	RT	1		1	1	2		
178+74.00	RT		1	2	2	2		
183+30.00	RT	1		1	1	2		
199+27.00	RT		1	3	3	2		
207+08.00	RT		1	2	2	2		
218+91.00	RT		1	3	3	2		
226+64.00	LT		1	2	2	2		
232+35.00	LT	1		1	1	2		
239+34.00	RT	1		1	1	2		
TOTAL =		16	7	32	32	46		

SEE SHEET 3 FOR DETAILS

SIDEDRAIN SUMMARY											
STR. NO.	STATION	OFFSET FT.	SIDE	DESCRIPTION	DESIGN	FLOWLINE IN	FLOWLINE OUT	C.G.M.P. ROUND		C.E.T. TYPE A4	C.E.T. TYPE B4
								18"	24"x35"		
								613(B) L.F.	613(M) L.F.		
1	226+92.00	20.65	LT.	CONSTR. 18" x 60' C.G.S.P. - ROUND W/CET	CET4S-3	663.91	662.92	60		2	
2	232+59.00	28.24	LT.	CONSTR. 35" x 24" x 56' C.G.S.P. - ARCH W/CET	CET4S-3	654.91	654.78		54		2
3	251+52.00	20.22	RT.	CONSTR. 18" x 42' C.G.S.P. - ROUND W/CET	CET4S-3	652.31	651.39	42		2	
4	251+52.00	20.5	LT.	CONSTR. 18" x 40' C.G.S.P. - ROUND W/CET	CET4S-3	653.49	652.26	40		2	
TOTAL =								142	54	6	2

FENCE SUMMARY	
STATION EXTENTS	FENCE-STYLE SWF (5 BARBED WIRE) 624(C)
	L.F.
234+20.58 TO 244+42.86 LT.	1,073
TOTALS =	1,073

SUMMARY OF PAVEMENT MARKINGS				
STATION EXTENTS	DELINEATORS (TYPE 1, CODE 3) 853	DELINEATORS (TYPE 2, CODE 3) 853	TRAFFIC STRIPE (PAINT) (4" WIDE) WHITE 854(A)	TRAFFIC STRIPE (PAINT) (4" WIDE) YELLOW 854(A)
	EA.	EA.	L.F.	L.F.
137+07.00	4			
148+15.00	4			
165+05.00		2		
180+02.00		2		
206+58.00	4			
224+95.00	4			
100+09.75 TO 260+50.00			32,081	32,081
TOTALS =	16	4	32,081	32,081

DESIGN	RAA	12/15	OKLAHOMA DEPARTMENT OF TRANSPORTATION GUY ENGINEERING SERVICES, INC.
DRAWN	ALM	12/15	
CHECKED	RAP	12/15	
APPROVED	RAA	12/15	
SQUAD			
ROADWAY SUMMARIES (2)			
STATE JOB NO. 29394(04) SHEET NO. 8			