

PAY QUANTITIES				
TRAFFIC SECT. 0300				
ITEM NO.	CODE NO.	DESCRIPTION	UNIT	QUANTITY
201(B)	0181	SELECTIVE CLEARING	(SP-10) LSUM	1
230(A)	2806	SOLID SLAB SODDING	S.Y.	53
610(I)	4615	TACTILE WARNING DEVICE-RETROFIT	S.F.	96
619(B)	4792	REMOVAL OF SIDEWALK	(R-49, 50) S.Y.	18
802(B)	8344	3" PVC SCH.40 PLASTIC CONDUIT BORED	(TP-1) L.F.	660
802(B)	8346	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	(TP-1) L.F.	120
802(B)	8348	4" PVC SCH.40 PLASTIC CONDUIT BORED	(TP-1) L.F.	233
802(B)	8350	4" PVC SCH.40 PLASTIC CONDUIT TRENCHED	(TP-1) L.F.	24
802(C)	8552	2" HIGH DENSITY PE PIPE-BORED	(TP-1) (SP-13) L.F.	7070
802(C)	8557	2" HIGH DENSITY PE PIPE-TRENCHED	(TP-1) (SP-13) L.F.	12
803(A)	8066	PULL BOX (SIZE II)	(SP-9) EA.	14
803(B)	8085	GROUND BOX (GB36)	(SP-9) EA.	18
803(B)	8105	GROUND BOX (R46)	(SP-9) EA.	9
804(A)	2915	STRUCTURAL CONCRETE	C.Y.	12
804(B)	2916	REINFORCING STEEL	LB.	1733.7
805(A)	8704	REMOVAL OF PULL BOX	EA	5
805(A)	8712	(PL) REMOVAL OF LIGHT POLE	(TL-44) EA	1
805(A)	8726	(PL) REMOVAL OF EXISTING TRAFFIC SIGNAL EQUIPMENT	LSUM	1
806(B)	8894	10' MTG. HT. TS PED POLE (G. STL.)	(SP-1,20 & 21) (C-6) EA	4
806(E)	200	DECORATIVE POLE AND MAST ARM	(SP-1, 2, 3 & 20) (C-6) EA	4
809(A)	8090	ROADWAY LUMINAIRE	(SP-3) EA	4
810(A)	3118	SERVICE POLE	(SP-18) EA	1
811	8040	1/2 NO.8 ELECT.COND.	(TP-1) L.F.	150
811	8042	1/2 NO.8 ELECT.COND.	(TP-1) L.F.	375
811	8044	1/2 NO.10 ELECT.COND.	(TP-1) L.F.	762
818(A)	8710	(SP) FIBER OPTIC CABLE, 12 SMF	(TP-1) (ITS-2, 6, 7 & 12) (SP-12 & 14) L.F.	380
818(A)	8733	(SP) FIBER OPTIC CABLE, 144 SMF	(TP-1) (ITS-2, 7 & 12) (SP-12 & 14) L.F.	6150
818(B)	8743	(SP) FIBER OPTIC PATCH PANEL, 12 PORT	(SP-12) EA.	7
818(C)	8735	(SP) FIBER OPTIC CABLE SPLICE	(ITS-12) (SP-12) EA.	292
818(D)	8740	(SP) FIBER OPTIC CABLE TERMINATION	(ITS-15) (SP-12) EA.	108
818(F)	8370	(SP) SHIELD ISOLATION PEDESTAL	(ITS-22) (SP-12) EA.	9
818(G)	5570	(SP) FIBER OPTIC ROUTE SIGN AND INSTALLATION	(ITS-22) (SP-12) EA.	22
825	8550	TRAFFIC SIGNAL CONTROLLER ASSEMBLY	(SP-5, 11, 15, 16 & 17) EA.	3
828	8132	(PL) DETECTION SYSTEM (VIDEO)	(SP-8) LSUM	1
830	8000	PEDESTRIAN PUSH BUTTON	(SP-4, 5 & 19) EA.	8
831	8231	1WAY 3 SEC. ADJ. SIG. HD. S-6	(SP-7 & 19) EA.	7
831	8286	1WAY 5 SEC. ADJ. SIGN. HD. S-19	(SP-7 & 19) EA.	1
831	8295	1WAY 2 SEC. ADJ. PED. SIG. HD. S-20	(SP-5 & 19) EA.	8
833	3030	BACKPLATE	EA.	8
834(A)	8207	5/C TRAFFIC SIGNAL ELECTRICAL CABLE	(TP-1) L.F.	983
834(A)	8208	7/C TRAFFIC SIGNAL ELECTRICAL CABLE	(TP-1) L.F.	528
834(A)	8213	21/C TRAFFIC SIGNAL ELECTRICAL CABLE	(TP-1) L.F.	1235
834(B)	8220	2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	(TP-1) L.F.	32
840(A)	8592	E.P.S. OPTICAL EMITTER	(SP-15) EA.	1
840(B)	8593	E.P.S. OPTICAL DETECTOR	(SP-15) EA.	1
840(C)	8594	E.P.S. OPTICAL DETECTOR CABLE	(SP-15) L.F.	63
840(D)	8595	(PL) E.P.S. 2 CHANNEL PHASE SELECTOR	(SP-15) EA.	2
850(A)	8110	SHEET ALUMINUM SIGNS	(TS-6) S.F.	42
850(C)	8118	MAST ARM MOUNTED SIGNS (ALUM.)	(TS-6)(C-6) S.F.	79
855(A)	8812	TRAFFIC STRIPE (PLASTIC) (4" WIDE)	(TS-19) L.F.	70
855(A)	8814	TRAFFIC STRIPE (PLASTIC) (8" WIDE)	(TS-21) L.F.	50
855(A)	8825	TRAFFIC STRIPE (PLASTIC) (24" WIDE)	(TS-23) L.F.	179
880(J)	8905	CONSTRUCTION TRAFFIC CONTROL	(TC-25) (SP-22) LSUM	1

PAY QUANTITIES				
STAKING SECT. 0600				
ITEM NO.	CODE NO.	DESCRIPTION	UNIT	QUANTITY
642(B)	0096	CONSTRUCTION STAKING LEVEL II	LSUM	1

PAY QUANTITIES				
MOBILIZATION SECT. 0640				
ITEM NO.	CODE NO.	DESCRIPTION	UNIT	QUANTITY
641	1552	MOBILIZATION	LSUM	1

DESIGN	CEM	02/16	BOYD ST. AND UNIVERSITY BLVD.
DRAWN	CEM	02/16	
CHECKED	NDT	02/16	
APPROVED			
SQUAD	GARVER		
			SUMMARY OF PAY QUANTITIES
			STATE JOB NO. 24285(04) SHEET NO. 2