

7/8/2016 11:16:13 PM N:\OK\TRANSPORTATION\HIGHWAY\PRODUCTION\000110019.04 - WEATHERFORD - I-40 RAMP PHASE 2\PROJECT DRAWINGS\GENERAL\PAY QUANTITIES (ROADWAY).DWG

27911(06) 0600			
<b>PAY QUANTITIES</b>			
STAKING			
ITEM	DESCRIPTION	UNIT	QUANTITY
642(B)	0096 CONSTRUCTION STAKING LEVEL II	(12) L.SUM	1.00

27911(06) 0640			
<b>PAY QUANTITIES</b>			
CONSTRUCTION			
ITEM	DESCRIPTION	UNIT	QUANTITY
220	2800 SWPPP DOCUMENTATION AND MANAGEMENT	L.SUM	1.00
641	1552 MOBILIZATION	L.SUM	1.00

27911(06) 0100			
<b>PAY QUANTITIES</b>			
ROADWAY			
ITEM	DESCRIPTION	UNIT	QUANTITY
201(A)	0102 CLEARING AND GRUBBING	L.SUM	1.00
202(A)	0183 UNCLASSIFIED EXCAVATION	(1)(R-1) C.Y.	21,652.00
202(D)	0184 UNCLASSIFIED BORROW	(R-4) C.Y.	26,590.00
205(A)	4229 TYPE A-SALVAGED TOPSOIL	(R-5) L.SUM	1.00
221(C)	2801 TEMPORARY SILT FENCE	(3)(2) L.F.	4,000.00
221(D)	2803 TEMPORARY SEDIMENT FILTER	(2) EA.	5.00
221(F)	0100 TEMPORARY SILT DIKE	(2) L.F.	300.00
229	4318 DITCH LINER PROTECTION	L.F.	80.00
230(A)	2806 SOLID SLAB SODDING	(R-7)(R-8) S.Y.	23,327.00
233(A)	2817 VEGETATIVE MULCHING	(R-11) AC.	4.82
241	2832 MOWING	(4)(R-16) AC.	9.64
307(K)	4300 STABILIZED SUBGRADE	(5) S.Y.	27,148.00
325	5271 SEPARATOR FABRIC	S.Y.	26,651.00
402(E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	(6)(R-25) TON	250.00
407(B)	0250 TACK COAT	(7) GAL.	329.00
408	5774 PRIME COAT	(R-28) GAL.	9,397.00
411(B)	5945 SUPERPAVE, TYPE S3 (PG 64-22 OK)	(R-32) TON	4,447.00
411(C)	5950 SUPERPAVE, TYPE S4 (PG 76-28 OK)	(R-32) TON	584.00
412	5267 COLD MILLING PAVEMENT	(R-34) S.Y.	5,322.00
414(B)	5725 DOWEL JOINTED P.C. CONCRETE PAVEMENT (PLACEMENT)	S.Y.	24,058.00
414(G)	5275 P.C. CONCRETE FOR PAVEMENT	C.Y.	6,683.00
501(A)	0313 STRUCTURAL EXCAVATION UNCLASSIFIED	C.Y.	85.00
509(A)	0319 CLASS AA CONCRETE	(8)(R-1) C.Y.	215.00
509(D)	0325 CLASS C CONCRETE	(R-41) C.Y.	40.00
511(A)	0332 REINFORCING STEEL	(R-1) LB.	31,990.00
609(A)	0380 CONCRETE CURB (8" BARRIER-INTEGRAL)	L.F.	4,662.00
609(B)	1526 2'-8" COMB. CURB & GUTTER (8" BARRIER)	L.F.	656.00
610(A)	0602 4" CONCRETE SIDEWALK	S.Y.	7,640.00
610(B)	0604 6" CONCRETE DRIVEWAY	S.Y.	1,513.00
610(C)	0610 8" CONCRETE DIVIDING STRIP	S.Y.	247.00
610(I)	4610 TACTILE WARNING DEVICE-NEW	S.F.	188.00
610(J)	4810 (PL) STAMPED CONCRETE FINISH	(9) S.Y.	215.00
611(G)	5112 INLET CI DES. 2 (STD)	(R-44) EA.	5.00
611(G)	6002 INLET (SMD-TYPE 2)	EA.	4.00
611(H)	5325 ADD'L DEPTH IN INLET CI DES. 2	V.F.	7.00
611(I)	4488 REPLACEMENT OF INLET FRM & GRT (SSIF-FRM, CIG-GRT-VG-F)	EA.	6.00
611(M)	4488 REPLACEMENT OF CAST IRON HOOD	EA.	10.00
612(A)	0641 MANHOLES ADJUST TO GRADE	EA.	2.00
612(C)	0645 INLET ADJUST TO GRADE	EA.	1.00
613(A)	0491 18" R.C. PIPE CLASS III	(10) L.F.	298.00
613(A)	0492 24" R.C. PIPE CLASS III	(10) L.F.	174.00
613(L)	5726 18" PREFAB. CULVERT END SECTION, ROUND	(1) EA.	1.00
619(A)	0920 REMOVAL OF STRUCTURES & OBSTRUCTIONS	(R-48)(R-49) L.SUM	1.00
619(B)	4726 REMOVAL OF CURB AND GUTTER	(11)(R-49)(R-50) L.F.	3,392.00
619(B)	4727 REMOVAL OF CONCRETE PAVEMENT	(11)(R-49)(R-50) S.Y.	5,162.00
619(B)	4728 REMOVAL OF ASPHALT PAVEMENT	(11)(R-49)(R-50) S.Y.	24,013.00
619(B)	4766 REMOVAL OF CONCRETE DRIVEWAY	(11)(R-49)(R-50) S.Y.	1,232.00
619(B)	4780 REMOVAL OF GUARDRAIL	(R-49)(R-50) L.F.	2,780.00
619(B)	6133 REMOVAL OF 8" CONCRETE DIVIDING STRIP	(R-49)(R-50) S.Y.	812.00
622(A)	4746 PIPE RAILING	L.F.	20.00
623(A)	0932 BEAM GUARDRAIL W-BEAM SINGLE	L.F.	650.00
623(F)	8300 GUARDRAIL TRAIL END TURNDOWN (31")	EA.	2.00
623(G)	8590 GUARDRAIL END TREATMENT (31")	EA.	2.00
627(A)	4317 CONCRETE LONGITUDINAL BARRIER, DESIGN 1	(R-54) L.F.	550.00
627(B)	4410 CONCRETE LONGITUDINAL BARRIER END SECTIONS	EA.	4.00

MAIN ST. CUSTER COUNTY

**PAY ITEMS (ROADWAY)**