

SUMMARY OF SURFACING QUANTITIES

SHEET NO.	STATION EXTENTS	STABILIZED SUBGRADE 307(K)	TACK COAT 407(B)	PRIME COAT 408	SUPERPAVE TYPE S3 (PG 64-22 OK) 411(B)	SUPERPAVE TYPE S4 (PG 64-22 OK) 411(C)
		SY	GAL	GAL	TON	TON
	Mainline					
15	STA. 396+50.00 TO STA. 404+00.00	1,436.83	575.22	502.89	640.98	139.90
16	STA. 404+00.00 TO STA. 413+50.00	3,905.56	1,563.54	1,366.94	1,742.30	380.28
	Guardrail					
15	STA. 396+50.00 TO STA. 404+00.00			235.73	113.15	75.43
16	STA. 404+00.00 TO STA. 413+50.00			85.65	41.11	27.41
	TOTALS	5,342.39	2,138.76	2,191.21	2,537.55	623.03

SUMMARY OF DITCH TREATMENT

SHEET NO.	STATION EXTENTS	LOCATION	DESIGN NO.	BOTTOM WIDTH	CURTAIN WALL	DITCH LINER PROTECTION 229	CLASS C CONCRETE 509(D)
				LF	EA	LF	CY
	Mainline						
16	STA. 404+00.00 TO STA. 413+50.00	LEFT	2A	8	7	550.00	98.84
8	SPECIAL INLET	RIGHT	2A	4	3	107.33	14.21
	TOTALS			10		657.33	113.05

SUMMARY OF PERMANENT EROSION CONTROL

SHEET NO.	STATION EXTENTS	LOCATION AND DESCRIPTION	SOLID SLAB SODDING 230(A)	MOWING 241
			SY	AC
	Mainline			
15	STA. 396+50.00 TO STA. 404+00.00	LEFT AND RIGHT	2,680.64	1.66
16	STA. 404+00.00 TO STA. 413+50.00	LEFT AND RIGHT	10,013.26	3.93
8	SPECIAL INLET	RIGHT	4,068.00	
	TOTALS		16,761.90	5.59

SUMMARY OF GUARDRAIL

SHEET NO.	STATION EXTENTS	BEAM GUARDRAIL W-BEAM SINGLE 623(A)		GUARDRAIL END TREATMENT (31") 623(G)	GUARDRAIL BRIDGE CONN-THRIE BEAM (31") 623(I)	GUARDRAIL DELINEATORS (TYPE 2, CODE 1) 853
		LT	RT	EA	EA	EA
15	STA. 396+25.93 TO STA. 398+43.45		X	1	1	5
15	STA. 397+38.43 TO STA. 398+43.45	X		1	1	2
15	STA. 402+89.40 TO STA. 403+94.43		X	1	1	2
15 / 16	STA. 402+89.40 TO STA. 405+06.93	X		1	1	5
	TOTALS			4	4	14

SUMMARY OF TEMPORARY SEDIMENT CONTROLS

SHEET NO.	STATION	LOCATION AND DESCRIPTION	TEMPORARY SILT FENCE 221(C)	TEMPORARY SEDIMENT FILTER 221(D)	TEMPORARY SILT DIKE 221(F)
			LF	EA	LF
	Mainline				
10	STA. 396+50.00 TO STA. 404+00.00	LEFT AND RIGHT	900		
10	STA. 404+00.00 TO STA. 413+50.00	LEFT AND RIGHT	136		42
10	SPECIAL INLET	RIGHT		1	
	TOTALS		1036	1	42

SUMMARY OF REMOVAL QUANTITIES

SHEET NO.	STATION EXTENTS	REMOVAL OF ASPHALT 619(B)	SAWING PAVEMENT 619(C)
		SY	LF
13	STA. 396+50.00 TO STA. 404+00.00	1,686.75	29.95
13	STA. 404+00.00 TO STA. 413+50.00	2,333.98	27.57
	TOTALS	4,020.73	57.52

SUMMARY OF EARTHWORK QUANTITIES

DESCRIPTION	UNCLASSIFIED EXCAVATION 202(A)	EMBANKMENTS 15% COMP. 202(F)	EXCESS EXCAVATION	UNCLASSIFIED BORROW 202(D)
	CY	CY	CY	CY
Mainline	7,756	9,717		1,961
SPECIAL INLET	3,143	47	3,096	
TOTALS	10,899	9,764	1,135 ▼	0 ●

● QUANTITY SHOWN HAS BEEN REDUCED BY 1,961 CY OF EXCESS EXCAVATION FROM SPECIAL INLET

▼ QUANTITY SHOWN HAS BEEN REDUCED BY 1,961 CY THAT WAS USED TO REDUCE THE MAINLINE BORROW

SUMMARY SHEET (ROADWAY)