

REV. NO.	DESCRIPTION	REVISIONS	DATE

### TRAFFIC CONTROL PAY QUANTITIES NOTES

- (TC-14) SEE STANDARD DRAWING PM1-1, PM2-1, PM3-1, PM4-1, PM5-1, PM6-1, PM7-1, PM8-1 (LATEST REVISION). A PART, OR ALL, OF THE QUANTITY SHOWN IS TO BE USED AS FINAL PAVEMENT MARKING.
- (TC-23) QUANTITY SHOWN FOR THIS ITEM INCLUDES THOSE SIGNS WHICH COMPRISE THE ROUTE MARKER ASSEMBLIES USED TO INDICATE THE DETOUR ROUTE.
- (TC-26) ALL CONSTRUCTION TRAFFIC CONTROL WILL BE IMPLEMENTED ACCORDING TO CONSTRUCTION PLANS, AND INSTALLED IN A MANNER APPROVED BY THE ENGINEER, IN ACCORDANCE WITH CHAPTER VI OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, (CURRENT EDITION), AND COMPLIANT WITH APPLICABLE O.D.O.T. STANDARD DRAWINGS. PRICE BID FOR THIS ITEM SHALL BE PAYMENT IN FULL FOR THE INSTALLATION, MAINTENANCE AND SUBSEQUENT REMOVAL OF ALL NECESSARY CONSTRUCTION TRAFFIC CONTROL DEVICES REQUIRED FOR COMPLETION OF THE PROJECT.
- ALL SIGNS AND BARRICADES WHICH ARE SHOWN WITH TYPE "A" LIGHTS IN THE STANDARD DRAWINGS SHALL HAVE THE CORRESPONDING LIGHT ATTACHED DURING NON-DAYLIGHT HOURS.
- (TC-33) ALL CONSTRUCTION WORK ZONE SIGNS AND CHANNELIZING DEVICES SHALL HAVE FLOURESCENT SHEETING. THE FLOURESCENT SHEETING SHALL MEET THE REQUIREMENTS OF ASTM D4956 (LATEST REVISION)
- THE MANUFACTURER SHALL FURNISH A TYPE 'D' CERITFICATION IN ACCORDANCE WITH O.D.O.T. STANDARD SPECIFICATIONS (CURRENT EDITION) SUBSECTION 106.04. THE CERTIFICATION SHALL INCLUDE TEST RESULTS ON MATERIAL SUBMITTED FOR APPROVAL.
- (TC-52) ANY USED CHANGEABLE MESSAGE SIGN TO BE PLACED ON THIS PROJECT SHALL BE SUBJECT TO INSPECTION AND APPROVAL, BY THE OKLAHOMA DEPARTMENT OF TRANSPORTATION, TO ASSURE THAT THEY ARE IN GOOD WORKING CONDITION, PRIOR TO PLACEMENT ON THE PROJECT.
- (TC-70) THIS ITEM IS AN ESTIMATED QUANTITY TO BE USED AS DEEMED NECESSARY BY THE ENGINEER.
- (TC-84) 60 CONSTRUCTION CALENDAR DAYS WERE USED TO COMPUTE THE SIGN DAY PAY ITEMS. THE AMOUNT OF CALENDAR DAYS USED TO COMPUTE THE SIGN DAY PAY ITEMS IS AN ESTIMATED QUANTITY ONLY, BASED ON THE CURRENT O.D.O.T. STANDARDS AND SUGGESTED CONSTRUCTION SEQUENCE FOR THIS PROJECT. THESE ESTIMATED SIGN DAY QUANTITIES MAY CHANGE AS THE PROJECT'S CONSTRUCTION TRAFFIC CONTROL IS MODIFIED DURING CONSTRUCTION.
- (TC-85) THESE SIGNS MUST BE ON THE OKLAHOMA DEPARTMENT OF TRANSPORTATION LIST OF APPROVED CHANGEABLE MESSAGE SIGNS. FOR A LIST OF THE APPROVED SIGNS GO TO THE OKLAHOMA DEPARTMENT OF TRANSPORTATION WEBSITE AT:  
<http://www.okladot.state.ok.us/traffic/qpl/index.php>

### SIGNING PAY QUANTITIES NOTES

- (TS-19) QUANTITY SHOWN INCLUDES 1,000 L.F. TRAFFIC STRIPE (PLASTIC)(WHITE) AND 1,000 L.F. TRAFFIC STRIPE (PLASTIC)(YELLOW) AND WILL BE MEASURED BY THE LINEAR FOOT OF FOUR INCH (4") WIDE TRAFFIC STRIPE.

### SPECIAL PAY QUANTITIES NOTES

- (SP-1) CHANGEABLE MESSAGE SIGNS SHALL BE PLACED ON THE PROJECT 14 DAYS IN ADVANCE OF THE START DATE.
- (SP-2) 74 CONSTRUCTION CALENDAR DAYS WERE USED TO COMPUTE THE SIGN DAY PAY FOR THIS ITEM.

### GENERAL CONSTRUCTION NOTES

ANY DAMAGE CAUSED BY THE CONTRACTOR TO ANY STRUCTURES, ROADWAY SURFACES, STRIPING, RAISED PAVEMENT MARKERS, GUARDRAIL, SLOPES, AND SIGNS SHALL BE REPAIRED AT CONTRACTOR'S EXPENSE TO THE SATISFACTION OF THE ENGINEER.

ALL TEMPORARY TRAFFIC CONTROL DEVICES SHALL MEET ODOT'S "QUALITY STANDARDS FOR TEMPORARY TRAFFIC CONTROL DEVICES."

"THE CONTRACTOR SHALL PROVIDE A PERSON TO BE ON 24 HOUR CALL AS NEEDED AS DETERMINED BY THE ENGINEER. THIS PERSON SHALL HOLD A CURRENT CERTIFICATION FROM THE AMERICAN TRAFFIC SAFETY ASSOCIATION (ATSSA) OR THE OKLAHOMA TRAFFIC ENGINEERING ASSOCIATION (OTEA) AS A TRAFFIC CONTROL TECHNICIAN OR TRAFFIC CONTROL SUPERVISOR."

### SUMMARY OF PAY QUANTITIES - TRAFFIC CONTROL

WASHITA COUNTY  
 JP NO. 28774(04)  
 0300 TRAFFIC CONTROL

ITEM	CODE	DESCRIPTION	UNIT	QUANTITY
880(B)	8818	CONSTRUCTION SIGNS 0 TO 6.25 SF ( TC -23, 26, 33, 84)	SD	9,240.00
880(B)	8821	CONSTRUCTION SIGNS 6.26 TO 15.99 SF ( TC -26, 33, 84)	SD	1,860.00
880(B)	8824	CONSTRUCTION SIGNS 16.0 SF TO 32.99 S.F. ( TC -26, 33, 84)	SD	960.00
880(C)	8842	CONSTRUCTION BARRICADES (TYPE III) ( TC -26, 84)	SD	1,800.00
880(C)	8848	WING BARRICADES ( TC -26, 84)	SD	240.00
880(E)	8860	WARNING LIGHTS (TYPE A) ( TC -26, 84)	SD	4,560.00
882(A)	8306	PORT. CHANGEABLE MESSAGE SIGN ( TC -26, 52, 70, 85) ( SP-1, 2)	SD	148.00

### SUMMARY OF PAY QUANTITIES - STRIPING

WASHITA COUNTY  
 JP NO. 28774(04)  
 0301 SIGNING & STRIPING

ITEM	CODE	DESCRIPTION	UNIT	QUANTITY
855(A)	8812	TRAFFIC STRIPE (PLASTIC)(4" WIDE) (TC-14)(TS-19)	LF	2,000.00

### SUMMARY OF PAY QUANTITIES AND NOTES (TRAFFIC)