

SUMMARY OF SURFACING QUANTITIES						
SHEET NO.	STATION EXTENTS	SUBGRADE METHOD B 310(B)	TACK COAT 407(B)	PRIME COAT 408	SUPERPAVE TYPE S3 (PG 64-22 OK) 411(B)	SUPERPAVE TYPE S4 (PG 64-22 OK) 411(C)
		SY	GAL	GAL	TON	TON
11	STA. 599+00.00 TO STA. 603+75.00	1,500.00	719.72	545.42	690.20	228.72
	TOTALS	1,500.00	719.72	545.42	690.20	228.72

SUMMARY OF EARTHWORK QUANTITIES				
DESCRIPTION	UNCLASSIFIED EXCAVATION 202(A)	EMBANKMENTS 15% COMP. 202(F)	EXCESS EXCAVATION	UNCLASSIFIED BORROW 202(D)
	CY	CY	CY	CY
MAINLINE	139.31	3968.78		3829.47
TOTALS	139.31	3968.78		3829.47

SUMMARY OF REMOVAL QUANTITIES					
SHEET NO.	STATION EXTENTS	COLD MILLING PAVEMENT 412	REMOVAL OF ASPHALT 619(B)	REMOVAL OF GUARD RAIL 619(B)	SAWING PAVEMENT 619(C)
		SY	SY	LF	LF
8	STA. 599+00.00 TO STA. 603+75.00	700.79	1,577.71	650.32	360.00
	TOTALS	700.79	1,577.71	650.32	360.00

SUMMARY OF PERMANENT EROSION CONTROL				
SHEET NO.	STATION EXTENTS	LOCATION AND DESCRIPTION	SOLID SLAB SODDING 230(A)	MOWING 241
			SY	AC
8	STA. 599+00.00 TO STA. 603+75.00	LEFT AND RIGHT	2,044.60	0.72
	TOTALS		2,044.60	0.72

SUMMARY OF TEMPORARY SEDIMENT CONTROLS				
SHEET NO.	STATION EXTENTS	LOCATION AND DESCRIPTION	TEMPORARY SILT FENCE 221(C)	TEMPORARY FOCK FILTER DAM (TYPE 2) 221(G)
			LF	CY
8	STA. 599+00.00 TO STA. 603+75.00	LEFT AND RIGHT	194	102.4
	TOTALS		194	102.4

SUMMARIES
(ROADWAY)