

TRAFFIC SIGNING AND STRIPING PAY QUANTITY NOTES

(TS-II) QUANTITY SHOWN INCLUDES 6290 L.F. TRAFFIC STRIPE (PLASTIC)(WHITE) AND 2409 L.F. TRAFFIC STRIPE (PLASTIC)(YELLOW) AND WILL BE MEASURED BY THE LINEAR FOOT OF FOUR INCH (4') WIDE TRAFFIC STRIPE. THIS STRIPE SHALL BE APPLIED AT A THICKNESS OF 70 MILS, IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS AND APPROVAL BY THE ENGINEER.

(SP-I) MILLED SHOULDER RUMBLE STRIPS, WHEN INSTALLED ON ASPHALT SURFACES, SHALL BE FOG SEALED A NOMINAL ONE INCH OUTSIDE THE MILLED LENGTH AND WIDTH AT A RATE OF 0.15Y/FT IN ACCORDANCE TO SECTION 407 OF THE 2009 OKLAHOMA STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION. AN ESTIMATED QUANTITY OF 78 GALS. OF FOG SEAL. FOG SEAL SHALL NOT COME IN CONTACT WITH EXISTING STRIPING DURING FOG SEAL OPERATIONS. IF THE FOG SEAL DOES COME INTO CONTACT WITH EXISTING STRIPING, THE CONTRACTOR SHALL REMOVE AND RESTRIPE AT THE CONTRACTORS EXPENSE IN A TIMELY MANNER TO THE SATISFACTION OF THE ENGINEER.




2894I (04)		PAY QUANTITIES SIGNING AND STRIPING		
0303 SIGNING AND STRIPING				
ITEM NO.		ITEM DESCRIPTION	UNIT	QUANTITY
855(A)	8840	TRAFFIC STRIPE (PLASTIC) (THIN LINE) (4' WIDE)	(TS-II) (TC-13, 14) LF	8,699
407 (A)	4659	FOG SEAL	(SP-II) GAL	78
413 (B)	4863	RUMBLE STRIP-METHOD HMA-CYC	(SP-II) LF	6,045

TRAFFIC SIGNING AND STRIPING GENERAL CONSTRUCTION NOTES

ANY DAMAGE CAUSED BY THE CONTRACTOR TO ANY STRUCTURES, ROADWAY SURFACES, STRIPING, RAISED PAVEMENT MARKERS, GUARDRAIL, SLOPES, AND SIGNS SHALL BE REPAIRED AT CONTRACTORS EXPENSE TO THE SATISFACTION OF THE ENGINEER.

ANY AND ALL 9th STREET NAME SIGNS LOCATED WITHIN THE PROJECT ARE TO BE REMOVED AND STATE FORCES WILL PICK UP AT THE JOB SITE.

H:\Projects\2012\GK_0001_EC394F_US17\CAD\Sheets\EC394-06_01Y01.dgn 7/11/2016



07-11-2016
 CA 5769 PE/LS
 LAMB-STAR ENGINEERING, L.P.
 5700 W. PLANO PARKWAY, SUITE 1000
 PLANO, TX 75093
 214-440-3600

US-177

DESIGN	TWW
DRAWN	TWW
CHECKED	WLO
APPROVED	JML
SQUAD	L-S ENGR.

SUMMARY OF PAY QUANTITIES
(SIGNING AND STRIPING)

JOB PIECE NO. 2894I(04) SHEET NO. 5