

### SUMMARY OF TEMPORARY EROSION CONTROL

STATION TO STATION	DESCRIPTION	TEMPORARY SILT FENCE 221(C)	TEMPORARY FIBER LOG 221(K)	TEMPORARY SILT DIKE 221(F)
		L.F.	L.F.	L.F.
1521+71.00	FRONT OF CURB INLET LT. & RT.		30.00	
1525+62.00	FRONT OF CURB INLET LT. & RT.		30.00	
1527+00.00	ACROSS DITCH BOTTOM RT.			14.00
1528+00.00	ACROSS DITCH BOTTOM LT.			14.00
1529+44.00	FRONT OF CURB INLET LT.		15.00	
1529+50.00	ACROSS DITCH BOTTOM LT.			14.00
1530+50.00	FRONT OF CURB INLET LT.		15.00	
1530+50.00	FRONT OF CURB INLET RT.		21.00	
1530+75.00	ACROSS DITCH BOTTOM LT. & RT.			56.00
1534+00.00	ACROSS DITCH BOTTOM RT.			14.00
1534+12.40	FRONT OF CURB INLET LT.		15.00	
1534+12.40	FRONT OF CURB INLET RT.		21.00	
1534+15.00	ACROSS DITCH BOTTOM LT.			14.00
1536+60.00	ACROSS DITCH BOTTOM LT. & RT.			28.00
1538+00.00	ACROSS DITCH BOTTOM LT. & RT.			28.00
1540+50.00	ACROSS DITCH BOTTOM LT. & RT.			28.00
1543+00.00	ACROSS DITCH BOTTOM LT. & RT.			28.00
1546+00.00	ACROSS DITCH BOTTOM LT. & RT.			28.00
1548+65.00	ACROSS DITCH BOTTOM LT. & RT.			28.00
1551+00.00	ACROSS DITCH BOTTOM LT. & RT.			28.00
VAR. LOC. ALONG 5TH ST.	ACROSS DITCH BOTTOM LT. & RT.			56.00
1+67.00 (LT. 5TH ST.)	FRONT OF CURB INLET		12.00	
1+67.00 (RT. 5TH ST.)	FRONT OF CURB INLET		12.00	
1554+98.50	AROUND CURB INLET LT.		42.00	
1557+05.40	AROUND STORM SEWER DRAIN RT.		66.00	
1557+95.30	AROUND SMD RT.		12.00	
VARIOUS LOCATIONS TO BE DETERMINED BY THE ENGINEER		2,000.00	15.00	70.00
TOTALS		2,000.00	306.00	448.00

### SUMMARY OF PERMANENT EROSION CONTROL

STATION TO STATION	DESCRIPTION	WORK AREA	SOLID SLAB SODDING 230(A)
			S.Y.
1518+71.00 TO 1522+15.00 LT.	BEHIND CURB TO PRES. R/W (MINUS SIDEWALK)	1	341.05
1518+70.00 TO 1522+02.00 RT.	BEHIND CURB TO PRES. R/W (MINUS SIDEWALK)	1	323.61
1522+55.00 TO 1527+35.00 LT.	BEHIND CURB TO PRES. R/W (MINUS SIDEWALK)	1	482.98
1522+55.00 TO 1523+70.00 RT.	BEHIND CURB TO PRES. R/W (MINUS SIDEWALK)	1	84.26
1527+45.00 TO 1529+72.00 LT.	BEHIND SIDEWALK TO TOC/TOS	2	929.45
1523+80.00 TO 1538+52.45 RT.	BEHIND SIDEWALK TO TOC/TOS	2	8,592.62
1530+00.00 TO 1533+55.00 LT.	BEHIND SIDEWALK TO TOC/TOS	2	2,102.72
1533+83.00 TO 1538+52.45 LT.	BEHIND SIDEWALK TO TOC/TOS	2	2,608.00
1560+00.00 TO 1563+00.00 LT.	BEHIND CURB TO PRES. R/W (MINUS SIDEWALK)	1	344.04
1560+00.00 TO 1563+00.00 RT.	BEHIND CURB TO PRES. R/W (MINUS SIDEWALK)	1	325.62
TOTALS			16,134.35

### SUMMARY OF DRIVEWAYS

STATION	TYPE	LENGTH	WIDTH	STABILIZED SUBGRADE 307(K)	TACK COAT 407	SUPERPAVE TYPE S3 (PG 70-28 OK) 411(B)	SUPERPAVE TYPE S4 (PG 70-28 OK) 411(C)	2'-8" COMB. CRB. & GUT. (6" BARRIER) 609(B)	6" CONC. DRIVEWAY 610(B)	8" CONC. DRIVEWAY 610(B)	REMOVAL OF CONCRETE DRIVEWAY 619(B)	REMOVAL OF ASPHALT DRIVEWAY 619(B)
				S.Y.	GAL.	TON	TON	L.F.	S.Y.	S.Y.	S.Y.	S.Y.
1519+15.10 RT.	TYPE 1	9.90'	10'						15.22		27.16	
1519+99.26 RT.	TYPE 1	17.25'	20'						42.55		75.61	
1520+03.57 LT.	TYPE 1	17.18'	10'						23.31		17.35	
1520+55.90 LT.	TYPE 1	16.20'	24'						47.42		52.60	
1520+78.39 RT.	TYPE 1	35.79'	10'						43.99		17.30	
1521+33.66 LT.	TYPE 1	14.74'	10'						20.60		11.48	
1521+90.29 LT.	TYPE 1	13.68'	10'						19.42		22.81	
1522+28.07 RT.	STREET RETURN	56.00'	26'	219.85	12.13	36.24	18.12	112.00				
1522+28.63 LT.	STREET RETURN	25.00'	26'	98.15	5.42	16.18	8.09	50.00				
1523+33.22 LT.	TYPE 1	14.48'	10'						20.31			19.91
1523+75.17 RT.	TYPE 1	11.46'	10'						16.95		11.41	
1524+54.94 LT.	TYPE 1	16.61'	10'						22.68		23.60	
1526+06.89 LT.	STREET RETURN	42.00'	26'	164.89	9.10	27.18	13.59	84.00				
1526+80.00 LT.	TYPE 2 COMMERCIAL	19.79'	30'							75.55	69.76	
1527+40.00 LT.	TYPE 1	19.47'	12'						25.85		32.51	
1529+88.08 LT.	STREET RETURN	99.00'	26'	388.67	21.45	64.07	32.03	198.00				
1533+68.03 LT.	STREET RETURN	137.00'	26'	537.85	29.68	88.66	44.33	274.00				
1555+75.59 LT.	TYPE 1	5.67'	10'						8.41			
1559+84.74 RT.	STREET RETURN	31.00'	30'	121.70	6.72	20.06	10.03	62.00				
1559+87.23 LT.	STREET RETURN	61.00'	30'	239.48	13.22	39.48	19.74	122.00				
1561+04.10 LT.	TYPE 2 COMMERCIAL	18.88'	24'							51.77	55.68	
1561+57.54 RT.	TYPE 2 PRIVATE	2.50'	15'						12.57		30.71	
1561+84.38 LT.	TYPE 2 COMMERCIAL	19.33'	30'							74.03	116.68	
TOTALS				1,770.59	97.72	291.87	145.93	902.00	319.28	201.35	564.66	19.91

### EROSION CONTROL TYPICALS

