

OKLAHOMA DEPARTMENT OF TRANSPORTATION					
DDOT DIVISION	STATE	JOB PIECE No.	FISCAL YEAR	SHEET No.	TOTAL SHEETS
8	OKLA	27092(04)		12	143
DESCRIPTION		REVISIONS	DATE		

0100 ROADWAY

DRAINAGE STRUCTURE SUMMARY																					
STR. NO.	ALIGNMENT	STATION	DESCRIPTION	DESIGN	ELEV. TOP MANHOLE OR GRATE	FLOWLINE IN	FLOWLINE OUT	STRUCTURAL INSTALLATION				PIPES				STR. NO.					
								UNCLASSIFIED EXCAVATION*	STRUCTURAL EXCAVATION UNCLASSIFIED*	TRENCH EXCAVATION*	STD. BEDDING MATERIAL*	CLASS AA CONCRETE	REINFORCING STEEL	18" RCP CLASS III	18" CORR. GALV. STEEL PIPE		18" PREFAB. CULVERT END SECTION, ROUND	18" GALV. STEEL CULVERT END SECTION, ROUND			
								FT	FT	FT	CY	CY	CY	CY	509(A) CY		511(A) LB	613(A) LF	613(B) LF	613(L) EA	613(P) EA
1	US 169	839+47.77	CONST 7' X 6' X 37.54' LG RCB XD 27.80' RT & 60.20' RT	SBI-4, RCB DETAILS (1, 2, 3, 4, 5, & 6)	--	705.00	704.64	E	337	28			85	12780							1
2	US 169	878+57.45	CONST 18' X 56' LG RCP SD 78.66' RT	PCES-4, SPI-4, SPB-1, FHTCP-3	--	705.46	704.67	S			42	22			56		2				2
T-1	NORTH DETOUR	4876+93.28	CONST TEMP 18' X 56' LG CGSP SD 37.75' RT	PCES-4, SPI-4, SPB-1, FHTMPP-1	--	706.39	705.15	S			43	22				56			2		T-1
TOTALS									337	28	42	22	85	12780	56	56	2	2			

*FOR INFORMATION ONLY

0310 TRAFFIC SIGNING & STRIPING

SUMMARY OF STRIPING		
TYPE		LF
TOTAL WHITE (MULTI-POLYMER)		
4" SOLID		10,733
TOTAL YELLOW (MULTI-POLYMER)		
4" DASHED		1,369
856(A) TRAFFIC STRIPE (MULTI-POLYMER) (4" WIDE)	LF	12,102

0310 TRAFFIC SIGNING & STRIPING

SUMMARY OF SIGNING							
SIGN NO.	LOCATION		SIGN TYPE	SHEET ALUM. SIGNS		REMARKS	
				850(A)	851(C)		
				SF	LF		
US 169							
1	853+50	32' RT	W8-13	9.00	17.00		
2	859+51	36' RT	SP. SIGN NO. 1 (OPOSSUM CREEK)	16.50	16.00		
3	865+05	36' LT	SP. SIGN NO. 1 (OPOSSUM CREEK)	16.50	16.00		
4	871+00	32' LT	W8-13	9.00	17.00		
5	871+00	32' RT	W10-2L	9.00	17.00		
6	878+00	32' LT	RTE. ASS. NO. 1	7.00	17.00		
7	878+24	47' LT	R1-1	5.18	15.00		
8	878+57	64' LT	W10-1	7.07	15.00		
9	878+70	48' RT	R1-1	5.18	15.00		
10	885+60	32' LT	W10-2R	9.00	17.00		
11	878+27	49' RT	D-3	-	-	(HWY 169, EW04 - REMOVE AND RESET)	
12	878+60	49' LT	D-3	-	-	(HWY 169, EW04 - REMOVE AND RESET)	
TOTALS				85.00	145		

0100 ROADWAY

SUMMARY OF EARTHWORK				
BY CONSTRUCTION SEQUENCE				
	UNCL. EXCAVATION	Fill	UNCL. BORROW	Waste
	202(A)	(+20%)	202(D)	
	C.Y.	CY	C.Y.	CY
Phase 1 (Detour)	3764	50678	46,914	0
Phase 2	19829	10441	0	9388
Phase 3	52816	509	0	52307
TOTALS:	76409	61628	46914	61695

Design		US 169 OVER OPOSSUM CREEK	NOWATA COUNTY
Drawn		SUMMARIES (2)	
Checked			
Approved			
Squad			
		Job Piece No. 27092(04)	Sheet No. 12