

CITY OF <b>stillwater</b>						
FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS	
6	OKLA	31595(04)	16			
DESCRIPTION		REVISIONS		DATE		
REVISED DRIVE				8-3-2016		

PLAN SHEET NO.	STATION TO STATION	ALIGNMENT	STABILIZED SUBGRADE	DOWEL JOINTED P.C.C. PAVT. (PLACEMENT)	P.C. CONCRETE FOR PAVEMENT	2'-8" COMB. CURB & GUTTER (6" BARRIER)	4" CONCRETE SIDEWALK
			307(K) SY	414(B) SY	414(G) CY	609(B) LF	610(A) SY
WESTERN RD.							
22	31+82.42 TO 36+26.12	CRL WESTERN RD.	1173.74	900.58	237.65	575.95	585.77
23	36+26.12 TO 38+00.00	CRL WESTERN RD.	1138.61	935.61	246.90	325.77	332.41
24	38+00.00 TO 53+00.00	CRL WESTERN RD.	9361.66	8139.03	2147.80	3000.00	1721.76
25	53+00.00 TO 68+00.00	CRL WESTERN RD.	9222.22	8000.00	2111.11	3000.00	1889.50
26	68+00.00 TO 83+00.00	CRL WESTERN RD.	9222.22	8000.00	2111.11	3000.00	1925.77
27	83+00.00 TO 89+08.34	CRL WESTERN RD.	4254.06	3748.62	989.22	1302.28	691.96
McELROY RD.							
28	12+00.00 TO 14+67.14	CL SURVEY McELROY RD.	949.83	831.10	219.32	0.00	0.00
	15+31.14 TO 16+50.00	CL SURVEY McELROY RD.	422.61	369.79	97.58	0.00	0.00
TOTALS			35,744.95	30,924.73	8,160.69	11,204.00	7,147.17

PLAN SHEET NO.	STATION TO STATION	TEMPORARY				PERMANENT	
		*TEMPORARY SILT FENCE 221(C) LF	TEMPORARY SEDIMENT FILTER (TYPE 1) 221(D) EA	TEMPORARY SILT DIKE 221(F) LF	TEMPORARY ROCK FILTER DAM TYPE 1 221(G) CY	SOLID SLAB SODDING 230(A) SY	TYPE I PLAIN RIPRAP 601(A) TON
15	STA. 31+82.42 TO STA. 60+00.00	2,560	14	140.00	0.00	10,523.35	19.69
16	STA. 60+00.00 TO STA. 89+08.34	3,353	10	0.00	8.84	7,692.12	94.88
TOTALS		5,913.00	24.00	140.00	8.84	18,215.47	114.57

\* QUANTITY INCLUDES 1000 LINEAR FEET TO BE USED AT THE DIRECTION OF THE ENGINEER.

STATION TO STATION LIMITS OF FENCE	LOCATION	SIDE	FENCE STYLE SWF (5 BARBED WIRE) 624(C) LF
STA. 37+02.29 TO STA. 82+71.48	WESTERN RD.	LT.	4,569
STA. 79+00.00 TO STA. 82+79.84	WESTERN RD.	RT.	2,443
TOTAL			7,012

PLAN SHEET NO.	STATION TO STATION	ALIGNMENT	DECORATIVE MEDIAN CONCRETE 610(C) SY
22	STA. 31+82.42 TO STA. 38+00.00	WESTERN RD.	274.54
23	STA. 38+00.00 TO STA. 53+00.00	WESTERN RD.	443.08
24	STA. 53+00.00 TO STA. 68.00.00	WESTERN RD.	434.91
25	STA. 68+00.00 TO STA. 83+00.00	WESTERN RD.	471.57
26	STA. 83+00.00 TO STA. 89+08.34	WESTERN RD.	146.77
TOTAL			1,771.00

PLAN SHEET NO.	LOCATION STATION TO STATION	DESIGN NO.	BOTTOM WIDTH	SIDE SLOPE RATIO	LENGTH	NO. OF CURTAIN WALLS	CLASS C CONCRETE
			FT.	XX:1	L.F.	EA.	509(D) C.Y.
23	STA. 41+50.00 TO STA. 43+50.00, RT	2A	8	3:1	201.15	4	36.48
TOTAL							36.48

PLAN SHEET NO.	LOCATION CL SURVEY WESTERN RD.	REMOVAL OF CONCRETE PAVEMENT 619(B) SY	REMOVAL OF ASPHALT PAVEMENT 619(B) SY	REMOVAL OF CONCRETE DRIVEWAY 619(B) SY	REMOVAL OF ASPHALT DRIVEWAY 619(B) SY	REMOVAL OF CURB 619(B) LF	REMOVAL OF SIDEWALK 619(B) SY	SAWING PAVEMENT 619(C) LF
40	STA. 31+82.42 TO STA. 48+00.00	122	7,608	0	716	481	580	232
41	STA. 48+00.00 TO STA. 75+47.21	243	6,948	417	245	127	0	226
TOTALS		365	14,556	417	961	608	580	458

LOCATION	UNCLASSIFIED EXCAVATION 202(A) CY	EMBANKMENT CY	EMBANKMENT +15%' CY	UNCLASSIFIED BORROW 202(C) CY	EXCESS EXCAVATION CY
WESTERN RD.	13,929	17,299	19,894	5,965	
McELROY RD.	980	11	13	0	967
TOTALS (ROADWAY)	14,909			4,998 *	

\* NOTE: EXCESS EXCAVATION FROM McELROY RD. WAS USED TO OFFSET THE UNCLASSIFIED BORROW FROM WESTERN RD.

PLAN SHEET NO.	STATION/LOCATION	TYPE	WIDTH FT	LENGTH FT	RADII FT	6" CONCRETE DRIVEWAY 610(B) SY
23	STA 49+16.74 RT. WESTERN RD. CRL	COMM. DR. TYPE 2	30.00	29.00	25	126.47
23	STA 51+21.91 RT. WESTERN RD. CRL	COMM. DR. TYPE 2	23.00	34.00	25	116.69
23	STA 52+59.13 RT. WESTERN RD. CRL	COMM. DR. TYPE 2	20.00	43.00	25	125.36
24	STA 56+24.73 RT. WESTERN RD. CRL	COMM. DR. TYPE 2	19.00	43.00	25	120.58
24	STA 57+82.35 RT. WESTERN RD. CRL	COMM. DR. TYPE 2	19.00	43.00	25	120.58
24	STA 61+67.28 RT. WESTERN RD. CRL	COMM. DR. TYPE 2	30.00	43.00	15	154.06
24	STA 67+00.00 RT. WESTERN RD. CRL	COMM. DR. TYPE 2	24.00	43.00	25	144.47
25	STA 82+51.54 RT. WESTERN RD. CRL	COMM. DR. TYPE 2	23.00	43.00	42	194.01
26	STA 84+61.77 RT. WESTERN RD. CRL	COMM. DR. TYPE 2	36.00	42.00	25	197.81
26	STA 87+04.40 RT. WESTERN RD. CRL	COMM. DR. TYPE 2	36.00	29.65	10	123.37
TOTALS						1,423.42

Design		WESTERN ROAD	PAYNE COUNTY
Drawn		<b>SUMMARY OF SHEETS (1)</b> Project No. 31595(04) Sheet No. 9	
Checked			
Approved			
Squad	OLSSON ASSOCIATES		