


I:\Active\0403\COMMON A-B-D\13-SUM PAY QTY.dwg, 7/5/2016 2:57:34 PM, Howard

J.P. NO. 14999(04) 0200 BRIDGE "Q"				
PAY QUANTITIES				
U.S. HIGHWAY 69 SOUTHBOUND OVER WADE WATTS 108'-8 1/2" TYPE IV P.C.B. SPAN 69'-5" CLEAR ROADWAY WITH CONCRETE PARAPETS 0° SKEW, C. STA. 3259+10.79				
ITEM NO.	ITEM	UNIT	TOTAL	
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON (BR-1, 2)	C.Y.	175	
501(G) 6309	CLSM BACKFILL (BR-1)	C.Y.	210	
503(A) 1313	PRESTRESSED CONCRETE BEAMS (TYPE IV) (BR-1)	L.F.	549	
504(A) 1304	APPROACH SLAB (BR-1, 4)	S.Y.	364.1	
504(B) 1305	SAW-CUT GROOVING (BR-1)	S.Y.	735.5	
504(C) 6250	SEALED EXPANSION JOINT (BR-1)	L.F.	70.4	
504(E) 1381	CONCRETE PARAPET (BR-1)	L.F.	32.4	
504(E) 6190	42" F-SHAPED PARAPET (BR-1)	L.F.	170.7	
506(A) 1322	STRUCTURAL STEEL (BR-1)	LB.	380	
507(A) 6170	STAINLESS STEEL FIXED BEARING ASSEMBLY (BR-1, 6)	EA.	5	
507(B) 6174	STAINLESS STEEL EXPANSION BEARING ASSEMBLY (BR-1, 7)	EA.	5	
509 6152	SPECIAL CONCRETE FINISH (BR-1, 8)	S.Y.	119	
509(A) 1326	CLASS AA CONCRETE (BR-1, 9)	C.Y.	102.6	
509(B) 1328	CLASS A CONCRETE (BR-1)	C.Y.	134.9	
510(C) 6138	SLOPE WALL (5") (BR-1)	S.Y.	565	
511 6306	MECHANICAL SPLICES (BR-1)	EA.	317	
511(B) 6010	EPOXY COATED REINFORCING STEEL (BR-1)	LB.	31,360	
514(A) 6011	PILES, FURNISHED (HP12x53) (BR-10)	L.F.	444	
514(B) 6294	PILES, DRIVEN (HP12x53)	L.F.	444	
514(L) 6220	PILE SPLICE, H-PILE (NON-BIDDABLE)	EA.	1	
515(A) 6013	WATER REPELLENT (VISUALLY INSPECTED) (BR-1)	S.Y.	450	
521(A) 6210	PNEUMATICALLY PLACED MORTAR (BR-11)	S.Y.	3.0	
523(A) 6550	SEALER CRACK PREPARATION (BR-1)	L.F.	110.7	
523(B) 6560	SEALER RESIN (BR-1, 12)	GAL.	2	
613(H) 6204	6" PERFORATED PIPE UNDERDRAIN ROUND (BR-1, 14)	L.F.	56	
613(I) 6207	6" NON-PERF. PIPE UNDERDRAIN RND. (BR-15)	L.F.	112	
619(B) 2515	REMOVAL OF BRIDGE ITEM (TYPE A) (BR-16)	EA.	2	
619(B) 2525	REMOVAL OF BRIDGE ITEM (TYPE B) (BR-17)	EA.	2	
619(B) 2535	REMOVAL OF BRIDGE ITEM (TYPE C) (BR-18)	EA.	6	
619(B) 6189	REMOVAL OF EXISTING SLAB (BR-19)	S.Y.	149.9	
619(B) 6252	REMOVAL OF EXISTING PARAPET (BR-20)	L.F.	203.1	
619(B) 6319	REMOVAL OF DECK (BR-21)	S.Y.	28.9	

J.P. NO. 14999(04) 0201 BRIDGE "R"				
PAY QUANTITIES				
U.S. HIGHWAY 69 NORTHBOUND OVER WADE WATTS 108'-8 1/2" TYPE IV P.C.B. SPAN 69'-5" CLEAR ROADWAY WITH CONCRETE PARAPETS 0° SKEW, C. STA. 3259+10.79				
ITEM NO.	ITEM	UNIT	TOTAL	
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON (BR-1, 2)	C.Y.	175	
501(G) 6309	CLSM BACKFILL (BR-1)	C.Y.	210	
503(A) 1313	PRESTRESSED CONCRETE BEAMS (TYPE IV) (BR-1)	L.F.	549	
504(A) 1304	APPROACH SLAB (BR-1, 4)	S.Y.	364.1	
504(B) 1305	SAW-CUT GROOVING (BR-1)	S.Y.	735.5	
504(C) 6250	SEALED EXPANSION JOINT (BR-1)	L.F.	70.4	
504(E) 1381	CONCRETE PARAPET (BR-1)	L.F.	32.4	
504(E) 6190	42" F-SHAPED PARAPET (BR-1)	L.F.	170.7	
506(A) 1322	STRUCTURAL STEEL (BR-1)	LB.	380	
507(A) 6170	STAINLESS STEEL FIXED BEARING ASSEMBLY (BR-1, 6)	EA.	5	
507(B) 6174	STAINLESS STEEL EXPANSION BEARING ASSEMBLY (BR-1, 7)	EA.	5	
509 6152	SPECIAL CONCRETE FINISH (BR-1, 8)	S.Y.	119	
509(A) 1326	CLASS AA CONCRETE (BR-1, 9)	C.Y.	102.6	
509(B) 1328	CLASS A CONCRETE (BR-1)	C.Y.	135.0	
510(C) 6138	SLOPE WALL (5") (BR-1)	S.Y.	565	
511 6306	MECHANICAL SPLICES (BR-1)	EA.	317	
511(B) 6010	EPOXY COATED REINFORCING STEEL (BR-1)	LB.	31,360	
514(A) 6011	PILES, FURNISHED (HP12x53) (BR-10)	L.F.	525	
514(B) 6294	PILES, DRIVEN (HP12x53)	L.F.	525	
514(L) 6220	PILE SPLICE, H-PILE (NON-BIDDABLE)	EA.	1	
515(A) 6013	WATER REPELLENT (VISUALLY INSPECTED) (BR-1)	S.Y.	450	
521(A) 6210	PNEUMATICALLY PLACED MORTAR (BR-11)	S.Y.	3.0	
523(A) 6550	SEALER CRACK PREPARATION (BR-1)	L.F.	110.7	
523(B) 6560	SEALER RESIN (BR-1, 12)	GAL.	2	
613(H) 6204	6" PERFORATED PIPE UNDERDRAIN ROUND (BR-1, 14)	L.F.	56	
613(I) 6207	6" NON-PERF. PIPE UNDERDRAIN RND. (BR-15)	L.F.	112	
619(B) 2515	REMOVAL OF BRIDGE ITEM (TYPE A) (BR-16)	EA.	2	
619(B) 2525	REMOVAL OF BRIDGE ITEM (TYPE B) (BR-17)	EA.	2	
619(B) 2535	REMOVAL OF BRIDGE ITEM (TYPE C) (BR-18)	EA.	6	
619(B) 6189	REMOVAL OF EXISTING SLAB (BR-19)	S.Y.	149.9	
619(B) 6252	REMOVAL OF EXISTING PARAPET (BR-20)	L.F.	203.1	
619(B) 6319	REMOVAL OF DECK (BR-21)	S.Y.	28.9	

NOTE:  
FOR PAY ITEM NOTES,  
SEE SHEET 14.



Design	CEG		<b>U.S. HIGHWAY 69 - McALESTER</b> <b>SUMMARY OF BRIDGE PAY QUANTITIES</b> <b>SHEET 1 OF 2</b> BRIDGE "Q" AND BRIDGE "R" JOB PIECE NO. 14999(04)      SHEET NO. 13
Drawn	KGL	HEJ	
Checked	ADT		
Approved	CEG		
Squad	WEA		