


SUMMARY OF TEMPORARY EROSION CONTROL

SHEET NUMBER	STATION (CTR. LINE OR REF. LINE)	DESCRIPTION			221(G) 2801 TEMPORARY SILT FENCE			
					221(D) 2803 TEMPORARY SEDIMENT FILTER		221(F) 0100 TEMPORARY SILT DIKE	
					LF	EA	LF	CY
		LEFT	CENTER	RIGHT				
24	STA 3220+00.00 TO STA 3250+00.00, US-69	X						10
24	STA 3220+00.00 TO STA 3250+00.00, US-69		X					7
24	STA 3220+00.00 TO STA 3250+00.00, US-69			X				9
24	STA 3228+00.00, US-69		X					16
24	STA 3228+00.00, US-69	X						16
24	STA 3232+00.00, US-69		X					16
24	STA 3232+00.00, US-69	X		X				32
24	STA 3236+00.00, US-69	X		X				32
24	STA 3240+00.00, US-69		X					16
24	STA 3240+00.00, US-69			X				16
24	STA 3243+00.00, US-69			X				16
24	STA 3249+00.00, US-69	X		X				32
25	STA 3250+00.00 TO STA 3265+00.00, US-69	X						10
25	STA 3250+00.00 TO STA 3265+00.00, US-69		X					1
25	STA 3250+00.00 TO STA 3265+00.00, US-69		X					2
25	STA 3250+00.00 TO STA 3265+00.00, US-69			X				10
25	STA 3252+00.00, US-69		X					16
25	STA 3255+00.00, US-69		X					16
25	STA 3261+00.00, US-69			X				16
25	STA 3260+34.37, US-69			X				4
25	STA 3263+00.00, US-69			X				16
25	STA 3256+50.00 TO STA 3258+00.00, US-69	X						180
25	STA 3258+00.00 TO STA 3265+00.00, US-69	X						265
25	STA 3258+00.00 TO STA 3265+00.00, US-69	X						570
25	STA 3255+00.00 TO STA 3265+00.00, US-69			X				840
26	STA 3265+00.00 TO STA 3272+41.00, US-69			X				920
TOTAL					2775	49	256	4

SUMMARY OF EROSION CONTROL

SHEET NUMBER	STATION (CTR. LINE OR REF. LINE)	DESCRIPTION	WORK AREA	230(A) 2806 SOLID SLAB SODDING	
				SY	
24	STA 3220+00.00 TO STA 3250+00.00, US-69	LEFT SIDE	1		6,325
24	STA 3220+00.00 TO STA 3250+00.00, US-69	INSIDE GRASS MEDIAN	2		9,325
24	STA 3220+00.00 TO STA 3250+00.00, US-69	RIGHT SIDE	3		6,845
25	STA 3250+00.00 TO STA 3265+00.00, US-69	LEFT SIDE	1		11,010
25	STA 3250+00.00 TO STA 3265+00.00, US-69	INSIDE GRASS MEDIAN	2		2,985
25	STA 3250+00.00 TO STA 3265+00.00, US-69	RIGHT SIDE	3		13,520
26	STA 3265+00.00 TO STA 3280+00.00, US-69	LEFT SIDE	1		45
26	STA 3265+00.00 TO STA 3280+00.00, US-69	RIGHT SIDE	3		4,510
TOTAL					54,565



EROSION CONTROL TYPICAL SECTION

VEGETATIVE MULCHING WILL BE USED FOR TEMPORARY EROSION CONTROL

REMOVAL QUANTITIES

ITEM	DESCRIPTION	UNIT	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY TOTAL
			STA 3205+00 TO STA 3220+00	STA 3220+00 TO STA 3235+00	STA 3235+00 TO STA 3250+00	STA 3250+00 TO STA 3265+00	STA 3265+00 TO STA 3280+00	
619(B) 0291	REMOVAL OF HEADWALL	EA			1	5		6
619(B) 4726	REMOVAL OF CURB AND GUTTER	LF			348	2,452		2,800
619(B) 4727	REMOVAL OF CONCRETE PAVEMENT	SY		509		4,762	50	5,321
619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	SY	1,129	6,066	13,514	12,419	715	33,843
619(B) 4766	REMOVAL OF CONCRETE DRIVEWAY	SY				889		889
619(B) 4780	REMOVAL OF GUARDRAIL	LF				1,428	96	1,524
619(B) 4792	REMOVAL OF SIDEWALK	SY				458		458
619(B) 5881	REMOVAL OF CONCRETE DITCH LINER	LF				1,175	160	1,335

SUMMARY OF DITCH QUANTITIES

LOCATION DESCRIPTION OR LOCATION	PAVED DITCH AND FLUME				
	DESIGN	LENGTH	BOTTOM WIDTH	CURTAIN WALLS	CLASS 'C' CONC.
		FT	FT	EA	CY
STA 3256+50 TO 3258+21, LT.	DC-3, DES. 2A	179	8	3	32.33
STA 3258+34.36, LT. N1 TO N2	DC-3, DES. 2A	25	8	2	4.88
STA 3257+08 TO 3258+22, RT.	DC-3, DES. 2A	114	4	3	15.06
TOTALS					52.27



Survey	CKS	U.S. 69 - COMANCHE AVENUE SUMMARY SHEET (ROADWAY) JOB PIECE NO. 14999(04)	PITTSBURG COUNTY SHEET NO. 19
Drawn	CKD		
Checked	CKE		
Approved			
Squad	C & K		