

SUMMARY OF BARRIER QUANTITIES			
LOCATION			
SHEET NUMBER	STATION (CTR. LINE OR REF. LINE)	OFFSET DISTANCE	CONCRETE LONGITUDINAL BARRIER, DESIGN 1
		FT	LF
33	STA 3257+53.00 TO 3258+25.35, US-69	CRL	72.35
33	STA 3256+83.33 TO 3258+25.35, US-69 ①	74 TO 72 RT	142.08
TOTALS			214.43

① PROVIDE 5'-0" LONG X 3" HIGH DRAIN OPENINGS AT 10' CENTERS.

SUMMARY OF GUARDRAIL				
LOCATION				
STATION (CTR. LINE OR REF. LINE)	623(A) 0932 BEAM GUARDRAIL W-BEAM SINGLE	623(F) 8300 GUARDRAIL TRAIL END TURNDOWN (31")	623(I) 8700 GUARDRAIL BRIDGE CONN-THREE BEAM (31")	853 9066 GUARDRAIL DELINEATORS (TYPE 1, CODE 1)
	LF	EA	EA	EA
3259+95.62 TO 3265+51.25 US 69 CRL, LT	525.00		2	11
3259+95.62 TO 3265+51.25 US 69 CRL, RT	525.00		2	11
3267+74.23 TO 3270+99.23 US 69 CRL, RT	275.00	1	1	7
TOTALS	1,325.00	1	5	29

NOTE: GUARDRAIL WIDENING QUANTITIES INCLUDED IN SUMMARY OF SURFACING QUANTITIES.

SUMMARY OF EARTHWORK QUANTITIES						
LOCATION						
SHEET NUMBER	STATION (CTR. LINE OR REF. LINE)	202(A) 01B3 UNCLASSIFIED EXCAVATION	EMBANKMENT +15% (NOT A PAY QTY.)	EXCESS EXCAVATION (NOT A PAY QTY.)	202(D) 01B4 UNCLASSIFIED BORROW	① WASTE (NOT A PAY QTY.)
		CY	CY	CY	CY	CY
33	STA 3252+29.35 TO STA 3258+75.54, US-69 PHASE 1A	3,676	4,344	-	668	-
33	STA 3259+40.81 TO STA 3265+00.00, US-69 PHASE 1A	2,011	23,300	-	21,289	-
33	STA 197+30.00 TO STA 201+92.05, WADE WATTS PHASE 1	2,242	0	-	0	-
34	STA 3265+00.00 TO STA 3272+41.00, US-69 PHASE 1A	721	2,699	-	1,978	-
31	STA 3227+70.00 TO STA 3235+00.00, US-69 PHASE 1B	3,106	422	2,684	0	-
32	STA 3235+00.00 TO STA 3250+00.00, US-69 PHASE 1B	4,875	451	4,424	0	-
33	STA 3250+00.00 TO STA 3258+25.35, US-69 PHASE 1B	4,029	5,073	-1,044	0	6,064
31	STA 3228+50.00 TO STA 3235+00.00, US-69 PHASE 2	2,908	103	2,805	0	-
32	STA 3235+00.00 TO STA 3250+00.00, US-69 PHASE 2	3,778	1,022	2,756	0	-
33	STA 3250+00.00 TO STA 3255+00.00, US-69 PHASE 2	1,080	881	199	0	5,760
TOTALS		28,426	-	-	23,935	11,824

**EARTHWORK NOTES**

① WASTE = 11,824 CY. THIS MATERIAL IS TO BECOME THE PROPERTY OF AND DISPOSED BY THE CONTRACTOR IN A MANNER APPROVED BY THE ENGINEER.

*Robin D. Sawell*  


Survey	CKS	U.S. 69 - COMANCHE AVENUE	PITTSBURG COUNTY
Drawn	CKD	<b>SUMMARY SHEET (ROADWAY)</b>	
Checked	CKE		
Approved			
Squad	C & K		
		JOB PIECE NO. 14999(04)	SHEET NO. 20