

SUMMARY OF QUANTITIES																	
ITEM	UNIT	BRIDGE "Q"								BRIDGE "R"							
		PHASE 1A				PHASE 2A			TOTAL	PHASE 1A				PHASE 2A			TOTAL
		ABUTMENTS	SUPERSTR.	APP. SLAB	SLOPE WALL	SUPERSTR.	APP. SLAB	SLOPE WALL		ABUTMENTS	SUPERSTR.	APP. SLAB	SLOPE WALL	SUPERSTR.	APP. SLAB	SLOPE WALL	
SUBSTRUCTURE EXCAVATION COMMON	C.Y.	175							175	175							175
CLSM BACKFILL	C.Y.	210							210	210							210
PRESTRESSED CONCRETE BEAMS (TYPE IV)	L.F.		549						549		549						549
APPROACH SLAB	S.Y.			236.6			127.5		364.1			236.6			127.5		364.1
SAW-CUT GROOVING	S.Y.		386.5	226.6			122.4		735.5		386.5	226.6			122.4		735.5
SEALED EXPANSION JOINT	L.F.		31.9			38.5			70.4		31.9			38.5			70.4
CONCRETE PARAPET	L.F.					1.3	31.1		32.4					1.3	31.1		32.4
42" F-SHAPED PARAPET	L.F.		110.7	60.0					170.7		110.7	60.0					170.7
STRUCTURAL STEEL	LB.	30	350						380	30	350						380
STAINLESS STEEL FIXED BEARING ASSEMBLY	EA.		5						5		5						5
STAINLESS STEEL EXPANSION BEARING ASSEMBLY	EA.		5						5		5						5
SPECIAL CONCRETE FINISH	S.Y.	119							119	119							119
CLASS AA CONCRETE	C.Y.		99.2			3.4			102.6		99.2			3.4			102.6
CLASS A CONCRETE	C.Y.	134.9							134.9	135.0							135.0
SLOPE WALL (5")	S.Y.							565	565							565	565
MECHANICAL SPLICES	EA.		317						317		317						317
EPOXY COATED REINFORCING STEEL	LB.	10,100	20,680			580			31,360	10,100	20,680			580			31,360
PILES, FURNISHED (HP12x53)	L.F.	444							444	525							525
PILES, DRIVEN (HP12x53)	L.F.	444							444	525							525
WATER REPELLENT (VISUALLY INSPECTED)	S.Y.	224	183	29		1	13		450	224	183	29		1	13		450
PNEUMATICALLY PLACED MORTAR	S.Y.	3.0							3.0	3.0							3.0
SEALER CRACK PREPARATION	L.F.		110.7						110.7		110.7						110.7
SEALER RESIN	GAL.		2						2		2						2
6" PERFORATED PIPE UNDERDRAIN ROUND	L.F.	56							56	56							56
6" NON-PERF. PIPE UNDERDRAIN RND.	L.F.	112							112	112							112
REMOVAL OF BRIDGE ITEM (TYPE A)	EA.	2							2	2							2
REMOVAL OF BRIDGE ITEM (TYPE B)	EA.				2				2				2				2
REMOVAL OF BRIDGE ITEM (TYPE C)	EA.					6			6					6			6
REMOVAL OF EXISTING SLAB	S.Y.			22.4			127.5		149.9			22.4			127.5		149.9
REMOVAL OF EXISTING PARAPET	L.F.	46.0	110.2	14.5		1.3	31.1		203.1	46.0	110.2	14.5		1.3	31.1		203.1
REMOVAL OF DECK	S.Y.		23.0			5.9			28.9		23.0			5.9			28.9

Design	CEG		U.S. HIGHWAY 60 - McALESTER				
Drawn	KGL	HEJ	SUMMARY OF QUANTITIES				
Checked	ADT	DMH	WADE WATTS AVENUE				
Approved	CEG		BRIDGE "Q" SOUTHBOUND, BRIDGE "R" NORTHBOUND				
Squad	WEA		JOB PIECE NO. 14999(04)		SHEET NO. B4		