

26346(04) PUSHMATAHA CO.

PAY QUANTITIES

SECTION 0100 – ROADWAY US 271

ITEM	NO.	DESCRIPTION	NOTES	UNIT	QUANTITY
201(A)	0102	CLEARING AND GRUBBING		LSUM	1.
202(A)	0183	UNCLASSIFIED EXCAVATION	(R-1)	CY	34511.
202(D)	0184	UNCLASSIFIED BORROW	(R-1)	CY	67215.
205(A)	4229	TYPE A-SALVAGED TOPSOIL	(R-5)(R-7)	LSUM	1.
221(C)	2801	TEMPORARY SILT FENCE	(1)	LF	2302.
221(D)	2803	TEMPORARY SEDIMENT FILTER	(1)	EA	4.
221(F)	0100	TEMPORARY SILT DIKE	(1)	LF	392.
221(G)	0153	TEMPORARY ROCK FILTER DAM TYPE 3	(1)	CY	76.
230(A)	2806	SOLID SLAB SODDING	(2)(R-7)(R-8)	SY	63960.
232(A)	2813	SEEDING METHOD A		AC	15.
233(A)	2817	VEGETATIVE MULCHING	(R-11)	AC	13.
241	2832	MOWING	(R-16)	AC	27.
303(A)	2100	AGGREGATE BASE TYPE A		CY	9358.
325	5271	SEPARATOR FABRIC		SY	25408.
326(B)	0100	GEOGRID REINFORCEMENT	(8)	SY	35408.
402(E)	0225	TRAFFIC BOUND SURFACE COURSE TYPE E	(R-25)	TON	4948.
407(B)	0250	TACK COAT		GAL	3046.
408	5774	PRIME COAT	(R-28)	GAL	6900.
411(B)	5945	SUPERPAVE, TYPE S3(PG 64-22 OK)	(R-32)	TON	5549.
411(C)	5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	(R-32)	TON	2320.
412	5267	COLD MILLING PAVEMENT	(R-34)	SY	477.
501(A)	0313	STRUCTURAL EXCAVATION UNCLASSIFIED		CY	47.18.
504(D)	6245	CONCRETE RAIL (TR-4)	(9)	LF	144.00.
509(A)	0319	CLASS AA CONCRETE		CY	191.63.
509(D)	0325	CLASS C CONCRETE	(3)	CY	40.28.
510(D)	6341	MSE RETAINING WALL	(4,5,6)	SY	144.80.
510(D)	0350	(SP)GRAFFITI TREATMENT	(4)	SF	1017.
511(A)	0332	REINFORCING STEEL		LB	26089.
601(A)	0297	TYPE I PLAIN RIPRAP		TON	97.
601(I)	6312	FILTER FABRIC (RIPRAP)		SY	290.
611(G)	6000	INLET (SMD-TYPE 1)		EA	4.
613(A)	0491	18" R.C.PIPE CLASS III		LF	393.
613(A)	0493	30" R.C.PIPE CLASS III		LF	21.
613(H)	0500	8" PERFORATED PIPE UNDERDRAIN ROUND	(7)	LF	1000.
613(I)	1097	8" NON-PERF.PIPE UNDERDRAIN RND.	(7)	LF	1000.
613(L)	5726	18" PREFAB. CULVERT END SECTION, ROUND		EA	2.
613(L)	5732	30" PREFAB. CULVERT END SECTION, ROUND		EA	1.
613(S)	1186	STANDARD BEDDING MATERIAL, CLASS B		CY	184.
613(V)	1180	TRENCH EXCAVATION		CY	317.
619(A)	0920	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	(R-48)(R-49)	LSUM	1.
619(B)	4728	REMOVAL OF ASPHALT PAVEMENT	(R-49)(R-50)	SY	13376.
619(B)	4780	REMOVAL OF GUARDRAIL	(R-49)	LF	1399.
623(A)	0932	BEAM GUARDRAIL W-BEAM SINGLE		LF	938.
623(G)	8590	GUARDRAIL END TREATMENT (31")		EA	4.
623(I)	8700	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")		EA	4.
624(C)	4459	FENCE-STYLE SWF (5 BARBED WIRE)	(R-52)(R-53)	LF	2989.
853	9033	DELINEATORS(TYPE 2, CODE 1)		EA	21.

26346(04) PUSHMATAHA CO.

PAY QUANTITIES

SECTION 0600 – STAKING US 271

ITEM	NO.	DESCRIPTION	NOTES	UNIT	QUANTITY
642(B)	0096	CONSTRUCTION STAKING LEVEL II		LSUM	1

26346(04) PUSHMATAHA CO.

PAY QUANTITIES

SECTION 0640 – CONSTRUCTION US 271

ITEM	NO.	DESCRIPTION	NOTES	UNIT	QUANTITY
220	2800	SWPPP DOCUMENTATION AND MANAGEMENT		LSUM	1
641	1552	MOBILIZATION		LSUM	1

2014-03-18 H:\202957 US-271\ACAD\202957\PO01.dwg

DESIGN	KS		OKLAHOMA DEPARTMENT OF TRANSPORTATION POE & ASSOCIATES PAY QUANTITIES AND NOTES (ROADWAY) STATE JOB NO. 26346(04) SHEET NO. 5 US-271 OVER KIAMICHI RIVER PUSHMATAHA COUNTY
DRAWN	KS		
CHECKED	BW		
APPROVED	RA		
SQUAD			