

FED. ROAD DIST. NO.	STATE	JOB PIECE NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
6	OKLA.				
DESCRIPTION		REVISIONS		DATE	

SUMMARY OF SURFACING

STATION TO STATION	AGGREGATE BASE TYPE A 303(A)	SEPARATOR FABRIC 325	GEOGRID REINFORCEMENT 326(B)	TRAFFIC BOUND SURFACE COURSE TYPE E 402(E)	TACK COAT 407(B)	PRIME COAT 408	SUPERPAVE. TYPE S3 (PG 64-22 OK) 411(B)	SUPERPAVE TYPE S4 (PG 64-22 OK) 411(C)	COLD MILLING PAVEMENT 412	
	CY	SY	SY	TON	GAL	GAL	TON	TON	SY	
US 271										
93+75.00	107+00.00	2,137	6,401	6,401	987	608	1,159	1,167	457	477
113+32.67	121+00.00	1,765	5,149	5,149	728	512	959	972	386	-
121+00.00	135+00.00	3,220	9,394	9,394	1,329	933	1,750	1,772	702	-
135+00.00	142+36.31	1,517	4,464	4,464	659	435	828	827	326	-
Gilley Rd.										-
200+50.00	202+84.73	-	-	-	-	76	197	149	58	-
DETOUR										-
95+40.06	102+70.81	266	-	-	61	52	289	59	59	-
136+75.00	144+62.32	633	-	-	1,099	135	1,132	151	151	-
	TOTALS	9,538	25,408	25,408	4,863	2,751	6,314	5,097	2,139	477

SUMMARY OF FENCING

STATION TO STATION	FENCE - STYLE SWF (5 BARBED WIRE) 624(C)
	L.F.
95+00.00 TO 107+68.79	1,269
117+09.67 TO 125+86.81	877
135+84.70 TO 144+28.02	843
TOTALS	2,989

SUMMARY OF EARTHWORK QUANTITIES

P H A S E	ALIGNMENT	STATION TO STATION	UNCLASSIFIED EXCAVATION 202(A)	EMBANKMENT (+15%)	UNCLASSIFIED BORROW 202 (D)
			CY	CY	CY
1	SOUTH DETOUR	95+40.06 TO 102+70.81	252	323	
	NORTH DETOUR	136+75.00 TO 144+62.32	282	6,722	
	PHASE 1 TOTALS		534	7,045	6,511
2	U.S. 271	96+47.91 TO 107+23.22	12,738	3,885	
	BRIDGE "A"	107+23.22 TO 113+09.42	6,994	2,111	
	U.S. 271	113+09.42 TO 142+36.31	9,251	78,125	
	PHASE 2 TOTALS		28,983	84,121	55,138
3	U.S. 271	96+47.91 TO 107+23.22	725	1,105	
	BRIDGE "A"	107+23.22 TO 113+09.42	1,950	730	
	U.S. 271	113+09.42 TO 142+36.31	1,101	3,979	
	GILLEY RD.	200+50.00 TO 202+84.73	1,218	4,746	
	PHASE 3 TOTALS		4,994	10,560	5,566
GRAND TOTALS			34,511	101,726	67,215

SUMMARY OF REMOVALS

STATION TO STATION	REMOVAL OF ASPHALT PAVEMENT 619(B)	REMOVAL OF GUARDRAIL 619(B)	SAWING PAVEMENT*
	S.Y.	L.F.	L.F.
US 271			
97+24.93 TO 110+00.00	3,258	424	27
110+00.00 TO 125+00.00	2,606	975	-
125+00.00 TO 137+00.00	3,667	-	-
137+00.00 TO 141+43.38	1,353	-	27
DETOURS			
95+40.06 TO 102+70.81	695		
136+75 TO 144+62.32	1,797		
TOTALS	13,376	1,399	54

* INCLUDED IN COST OF OTHER ITEMS

2014-02-25 11:20:2957 US-271-ACAD\202957\S101.dwg

DESIGN	KS		OKLAHOMA DEPARTMENT OF TRANSPORTATION POE & ASSOCIATES
DRAWN	KS		
CHECKED	BW		
APPROVED	RA		
SQUAD			
SUMMARY OF QUANTITIES			
STATE JOB NO. 26346(04) SHEET NO. 11			
US-271 OVER KIAMICHI RIVER			PUSHMATAHA COUNTY