



**I-244 TURNING ROADWAY TYPICAL SECTION NO. 3**  
**EASTBOUND (TWO LANE - ONE WAY RAMP)**  
 NOT TO SCALE  
 RAMP B  
 RAMP B STA. 759+76.68 TO STA. 768+72.92

PAVT. STRUCTURE	DRIVING LANES AND INSIDE SHOULDER	OUTSIDE SHOULDER
SURFACE COURSE	11" DOWEL JOINTED P.C. CONCRETE	11" TIED PLAIN JOINTED P.C. CONCRETE
INTERMEDIATE COURSE	4" OPEN GRADED BITUMINIOUS BASE	4" OPEN GRADED BITUMINIOUS BASE
BASE COURSE	8" AGGREGATE BASE TYPE 'A'	8" AGGREGATE BASE TYPE 'A'
SUBGRADE	8" STABILIZED SUBGRADE	8" STABILIZED SUBGRADE

- ① BACKFILL NOTE:  
THIS AREA IS TO BE BACKFILLED AND COMPACTED AS PART OF FINISHING OPERATIONS. BACKFILL MATERIAL TO BE TBC TYPE "E", AND PAID AS SUCH. MEASUREMENT BASED ON THEORETICAL CROSS SECTION.
- ② TOPSOIL NOTE:  
THE CONTRACTOR SHALL STRIP ALL OF THE AVAILABLE TOPSOIL, STOCKPILE IT, AND REPLACE IT IN ACCORDANCE WITH SECTION 205 OF THE STANDARD SPECIFICATIONS. RESERVED TOPSOIL SHALL BE SPREAD APPROX. 5" THICK FIRST ON THE COMPLETED SLOPES OF THE CUT SECTION, AND THE REMAINDER ON COMPLETED FILL SLOPES OR OTHER PRIORITY AREAS LOCATED BY THE ENGINEER. THE GRADING LINE AS SHOWN ON THE TYPICAL AND CROSS SECTIONS IS TO THE TOP OF TOPSOIL. EARTHWORK QUANTITIES WERE NOT ADJUSTED FOR SALVAGED TOPSOIL AND THE TOPSOIL QUANTITY IS INCLUDED IN THE MASS LINE BALANCE AND EARTHWORK SUMMARY.
- ③ DISTANCE MEASURED VERTICALLY FROM EDGE OF FINISHED SHOULDER.
- ④ SEE ROUNDING DETAIL SHEET 6 .
- ⑤ CONSTRUCT MEDIAN BARRIER. SEE ODOT STD. CLB-1-2.
- ⑦ REVOLVE THE SUPERELEVATION ABOUT THE PROFILE GRADE POINT.
- ⑪ CONSTRUCT F-SHAPED PARAPET. SEE DETAIL SHEET 11 FOR REINFORCEMENT DETAILS.



**EDGE TREATMENT NO. 3-1**  
 NOT TO SCALE  
 RAMP B STA. 762+61.87 TO STA. 768+72.92



**I-244 TURNING ROADWAY TYPICAL SECTION NO. 4**  
**EASTBOUND (TWO LANE - ONE WAY RAMP)**  
 NOT TO SCALE  
 RAMP B  
 RAMP B STA. 768+72.92 TO STA. 772+35.13

PAVT. STRUCTURE	DRIVING LANES	OUTSIDE SHOULDER
SURFACE COURSE	11" DOWEL JOINTED P.C. CONCRETE	11" TIED PLAIN JOINTED P.C. CONCRETE
INTERMEDIATE COURSE	4" OPEN GRADED BITUMINIOUS BASE	4" OPEN GRADED BITUMINIOUS BASE
BASE COURSE	8" AGGREGATE BASE TYPE 'A'	8" AGGREGATE BASE TYPE 'A'
SUBGRADE	8" STABILIZED SUBGRADE	8" STABILIZED SUBGRADE

DESIGN	DLT	8/12	TULSA & ROGERS COUNTIES
DRAWN	TML	8/12	
CHECKED	KMM	6/16	
APPROVED			
SQUAD	<b>GARVER</b>		

STATE JOB NO. 21899(04) SHEET NO. 8