

FED. ROAD DIST. NO.	STATE	JOB PIECE NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
6	OKLA.	21899(04)			

DESCRIPTION	REVISIONS	DATE
Updated Quantity		08/22/2016
Updated Quantity		08/24/2016



21899(04) 0200 BRIDGE "A"				
ITEM	DESCRIPTION	UNIT	QUANTITY	
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON (BR-1)	CY	115.700	⚠
501(G) 6309	CLSM BACKFILL (BR-1)	CY	251.000	
503(A) 1312	PRESTRESSED CONCRETE BEAMS (TYPE III) (BR-1)	LF	440.000	
503(A) 1313	PRESTRESSED CONCRETE BEAMS (TYPE IV) (BR-1)	LF	1,535.400	
504(A) 1304	APPROACH SLAB (BR-1)	SY	368.000	
504(B) 1305	SAW-CUT GROOVING (BR-1)	SY	1,918.600	
504(E) 6190	42" F-SHAPED PARAPET (BR-1)	LF	664.000	
506(A) 1322	STRUCTURAL STEEL (BR-1)	LB	3,126.000	
507(A) 6170	STAINLESS STEEL FIXED BEARING ASSEMBLY (BR-1)	EA	14.000	
507(A) 6172	WEATHERING STEEL FIXED BEARING ASSEMBLY (BR-1)	EA	14.000	
507(B) 6174	STAINLESS STEEL EXPANSION BEARING ASSEMBLY (BR-1)	EA	28.000	
507(C) 6282	ELASTOMERIC BEARING PADS (BR-1)	EA	42.000	
509 6152	SPECIAL CONCRETE FINISH (BR-1)	SY	166.000	⚠
509(E) 1333	CLASS P CONCRETE (BR-1)	CY	13.730	⚠
509(A) 1326	CLASS AA CONCRETE (BR-1)	CY	628.300	⚠
509(B) 1328	CLASS A CONCRETE (BR-1)	CY	360.50	⚠
510(C) 6138	SLOPE WALL (5")	SY	2,872.300	
511(A) 1332	REINFORCING STEEL (BR-1)	LB	4,231.000	⚠
511(B) 6010	EPOXY COATED REINFORCING STEEL (BR-1)	LB	342,529.000	⚠
514(A) 6010	PILES, FURNISHED (HP 10X42)	LF	648.000	
514(B) 6292	PILES, DRIVEN (HP 10X42)	LF	648.000	
514(K) 6260	(PL) PILOT HOLES	LF	600.000	
514(L) 6220	PILE SPLICE, H-PILE (NON-BIDDABLE)	EA	1.000	
515(A) 6013	WATER REPELLENT (VISUALLY INSPECTED) (BR-1)	SY	2,269.000	⚠
516(A) 6096	DRILLED SHAFTS 60" DIAMETER	LF	192.000	
516(C) 6200	CROSSHOLE SONIC LOGGING	EA	3.000	
523(A) 6550	SEALER CRACK PREPARATION (BR-1)	LF	419.400	
523(B) 6560	SEALER RESIN (BR-1)	GAL	3.600	
613(H) 6204	6" PERFORATED PIPE UNDERDRAIN ROUND (BR-1)	LF	670.000	
613(I) 6207	6" NON-PERF. PIPE UNDERDRAIN RND.	LF	58.000	
619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	LSUM	1.000	

BR-1:
 Payment for this item will be based on the plan quantities only. See Section 109.01.B of the 2009 Standard Specifications.

145TH OVER I-44 BRIDGE "A"	TULSA & ROGERS COUNTIES	DESIGN	MJY	2/14
SUMMARY OF PAY QUANTITIES AND NOTES (BRIDGE) (SHEET 2 OF 2)		DETAIL	SJL	2/14
		CHECK	MJY	10/14
		GARVER		
STATE OF OKLAHOMA	DEPARTMENT OF TRANSPORTATION			
		JOB PIECE NO. 21899(04)		SHEET NO. 15