REVISIONS		
REV NO	DESCRIPTION	DATE
1	PAGE ADDED	8/22/16

JP# 21899(04)		TOTALS	ITS-06 - I-44 & 145TH E AVE REMOVAL SHEET	ITS 07 - DYNAMIC MESSAGE SIGN I-44 & 165TH E AVE	ITS-10 - DYNAMIC MESSAGE SIGN US-75 & E 44TH ST N	ITS-12 - DYNAMIC MESSAGE SIGN I-44 & N 225TH E AVE																AS DIRECTED BY ENGINEER
DESCRIPTION																						
MACHINE GRADING	LF	270			135	135																
(PL) TRAFFIC BOUND SURFACE COURSE	TON	1157			637	520																
CLASS A CONCRETE	CY	148			62	86																
CLASS C CONCRETE	CY	21			21																	
DRILLED SHAFTS 48" DIAMETER	LF	85		42.5		42.5																
21" X 15" CORR. GALV. STEEL PIPE	LF	370			100	270																
TYPE A6 CULVERT END TREATMENT	EA	6			2	4																
REMOVAL OF CONCRETE MEDIAN BARRIER	LF	100		100																		
1 1/2" HDPE CONDUIT BORED	LF	120				120																
2" HDPE CONDUIT BORED	LF	280		160	20	100																
3" HDPE CONDUIT BORED	LF	50				50																
1 1/2" HDPE CONDUIT TRENCHED	LF	4080				4080																
2" HDPE CONDUIT TRENCHED	LF	1280		1000	120	160																
3" HDPE CONDUIT TRENCHED	LF	140			50	90																
GROUND BOX (R48)	EA	8		3	2	3																
PULL BOX(SIZE II)	EA	1				1																
REINFORCING STEEL	LB	1507			1507																	
(PL) REMOVE & RESET OVERHEAD SIGN STRUCTURE	EA	1	1																			
(PL) REMOVE & RESET /RELOCATE ITS EQUIPMENT	EA	1	1																			
SERVICE POLE	EA	2			1	1																
1/C NO.0 ELECTRICAL CONDUCTOR	LF	900		300	150	450																
(SP) FIBER OPTIC CABLE, 24 SMF	LF	2500		200		2300																
(SP) FIBER OPTIC PATCH PANEL, 24 PORT	EA	2		1		1																
(SP) FIBER OPTIC CABLE SPLICE	EA	16		8		8																
(SP) FIBER OPTIC CABLE TERMINATION	EA	16		8		8																
(SP) SHIELD ISOLATION PEDESTAL	EA	1				1																
(SP) FIBER OPTIC ROUTE SIGN & INSTALLATION	EA	6				6																
(PL) FIBER OPTIC & COMMUNICATION EQUIPMENT	LSUM	1																				1
(PL)INSTALLATION OF COMMUNICATION CABLE	LF	1050		650	200	200																
(SP) CABINET	EA	3		1	1	1																
UPRIGHTS FOR OVERHEAD SIGN STRUCTURE	EA	2			2																	
OVHD.SN.STR.TYPE D ALUM./G.STL	EA	2			1	1																
SAND FILLED IMPACT ATTENUATION MODULE	EA	95			57	38																
DELIVERY OF PORTABLE LONGITUDINAL BARRIER	LF	250		250																		
RELOCATION OF PORTABLE LONGTUDINAL BARRIER	LF	125		125																		
(SP)LED DYNAMIC MESSAGE SIGN FIELD EQUPMENT(18 INCH)	EA	4		2		2																
(SP)LED D.M.S SYSTEM SUPPORT EQUIPMENT	LSUM	1																				1

SUMMARY OF QUANTITIES SHEET
(ITS)

DESIGN	JEK	7/13/16
CHECKED	JS	7/13/16
APPR.	JS	7/13/16
MAINTENANCE / ITS		
JARED SCHWENNESEN		

STATE OF OKLAHOMA	DEPARTMENT OF TRANSPORTATION		
	DIVISION 8	STATE JOB NO. 21899(04)	SHT ITS-03