

DESCRIPTION	REVISIONS	DATE

### GENERAL CONSTRUCTION NOTES

ALL MATERIALS AND CONSTRUCTION SHALL CONFORM TO THE 2009 STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION. OKLAHOMA DEPARTMENT OF TRANSPORTATION, EXCEPT AS OTHERWISE NOTED ON THE DRAWINGS.

IN ACCORDANCE WITH THE OKLAHOMA UNDERGROUND FACILITIES DAMAGE PREVENTION ACT THE CONTRACTOR SHALL NOTIFY THE OKLAHOMA ONE-CALL SYSTEM, INC. 48 HOURS PRIOR TO BEGINNING EXCAVATION. OKLAHOMA ONE-CALL SYSTEM, INC. "CALL OKIE" 1-800-522-6543 OR 811.

THE CONTRACTOR IS TO MAKE EVERY EFFORT TO LOCATE AND PROTECT ALL UTILITIES AND STRUCTURES, WHETHER SHOWN OR NOT, PRIOR TO ANY CONSTRUCTION OPERATIONS. THE CONTRACTOR SHALL SO CARRY ON CONSTRUCTION WITHOUT CAUSING DAMAGE TO ANY UTILITIES OR STRUCTURES REMAINING IN PLACE.

ALL TREES, BRUSH, AND OTHER DEBRIS THAT MIGHT INTERFERE WITH THE FLOW OF WATER IS TO BE CLEANED OUT TO THE RIGHT-ON-WAY LINE AT EACH STRUCTURE AND BRIDGE, IN A MANNER APPROVED BY THE ENGINEER. ALL COST TO BE INCLUDED IN THE PRICE BID FOR OTHER ITEMS OF WORK.

ANY SODDED AREAS DISTURBED OUTSIDE THE CONSTRUCTION LIMITS SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.

### SPECIAL PAY ITEM NOTES

- ESTIMATED QUANTITY TO BE USED AS DIRECTED BY THE ENGINEER TO ADJUST PROFILE OF PAVEMENT ADJACENT TO NEW APPROACH SLAB.
- INCLUDES UNCLASSIFIED EXCAVATION AS NECESSARY TO PLACE NEW MATERIAL.

JP 28880(04)					
SUMMARY OF PAY QUANTITIES					
0100 ROADWAY					
ITEM NUMBER		DESCRIPTION	NOTES	UNIT	ESTIMATED QUANTITY
303(A)	2100	AGGREGATE BASE TYPE A	(1)	CY	92.0
307(K)	4300	STABILIZED SUBGRADE	(1)	SY	411.0
317	4270	CEMENT TREATMENT BASE	(1)	SY	411.0
325	5271	SEPARATOR FABRIC	(1)	SY	411.0
414(A)	0210	P.C. CONCRETE PAVEMENT (PLACEMENT)	(1)	SY	411.0
414(G)	5275	P.C. CONCRETE FOR PAVEMENT	(1)	CY	114.0
619(B)	4727	REMOVAL OF CONCRETE PAVEMENT	(1, 2)	SY	411.0

3/19/2016 3:43:43 PM - MATETRA TECH\11399.0DOTREC.1414\TASK ORDER 3\CAD\SHSHEETFILES\02 - PAY QUANTITIES (ROAD).DWG - MARQUART, MATT

DESIGN	JSH	3/16	OKLAHOMA DEPARTMENT OF TRANSPORTATION BRIDGE A TULSA COUNTY  SUMMARY OF PAY QUANTITIES (ROAD) STATE JOB NO. <u>28880(04)</u> SHEET NO. <u>2</u>
DRAWN	MRM	3/16	
CHECKED	JWB	3/16	
APPROVED			
SQUAD	TT		