

DESCRIPTION	REVISIONS	DATE

**SUMMARY OF BRIDGE PAY QUANTITIES**

ITEM	UNIT	ABUTMENTS	PIER	SUPER- STRUCTURE	APPROACH SLABS	TOTAL
CLSM BACKFILL	C.Y.				170	170
APPROACH SLAB	S.Y.				482.9	482.9
SAW-CUT GROOVING	S.Y.			804	374	1,178
SEALED EXPANSION JOINT	L.F.			125.2		125.2
CONCRETE PARAPET	L.F.			443.0	219.0	662.0
STRUCTURAL STEEL	LB.			208,740		208,740
WEATHERING STEEL FIXED BEARING ASSEMBLY	EA.			8		8
WEATHERING STEEL EXPANSION BEARING ASSEMBLY	EA.			16		16
SPECIAL CONCRETE FINISH	S.Y.	329	33			362
CLASS AA CONCRETE	C.Y.			292.5	26.3	318.8
CLASS A CONCRETE	C.Y.	5.6	35.1			40.7
MECHANICAL SPLICES	EA.		12			12
EPOXY COATED REINFORCING STEEL	LB.	670	6,290	75,230	1,800	83,990
WATER REPELLENT (VISUALLY INSPECTED)	S.Y.	220	96	649	237	1,202
PNEUMATICALLY PLACED MORTAR	S.Y.	93.5	6			99.5
SEALER CRACK PREPARATION	L.F.			151		151
SEALER RESIN	GAL.			2		2
(SP) CARBON FIBER-REINFORCED POLYMER	S.F.		146.6			146.6
(SP) CORROSION INHIBITOR (SURFACE APPLIED)	S.Y.		16.3			16.3
(PL) INSTALLATION OF BRIDGE ITEMS (TYPE A)	LSUM.	1				1
(PL) INSTALLATION OF BRIDGE ITEMS (TYPE B)	LSUM.		1			1
REMOVAL OF BRIDGE ITEMS	LSUM.			1		1

DESIGN	B.J.K.	4TH OVER I-444	TULSA COUNTY
DRAWN	R.A.P.		
CHECKED	J.W.H.		
APPROV.	T.A.C.		
SQUAD	CEC		

**SUMMARY OF BRIDGE  
PAY QUANTITIES**

JOB PIECE NO. 28868(04) SHEET NO. 10