

FED. ROAD DIST. NO.	STATE	JOB PIECE NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
X	OKLA.	28872(04)			
DESCRIPTION					DATE
ADDED PAY ITEM NOTES					8/18/16

28874(04) BRIDGES "A" & "B" 0100 ROADWAY		PAY QUANTITIES		I-40 WB & EB OVER S 38TH W AVE & TSU RR	
ITEM	DESCRIPTION	UNIT	QUANTITY		
221(C) 2801	TEMPORARY SILT FENCE	L.F.	3000		
230(A) 2806	SOLID SLAB SODDING	S.Y.	2000		
411(C) 5960	SUPERPAVE, TYPE S4 (PG 64-22 OK)	(2)(R-30) (R-32) TON	286		
619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	(R-49) (R-50) S.Y.	1268		
619(B) 4780	REMOVAL OF GUARDRAIL	(R-49) (R-50) L.F.	2725		
623(A) 0932	BEAM GUARDRAIL W-BEAM SINGLE	L.F.	2462.5		
623(G) 8590	GUARDRAIL END TREATMENT (31")	(1) EA.	4		
623(I) 8700	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	EA.	4		

GENERAL CONSTRUCTION NOTES:

This project shall be constructed without closing the existing road to local and through traffic. See Standard Specifications for maintenance of local and through traffic.

Maintenance of through traffic includes the maintenance of the existing road in close proximity to the new construction as shown on the plans.

In accordance with the Oklahoma Underground Facilities Damage Prevention Act, the Contractor shall notify the Oklahoma One-Call System, Inc. 48 hours prior to beginning excavation. Oklahoma One-Call System, Inc. "CALL OKIE" 1-800-522-6543 or 811.

Contractor to make every effort to locate and protect all utilities and structures whether shown or not, prior to construction operations. Contractor shall carry on construction such that no damage will occur to any utilities or structures remaining in place.

Existing guardrail shall be connected to new parapets within two weeks during E-N Ramp closure.

ROADWAY PAY ITEM NOTES:

(R-30) Price bid to include cost of 96 Gal. of tack coat, meeting the requirements of Section 407 of the Standard Specifications.

(R-32) Estimated at 112 Lbs. per Sq. Yd. per 1" thick.

(R-49) To become the property of and disposed of by the Contractor in a manner approved by the Engineer.

(R-50) Materials removed shall not be measured for payment under Section 202.06 Unclassified Excavation.

(1) Pay item shall be the SKT-SP-MGS or approved substitute. The ET-Plus will not be allowed.

(2) Cost of excavation to be included in the cost of this item. Subgrade is to be compacted in accordance with Subsection 202.04.A(5)(b)2). "Earth Fill"

I-44 WB & EB OVER S 38TH W AVE & TSU RR		TULSA COUNTY		DESIGN	JMO	11/15
BRIDGES "A" & "B"				DETAIL	SJL	11/15
SUMMARY OF PAY QUANTITIES AND NOTES (ROADWAY)				CHECK	BRT	11/15
				GARVER		
STATE OF OKLAHOMA	DEPARTMENT OF TRANSPORTATION					
	JOB PIECE NO. 28872(04)		SHEET NO. 7			