

**SIGN SUMMARY**

ALIGNMENT	APPROXIMATE C.R.L. STATION LOCATION			SIGN TYPE	POSTS		(PL) REMOVAL OF EXISTING SIGNS	(PL) REMOVE & RESET EXISTING SIGNS	BARRIER DELINEATORS (TYPE2, CODE1)	REMARKS
					12 GA.					
					2" SQUARE TUBE POST					
					851(C)		805(A)	805(D)	853	
					POST A	POST B	(EA.)	(EA.)	(EA.)	
					(L.F.)	(L.F.)	(EA.)	(EA.)	(EA.)	
C.R.L. I-44	338+92.16		R	(STD.)						
C.R.L. I-44	339+41.86		L	OM3-L			1			REMOVE
C.R.L. I-44	340+62.07		L	W4-3	13			1		REMOVE/RESET
C.R.L. I-44	335+11	TO	340+50	E5-1a	14	14		1		REMOVE/RESET
C.R.L. I-44	335+12	TO	340+51	TYPE 2, CODE 1					12	INSTALL BARRIER DELINEATOR
C.R.L. I-44				TYPE 2, CODE 1					12	INSTALL BARRIER DELINEATOR
SUB TOTALS:					27	14	1	2	24	
TOTALS:					41.00		1	2	24	

**SUMMARY OF STRIPING**

TYPE	L.F.
YELLOW(MULTI-POLYMER)	
6" SOLID	2,326
BLACK (MULTI-POLYMER)	
6" SOLID	672
WHITE (MULTI-POLYMER)	
6" SOLID	1,254
8" SOLID	1,600
12" SOLID	1,390
856(A) TRAFFIC STRIPE(MULTI-POLYMER)(6" WIDE)	4,252
856(A) TRAFFIC STRIPE(MULTI-POLYMER)(8" WIDE)	1,600
856(A) TRAFFIC STRIPE(MULTI-POLYMER)(12" WIDE)	1,390

DESIGN	MDF	3/16	I-44 OVER I-244 NB
DRAWN	TML	3/16	
CHECKED	KMM	5/16	
APPROVED			
SQUAD	<b>GARVER</b>		

**SUMMARY SHEET (TRAFFIC)**

STATE JOB NO. 29775(04) SHEET NO. 9