

GENERAL NOTES

/\ Rev. Note 8/9/2016

SPECIFICATIONS:

Comply with the requirements of the 2009 Oklahoma Standard Specifications for Highway Construction, except as modified by the Plans and Special Provisions.

VERIFICATION OF EXISTING CONDITIONS:

Bidders shall fully inform themselves of the nature of the work and conditions under which it will be performed. The Contractor shall adopt methods consistent with good construction practice and shall take all necessary precautions to prevent damage to the existing bridges or attachments. Any damage to the existing bridge structure or roadway due to the Contractor's negligence shall be repaired at the Contractor's expense, to the satisfaction of the Engineer.

EXISTING BRIDGE PLANS:

Construction plans for the existing bridge structures may be obtained from the Printing Services Branch of the Oklahoma Department of Transportation. Ask for:

OSAGE COUNTY:

Bridge "A"

Project No. NHPPY-257N(020)SS Job Piece No. 24287(04)

OSAGE COUNTY

Bridge "B"

Project No. NHPPY-257N(020)SS Job Piece No. 24287(04)

PAWNEE-OSAGE COUNTY:

Bridge "C"

Project No. STPY-159B(036) Job Piece No. 20895(04)

CREEK COUNTY:

Bridge "D"

PROJECT NO. STPY-119C(119)SS Job Piece No. 21908(04)

TULSA COUNTY:

Bridge "E"

Project No. NHPPI-0244-2(502)SS Job Piece No. 27145(04)

TULSA COUNTY:

Bridge "F"

Project No. NHPPY-172N(319) Job Piece No. 23167(04)

ROGERS COUNTY:

Bridge "G"

Project No. STPY-166C(208) Job Piece No. 24957(04)

ROGERS COUNTY:

Bridge "H"

Project No. SBR-266N(027)SB Job Piece No. 29777(04)

ROGERS COUNTY:

Bridge "I"

Project No. SBR-266N(026)SB Job Piece No. 29774(04)

CRAIG COUNTY:

Bridge "J"

Project No. STPY-118B(067)SS Job Piece No. 23126(04)

CRAIG COUNTY:

Bridge "K"

Project No. STPY-118B(067)SS Job Piece No. 23126(04)

OTTAWA COUNTY:

Bridge "L"

Project No. SSP-158C(131)SS Job Piece No. 24277(04)

OTTAWA COUNTY:

Bridge "M"

Project No. STPY-158C(077) Job Piece No. 21918(04)

OTTAWA COUNTY:

Project No. SPP-158C(128)SS Bridae "N" Job Piece No. 24276(04)

DELAWARE COUNTY:

Bridge "O"

Project No. BRFY-021C(256) Job Piece No. 10441(04)

MAYES COUNTY:

Bridge "P"

Project No. STP-149C(082)SS Job Piece No. 21911(04)

MAYES COUNTY:

Bridae "Q"

Project No. STPY-149C(076) Job Piece No. 21909(04)

PENETRATING WATER REPELLENT SURFACE TREATMENT:

A performance tested penetrating water repellent surface treatment shall be applied to the driving surface of the Bridge Decks and Approach Slabs in accordance with the Standard Specifications for Highway Construction.

The bridges have a detail sheet showing the extent of the surfaces to be treated. The Contractor shall only treat the surfaces shown in the plans.

↑ LANE CLOSURE:

The Engineer reserves the right to prohibit lane closures during holidays or special events. All work requiring the closing or narrowing of one lane of traffic on the bridges shall be performed during daylight hours only unless approved by the engineer except for Bridges E, F, G, H, and I work may need to be done at night to avoid work being done in Tulsa. Traffic on bridges shall be returned to normal during night time hours except for Bridges E, F, GH, and I unless directed by the Engineer. The Contractor shall make every effort to reopen these lane closures as soon as possible.

BRIDGE "A" - "Q"

TULSA COUNTY

GENERAL NOTES

Check KMS 4/16 Sauat MAYFIELD nor: FLYΔZGL

Design N/A N/A

Detail DjG 4/16

STATE OF DEPARTMENT OF TRANSPORTATION OKLAHOMA JOBPIECENO. 31943(04) SHEETNO. ABO1 J.

(BRIDGE)

0200 BRID		PAY QUANTITIES		
2500 01/10	ge "a" /	7 20211111111111111111111111111111111111	US 60 C	OVER DRY HOLLOW CREEK
ITE		DESCRIPTION	UNIT	QUANTITY
515(B)	6014	WATER REPELLENT (PERFORMANCE TESTED)	S.Y.	3,110.000
523(A)	6550	SEALER CRACK PREPARATION	L.F.	250.000
523(B)	6560	SEALER RESIN	GAL.	1.700
NBI: 29873				
	^	PAY QUANTITIES		
0201 BRIDO	E "B" ∠1\	•		US 60 OVER ROCK CREEK
ITE	M	DESCRIPTION	UNIT	QUANTITY
515(B)	6014	WATER REPELLENT (PERFORMANCE TESTED)	S.Y.	1,819.000
523(A)	6550	SEALER CRACK PREPARATION	L.F.	130.000
523(B)	6560	SEALER RESIN	GAL.	0.900
NBI: 30096				
		PAY QUANTITIES		
0202 BRID	GE "C"		SH 1	8 OVER ARKANSAS RIVER
ITE	M	DESCRIPTION	UNIT	QUANTITY
515(B)	6014	WATER REPELLENT (PERFORMANCE TESTED)	S.Y.	6,794.000
523(A)	6550	SEALER CRACK PREPARATION	L.F.	750.000
523(B)	6560	SEALER RESIN	GAL.	5.000
NBI: 30415 0203 BRID	GE "D"	PAY QUANTITIES		SH 16 OVER SKULL CREEK
ITE	M	DESCRIPTION	UNIT	QUANTITY
515(B)	6014	WATER REPELLENT (PERFORMANCE TESTED)	S.Y.	772.000
523(A)	6550	SEALER CRACK PREPARATION	L.F.	55.000
523(B)	6560	SEALER RESIN	GAL.	0.400
NBI: 16974		PAY QUANTITIES		
0204 BRID	GE "E" 🛆	AT QUANTITIES	12	44 OVER DELAWARE AVE.
		DESCRIPTION	UNIT	QUANTITY
111	6014		S.Y.	2,909.000
1TE	6550	WATER REPELLENT (PERFORMANCE TESTED) SEALER CRACK PREPARATION	L.F.	2,909.000
515(B) 523(A)				
515(B)	6560	SEALER RESIN	GAL.	1.400
515(B) 523(A) 523(B)	6560	SEALER RESIN	GAL.	1.400
515(B) 523(A)	6560		GAL.	1.400
515(B) 523(A) 523(B) NBI: 30585	^	PAY QUANTITIES	GAL.	
515(B) 523(A) 523(B)	GE "F" 1		UNIT	SH 266 OVER US 169
515(B) 523(A) 523(B) NBI: 30585	GE "F" 1	PAY QUANTITIES		SH 266 OVER US 169
515(B) 523(A) 523(B) NBI: 30585 0205 BRIDG	GE "F"	PAY QUANTITIES DESCRIPTION	UNIT	SH 266 OVER US 169

NBI: 18112				
	^	PAY QUANTITIES		
0206 BRIDGE	"G" <u>/1</u>	2	SH 266 OVER	VERIGRIS RIVER OVERFLO
ITEM	Л	DESCRIPTION	UNIT	QUANTITY
515(B)	6014	WATER REPELLENT (PERFORMANCE TESTED)	S.Y.	1,619.0
523(A)	6550	SEALER CRACK PREPARATION	L.F.	115.0
523(B)	6560	SEALER RESIN	GAL.	3.0
NBI: 18787		PAY QUANTITIES		
0207 BRIDGE	"H" 🔨	7 YI WOANTITES		SH 167 OVER BIRD CREI
ITEM	1	DESCRIPTION	UNIT	QUANTITY
515(B)	6014	WATER REPELLENT (PERFORMANCE TESTED)	S.Y.	2,922.0
523(A)	6550	SEALER CRACK PREPARATION	L.F.	235.0
523(B)	6560	SEALER RESIN	GAL.	1.5
0208 BRIDGE ITEM		DESCRIPTION S	UNIT	SF R.R. AND COUNTRY RO QUANTITY
515(B)	6014	WATER REPELLENT (PERFORMANCE TESTED)	S.Y.	1,530.0
523(A)	6550	SEALER CRACK PREPARATION	L.F.	110.0
523(B)	6560	SEALER RESIN	GAL.	
523(B)				0.7
523(B)	6560	SEALER RESIN		
523(B) NBI: 30555	6560	SEALER RESIN		0.7
523(B) NBI: 30555 0209 BRIDGE	6560	PAY QUANTITIES	GAL.	US 59 OVER ELM CRE
523(B) NBI: 30555 0209 BRIDGE	6560 : "J"	PAY QUANTITIES DESCRIPTION	GAL.	US 59 OVER ELM CRE QUANTITY
523(B) NBI: 30555 0209 BRIDGE ITEM 515(B)	6560 : "J" 1	PAY QUANTITIES DESCRIPTION WATER REPELLENT (PERFORMANCE TESTED)	UNIT S.Y.	US 59 OVER ELM CRE QUANTITY 673.0 50.0
523(B) NBI: 30555 0209 BRIDGE ITEM 515(B) 523(A)	6560 : "J" 1 6014 6550	PAY QUANTITIES DESCRIPTION WATER REPELLENT (PERFORMANCE TESTED) SEALER CRACK PREPARATION	UNIT S.Y. L.F.	US 59 OVER ELM CRE QUANTITY 673.0 50.0
523(B) NBI: 30555 0209 BRIDGE ITEM 515(B) 523(A) 523(B) NBI: 30554	6560 E"J" 1 6014 6550 6560	PAY QUANTITIES DESCRIPTION WATER REPELLENT (PERFORMANCE TESTED) SEALER CRACK PREPARATION	UNIT S.Y. L.F.	US 59 OVER ELM CRE QUANTITY 673.0
523(B) NBI: 30555 0209 BRIDGE ITEM 515(B) 523(A) 523(B)	6560 E"J" 1 6014 6550 6560	PAY QUANTITIES DESCRIPTION WATER REPELLENT (PERFORMANCE TESTED) SEALER CRACK PREPARATION SEALER RESIN	UNIT S.Y. L.F. GAL.	US 59 OVER ELM CRE QUANTITY 673.0 50.0
523(B) NBI: 30555 0209 BRIDGE ITEM 515(B) 523(A) 523(B) NBI: 30554	6560 6560 6014 6550 6560	PAY QUANTITIES DESCRIPTION WATER REPELLENT (PERFORMANCE TESTED) SEALER CRACK PREPARATION SEALER RESIN	UNIT S.Y. L.F. GAL.	0.7 US 59 OVER ELM CRE QUANTITY 673.0 50.0 0.4
523(B) NBI: 30555 0209 BRIDGE ITEM 515(B) 523(A) 523(B) NBI: 30554	6560 6560 6014 6550 6560	PAY QUANTITIES DESCRIPTION WATER REPELLENT (PERFORMANCE TESTED) SEALER CRACK PREPARATION SEALER RESIN PAY QUANTITIES	UNIT S.Y. L.F. GAL.	US 59 OVER ELM CRE QUANTITY 673.0 50.0 0.4
523(B) NBI: 30555 0209 BRIDGE ITEN 515(B) 523(A) 523(B) NBI: 30554 0210 BRIDGE	6560 E "J" 6014 6550 6560	PAY QUANTITIES DESCRIPTION WATER REPELLENT (PERFORMANCE TESTED) SEALER CRACK PREPARATION SEALER RESIN PAY QUANTITIES DESCRIPTION	GAL. UNIT S.Y. L.F. GAL. UNIT	US 59 OVER ELM CRE QUANTITY 673.0 0.4 US 59 OVER RUSSELL CRE QUANTITY 1,058.0
523(B) NBI: 30555 0209 BRIDGE ITEM 515(B) 523(A) 523(B) NBI: 30554 0210 BRIDGE ITEM 515(B)	6560 "K"	PAY QUANTITIES DESCRIPTION WATER REPELLENT (PERFORMANCE TESTED) SEALER CRACK PREPARATION PAY QUANTITIES DESCRIPTION WATER REPELLENT (PERFORMANCE TESTED)	UNIT S.Y. L.F. GAL. UNIT S.Y.	US 59 OVER ELM CRE QUANTITY 673.0 50.0 0.4 US 59 OVER RUSSELL CRE QUANTITY 1,058.0 75.0
523(B) NBI: 30555 0209 BRIDGE ITEM 515(B) 523(A) NBI: 30554 0210 BRIDGE ITEM 515(B) 523(A)	6560 6560 6560 "K" 6014 6560	SEALER RESIN PAY QUANTITIES DESCRIPTION WATER REPELLENT (PERFORMANCE TESTED) SEALER CRACK PREPARATION SEALER RESIN PAY QUANTITIES DESCRIPTION WATER REPELLENT (PERFORMANCE TESTED) SEALER CRACK PREPARATION SEALER CRACK PREPARATION SEALER RESIN	UNIT S.Y. L.F. GAL. UNIT S.Y. L.F.	US 59 OVER ELM CRE QUANTITY 673.0 50.0 0.4 US 59 OVER RUSSELL CRE QUANTITY
523(B) NBI: 30555 0209 BRIDGE ITEM 515(B) 523(A) 523(B) NBI: 30554 U210 BRIDGE ITEM 515(B) 523(A) 523(A) NBI: 30667	6560 6560 "K" 6014 6550 6560	PAY QUANTITIES DESCRIPTION WATER REPELLENT (PERFORMANCE TESTED) SEALER CRACK PREPARATION PAY QUANTITIES DESCRIPTION WATER REPELLENT (PERFORMANCE TESTED) SEALER CRACK PREPARATION DESCRIPTION	UNIT S.Y. L.F. GAL. UNIT S.Y. L.F.	US 59 OVER ELM CRE QUANTITY 673.0 50.0 0.4 US 59 OVER RUSSELL CRE QUANTITY 1,058.0 75.0
523(B) NBI: 30555 0209 BRIDGE ITEM 515(B) 523(A) 523(B) NBI: 30554 U210 BRIDGE ITEM 515(B) 523(A) 523(A) 523(B)	6560 6560 "K" 6014 6550 6560	SEALER RESIN PAY QUANTITIES DESCRIPTION WATER REPELLENT (PERFORMANCE TESTED) SEALER CRACK PREPARATION SEALER RESIN PAY QUANTITIES DESCRIPTION WATER REPELLENT (PERFORMANCE TESTED) SEALER CRACK PREPARATION SEALER CRACK PREPARATION SEALER RESIN	UNIT S.Y. L.F. GAL. UNIT S.Y. L.F.	US 59 OVER ELM CRE QUANTITY 673.0 50.0 0.4 US 59 OVER RUSSELL CRE QUANTITY 1,058.0 75.0 0.5
523(B) NBI: 30555 0209 BRIDGE ITEM 515(B) 523(A) 523(B) NBI: 30554 U210 BRIDGE ITEM 515(B) 523(A) 523(A) NBI: 30667	6560 E "J" 6014 6550 6560 "K" 6014 6550 6560	SEALER RESIN PAY QUANTITIES DESCRIPTION WATER REPELLENT (PERFORMANCE TESTED) SEALER CRACK PREPARATION SEALER RESIN PAY QUANTITIES DESCRIPTION WATER REPELLENT (PERFORMANCE TESTED) SEALER CRACK PREPARATION SEALER CRACK PREPARATION SEALER RESIN	UNIT S.Y. L.F. GAL. UNIT S.Y. L.F.	US 59 OVER ELM CRE QUANTITY 673.0 50.0 0.4 US 59 OVER RUSSELL CRE QUANTITY 1,058.0 75.0
523(B) NBI: 30555 0209 BRIDGE ITEM 515(B) 523(A) 523(B) NBI: 30554 ITEM 515(B) 523(A) 523(B) NBI: 30667 0211 BRIDGE	6560 E "J" 6014 6550 6560 "K" 6014 6550 6560	PAY QUANTITIES DESCRIPTION WATER REPELLENT (PERFORMANCE TESTED) SEALER CRACK PREPARATION SEALER RESIN PAY QUANTITIES DESCRIPTION WATER REPELLENT (PERFORMANCE TESTED) SEALER CRACK PREPARATION PAY QUANTITIES PAY QUANTITIES	UNIT S.Y. L.F. GAL. UNIT S.Y. L.F. GAL.	US 59 OVER ELM CRE QUANTITY 673.0 50.0 0.4 US 59 OVER RUSSELL CRE QUANTITY 1,058.0 75.0 0.5 SH 10C OVER LOST CRE

			REV	REVISIO
			Z	ADDED PAY ITE
NBI: 30035	<u> </u>			
		PAY QUANTITIES		
0212 BRIDO	GE "M" 🔼		SH 10 OVE	ER SYCAMORE CREEK
ITE	EM	DESCRIPTION	UNIT	QUANTITY
515(B)	6014	WATER REPELLENT (PERFORMANCE TESTED)	S.Y.	1,731.000
523(A)	6550	SEALER CRACK PREPARATION	L.F.	125.000
523(B)	6560	SEALER RESIN	GAL.	0.800
NBI: 30066	,			
	^	PAY QUANTITIES		
0213 BRID	3E "N" <u> </u>		SH 125	OVER HUDSON CREEK
ITE	ΕM	DESCRIPTION	UNIT	QUANTITY
515(B)	6014	WATER REPELLENT (PERFORMANCE TESTED)	S.Y.	1,012.000
523(A)	6550	SEALER CRACK PREPARATION	L.F.	75.000
523(B)	6560	SEALER RESIN	GAL.	0.500
NBI: 29164				
NBI: 29164		PAY QUANTITIES		
NBI: 29164 0214 BRIDO	^	PAY QUANTITIES		SH 10 OVER ELK RIVER
	GE "O"	PAY QUANTITIES DESCRIPTION	UNIT	SH 10 OVER ELK RIVER QUANTITY
0214 BRIDO	GE "O"			
0214 BRIDO	ge "o" 🔨	DESCRIPTION	UNIT	QUANTITY
0214 BRIDO ITE 515(B)	GE "O" 1 EM 6014	DESCRIPTION WATER REPELLENT (PERFORMANCE TESTED)	UNIT s.y.	QUANTITY 5,344.000
0214 BRIDO ITE 515(B) 523(A) 523(B)	6014 6550 6560	DESCRIPTION WATER REPELLENT (PERFORMANCE TESTED) SEALER CRACK PREPARATION	UNIT S.Y. L.F.	QUANTITY 5,344.000 480.000
0214 BRIDO ITE 515(B) 523(A)	6014 6550 6560	DESCRIPTION WATER REPELLENT (PERFORMANCE TESTED) SEALER CRACK PREPARATION	UNIT S.Y. L.F.	QUANTITY 5,344.000 480.000
0214 BRIDG ITE 515(B) 523(A) 523(B) NBI: 30037	6014 6550	DESCRIPTION WATER REPELLENT (PERFORMANCE TESTED) SEALER CRACK PREPARATION SEALER RESIN	UNIT S.Y. L.F. GAL.	QUANTITY 5,344.000 480.000
0214 BRIDO ITE 515(B) 523(A) 523(B)	6014 6550 6560	DESCRIPTION WATER REPELLENT (PERFORMANCE TESTED) SEALER CRACK PREPARATION SEALER RESIN	UNIT S.Y. L.F. GAL.	QUANTITY 5,344.000 480.000 3.200
0214 BRIDO ITE 515(B) 523(A) 523(B) NBI: 30037	6014 6550 6560	DESCRIPTION WATER REPELLENT (PERFORMANCE TESTED) SEALER CRACK PREPARATION SEALER RESIN PAY QUANTITIES	UNIT S.Y. L.F. GAL.	QUANTITY 5,344.000 480.000 3.200 2 OVER GRAND RIVER
0214 BRIDG ITE 515(B) 523(A) 523(B) NBI: 30037 0215 BRIDG	6014 6550 6560 6560	DESCRIPTION WATER REPELLENT (PERFORMANCE TESTED) SEALER CRACK PREPARATION SEALER RESIN PAY QUANTITIES DESCRIPTION	UNIT S.Y. L.F. GAL. SH 8	QUANTITY 5,344.000 480.000 3.200 2 OVER GRAND RIVER QUANTITY

NBI: 30036				
	^	PAY QUANTITIES		
0216 BRIDG	BE "Q" <u>/1\</u>		SH 2	20 OVER ROCK CREEK
ITE	M	DESCRIPTION	UNIT	QUANTITY
515(B)	6014	WATER REPELLENT (PERFORMANCE TESTED)	S.Y.	1,584.000
523(A)	6550	SEALER CRACK PREPARATION	L.F.	110.000
523(B)	6560	SEALER RESIN	GAL.	0.700

0640 0	0640 CONSTRUCTION				
ITEM		DESCRIPTION	UNIT	QUANTITY	
641	1399	MOBILIZATION	LSUM.	1.000	

BRIDGE "A" - "Q"	TULSA COUNTY	Design	N/A	N/A
			DjG	4/16
SUMMARY OF PAY QUA	JANTITIES	Check	KMS	5/16
(BRIDGE)		Squad: M. Engr.: EL		

STATE OF DEPARTMENT OF TRANSPORTATION OKLAHOMA JOBPIECENO. 31943(04) SHEETINO. ABOQ2

	REVISIONS	
EV. NO.	DESCRIPTION	DATE

TRAFFIC GENERAL CONSTRUTION NOTES

EXISTING ROADWAY SHALL REMAIN OPEN DURING CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROPER BARRICADES, LIGHTS, AND SIGNING WITHIN THE LIMITS OF CONSTRUCTION. ALL CONSTRUCTION SIGNING WILL BE IMPLEMENTED ACCORDING TO CONSTRUCTION PLANS. CONSTRUCTION TRAFFIC CONTROL WILL BE INSTALLED IN A MANNER APPROVED BY THE ENGINEER, IN ACCORDANCE WITH CHAPTER VI OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, (CURRENT EDITION), AND COMPLIANT WITH APPLICABLE O.D.O.T. STANDARD DRAWINGS.

REMOVED MATERIAL TO BECOME PROPERTY OF CONTRACTOR AND IT SHALL BE DISPOSED OF IN A MANNER APPORVED BY THE RESIDENT ENGINEER.

THE CONTRACTOR SHALL PROVIDE A PERSON TO BE ON 24 HOUR CALL AS NEEDED AS DETERMINED BY THE ENGINEER. THIS PERSON SHALL HOLD A CURRENT CERTIFICATION FROM THE AMERICAN TRAFFIC SAFETY SERVICE ASSOCIATION (ATSSA) OR THE OKLAHOMA TRAFFIC ENGINEERING ASSOCIATION (OETA) AS A TRAFFIC CONTROL TECHNICIAN OR TRAFFIC CONTROL SUPERVISOR.

ALL TEMPORARY TRAFFIC CONTROL DEVICES SHALL MEET ODOT'S "QUALITY STANDARDS FOR TEMPORARY TRAFFIC CONTROL DEVICES." CHANNELIZING DEVICES SHALL HAVE A MINIMUM HEIGHT OF 36 INCHES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE OF THE TEMPORARY TRAFFIC CONTROL DEVICES, AND SHALL BE ESPONSIBLE FOR REPAIRING OR REPLACING ANY DEVICE DURING CONSTRUCTION.

TRAFFIC PAY QUANTITY NOTES

- (TC-26) ALL CONSTRUCTION TRAFFIC CONTROL WILL BE IMPLEMENTED ACCORDING TO CONSTRUCTION PLANS, AND INSTALLED IN A MANNER APPROVED BY THE ENGINEER, IN ACCORDANCE WITH CHAPTER VI OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, (CURRENT EDITION), AND COMPLIANT WITH APPLICABLE O.D.O.T. STANDARD DRAWINGS. PRICE BID FOR THIS ITEM SHALL BE PAYMENT IN FULL FOR THE INSTALLATION, MAINTENANCE AND SUBSEQUENT REMOVAL OF ALL NECESSARY CONSTRUCTION TRAFFIC CONTROL DEVICES REQUIRED FOR COMPLETION OF THE PROJECT. ALL SIGNS AND BARRICADES WHICH ARE SHOWN WITH TYPE 'A' LIGHTS IN THE STANDARD DRAWINGS SHALL HAVE THE CORRESPONDING LIGHT ATTACHED DURING NON-DAYLIGHT HOURS.
- (TC-30) INCLUDED IN THIS ITEM ARE ALL S.C.S. (SPECIAL CONSTRUCTION SIGNING) SIGNS WHICH ARE BETWEEN 16.0 S.F. AND 32.99 S.F. ALSO INCLUDED IN THIS ITEM SHALL BE THE COST OF INSTALLATION, MAINTENANCE, AND REMOVAL OF THESE SIGNS.
- (TC-33) ALL CONSTRUCTION WORK ZONE SIGNS SHALL HAVE FLUORESCENT SHEETING. THE FLUORESCENT SHEETING SHALL MEET THE REQUIREMENTS OF ASTM D4956 (LATEST REVISION) THE MANUFACTURER SHALL FURNISH A TYPE 'D' CERTIFICATION IN ACCORDANCE WITH O.D.O.T. STANDARD SPECIFICATIONS (CURRENT EDITION) SUBSECTION 106.04. THE CERTIFICATION SHALL INCLUDE TEST RESULTS ON MATERIAL SUBMITTED FOR APPROVAL.
- (TC-52) ANY USED TRUCK MOUNTED ATTENUATOR OR CHANGEABLE MESSAGE SIGN TO BE PLACED ON THIS PROJECT SHALL BE SUBJECT TO INSPECTION AND APPROVAL, BY THE OKLAHOMA DEPARTMENT OF TRANSPORTATION, TO ASSURE THAT THEY ARE IN GOOD WORKING CONDITION. PRIOR TO PLACEMENT ON THE PROJECT.
- (TC-70) THIS ITEM IS AN ESTIMATED QUANTITY TO BE USED AS DEEMED NECESSARY BY THE ENGINEER.
- (TC-76) ANY TRUCK MOUNTED ATTENUATOR USED ON THIS PROJECT SHALL HAVE PASSED ALL MANDATORY AND OPTIONAL TESTS LISTED IN NCHRP 350, TL-3 CRITERIA. THIS ITEM IS TO BE USED WHERE SHOWN IN THE STANDARD DRAWINGS OR AT THE DISCRETION OF THE ENGINEER ON SHADOW VEHICLES PROTECTING THE WORK AREAS AND TEMPORARY ROADSIDE HAZARDS.
- (TC-77) TRUCK MOUNTED ATTENUATORS ARE TO BE INSTALLED ON NON-STATE OWNED TRUCKS HAVING A MINIMUM GROSS WEIGHT RATING OF 15,000 POUNDS. EACH OF THESE TRUCKS SHALL ALSO BE EQUIPPED WITH AN ARROW DISPLAY (TYPE B)
- (TC-84)

 120 CONSTRUCTION CALENDAR DAYS WERE USED TO COMPUTE THE SIGN DAY PAY ITEMS. THE AMOUNT OF CALENDAR DAYS USED TO COMPUTE THE SIGN DAY PAY ITEMS IS AN ESTIMATED QUANTITY ONLY, BASED ON THE CURRENT O.D.O.T. STANDARDS AND SUGGESTED CONSTRUCTION SEQUENCE FOR THIS PROJECT. THESE ESTIMATED SIGN DAY QUANTITIES MAY CHANGE AS THE PROJECT'S CONSTRUCTION TRAFFIC CONTROL IS MODIFIED DURING CONSTRUCTION.
- (TC-85) THESE SIGNS MUST BE ON THE OKLAHOMA DEPARTMENT OF TRANSPORTATION LIST OF APPROVED CHANGEABLE MESSAGE SIGNS. FOR A LIST OF THE APPROVED SIGNS GO TO THE OKLAHOMA DEPARTMENT OF TRANSPORTATION WEBSITE AT: http://www.okladot.state.ok.us/traffic/qpl/index.php

SPECIAL NOTES

- (SP-1) PORTABLE CHANGEABLE MESSAGE SIGNS TO BE PLACED WHERE DEEMED NECESSARY BY THE ENGINEER.
- (SP-2) PORTABLE CHANGEABLE MESSAGE SIGN(S) SHALL BE PLACED 14 DAYS PRIOR TO CONSTRUCTION.
- (SP-3) TYPE "C" WARNING LIGHTS ARE NOT REQUIRED.

0300 TRAFFIC CONTROL


0000 1111	1110 001	11.102			
PAY ITEM	CODE NO.	DESCRIPTION		UNIT	QUANTITY
876(A)	8482	(PL) TRUCK MOUNTED ATTENUATOR	(TC-52,70,76,77)	SD	120.00
880(A)	8812	ARROW DISPLAY(TYPE C)	(TC-26,84)	SD	120.00
880(B)	8818	CONSTRUCTION SIGNS 0 TO 6.25 SF	(TC-26,33,84)	SD	1800.00
880(B)	8821	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	(TC-26,33,84)	SD	600.00
880(B)	8824	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	(TC-26,30,33,84)	SD	1440.00
880(C)	8848	WING BARRICADES	(TC-26,84)	SD	480.00
880(E)	8860	WARNING LIGHTS(TYPE A)	(TC-26,84)	SD	1200.00
880(F)	8878	DRUMS	(SP-3)(TC-26,84)	SD	3120.00
880(G)	8890	CHANNELIZER CONES	(TC-26,84)	SD	5400.00
880(I)	8902	FLAGGER	(TC-70)	SD	60.00
882(A)	8306	PORT. CHANGEABLE MESSAGE SIGN	(SP-1,2)(TC-52,70,85)	SD	222.00
			·		





SUMMARY OF PAY QUANTITIES & NOTES (TRAFFIC)

Drawn	SC	5/16
Design	sc	5/16
Checked	SEB	5/16
	C ENGIN MI SHO	NEERING RT


STATE OF DEPARTMENT OF TRANSPORTATION OKLAHOMA DIVISION 8 JOB PIECENO. 31943(04) SHEETING. ATOT.












PLAN



HALF SECTION AT INTERMEDIATE DIAPHRAGM


HALF SECTION AT PIER DIAPHRAGM

TYPICAL CROSS SECTION


31943(04)		
QUANTITIES		
BRIDGE 'D' - NBI 30415	SH-16 OVER S	KULL CREEK
DESCRIPTION	UNIT	QUANTITY
WATER REPELLENT (PERFORMANCED TESTED)	S.Y.	772.00


BRIDGE "D" CREEK COUNTY Design N/A	N/A
SH 16 OVER SKULL CREEK Detail KMS	4/16
GENERAL PLAN AND TYPICAL SECTION Check KMS	6/16
(BRIDGE "D") Squad MAYFIELD	D
Engr: ELYAZGI	

STATE OF DEPARTMENT OF TRANSPORTATION OKLAHOMA JOBPIECENO. 31943(04) SHEETNO. BOO4



REVISIONS







TYPICAL CROSS SECTION

31943(04)		
QUANTITIES		
BRIDGE 'F' - NBI 30585	SH-26	6 OVER US-169
DESCRIPTION	UNIT	QUANTITY
WATER REPELLENT (PERFORMANCE TESTED)	S.Y.	2,581.0

BRIDGE "F"	TULSA COUNTY	Design	N/A	N/A
SH 266 OVER US 169		Detail	ADG	4/16
GENERAL PLAN AND TYPICA	L SECTION	Check	KMS	6/16
(BRIDGE "F")		Squad: M.	AYFIEL	.D
		Engr: EL	.YAZG	
CTATE OF DEDARTMENT	OF TRANSE	\sim	$\Gamma \Lambda T$	\overline{Z}

STATE OF DEPARTMENT OF TRANSPORTATION OKLAHOMA JOBPICCENO. 31943(04) SHEETINO. BOOG







REVISIONS

REV. NO DESCRIPTION DATE








TYPICAL CROSS SECTION

31943(04)			
(QUANTITIES		
BRIDGE 'I' - NBI 18768	SH-167 OVER BNS	SF R.R. & (COUNTY ROAD
DESCRIPTION	NC	UNIT	QUANTITY
WATER REPELLENT (PERFORMANCE	TESTED)	S.Y.	1,530.00


BRIDGE "I"	ROGERS COUNTY	Design	N/A	N/A
SH 167 OVER BNSF R.R. & COUNTY ROAD		Detail	ADG	04/16
GENERAL PLAN AND TYPICA	AL SECTION	Check	KMS	6/16
(BRIDGE "I")		Squad: M.	AYFIEL	.D
		Engr.: EL	.YAZG	l

STATE OF DEPARTMENT OF TRANSPORTATION OKLAHOMA JOBPIECENO. 31943(04) SHEETNO. BOOD





PLAN




TYPICAL CROSS SECTION


31943(04) QUANTITIES		
BRIDGE 'J' - NBI 30555	US-59 O\	/ER ELM CREEK
DESCRIPTION	UNIT	QUANTITY
WATER REPELLENT (PERFORMANCE TESTED)	S.Y.	673.00

	-			
BRIDGE "J"	CRAIG COUNTY	Design	N/A	N/A
US 59 OVER ELM CREEK		Detail	DjG	4/16
GENERAL PLAN AND TYPICAL SECTION		Check	KMS	6/16
(BRIDGE "J")		Squad: M. Engr.: EL	AYFIEL YAZG	
CTATE OF IDEDADTMENT OF TRANSPORTATION				

STATE OF DEPARTMENT OF TRANSPORTATION OKLAHOMA JOBPECENO. 31943(04) SHEETINO. BO10







<u>PLAN</u>

CLEAR ROADWAY = 40'-0'

TR-4

WATER REPELLENT - PERFORMANCE TESTED
SHALL BE APPLIED TO EXISTING BRIDGE DECK
AND APPROACH SLABS AS INDICATED BY
HEAVY LINE

2% SLOPE

2% SLOPE

2% SLOPE

HALF SECTION AT INTERMEDIATE DIAPHRAGM


HALF SECTION AT PIER DIAPHRAGM


TYPICAL CROSS SECTION

31943(04) QUANTITIES		
BRIDGE 'L' - NBI 30667 SH-	-10C OVEF	R LOST CREEK
DESCRIPTION	UNIT	QUANTITY
WATER REPELLENT (PERFORMANCE TESTED)	S.Y.	863.00


	•			
RIDGE "L"	OTTAWA COUNTY	Design	N/A	4/16
H 10C OVER LOST CREEK		Detail	DjG	4/16
GENERAL PLAN AND TYPICAL SECTION			KMS	6/16
(BRIDGE "L")		Squad: M.	AYFIEL	.D
		Engr.: El	YAZG	l
~ ~-				

STATE OF DEPARTMENT OF TRANSPORTATION OKLAHOMA JOBPECENO. 31943(04) SHEETINO. BO12





PLAN



HALF SECTION AT INTERMEDIATE DIAPHRAGM

HALF SECTION AT END DIAPHRAGM

TYPICAL CROSS SECTION


31943(04)		
QUANTITIES		
BRIDGE 'M' - NBI 30035 SH-10	OVER SYC	AMORE CREEK
DESCRIPTION	UNIT	QUANTITY
WATER REPELLENT (PERFORMANCE TESTED)	S.Y.	1731.00


BRIDGE "M"	OTTAWA COUNTY	Design	N/A	N/A
SH 10 OVER SYCAMORE CREEK		Detail	DjG	4/16
GENERAL PLAN AND TYPIC	CAL SECTION	Check	KMS	6/16
(BRIDGF "M")	, .L 3L31101 1	Squad: M.	AYFIEL	.D

STATE OF DEPARTMENT OF TRANSPORTATION OKLAHOMA JOBPIECENO. 31943(04) SHETINO. B013

REVISIONS







HALF SECTION AT INTERMEDIATE DIAPHRAGM


HALF SECTION AT PIER DIAPHRAGM

TYPICAL CROSS SECTION

31943(04)		
QUANTITIES		
BRIDGE 'N' - NBI 30066	SH-125 OVER	HUDSON CREEK
DESCRIPTION	UNIT	QUANTITY
WATER REPELLENT (PERFORMANCE TESTED)	S.Y.	1012.00

BRIDGE "N"	OTTAWA COUNTY	Design	N/A	N/A
SH 125 OVER HUDSON CREEK		Detail	DjG	4/16
GENERAL PLAN AND TYP	ICAL SECTION	Check	KMS	6/16
(BRIDGE "N"	')	Squad: MAYFIELD		
		Engr.: EL	.YAZG	


STATE OF DEPARTMENT OF TRANSPORTATION OKLAHOMA JOBPECENO. 31943(04) SHEETINO. BO14





REVISIONS


DESCRIPTION

DATE











31943(04)			
QUANTITIES			
BRIDGE 'P' - NBI 30037	SH	I-82 OVER	GRAND RIVER
DESCRIPTION		UNIT	QUANTITY
WATER REPELLENT (PERFORMANCE TESTED)		S.Y.	3,902.00

STATE OF DEPARTMENT OF TRANSPORTATION OKLAHOMA JOBPIECENO. 31943(04) SHEETINO. B016


YPICAL	CROSS SECTION	






THERE IS NO SUGGESTED SEQUENCE OF CONSTRUCTION IN THIS DRAWING. INSIDE AND OUTSIDE LANES SHALL BE WORKED AS STATED IN THE PLANS OR AS DIRECTED BY THE DETAILS SHOWN ARE FOR ONE LANE OF TRAFFIC CONTROL. ALL TRAFFIC CONTROL FOR THE ALTERNATE LANE WILL BE OPPOSITE OF THAT SHOWN.

TRAFFIC CONTROL TO BE LIMITED TO NIGHTS
ONLY FROM SUNDAY TO THURSDAY AND TIMES
ARE SUBJECT TO THE DISCRETION OF THE
ENGINEER. (BRIDGE E)





NOTE

MAXIMUM SPACING BETWEEN CHANNELIZING DEVICES (FEET) SHALL BE TWICE THE POSTED SPEED LIMIT (M.P.H.) WITH THE FOLLOWING EXCEPTIONS. SPACING SHALL NOT EXCEED 50 FEET FOR CONES OR TUBE CHANNELIZERS. SPACING SHALL NOT EXCEED 75 FEET FOR CHANNELIZER CONES.SPACING SHALL NOT EXCEED 100 FEET FOR TYPE II BARRICADES, VERTICAL PANELS OR DRUMS.

NOTE.

MAXIMUM SPACING BETWEEN CHANNELIZING DEVICES (FEET) SHALL BE EQUAL TO THE POSTED SPEED LIMIT (M.P.H.) WITH THE FOLLOWING EXCEPTIONS. SPACING SHALL NOT EXCEED 25 FEET FOR CONES OR TUBE CHANNELIZERS. SPACING SHALL NOT EXCEED 50 FEET FOR TYPE II BARRICADES, VERTICAL PANELS OR DRUMS.

NOTE 3

A MINIMUM OF FIVE (5) CHANNELIZING DEVICES SHALL BE PLACED THROUGH THIS TAPER.

NOTE 4

DOWNSTREAM TAPERS SHALL CONTAIN A MINIMUM OF FOUR (4) CHANNELIZING DEVICES.

NOTE 5

A LONGITUDINAL BUFFER AREA, TO ALLOW WORKERS TIME TO EVACUATE THE WORK AREA, SHOULD BE PROVIDED. FOR GUIDELINES ON SETTING THE LENGTH OF THIS BUFFER, SEE STANDARD DRAWING TCS2-1-(LATEST REVISION). ACTUAL LENGTH SHALL BE DETERMINED BY FIELD CONDITIONS AND THE JUDGEMENT OF THE ENGINEER.


NOTE

TYPE III BARRICADES WITH SIGNS READING "LANE CLOSED" (R11-2) SHALL BE PLACED EVERY 2,000 FEET THROUGH ACTIVITY AREA AND LOGITUDINAL BUFFERS LONGER THAN THAT SHOWN. THESE TYPE III BARRICADES AND SIGNS MAY BE OMITTED ON MOVING OPERATIONS AND SHORT DURATION PROJECTS.

NOTE 7

CONSTRUCTION SPEED LIMIT TO BE DETERMINED BY THE DIVISION ENGINEER.

FOR ADDITIONAL INFORMATION ABOUT TAPER LENGTHS AND SPACING OF CHANNELIZING DEVICES, SEE STANDARD DRAWING TCS2-1-(LATEST REVISION).





TRAFFIC CONTROL DETAIL (BRIDGE E, F)

NOT TO SCALE

 Drawn
 SC
 5/16

 Design
 SC
 5/16

 Checked
 SEB
 5/16

 TRAFFIC ENGINEERING

 JAMI SHORT

STATE OF DEPARTMENT OF TRANSPORTATION OKLAHOMA DIVISION 8 JOSPHECENO. 31943(04) SHEETNO. TOO2