

GENERAL NOTES

REVISIONS		
REV. NO.	DESCRIPTION	DATE
1	Rev. Note	8/9/2016

SPECIFICATIONS:

Comply with the requirements of the 2009 Oklahoma Standard Specifications for Highway Construction, except as modified by the Plans and Special Provisions.

VERIFICATION OF EXISTING CONDITIONS:

Bidders shall fully inform themselves of the nature of the work and conditions under which it will be performed. The Contractor shall adopt methods consistent with good construction practice and shall take all necessary precautions to prevent damage to the existing bridges or attachments. Any damage to the existing bridge structure or roadway due to the Contractor's negligence shall be repaired at the Contractor's expense, to the satisfaction of the Engineer.

EXISTING BRIDGE PLANS:

Construction plans for the existing bridge structures may be obtained from the Printing Services Branch of the Oklahoma Department of Transportation. Ask for:

OSAGE COUNTY:

Bridge "A" Project No. NHPPY-257N(020)SS
Job Piece No. 24287(04)

OSAGE COUNTY

Bridge "B" Project No. NHPPY-257N(020)SS
Job Piece No. 24287(04)

PAWNEE-OSAGE COUNTY:

Bridge "C" Project No. STPY-159B(036)
Job Piece No. 20895(04)

CREEK COUNTY:

Bridge "D" PROJECT NO. STPY-119C(119)SS
Job Piece No. 21908(04)

TULSA COUNTY:

Bridge "E" Project No. NHPPY-0244-2(502)SS
Job Piece No. 27145(04)

TULSA COUNTY:

Bridge "F" Project No. NHPPY-172N(319)
Job Piece No. 23167(04)

ROGERS COUNTY:

Bridge "G" Project No. STPY-166C(208)
Job Piece No. 24957(04)

ROGERS COUNTY:

Bridge "H" Project No. SBR-266N(027)SB
Job Piece No. 29777(04)

ROGERS COUNTY:

Bridge "I" Project No. SBR-266N(026)SB
Job Piece No. 29774(04)

CRAIG COUNTY:

Bridge "J" Project No. STPY-118B(067)SS
Job Piece No. 23126(04)

CRAIG COUNTY:

Bridge "K" Project No. STPY-118B(067)SS
Job Piece No. 23126(04)

OTTAWA COUNTY:

Bridge "L" Project No. SSP-158C(131)SS
Job Piece No. 24277(04)

OTTAWA COUNTY:

Bridge "M" Project No. STPY-158C(077)
Job Piece No. 21918(04)

OTTAWA COUNTY:

Bridge "N" Project No. SPP-158C(128)SS
Job Piece No. 24276(04)

DELAWARE COUNTY:

Bridge "O" Project No. BRFY-021C(256)
Job Piece No. 10441(04)

MAYES COUNTY:

Bridge "P" Project No. STP-149C(082)SS
Job Piece No. 21911(04)

MAYES COUNTY:

Bridge "Q" Project No. STPY-149C(076)
Job Piece No. 21909(04)

LANE CLOSURE:

The Engineer reserves the right to prohibit lane closures during holidays or special events. All work requiring the closing or narrowing of one lane of traffic on the bridges shall be performed during daylight hours only unless approved by the engineer except for Bridges E, F, G, H, and I work may need to be done at night to avoid work being done in Tulsa. Traffic on bridges shall be returned to normal during night time hours except for Bridges E, F, G H, and I unless directed by the Engineer. The Contractor shall make every effort to reopen these lane closures as soon as possible.

PENETRATING WATER REPELLENT SURFACE TREATMENT:

A performance tested penetrating water repellent surface treatment shall be applied to the driving surface of the Bridge Decks and Approach Slabs in accordance with the Standard Specifications for Highway Construction.

The bridges have a detail sheet showing the extent of the surfaces to be treated. The Contractor shall only treat the surfaces shown in the plans.

BRIDGE "A" - "Q"	TULSA COUNTY	Design	N/A	N/A
GENERAL NOTES (BRIDGE)		Detail	DJG	4/16
		Check	KMS	4/16
		Squad	MAYFIELD	
	Eng:	ELYAZGI		
STATE OF OKLAHOMA	DEPARTMENT OF TRANSPORTATION	JOBPIECE NO.	31943(04)	SHEET NO.
				AB01