

DESCRIPTION	REVISIONS	DATE
-------------	-----------	------

JP 28825(04) ROADWAY - 0100				
<b>PAY QUANTITIES (ROADWAY)</b>				
PAY ITEM	CODE NO.	DESCRIPTION	UNIT	QUANTITY
201(A)	0102	CLEARING AND GRUBBING	LSUM	1
202(A)	0183	UNCLASSIFIED EXCAVATION	(R-1)(R-4) CY	26,288
202(D)	0184	UNCLASSIFIED BORROW	(R-4) CY	8,644
205(A)	4230	TYPE A SALVAGED TOPSOIL	(R-5)(R-7) CY	6,789
221(C)	2801	TEMPORARY SILT FENCE	LF	1,368
221(F)	0100	TEMPORARY SILT DIKE	LF	140
221(G)	0150	TEMPORARY ROCK FILTER DAM TYPE 1	CY	20
230(A)	2806	SOLID SLAB SODDING	(R-7)(R-8) SY	36,464
233(A)	2817	VEGETATIVE MULCHING	(3)(R-11) AC	5.70
241	2832	MOWING	(R-16) AC	28.50
307(K)	4300	STABILIZED SUBGRADE	(1)(R-1) SY	7,888
310(B)	0149	SUBGRADE, METHOD B	(R-1) SY	1,412
407(B)	0250	TACK COAT	GAL	4,583
408	5774	PRIME COAT	(R-28) GAL	7,086
411(B)	5940	SUPERPAVE, TYPE S3 (PG 70-28 OK)	(R-32) TON	693
411(B)	5945	SUPERPAVE, TYPE S3 (PG 64-22 OK)	(R-32) TON	4,342
411(C)	5955	SUPERPAVE, TYPE S4 (PG 70-28 OK)	(R-32) TON	594
411(C)	5960	SUPERPAVE, TYPE S4 (PG 64-22 OK)	(R-32) TON	1,272
613(A)	4496	28" X 18" R.C. PIPE ARCH CLASS A-III	LF	70
613(A)	4497	36" X 22" R.C. PIPE ARCH CLASS A-III	LF	96
613(A)	4498	43" X 26" R.C. PIPE ARCH CLASS A-III	LF	108
613(B)	0689	18" CORR. GALV. STEEL PIPE	(R-46) LF	32
613(B)	0690	24" CORR. GALV. STEEL PIPE	(R-46) LF	87
613(B)	0697	66" CORR. GALV. STEEL PIPE	(R-46) LF	203
613(B)	5075	108" CORR. GALV. STEEL PIPE	(R-46) LF	110
613(M)	7197	TYPE B6 CULVERT END TREATMENT	EA	4
613(M)	7198	TYPE C6 CULVERT END TREATMENT	EA	2
619(A)	0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	(R-48)(R-49) LSUM	1
619(B)	4725	REMOVAL OF FENCE	(R-49) LF	4,291
619(B)	4728	REMOVAL OF ASPHALT PAVEMENT	(R-49)(R-50) SY	12,876
619(B)	4767	REMOVAL OF ASPHALT DRIVEWAY	(R-49)(R-50) SY	1,355
619(B)	4780	REMOVAL OF GUARDRAIL	(R-49) LF	566
623(A)	0932	BEAM GUARDRAIL W-BEAM SINGLE	LF	756.25
623(F)	8300	GUARDRAIL TRAIL END TURNDOWN (31")	EA	2
623(G)	8590	GUARDRAIL END TREATMENT (31")	(2) EA	4
623(I)	8700	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	EA	4
624(C)	4459	FENCE-STYLE SWF (5 BARBED WIRE)	(R-52)(R-53) LF	4,431

JP 28825(04) STAKING - 0800				
<b>PAY QUANTITIES (STAKING)</b>				
PAY ITEM	CODE NO.	DESCRIPTION	UNIT	QUANTITY
642(B)	0096	CONSTRUCTION STAKING LEVEL II	(4) LSUM	1

JP 28825(04) CONSTRUCTION - 0640				
<b>PAY QUANTITIES (CONSTRUCTION)</b>				
PAY ITEM	CODE NO.	DESCRIPTION	UNIT	QUANTITY
220	2800	SWPPP DOCUMENTATION AND MANAGEMENT	LSUM	1
641	1552	MOBILIZATION	(4) LSUM	1

### SUGGESTED SEQUENCE OF CONSTRUCTION

- CONSTRUCT TEMPORARY DETOUR.
- SHIFT TRAFFIC TO TEMPORARY DETOUR. REMOVE EXISTING SH-34 SECTION AND BRIDGE. CONSTRUCT NEW SH-34 SECTION AND BRIDGE.
- SHIFT TRAFFIC TO NEW SH-34 SECTION, REMOVE TEMPORARY DETOUR AND PERFORM FINISHING OPERATIONS.

### PAY ITEMS & NOTES (ROADWAY)

- (R-1) PAYMENT FOR THIS ITEM WILL BE BASED ON PLAN QUANTITY ONLY. SEE SECTION 109.01B OF THE STANDARD SPECIFICATIONS.
- (R-4) INCLUDES 1,000 CU. YDS. FOR DRIVEWAYS, RETURNS, DIKES, AND MISCELLANEOUS EARTHWORK.
- (R-5) AN ESTIMATED QUANTITY OF 6,789 C.Y. TOPSOIL TO BE RESERVED FOR REPLACEMENT OF APPROXIMATELY 5" ON COMPLETED FORESLOPES, DITCHES, AND BACKSLOPES. THIS QUANTITY IS INCLUDED IN THE EARTHWORK BALANCE. ANY ADDITIONAL EXCAVATION REQUIRED IN CUT SECTIONS TO ALLOW FOR PLACEMENT OF TOPSOIL TO FINAL GRADE, SHALL BE INCLUDED IN THE PRICE BID.
- (R-7) FOR TYPE A SALVAGED TOPSOIL, PRICE BID TO INCLUDE COST OF 10-20-10 FERTILIZER, ESTIMATED AT 200 POUNDS PER 1,000 SQUARE YARDS.
- FOR SOLID SLAB SODDING, PRICE BID TO INCLUDE COST OF 10-20-10 FERTILIZER ESTIMATED AT 200 POUNDS PER 1,000 SQUARE YARDS.
- (R-8) FOR SOLID SLAB SODDING, PRICE BID TO INCLUDE COST OF WATERING, ESTIMATED AT 40 GALLONS PER SQUARE YARD.
- (R-11) THE QUANTITIES ESTIMATED FOR TEMPORARY EROSION AND SEDIMENT CONTROL IS 5.70 ACRES.
- (R-16) QUANTITY BASED ON TWO APPLICATIONS.
- (R-28) PRIME COAT SHALL BE APPLIED AT AN ESTIMATED RATE OF 0.35 GAL. PER SQ. YD. WHEN APPLIED TO SUBGRADE, AND 0.25 GAL. PER SQ. YD. WHEN APPLIED TO AGGREGATE BASE. THE ACTUAL CUTBACK PRIME COAT REQUIRED FOR PLACEMENT OPERATIONS WILL BE DETERMINED BY THE CONTRACTOR, AND SHALL CONSIDER THE RESIDUE FROM DISTILLATION PERCENTAGE SHOWN IN SECTION 708.03 OF THE STANDARD SPECIFICATIONS.
- (R-32) ESTIMATED AT 112 LBS. PER SQ. YD PER 1" THICK.
- (R-46) ANY DRAINAGE STRUCTURE DESCRIBED AS TEMPORARY, SHALL AFTER COMPLETION OF THE PROJECT, BE REMOVED BY AND BECOME THE PROPERTY OF THE CONTRACTOR.
- (R-48) INCLUDES REMOVAL OF ALL EXISTING ROADWAY DRAINAGE STRUCTURES, HEADWALLS (UNLESS OTHERWISE SPECIFIED), INLETS, FENCES, AND OTHER STRUCTURES WITHIN THE RIGHT OF WAY.
- (R-49) TO BECOME THE PROPERTY OF AND BE DISPOSED OF BY THE CONTRACTOR IN A MANNER APPROVED BY THE ENGINEER.
- (R-50) MATERIALS REMOVED SHALL NOT BE MEASURED FOR PAYMENT UNDER SECTION 202.06 UNCLASSIFIED EXCAVATION.
- (R-52) INCLUDES 2% FOR GROUND MEASUREMENT.
- (R-53) ALL GATES AND GATE END POSTS FOR STRANDED WIRE FENCE (SWF) SHALL BE CONSTRUCTED AT THE SAME WIDTH AS THE EXISTING, UNLESS OTHERWISE DIRECTED BY THE ENGINEER.
- (1) STABILIZED SUBGRADE TO PAID FOR BY THE SQUARE YARD IN ACCORDANCE TO SECTION 307.06 IN THE 2009 ODOT SPECIFICATIONS. THE SOILS REPORT INDICATED THE USE OF CHEMICAL ADDITIVES SHOULD NOT BE PROBLEMATIC WITH REGARDS TO SOLUBLE SULFATES, BUT CAUTION SHOULD BE USED WITH REGARDS TO THE POTENTIAL OF RANDOMLY OCCURRING HIGH SULFATE AREAS NOT FOUND IN THE SOILS INVESTIGATION.
- (2) THIS PAY ITEM WILL INCLUDE THE SKT-SP-MSG OR APPROVED SUBSTITUTE. THE ET-PLUS WILL NOT BE ALLOWED.
- (3) THIS ITEM SHALL BE WHEAT HAY ONLY.
- (4) THE BID PRICE FOR STAKING & MOBILIZATION WILL INCLUDE THIS PROJECT, AND THE MANDATORY TIED PROJECT, JOB PIECE 28827(04).

### EROSION CONTROL AND CONSTRUCTION NOTES

SOLID SLAB SODDING SHALL BE PLACED ON ALL DISTURBED AREAS.

AT THE BEGINNING OF SODDING OPERATIONS, ANY AREA INCLUDED IN THE PLANNED QUANTITIES THAT HAS GROWN A SATISFACTORY TURF OF PERENNIAL GRASS, AS DETERMINED BY THE ENGINEER, SHALL NOT BE SODDED, WATERED OR FERTILIZED.

TEMPORARY EROSION CONTROL: IF THE DIRT WORK IS COMPLETED AFTER THE APPROVED PLANTING SEASON FOR SODDING HAS ENDED, DISTURBED AREAS WILL BE PLANTED WITH A TEMPORARY COVER CROP CONSISTING OF WHEAT OR OTHER SMALL GRAIN AT THE RATE OF 20 POUNDS/ACRE IN ACCORDANCE WITH SECTION 232 OF THE STANDARD SPECIFICATIONS. COST OF TEMPORARY COVER CROP TO BE INCLUDED IN THE PRICE BID FOR SOLID SLAB SODDING.

### GENERAL CONSTRUCTION NOTES

THIS PROJECT SHALL BE CONSTRUCTED WITHOUT CLOSING THE EXISTING ROAD TO LOCAL AND THROUGH TRAFFIC. SEE STANDARD SPECIFICATIONS FOR MAINTENANCE OF LOCAL AND THROUGH TRAFFIC.

MAINTENANCE OF THROUGH TRAFFIC INCLUDES THE MAINTENANCE OF THE EXISTING ROAD IN CLOSE PROXIMITY TO THE NEW CONSTRUCTION AS SHOWN ON THE PLANS.

THIS PROJECT SHALL BE CONSTRUCTED WITHOUT CLOSING THE EXISTING SECTION LINE ROADS TO LOCAL AND THROUGH TRAFFIC. SEE STANDARD SPECIFICATIONS FOR MAINTENANCE OF LOCAL AND THROUGH TRAFFIC.

ALL TREES, BRUSH, AND OTHER DEBRIS THAT MIGHT INTERFERE WITH THE FLOW OF WATER SHALL BE CLEANED OUT TO THE RIGHT-OF-WAY LINE, AT EACH STRUCTURE AND BRIDGE, IN A MANNER APPROVED BY THE ENGINEER. ALL COST TO BE INCLUDED IN OTHER ITEMS OF WORK.

THE CONTRACTOR SHALL PROVIDE ALL TEMPORARY RIGHT-OF-WAY FENCE AS REQUIRED. WHEN THE PORTION OF THE PROJECT THAT REQUIRED THIS FENCE IS COMPLETED, THE TEMPORARY FENCE SHALL BE REMOVED, AND PERMANENT RIGHT-OF-WAY FENCING SHALL BE RESTORED OR INSTALLED IN A MANNER APPROVED BY THE ENGINEER. ALL COST OF TEMPORARY FENCING SHALL BE INCLUDED IN OTHER ITEMS OF WORK.

ALL FLOWLINES THAT ARE TO BE FILLED SHALL BE THOROUGHLY TAMPED BEFORE CONSTRUCTION OR EXTENSION OF DRAINAGE STRUCTURES. ALL COST TO BE INCLUDED IN OTHER ITEMS OF WORK.

IN ORDER TO ALLEVIATE DUST CONDITIONS DURING GRADING OPERATIONS AND BEFORE PAVEMENT WORK IS COMPLETED, THE CONTRACTOR SHALL SPRINKLE GRADING AT INTERVALS APPROVED BY THE ENGINEER. ALL COST TO BE INCLUDED IN OTHER ITEMS OF WORK.

THIS PROJECT IS LOCATED NEAR KNOWN SOURCES OF GYPSUM (SULFATE) DEPOSITS. SPECIAL ATTENTION SHOULD BE USED TO AVOID BORROW MATERIAL THAT COULD ADVERSELY INTERACT WITH THE CALCIUM BASED ADDITIVES (FLY ASH, PORTLAND CEMENT, CEMENT KILN DUST, AND LIME) USED IN THE STABILIZED SUBGRADE. THE CONTRACTOR MAY BE REQUIRED TO PROVIDE SULFATE TESTING OF BORROW PIT SITES AS DIRECTED BY THE ENGINEER.

THE CONTRACTOR SHALL NOT WASTE ANY EXCESS EXCAVATION UNTIL ALL PLANNED EMBANKMENTS AND BACKFILLS ARE COMPLETED. EXCESS UNCLASSIFIED EXCAVATION MATERIAL DETERMINED BY THE ENGINEER TO BE SUITABLE FOR BACKFILL SHALL BE USED TO REDUCE ANY UNCLASSIFIED BORROW NEEDED. COST OF SECOND HANDLING SHALL BE INCLUDED IN OTHER ITEMS OF WORK. ANY REMAINING EXCESS EXCAVATION SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND BE DISPOSED OF IN A MANNER APPROVED BY THE ENGINEER.

PRIME COAT SHALL BE APPLIED TO THE SUBGRADE IMMEDIATELY AFTER FINAL COMPACTION AND SHAPING TO RETAIN MOISTURE FOR PROPER CHEMICAL REACTION OF THE SOIL ADDITIVE.

THE CONTRACTOR SHALL KEEP THE OPEN TRENCH DRAINED. COST TO BE INCLUDED IN OTHER ITEMS OF WORK.

VEGETATIVE MULCHING: THE VEGETATIVE MULCH SHALL BE ANCHORED IN ACCORDANCE WITH THE "MULCHING-TILLER METHOD", AS SPECIFIED IN 233.04B(2) OF THE STANDARD SPECIFICATIONS.

AREAS ON WHICH SALVAGED TOPSOIL IS TO BE REPLACED SHALL HAVE 18-46-0 FERTILIZER APPLIED, AT THE RATE OF 150 POUNDS PER ACRE, JUST PRIOR TO THE REPLACEMENT OF SALVAGED TOPSOIL.

SURFACING OF RETURNS, UNLESS OTHERWISE SHOWN ON THE PLANS, SHALL BE OF THE SAME MATERIAL (BASE AND SURFACE) AS THAT OF THE ABUTTING SHOULDER OF THE MAINLINE. BASE AND SURFACE THICKNESS SHALL BE THE THICKNESS SHOWN ON PLANS.

EXCESS ASPHALT AT JOINTS AND CRACKS IN EXISTING PAVEMENT SHALL BE REMOVED FLUSH TO TOP OF PAVING IN A MANNER APPROVED BY THE ENGINEER.

IN ACCORDANCE WITH THE OKLAHOMA UNDERGROUND FACILITIES DAMAGE PREVENTION ACT THE CONTRACTOR SHALL NOTIFY THE OKLAHOMA ONE-CALL SYSTEM, INC. 48 HOURS PRIOR TO BEGINNING EXCAVATION. OKLAHOMA ONE-CALL SYSTEM, INC. "CALL OKIE" 1-800-522-6543 OR 811.

### ENVIRONMENTAL NOTES

CLIFF SWALLOWS AND BARN SWALLOWS ARE SMALL COLONIAL NESTING BIRDS PROTECTED BY THE FEDERAL MIGRATORY BIRD TREATY ACT. THESE SPECIES COMMONLY USE BRIDGES AND CULVERTS FOR NESTING. THE NESTING SEASON FOR THE SWALLOWS RUNS FROM APRIL 1 TO AUGUST 31. ANY ACTIVITIES WHICH WOULD DESTROY ACTIVE NESTS OR HARM EGGS OR BIRDS WOULD VIOLATE THE MIGRATORY BIRD TREATY ACT. SWALLOW USE OF BRIDGE NBI NO. 03426 WAS NOT OBSERVED DURING THE INITIAL SURVEYS CONDUCTED AS PART OF THE BIOLOGICAL STUDIES IN 2013. SWALLOWS MAY OCCUPY THE BRIDGE IN FUTURE NESTING SEASONS. THE RESIDENT ENGINEER WILL EVALUATE THE CONTRACTOR'S PROPOSED WORK METHODS AND CONCLUDE WHETHER THE PROPOSED WORK WOULD POSE DISRUPTION TO ANY NESTING BIRDS BEFORE WORK NEAR THE STRUCTURE IS AUTHORIZED. IF THE PROPOSED WORK WILL HARM ANY NESTING BIRDS, THE BRIDGE MAY BE NETTED PRIOR TO APRIL 1 OR THE WORK DELAYED UNTIL THE NESTING SEASON IS COMPLETE. METHODS OTHER THAN NETTING MUST BE PRE-APPROVED BY THE ODOT BIOLOGISTS.

FILENAME: 3 PAY QUANTITIES & NOTES (ROADWAY).DWG

DESIGN		SH-34 OVER S. PERSIMMON CREEK	WOODWARD COUNTY
DRAWN		<b>PAY ITEMS &amp; NOTES (ROADWAY)</b>	
CHECKED			
CEC			
		STATE JOB NO. 28825(04)	SHEET NO. 3