

DESCRIPTION	REVISIONS	DATE

JP 28825(04) 0301					
PAY QUANTITIES (PERMANENT TRAFFIC)					
PAY ITEM	CODE NO.	DESCRIPTION	UNIT	QUANTITY	
850(A)	8110	SHEET ALUMINUM SIGNS (TS-34)	SF	28.36	
851(C)	8327	2 1/4" SQUARE TUBE POST (TS-33)	LF	12	
851(C)	8330	2 1/2" SQUARE TUBE POST (TS-33)	LF	48	
853	9069	GUARDRAIL DELINEATORS (TYPE 2, CODE 1)	EA	23	
856(A)	8530	TRAFFIC STRIPE (MULTI-POLY.) (4" WIDE) (TS-24)	LF	5,481	

JP 28825(04) 0302						
PAY QUANTITIES (TEMPORARY TRAFFIC)						
PAY ITEM	CODE NO.	DESCRIPTION	UNIT	JP 28825(04)	JP 28827(04)	
857(A)	8839	CONSTRUCTION TRAFFIC STRIPE (PAINT) (4" WIDE) (TC-16)(TC-17)(TC-20)(TC-70)(TC-75)	LF	11,692	10,800	
857(F)	8006	PAVEMENT MARKING REMOVAL (TRAFFIC STRIPE) (TC-22)(TC-70)(TC-75)	LF	1,397	1,322	
880(B)	8818	CONSTRUCTION SIGNS 0 TO 6.25 SF (TC-26)(TC-33)(TC-84)	SD	4,800	4,800	
880(B)	8821	CONSTRUCTION SIGNS 6.26 TO 15.99 SF (TC-26)(TC-33)(TC-84)	SD	4,800	2,880	
880(B)	8824	CONSTRUCTION SIGNS 16.0 TO 32.99 SF (TC-26)(TC-30)(TC-33)(TC-84)	SD	3,360	3,360	
880(C)	8842	CONSTRUCTION BARRICADES (TYPE III) (TC-26)(TC-84)	SD	2,880	960	
880(C)	8848	WING BARRICADES (TC-26)(TC-84)	SD	960	960	
880(E)	8860	WARNING LIGHTS (TYPE A) (TC-26)(TC-84)	SD	7,680	3,840	
880(G)	8890	CHANNELIZER CONES (TC-26)(TC-84)	SD	23,040	23,040	
882(A)	8306	PORTABLE CHANGEABLE MESSAGE SIGN (SP-1)(TC-52)(TC-84)(TC-85)	SD	14	14	

NOTE:
PAY ITEM NOTES LISTED ONLY PERTAIN TO JP 28825(04). FOR ADDITIONAL PAY ITEM NOTES SPECIFIC TO JP 28827(04), REFER TO THE JP 28827(04) PLAN SHEETS.

MANDATORY TIE

THIS PROJECT SHALL BE MANDATORILY TIED WITH WOODWARD COUNTY JOB PIECE 28827(04) AND SHALL BE BID ACCORDINGLY.

PAY ITEMS & NOTES (PERMANENT TRAFFIC)

- (TS-24) QUANTITY SHOWN INCLUDES 3,350 L.F. TRAFFIC STRIPE (MULTI-POLYMER)(WHITE) AND 2,131 L.F. TRAFFIC STRIPE (MULTI-POLYMER)(YELLOW) AND WILL BE MEASURED BY THE LINEAR FOOT OF FOUR INCH (4") WIDE TRAFFIC STRIPE.
- (TS-33) INCLUDED IN THIS PAY ITEM IS ALL HARDWARE ASSOCIATED WITH PROPERLY ANCHORING AND MOUNTING THE HIGHWAY SIGN IN ACCORDANCE WITH O.D.O.T. PLANS AND STANDARD DRAWINGS SSA1-1 AND SSP1-1-(LATEST REVISION).
- (TS-34) INCLUDED IN THIS PAY ITEM IS THE REMOVAL OF ANY EXISTING SIGNS TO BE REPLACED BY NEW ASSEMBLIES AND THE REMOVAL OF ANY EXISTING SIGNS THAT WILL BE IN CONFLICT WITH THE NEW ROADWAY OR NEW SIGNAGE.

PAY ITEMS & NOTES (TEMPORARY TRAFFIC)

- (TC-16) PAINT SHALL CONFORM TO SECTION 711 "TRAFFIC STRIPE", OF THE O.D.O.T. STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION (CURRENT EDITION).
- IF CONSTRUCTION TRAFFIC STRIPE PAINT IS INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS AND FAILS DURING THE FIRST SIX MONTHS OF SERVICE, REPLACEMENT WILL BE MADE AT THE CONTRACTOR'S EXPENSE AND SHALL BE ACCOMPLISHED IN A TIMELY MANNER UPON NOTIFICATION BY THE ENGINEER OF SUCH FAILURE.
- (TC-17) INCLUDES AN ESTIMATED 5,846 L.F. (PAINT)(4" WIDE) WHITE 5,846 L.F. (PAINT)(4" WIDE) YELLOW STRIPE.
- (TC-20) ALL STRIPING TO BE PLACED ON TEMPORARY SURFACES OR ON SURFACES SCHEDULED TO BE REMOVED SHALL BE DONE WITH PAINT UNLESS OTHERWISE NOTED ON THE PLANS OR STANDARD DRAWINGS. TEMPORARY PAVEMENT MARKINGS PLACED ON FINISHED PAVEMENT OR EXISTING PAVEMENT TO REMAIN IN PLACE SHALL USE ONE OF THE FOLLOWING METHODS:
- REMOVABLE PAVEMENT MARKING TAPE
 - CLASS A PAVEMENT MARKERS
- (TC-22) AMOUNT SHOWN IS AN APPROXIMATION AND THE ACTUAL AMOUNT OF REMOVAL, IF NECESSARY, SHALL BE DETERMINED BY THE ENGINEER. PRICE BID FOR PAVEMENT MARKING REMOVAL SHALL INCLUDE THE COST OF REMOVING STRIPE, ARROWS, WORDS AND SYMBOLS, AS SHOWN IN THE PLANS. THESE ITEMS MAY CONSIST OF PLASTIC, PAINT OR NON-REMOVABLE MARKING TAPE.
- (TC-26) ALL CONSTRUCTION TRAFFIC CONTROL WILL BE IMPLEMENTED ACCORDING TO CONSTRUCTION PLANS, AND INSTALLED IN A MANNER APPROVED BY THE ENGINEER, IN ACCORDANCE WITH CHAPTER VI OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, (CURRENT EDITION), AND COMPLIANT WITH APPLICABLE O.D.O.T. STANDARD DRAWINGS. PRICE BID FOR THIS ITEM SHALL BE PAYMENT IN FULL FOR THE INSTALLATION, MAINTENANCE AND SUBSEQUENT REMOVAL OF ALL NECESSARY CONSTRUCTION TRAFFIC CONTROL DEVICES REQUIRED FOR COMPLETION OF THE PROJECT.
- ALL SIGNS AND BARRICADES WHICH ARE SHOWN WITH TYPE 'A' LIGHTS IN THE STANDARD DRAWINGS SHALL HAVE THE CORRESPONDING LIGHT ATTACHED DURING NON-DAYLIGHT HOURS.
- (TC-30) INCLUDED IN THIS ITEM ARE ALL S.C.S. (SPECIAL CONSTRUCTION SIGNING) SIGNS WHICH ARE BETWEEN 16.00 S.F. AND 32.99 S.F. ALSO INCLUDED IN THIS ITEM SHALL BE THE COST OF INSTALLATION, MAINTENANCE, AND REMOVAL OF THESE SIGNS.
- (TC-33) ALL CONSTRUCTION WORK ZONE SIGNS SHALL HAVE FLUORESCENT SHEETING. THE FLUORESCENT SHEETING SHALL MEET THE REQUIREMENTS OF ASTM D4956 (LATEST REVISION)
- THE MANUFACTURER SHALL FURNISH A TYPE 'D' CERTIFICATION IN ACCORDANCE WITH O.D.O.T. STANDARD SPECIFICATIONS (CURRENT EDITION) SUBSECTION 106.04. THE CERTIFICATION SHALL INCLUDE TEST RESULTS ON MATERIAL SUBMITTED FOR APPROVAL.
- (TC-52) ANY USED CHANGEABLE MESSAGE SIGN TO BE PLACED ON THIS PROJECT SHALL BE SUBJECT TO INSPECTION AND APPROVAL, BY THE OKLAHOMA DEPARTMENT OF TRANSPORTATION, TO ASSURE THAT THEY ARE IN GOOD WORKING CONDITION, PRIOR TO PLACEMENT OF THE PROJECT.
- (TC-70) THIS ITEM IS AN ESTIMATED QUANTITY TO BE USED AS DEEMED NECESSARY BY THE ENGINEER.
- (TC-75) TEMPORARY PAVEMENT MARKINGS SHALL BE IN PLACE THE SAME DAY THAT EXISTING PAVEMENT MARKINGS ARE REMOVED FROM ANY ROADWAY OPEN TO TRAFFIC. ALSO, ALL TEMPORARY PAVEMENT MARKINGS SHALL BE REMOVED PRIOR TO THE INSTALLATION OF FINAL STRIPING.
- (TC-84) 240 CONSTRUCTION CALENDAR DAYS WERE USED TO COMPUTE THE SIGN DAY PAY ITEMS. THE AMOUNT OF CALENDAR DAYS USED TO COMPUTE THE SIGN DAY PAY ITEMS IS AN ESTIMATED QUANTITY ONLY, BASED ON THE CURRENT O.D.O.T. STANDARDS AND SUGGESTED CONSTRUCTION SEQUENCE FOR THIS PROJECT. THESE ESTIMATED SIGN DAY QUANTITIES MAY CHANGE AS THE PROJECTS CONSTRUCTION TRAFFIC CONTROL IS MODIFIED DURING CONSTRUCTION.
- (TC-85) THESE SIGNS MUST BE ON THE OKLAHOMA DEPARTMENT OF TRANSPORTATION LIST OF APPROVED CHANGEABLE MESSAGE SIGNS. FOR A LIST OF THE APPROVED SIGNS GO TO THE OKLAHOMA DEPARTMENT OF TRANSPORTATION WEBSITE AT:
<http://www.okladot.state.ok.us/traffic/qpl/index.php>
- (SP-1) SIGN PLACEMENT LOCATIONS SHALL BE DETERMINED BY THE ENGINEER.

FILENAME: 3A PAY QUANTITIES & NOTES (TRAFFIC).DWG

DESIGN		SH-34 OVER S. PERSIMMON CREEK	WOODWARD COUNTY
DRAWN		PAY ITEMS & NOTES (TRAFFIC)	
CHECKED			
CEC		STATE JOB NO. <u>28825(04)</u>	SHEET NO. <u>3A</u>