

**THIS PROJECT IS A MANDATORY TIE TO A NEARBY PROJECT, JOB PIECE NUMBER 28825(04)**

STATE OF OKLAHOMA  
DEPARTMENT OF TRANSPORTATION

PLAN OF PROPOSED  
**STATE HIGHWAY**  
FEDERAL AID PROJ. NO. ACSTP-277B(035)SS  
BRIDGE AND APPROACHES  
SH-34 OVER NORTH PERSIMMON CREEK  
WOODWARD COUNTY

STATE JOB NO. 28827(04)  
CONTROL SECTION NO. 34-77-16

BRIDGE "A" LOCATION NO. 7716 0757 X  
EXISTING NBI NO. 03444; NEW NBI NO. 31750

**DESIGN DATA**

ADT 2016 = 2,120  
ADT 2036 = 3,030  
DHV (2-WAY) = 333  
K (DHV/ADT) = 11%  
D = 55%  
T (% DHV) = 20%  
T (% ADT) = 17%  
T' (% ADT) = 13%  
V = 65 MPH  
(20YR)FLEX ESAL's = 3.2M

BRIDGE "A"

EXIST. NBI NO. 03444  
NEW NBI NO. 31750  
LOCATION NO. 7716 0757 X  
BEGIN STA. 2440+65.16  
END STA. 2443+66.83  
LENGTH 301.67 FT

**SCALES**


PLAN 1"=50'  
PROFILE HOR. 1"=50'  
PROFILE VERT. 1"=5'  
LAYOUT MAP N.T.S.

**CONVENTIONAL SYMBOLS**

- PROPOSED ROADS
- SECTION LINES
- QUARTER SECTION LINES
- x- FENCES (EXISTING)
- - - EXISTING GRADE
- - - EXISTING ROADS
- - - EXISTING INDEX CONTOURS
- - - EXISTING INTERMEDIATE CONTOURS
- BASE LINE
- PROPOSED GRADE
- FOC COMMUNICATION LINES (EXISTING)
- OHE POWER LINES (EXISTING)
- G GAS LINE (EXISTING)
- SS SANITARY SEWER LINES (EXISTING)
- W WATER LINES (EXISTING)
- OHE COMMUNICATION LINES (PROPOSED)
- G POWER LINES (PROPOSED)
- SS SANITARY SEWER LINES (PROPOSED)
- W WATER LINES (PROPOSED)
- /// BUILDINGS (EXISTING)
- DRAINAGE STRUCTURES (EXISTING)
- DRAINAGE STRUCTURES (PROPOSED)
- RIGHT-OF-WAY LINES (EXISTING)
- RIGHT-OF-WAY LINES (PROPOSED)
- RIGHT-OF-WAY FENCE
- FLOWLINE (EXISTING)
- FLOWLINE (PROPOSED)
- TOE OF SLOPE (EXISTING)



STA. 2428+49.86  
BEGIN INCIDENTAL  
CONST.



STA. 2455+03.88  
END INCIDENTAL CONST.

STA. 2449+50.00  
END PROJECT  
BEGIN INCIDENTAL  
CONST.  
T-21-N

STA. 2434+50.00  
END INCIDENTAL CONST.  
BEGIN PROJECT  
CONTROL SUBSECTION 7.45

**INDEX OF SHEETS**

SHT. NO.	DESCRIPTION
1.	TITLE SHEET
2.	TYPICAL SECTIONS
3.	PAY ITEMS & NOTES (ROADWAY)
3A.	PAY ITEMS & NOTES (TRAFFIC)
4.	BRIDGE GENERAL NOTES
5.	PAY ITEMS & NOTES (BRIDGE)
6.	SUMMARY SHEET
7.-7A.	MASS DIAGRAMS
8.	STORM WATER MANAGEMENT PLAN
9.	DRAINAGE AREA MAP
10.	SURVEY DATA TITLE SHEET
11.	HISTORICAL LETTER & WRITTEN REPORT
12.	LEVELS, COGO POINTS & ALIGNMENT REPORT
13.	CONTROL MAP & INFORMATION
14.-15.	SURVEY DATA SHEETS
16.	LAND TIE SHEET
17.	EROSION CONTROL SHEET
18.-19.	PLAN & PROFILE SHEETS
20.	GENERAL PLAN AND ELEVATION
21.	SUMMARY OF BRIDGE PAY QUANTITIES
22.	FOUNDATION REPORT
23.	SUBSTRUCTURE LAYOUT
24.	SUBSTRUCTURE EXCAVATION AT PIERS
25.	ABUTMENT DETAILS
26.	ABUTMENT WING DETAILS
27.-29.	PIER NO. 1 AND 2 DETAILS
30.	PIER STEEL PILING DETAIL AND BAR LIST
31.	TYPICAL CROSS SECTION
32.	LONGITUDINAL SECTION
33.	BEAM FRAMING PLAN
34.	P.C.B. DETAILS-TYPE IV
35.	DIAPHRAGM AND BEARING DETAILS
36.	SUPERSTRUCTURE DETAILS
37.	ADDITIONAL SLAB REINFORCING
38.	SLOPE DRAIN DETAILS
39.	SIGNING & STRIPING SHEET
40.-41.	TRAFFIC CONTROL SHEETS
X1.-X18.	CROSS SECTIONS

**STANDARDS**

THE FOLLOWING ODOT STANDARDS ARE  
REQUIRED FOR THIS PROJECT:

ROADWAY	TRAFFIC	TRAFFIC CONTROL	BRIDGE
SSS-1-1	PM3-1-02	TCS1-1-01	B40-1-ABUT-MISC-01E
TSC2-3-2	DU1-1-00	TCS2-1-00	B40-1-AS-03E
TSD-2-0	DU2-1-00	TCS4-1-01	TR4-2-00E
TRFD-1-2	RSD1-1-00	TCS5-1-00	HP1-2-00E
ASCD-5-2	WSD3-1-00	TCS6-1-02	
LECS-4-1	SBS1-1-00	TCS7-1-02	
PSE-1-0	GMS1-1-00	TCS8-1-00	
CET6S-3-2	SSP1-1-02	TCS9-1-01	
SPI-4-1	SSA1-1-00	TCS10-1-00	
SPB-1-4	THRI-1-02	TCS11-1-01	
FHTMPP-1-0	SKT-1-00	TCS13-1-00	
FHTCP-3-1	GA31-1-00	TCS14-1-00	
PUD-3-2	GHW1-1-00	TCS19-1-01	
PDT-1-3	GHW2-1-00	TCS20-1-00	
RWF2-2-1		TCS21-1-02	
		TCS22-1-00	


**PROJECT LENGTH BASED ON CL SURVEY STATIONING**

ROADWAY LENGTH \_\_\_\_\_ 1,198.33 FT \_\_\_\_\_ 0.226 MI  
BRIDGE LENGTH \_\_\_\_\_ 301.67 FT \_\_\_\_\_ 0.057 MI  
PROJECT LENGTH \_\_\_\_\_ 1,500.00 FT \_\_\_\_\_ 0.284 MI

EXCEPTIONS \_\_\_\_\_ NONE  
EQUATIONS \_\_\_\_\_ NONE

 REGISTERED PROFESSIONAL ENGINEER JEREMY P. STAHLER 21725 OKLAHOMA	PREPARED BY: CEC CORPORATION CA32 6/30/18 TULSA, OKLAHOMA	 REGISTERED PROFESSIONAL ENGINEER TRAVIS A. COLLINS 22794 OKLAHOMA	PREPARED BY: CEC CORPORATION CA32 6/30/18 OKLAHOMA CITY, OKLAHOMA
	<i>Jeremy P. Stahle</i> JEREMY P. STAHLER, P.E. OKLA. REG. NO. 21725		<i>Travis A. Collins</i> TRAVIS A. COLLINS, P.E. OKLA. REG. NO. 22794
OKLAHOMA DEPARTMENT OF TRANSPORTATION		DEPARTMENT OF TRANSPORTATION FEDERAL HIGHWAY ADMINISTRATION	
DATE APPROVED _____ BY _____ CHIEF ENGINEER		DATE APPROVED _____ BY _____ DIVISION ADMINISTRATOR	
SWO 4844(1) WOODWARD COUNTY		PROJECT NO. ACSTP-277B(035)SS SH-34	
		SHEET NO. 1	

DESCRIPTION	REVISIONS	DATE



**TYPICAL NO. 1 (MAINLINE)**

**STA. 2434+50.00 TO STA. 2440+35.16**  
**STA. 2443+96.83 TO STA. 2449+50.00**



\* SEE CROSS SECTIONS FOR VARIATION

- (A) 2'-0" TO 8'-0" FROM STA. 2434+50.00 TO STA. 2435+50.00
- 8'-0" TO 2'-0" FROM STA. 2448+50.00 TO STA. 2449+50.00

PAVEMENT REQUIREMENT			
10" PAVT. STRUCTURE	12'-0" DRIVING LANES	2'-0" TO 8'-0" PAVED SHOULDERS	0'-0" TO 5'-0" GUARDRAIL WIDENING SECTION
SURFACE COURSE	2" SUPERPAVE TYPE S4 (PG 70-28 OK)	2" SUPERPAVE TYPE S4 (PG 64-22 OK)	4" SUPERPAVE TYPE S4 (PG 64-22 OK)
BASE COURSE	3" SUPERPAVE TYPE S3 (PG 70-28 OK) 2-2.5" SUPERPAVE TYPE S3 (PG 64-22 OK)	3" SUPERPAVE TYPE S3 (PG 64-22 OK) 2-2.5" SUPERPAVE TYPE S3 (PG 64-22 OK)	

- (1) BACKFILL NOTE:  
THIS AREA TO BE BACKFILLED AND COMPACTED AS A PART OF THE FINISHING OPERATIONS. QUANTITY IS MEASURED IN UNCLASSIFIED BORROW.
- (2) TOPSOIL NOTE:  
THE CONTRACTOR SHALL STRIP ALL OF THE AVAILABLE TOPSOIL, STOCKPILE IT, AND PLACE IT BACK ON THE SECTION IN ACCORDANCE WITH SECTION 205 OF THE STANDARD SPECIFICATION. RESERVED TOPSOIL SHALL BE SPREAD FIRST ON THE COMPLETED SLOPES OF THE CUT SECTIONS AND THE REMAINDER ON COMPLETED FILL SLOPES OR OTHER PRIORITY AREAS LOCATED BY THE ENGINEER. ALL ADDITIONAL COSTS ASSOCIATED WITH OPERATION SHALL BE INCLUDED IN THE PAY ITEM FOR SALVAGED TOPSOIL, LUMP SUM. THE GRADING LINE IS TO THE TOP OF THE TOPSOIL. EARTHWORK QUANTITIES WERE NOT ADJUSTED FOR SALVAGE AND THE TOPSOIL QUANTITY IS INCLUDED IN THE MASSLINE BALANCE.
- (3) DISTANCE MEASURED VERTICALLY FROM EDGE OF FINISHED GRADE SHOULDER

**ROUNDING DETAIL**




**TYPICAL NO. 2 (GUARDRAIL WIDENING)**

**LEFT**  
 STA. 2437+26.41 TO STA. 2440+35.16  
 STA. 2443+96.83 TO STA. 2447+80.58

- (B) 0'-0" TO 5'-0" FROM STA. 2437+26.41 TO STA. 2437+96.41
- 5'-0" FROM STA. 2437+96.41 TO STA. 2440+35.16
- 5'-0" FROM STA. 2443+96.83 TO STA. 2447+10.52
- 5'-0" TO 0'-0" FROM STA. 2447+10.52 TO STA. 2447+80.58

**RIGHT**  
 STA. 2436+51.41 TO STA. 2440+35.16  
 STA. 2443+96.83 TO STA. 2447+05.58

- (B) 0'-0" TO 5'-0" FROM STA. 2436+51.41 TO STA. 2437+21.41
- 5'-0" FROM STA. 2437+21.41 TO STA. 2440+35.16
- 5'-0" FROM STA. 2443+96.83 TO STA. 2446+35.58
- 5'-0" TO 0'-0" FROM STA. 2446+35.58 TO STA. 2447+05.58



**TYPICAL NO. 3 (DETOUR)**

**STA. 2428+49.86 TO STA. 2455+03.88**

\* SEE CROSS SECTIONS FOR VARIATION  
 \*\* SUBGRADE TO BE COMPACTED AS PER SPECIFICATIONS. COST TO BE INCLUDED IN EARTHWORK.

- (C) 0'-0" TO 13'-0" FROM STA. 2428+49.86 TO STA. 2430+28.68
- 13'-0" FROM STA. 2430+28.68 TO STA. 2453+69.43
- 13'-0" TO 0'-0" FROM STA. 2453+69.43 TO STA. 2455+03.88
- (D) 0'-0" TO 13'-0" FROM STA. 2430+28.68 TO STA. 2430+96.24
- 13'-0" FROM STA. 2430+96.24 TO STA. 2453+03.33
- 13'-0" TO 0'-0" FROM STA. 2453+03.33 TO STA. 2453+69.43

PAVEMENT REQUIREMENT	
6" PAVT. STRUCTURE	0'-0" TO 13'-0" DRIVING LANES
SURFACE COURSE	2" SUPERPAVE TYPE S4 (PG 64-22 OK)
BASE COURSE	4" SUPERPAVE TYPE S3 (PG 64-22 OK)

FILENAME: 2 TYPICAL SECTIONS.DWG

DESIGN SH-34 OVER N. PERSIMMON CREEK WOODWARD COUNTY

DRAWN

CHECKED

CEC

**TYPICAL SECTIONS**

STATE JOB NO. 28827(04) SHEET NO. 2

JP 28827(04) ROADWAY - 0100				
<b>PAY QUANTITIES (ROADWAY)</b>				
PAY ITEM	CODE NO.	DESCRIPTION	UNIT	QUANTITY
201(A)	0102	CLEARING AND GRUBBING	LSUM	1
202(A)	0183	UNCLASSIFIED EXCAVATION	(R-1)(R-4) CY	12,667
202(D)	0184	UNCLASSIFIED BORROW	(R-4) CY	5,475
205(A)	4230	TYPE A SALVAGED TOPSOIL	(R-5)(R-7) CY	4,804
221(C)	2801	TEMPORARY SILT FENCE	LF	768
221(F)	0100	TEMPORARY SILT DIKE	LF	161
221(G)	0150	TEMPORARY ROCK FILTER DAM TYPE 1	CY	20
230(A)	2806	SOLID SLAB SODDING	(R-7)(R-8) SY	22,990
233(A)	2817	VEGETATIVE MULCHING	(3)(R-11) AC	3.80
241	2832	MOWING	(R-16) AC	23.68
307(K)	4300	STABILIZED SUBGRADE	(1)(R-1) SY	6,361
310(B)	0149	SUBGRADE, METHOD B	SY	303
407(B)	0250	TACK COAT	GAL	3,678
408	5774	PRIME COAT	(R-28) GAL	5,753
411(B)	5940	SUPERPAVE, TYPE S3 (PG 70-28 OK)	(R-32) TON	531
411(B)	5945	SUPERPAVE, TYPE S3 (PG 64-22 OK)	(R-32) TON	3,483
411(C)	5955	SUPERPAVE, TYPE S4 (PG 70-28 OK)	(R-32) TON	344
411(C)	5960	SUPERPAVE, TYPE S4 (PG 64-22 OK)	(R-32) TON	1,164
613(A)	4498	43" X 26" R.C. PIPE ARCH CLASS A-III	LF	96
613(B)	0689	18" CORR. GALV. STEEL PIPE	(R-46) LF	24
613(B)	0698	72" CORR. GALV. STEEL PIPE	(R-46) LF	204
613(B)	4819	96" CORR. GALV. STEEL PIPE	(R-46) LF	79
613(M)	7198	TYPE C6 CULVERT END TREATMENT	EA	2
619(A)	0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	(R-48)(R-49) LSUM	1
619(B)	4725	REMOVAL OF FENCE	(R-49) LF	2,539
619(B)	4728	REMOVAL OF ASPHALT PAVEMENT	(R-49)(R-50) SY	11,286
619(B)	4767	REMOVAL OF ASPHALT DRIVEWAY	(R-49)(R-50) SY	215
619(B)	4780	REMOVAL OF GUARDRAIL	(R-49) LF	560
623(A)	0932	BEAM GUARDRAIL W BEAM SINGLE	LF	750
623(G)	8590	GUARDRAIL END TREATMENT (31")	(2) EA	4
623(I)	8700	GUARDRAIL BRIDGE CONN THRIE BEAM (31")	EA	4
624(C)	4459	FENCE-STYLE SWF (5 BARBED WIRE)	(R-52)(R-53) LF	331

JP 28827(04) CONSTRUCTION - 0640				
<b>PAY QUANTITIES (CONSTRUCTION)</b>				
PAY ITEM	CODE NO.	DESCRIPTION	UNIT	QUANTITY
220	2800	SWPPP DOCUMENTATION AND MANAGEMENT	LSUM	1

STAKING & MOBILIZATION FOR THIS PROJECT WILL BE INCLUDED IN THE BID PRICE ON THE MANDATORY TIED PROJECT, JOB PIECE NUMBER 28825(04).

**SUGGESTED SEQUENCE OF CONSTRUCTION**

- CONSTRUCT TEMPORARY DETOUR.
- SHIFT TRAFFIC TO TEMPORARY DETOUR. REMOVE EXISTING SH-34 SECTION AND BRIDGE. CONSTRUCT NEW SH-34 SECTION AND BRIDGE.
- SHIFT TRAFFIC TO NEW SH-34 SECTION, REMOVE TEMPORARY DETOUR AND PERFORM FINISHING OPERATIONS.

**PAY ITEMS & NOTES (ROADWAY)**

- (R-1) PAYMENT FOR THIS ITEM WILL BE BASED ON PLAN QUANTITY ONLY. SEE SECTION 109.01B OF THE STANDARD SPECIFICATIONS.
- (R-4) INCLUDES 1,000 CU. YDS. FOR DRIVEWAYS, RETURNS, DIKES, AND MISCELLANEOUS EARTHWORK.
- (R-5) AN ESTIMATED QUANTITY OF 4,804 C.Y. TOPSOIL TO BE RESERVED FOR REPLACEMENT OF APPROXIMATELY 5" ON COMPLETED FORESLOPES, DITCHES, AND BACKSLOPES. THIS QUANTITY IS INCLUDED IN THE EARTHWORK BALANCE. ANY ADDITIONAL EXCAVATION REQUIRED IN CUT SECTIONS TO ALLOW FOR PLACEMENT OF TOPSOIL TO FINAL GRADE, SHALL BE INCLUDED IN THE PRICE BID.
- (R-7) FOR TYPE A SALVAGED TOPSOIL, PRICE BID TO INCLUDE COST OF 10-20-10 FERTILIZER, ESTIMATED AT 200 POUNDS PER 1,000 SQUARE YARDS.
- (R-8) FOR SOLID SLAB SODDING, PRICE BID TO INCLUDE COST OF 10-20-10 FERTILIZER ESTIMATED AT 200 POUNDS PER 1,000 SQUARE YARDS.
- (R-8) FOR SOLID SLAB SODDING, PRICE BID TO INCLUDE COST OF WATERING, ESTIMATED AT 40 GALLONS PER SQUARE YARD.
- (R-11) THE QUANTITIES ESTIMATED FOR TEMPORARY EROSION AND SEDIMENT CONTROL IS 3.80 ACRES.
- (R-16) QUANTITY BASED ON TWO APPLICATIONS.
- (R-28) PRIME COAT SHALL BE APPLIED AT AN ESTIMATED RATE OF 0.35 GAL. PER SQ. YD. WHEN APPLIED TO SUBGRADE, AND 0.25 GAL. PER SQ. YD. WHEN APPLIED TO AGGREGATE BASE. THE ACTUAL CUTBACK PRIME COAT REQUIRED FOR PLACEMENT OPERATIONS WILL BE DETERMINED BY THE CONTRACTOR, AND SHALL CONSIDER THE RESIDUE FROM DISTILLATION PERCENTAGE SHOWN IN SECTION 708.03 OF THE STANDARD SPECIFICATIONS.
- (R-32) ESTIMATED AT 112 LBS. PER SQ. YD PER 1" THICK.
- (R-46) ANY DRAINAGE STRUCTURE DESCRIBED AS TEMPORARY, SHALL AFTER COMPLETION OF THE PROJECT, BE REMOVED BY AND BECOME THE PROPERTY OF THE CONTRACTOR.
- (R-48) INCLUDES REMOVAL OF ALL EXISTING ROADWAY DRAINAGE STRUCTURES, HEADWALLS (UNLESS OTHERWISE SPECIFIED), INLETS, FENCES, AND OTHER STRUCTURES WITHIN THE RIGHT OF WAY.
- (R-49) TO BECOME THE PROPERTY OF AND BE DISPOSED OF BY THE CONTRACTOR IN A MANNER APPROVED BY THE ENGINEER.
- (R-50) MATERIALS REMOVED SHALL NOT BE MEASURED FOR PAYMENT UNDER SECTION 202.06 UNCLASSIFIED EXCAVATION.
- (R-52) INCLUDES 2% FOR GROUND MEASUREMENT.
- (R-53) ALL GATES AND GATE END POSTS FOR STRANDED WIRE FENCE (SWF) SHALL BE CONSTRUCTED AT THE SAME WIDTH AS THE EXISTING, UNLESS OTHERWISE DIRECTED BY THE ENGINEER.
- (1) STABILIZED SUBGRADE TO PAID FOR BY THE SQUARE YARD IN ACCORDANCE TO SECTION 307.06 IN THE 2009 ODOT SPECIFICATIONS. THE SOILS REPORT INDICATED THE USE OF CHEMICAL ADDITIVES SHOULD NOT BE PROBLEMATIC WITH REGARDS TO SOLUBLE SULFATES, BUT CAUTION SHOULD BE USED WITH REGARDS TO THE POTENTIAL OF RANDOMLY OCCURRING HIGH SULFATE AREAS NOT FOUND IN THE SOILS INVESTIGATION.
- (2) THIS PAY ITEM WILL INCLUDE THE SKT-SP-MSG OR APPROVED SUBSTITUTE. THE ET-PLUS WILL NOT BE ALLOWED.
- (3) THIS ITEM SHALL BE WHEAT HAY ONLY.

**EROSION CONTROL AND CONSTRUCTION NOTES**

SOLID SLAB SODDING SHALL BE PLACED ON ALL DISTURBED AREAS.

AT THE BEGINNING OF SODDING OPERATIONS, ANY AREA INCLUDED IN THE PLANNED QUANTITIES THAT HAS GROWN A SATISFACTORY TURF OF PERENNIAL GRASS, AS DETERMINED BY THE ENGINEER, SHALL NOT BE SODDED, WATERED OR FERTILIZED.

TEMPORARY EROSION CONTROL: IF THE DIRT WORK IS COMPLETED AFTER THE APPROVED PLANTING SEASON FOR SODDING HAS ENDED, DISTURBED AREAS WILL BE PLANTED WITH A TEMPORARY COVER CROP CONSISTING OF WHEAT OR OTHER SMALL GRAIN AT THE RATE OF 20 POUNDS/ACRE IN ACCORDANCE WITH SECTION 232 OF THE STANDARD SPECIFICATIONS. COST OF TEMPORARY COVER CROP TO BE INCLUDED IN THE PRICE BID FOR SOLID SLAB SODDING.

**GENERAL CONSTRUCTION NOTES**

THIS PROJECT SHALL BE CONSTRUCTED WITHOUT CLOSING THE EXISTING ROAD TO LOCAL AND THROUGH TRAFFIC. SEE STANDARD SPECIFICATIONS FOR MAINTENANCE OF LOCAL AND THROUGH TRAFFIC.

MAINTENANCE OF THROUGH TRAFFIC INCLUDES THE MAINTENANCE OF THE EXISTING ROAD IN CLOSE PROXIMITY TO THE NEW CONSTRUCTION AS SHOWN ON THE PLANS.

THIS PROJECT SHALL BE CONSTRUCTED WITHOUT CLOSING THE EXISTING SECTION LINE ROADS TO LOCAL AND THROUGH TRAFFIC. SEE STANDARD SPECIFICATIONS FOR MAINTENANCE OF LOCAL AND THROUGH TRAFFIC.

ALL TREES, BRUSH, AND OTHER DEBRIS THAT MIGHT INTERFERE WITH THE FLOW OF WATER SHALL BE CLEANED OUT TO THE RIGHT-OF-WAY LINE, AT EACH STRUCTURE AND BRIDGE, IN A MANNER APPROVED BY THE ENGINEER. ALL COST TO BE INCLUDED IN OTHER ITEMS OF WORK.

THE CONTRACTOR SHALL PROVIDE ALL TEMPORARY RIGHT-OF-WAY FENCE AS REQUIRED. WHEN THE PORTION OF THE PROJECT THAT REQUIRED THIS FENCE IS COMPLETED, THE TEMPORARY FENCE SHALL BE REMOVED, AND PERMANENT RIGHT-OF-WAY FENCING SHALL BE RESTORED OR INSTALLED IN A MANNER APPROVED BY THE ENGINEER. ALL COST OF TEMPORARY FENCING SHALL BE INCLUDED IN OTHER ITEMS OF WORK.

ALL FLOWLINES THAT ARE TO BE FILLED SHALL BE THOROUGHLY TAMPED BEFORE CONSTRUCTION OR EXTENSION OF DRAINAGE STRUCTURES. ALL COST TO BE INCLUDED IN OTHER ITEMS OF WORK.

IN ORDER TO ALLEVIATE DUST CONDITIONS DURING GRADING OPERATIONS AND BEFORE PAVEMENT WORK IS COMPLETED, THE CONTRACTOR SHALL SPRINKLE GRADING AT INTERVALS APPROVED BY THE ENGINEER. ALL COST TO BE INCLUDED IN OTHER ITEMS OF WORK.

THIS PROJECT IS LOCATED NEAR KNOWN SOURCES OF GYPSUM (SULFATE) DEPOSITS. SPECIAL ATTENTION SHOULD BE USED TO AVOID BORROW MATERIAL THAT COULD ADVERSELY INTERACT WITH THE CALCIUM BASED ADDITIVES (FLY ASH, PORTLAND CEMENT, CEMENT KILN DUST, AND LIME) USED IN THE STABILIZED SUBGRADE. THE CONTRACTOR MAY BE REQUIRED TO PROVIDE SULFATE TESTING OF BORROW PIT SITES AS DIRECTED BY THE ENGINEER.

THE CONTRACTOR SHALL NOT WASTE ANY EXCESS EXCAVATION UNTIL ALL PLANNED EMBANKMENTS AND BACKFILLS ARE COMPLETED. EXCESS UNCLASSIFIED EXCAVATION MATERIAL DETERMINED BY THE ENGINEER TO BE SUITABLE FOR BACKFILL SHALL BE USED TO REDUCE ANY UNCLASSIFIED BORROW NEEDED. COST OF SECOND HANDLING SHALL BE INCLUDED IN OTHER ITEMS OF WORK. ANY REMAINING EXCESS EXCAVATION SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND BE DISPOSED OF IN A MANNER APPROVED BY THE ENGINEER.

PRIME COAT SHALL BE APPLIED TO THE SUBGRADE IMMEDIATELY AFTER FINAL COMPACTION AND SHAPING TO RETAIN MOISTURE FOR PROPER CHEMICAL REACTION OF THE SOIL ADDITIVE.

THE CONTRACTOR SHALL KEEP THE OPEN TRENCH DRAINED. COST TO BE INCLUDED IN OTHER ITEMS OF WORK.

VEGETATIVE MULCHING: THE VEGETATIVE MULCH SHALL BE ANCHORED IN ACCORDANCE WITH THE "MULCHING-TILLER METHOD", AS SPECIFIED IN 233.04B(2) OF THE STANDARD SPECIFICATIONS.

AREAS ON WHICH SALVAGED TOPSOIL IS TO BE REPLACED SHALL HAVE 18-46-0 FERTILIZER APPLIED, AT THE RATE OF 150 POUNDS PER ACRE, JUST PRIOR TO THE REPLACEMENT OF SALVAGED TOPSOIL.

SURFACING OF RETURNS, UNLESS OTHERWISE SHOWN ON THE PLANS, SHALL BE OF THE SAME MATERIAL (BASE AND SURFACE) AS THAT OF THE ABUTTING SHOULDER OF THE MAINLINE. BASE AND SURFACE THICKNESS SHALL BE THE THICKNESS SHOWN ON PLANS.

EXCESS ASPHALT AT JOINTS AND CRACKS IN EXISTING PAVEMENT SHALL BE REMOVED FLUSH TO TOP OF PAVING IN A MANNER APPROVED BY THE ENGINEER.

IN ACCORDANCE WITH THE OKLAHOMA UNDERGROUND FACILITIES DAMAGE PREVENTION ACT THE CONTRACTOR SHALL NOTIFY THE OKLAHOMA ONE-CALL SYSTEM, INC. 48 HOURS PRIOR TO BEGINNING EXCAVATION. OKLAHOMA ONE-CALL SYSTEM, INC. "CALL OKIE" 1-800-522-6543 OR 811.

**ENVIRONMENTAL NOTES**

CLIFF SWALLOWS AND BARN SWALLOWS ARE SMALL COLONIAL NESTING BIRDS PROTECTED BY THE FEDERAL MIGRATORY BIRD TREATY ACT. THESE SPECIES COMMONLY USE BRIDGES AND CULVERTS FOR NESTING. THE NESTING SEASON FOR THE SWALLOWS RUNS FROM APRIL 1 TO AUGUST 31. ANY ACTIVITIES WHICH WOULD DESTROY ACTIVE NESTS OR HARM EGGS OR BIRDS WOULD VIOLATE THE MIGRATORY BIRD TREATY ACT. SWALLOW USE OF BRIDGE NBI NO. 03444 HAS BEEN OBSERVED DURING THE INITIAL SURVEYS CONDUCTED AS PART OF THE BIOLOGICAL STUDIES IN 2013. SWALLOWS MAY OCCUPY THE BRIDGE IN FUTURE NESTING SEASONS. THE RESIDENT ENGINEER WILL EVALUATE THE CONTRACTOR'S PROPOSED WORK METHODS AND CONCLUDE WHETHER THE PROPOSED WORK WOULD POSE DISRUPTION TO ANY NESTING BIRDS BEFORE WORK NEAR THE STRUCTURE IS AUTHORIZED. IF THE PROPOSED WORK WILL HARM ANY NESTING BIRDS, THE BRIDGE MAY BE NETTED PRIOR TO APRIL 1 OR THE WORK DELAYED UNTIL THE NESTING SEASON IS COMPLETE. METHODS OTHER THAN NETTING MUST BE PRE-APPROVED BY THE ODOT BIOLOGISTS.



DESCRIPTION	REVISIONS	DATE

JP 28827(04) 0301				
PAY QUANTITIES (PERMANENT TRAFFIC)				
PAY ITEM	CODE NO.	DESCRIPTION	UNIT	QUANTITY
853	9069	GUARDRAIL DELINEATORS (TYPE 2, CODE 1)	EA	26
856(A)	8530	TRAFFIC STRIPE (MULTI-POLY.) (4" WIDE)	(TS-24) LF	3,408

JP 28827(04) 0302				
PAY QUANTITIES (TEMPORARY TRAFFIC)				
PAY ITEM	CODE NO.	DESCRIPTION	UNIT	QUANTITY
857(A)	8839	CONSTRUCTION TRAFFIC STRIPE (PAINT) (4" WIDE)	(TC-16)(TC-17)(TC-20)(TC-70)(TC-75) LF	10,800
857(F)	8006	PAVEMENT MARKING REMOVAL (TRAFFIC STRIPE)	(TC-22)(TC-70)(TC-75) LF	1,322
880(B)	8818	CONSTRUCTION SIGNS 0 TO 6.25 SF	(TC-26)(TC-33)(TC-84) SD	4,800
880(B)	8821	CONSTRUCTION SIGNS 6.26 TO 15.99 SF	(TC-26)(TC-33)(TC-84) SD	2,880
880(B)	8824	CONSTRUCTION SIGNS 16.0 TO 32.99 SF	(TC-26)(TC-30)(TC-33)(TC-84) SD	3,360
880(C)	8842	CONSTRUCTION BARRICADES (TYPE III)	(TC-26)(TC-84) SD	960
880(C)	8848	WING BARRICADES	(TC-26)(TC-84) SD	960
880(E)	8860	WARNING LIGHTS (TYPE A)	(TC-26)(TC-84) SD	3,840
880(G)	8890	CHANNELIZER CONES	(TC-26)(TC-84) SD	23,040
882(A)	8306	PORTABLE CHANGEABLE MESSAGE SIGN	(SP-1)(TC-52)(TC-84)(TC-85) SD	14

**MANDATORY TIE**

THIS PROJECT SHALL BE MANDATORILY TIED WITH WOODWARD COUNTY JOB PIECE 28825(04) AND SHALL BE BID ACCORDINGLY.

**PAY ITEMS & NOTES (PERMANENT TRAFFIC)**

(TS-24) QUANTITY SHOWN INCLUDES 3,000 L.F. TRAFFIC STRIPE (MULTI-POLYMER)(WHITE) AND 408 L.F. TRAFFIC STRIPE (MULTI-POLYMER)(YELLOW) AND WILL BE MEASURED BY THE LINEAR FOOT OF FOUR INCH (4") WIDE TRAFFIC STRIPE.

(TS-33) INCLUDED IN THIS PAY ITEM IS ALL HARDWARE ASSOCIATED WITH PROPERLY ANCHORING AND MOUNTING THE HIGHWAY SIGN IN ACCORDANCE WITH O.D.O.T. PLANS AND STANDARD DRAWINGS SSA1-1 AND SSP1-1-(LATEST REVISION).

(TS-34) INCLUDED IN THIS PAY ITEM IS THE REMOVAL OF ANY EXISTING SIGNS TO BE REPLACED BY NEW ASSEMBLIES AND THE REMOVAL OF ANY EXISTING SIGNS THAT WILL BE IN CONFLICT WITH THE NEW ROADWAY OR NEW SIGNAGE.

**PAY ITEMS & NOTES (TEMPORARY TRAFFIC)**

(TC-16) PAINT SHALL CONFORM TO SECTION 711 "TRAFFIC STRIPE", OF THE O.D.O.T. STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION (CURRENT EDITION).

IF CONSTRUCTION TRAFFIC STRIPE PAINT IS INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS AND FAILS DURING THE FIRST SIX MONTHS OF SERVICE, REPLACEMENT WILL BE MADE AT THE CONTRACTOR'S EXPENSE AND SHALL BE ACCOMPLISHED IN A TIMELY MANNER UPON NOTIFICATION BY THE ENGINEER OF SUCH FAILURE.

(TC-17) INCLUDES AN ESTIMATED 5,400 L.F. (PAINT)(4" WIDE) WHITE 5,400 L.F. (PAINT)(4" WIDE) YELLOW STRIPE.

(TC-20) ALL STRIPING TO BE PLACED ON TEMPORARY SURFACES OR ON SURFACES SCHEDULED TO BE REMOVED SHALL BE DONE WITH PAINT UNLESS OTHERWISE NOTED ON THE PLANS OR STANDARD DRAWINGS. TEMPORARY PAVEMENT MARKINGS PLACED ON FINISHED PAVEMENT OR EXISTING PAVEMENT TO REMAIN IN PLACE SHALL USE ONE OF THE FOLLOWING METHODS:

- REMOVABLE PAVEMENT MARKING TAPE
- CLASS A PAVEMENT MARKERS

(TC-22) AMOUNT SHOWN IS AN APPROXIMATION AND THE ACTUAL AMOUNT OF REMOVAL, IF NECESSARY, SHALL BE DETERMINED BY THE ENGINEER. PRICE BID FOR PAVEMENT MARKING REMOVAL SHALL INCLUDE THE COST OF REMOVING STRIPE, ARROWS, WORDS AND SYMBOLS, AS SHOWN IN THE PLANS. THESE ITEMS MAY CONSIST OF PLASTIC, PAINT OR NON-REMOVABLE MARKING TAPE.

(TC-26) ALL CONSTRUCTION TRAFFIC CONTROL WILL BE IMPLEMENTED ACCORDING TO CONSTRUCTION PLANS, AND INSTALLED IN A MANNER APPROVED BY THE ENGINEER, IN ACCORDANCE WITH CHAPTER VI OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, (CURRENT EDITION), AND COMPLIANT WITH APPLICABLE O.D.O.T. STANDARD DRAWINGS. PRICE BID FOR THIS ITEM SHALL BE PAYMENT IN FULL FOR THE INSTALLATION, MAINTENANCE AND SUBSEQUENT REMOVAL OF ALL NECESSARY CONSTRUCTION TRAFFIC CONTROL DEVICES REQUIRED FOR COMPLETION OF THE PROJECT.

ALL SIGNS AND BARRICADES WHICH ARE SHOWN WITH TYPE 'A' LIGHTS IN THE STANDARD DRAWINGS SHALL HAVE THE CORRESPONDING LIGHT ATTACHED DURING NON-DAYLIGHT HOURS.

(TC-30) INCLUDED IN THIS ITEM ARE ALL S.C.S. (SPECIAL CONSTRUCTION SIGNING) SIGNS WHICH ARE BETWEEN 16.00 S.F. AND 32.99 S.F. ALSO INCLUDED IN THIS ITEM SHALL BE THE COST OF INSTALLATION, MAINTENANCE, AND REMOVAL OF THESE SIGNS.

(TC-33) ALL CONSTRUCTION WORK ZONE SIGNS SHALL HAVE FLUORESCENT SHEETING. THE FLUORESCENT SHEETING SHALL MEET THE REQUIREMENTS OF ASTM D4956 (LATEST REVISION)

THE MANUFACTURER SHALL FURNISH A TYPE 'D' CERTIFICATION IN ACCORDANCE WITH O.D.O.T. STANDARD SPECIFICATIONS (CURRENT EDITION) SUBSECTION 106.04. THE CERTIFICATION SHALL INCLUDE TEST RESULTS ON MATERIAL SUBMITTED FOR APPROVAL.

(TC-52) ANY USED CHANGEABLE MESSAGE SIGN TO BE PLACED ON THIS PROJECT SHALL BE SUBJECT TO INSPECTION AND APPROVAL, BY THE OKLAHOMA DEPARTMENT OF TRANSPORTATION, TO ASSURE THAT THEY ARE IN GOOD WORKING CONDITION, PRIOR TO PLACEMENT OF THE PROJECT.

(TC-70) THIS ITEM IS AN ESTIMATED QUANTITY TO BE USED AS DEEMED NECESSARY BY THE ENGINEER.

(TC-75) TEMPORARY PAVEMENT MARKINGS SHALL BE IN PLACE THE SAME DAY THAT EXISTING PAVEMENT MARKINGS ARE REMOVED FROM ANY ROADWAY OPEN TO TRAFFIC. ALSO, ALL TEMPORARY PAVEMENT MARKINGS SHALL BE REMOVED PRIOR TO THE INSTALLATION OF FINAL STRIPING.

(TC-84) 240 CONSTRUCTION CALENDAR DAYS WERE USED TO COMPUTE THE SIGN DAY PAY ITEMS. THE AMOUNT OF CALENDAR DAYS USED TO COMPUTE THE SIGN DAY PAY ITEMS IS AN ESTIMATED QUANTITY ONLY, BASED ON THE CURRENT O.D.O.T. STANDARDS AND SUGGESTED CONSTRUCTION SEQUENCE FOR THIS PROJECT. THESE ESTIMATED SIGN DAY QUANTITIES MAY CHANGE AS THE PROJECTS CONSTRUCTION TRAFFIC CONTROL IS MODIFIED DURING CONSTRUCTION.

(TC-85) THESE SIGNS MUST BE ON THE OKLAHOMA DEPARTMENT OF TRANSPORTATION LIST OF APPROVED CHANGEABLE MESSAGE SIGNS. FOR A LIST OF THE APPROVED SIGNS GO TO THE OKLAHOMA DEPARTMENT OF TRANSPORTATION WEBSITE AT:  
<http://www.okladot.state.ok.us/traffic/qpl/index.php>

(SP-1) SIGN PLACEMENT LOCATIONS SHALL BE DETERMINED BY THE ENGINEER.

FILENAME: 3A PAY ITEMS & NOTES (TRAFFIC).DWG

DESIGN	SH-34 OVER N. PERSIMMON CREEK	WOODWARD COUNTY
DRAWN	<b>PAY ITEMS &amp; NOTES (TRAFFIC)</b>	
CHECKED		
CEC	STATE JOB NO. 28827(04)	SHEET NO. 3A

DESCRIPTION	REVISIONS	DATE

**GENERAL NOTES**

SPECIFICATIONS –  
 COMPLY WITH THE REQUIREMENTS OF THE 2009 OKLAHOMA STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION, EXCEPT AS MODIFIED BY THE PLANS AND SPECIAL PROVISIONS.

EXISTING PLANS –  
 THE EXISTING STRUCTURE WAS ORIGINALLY CONSTRUCTED AS PART OF FEDERAL AID PROJECT NO. F-418(8). PLANS OF THIS PROJECT ARE AVAILABLE FROM THE OKLAHOMA DEPARTMENT OF TRANSPORTATION TECHNOLOGY SERVICES PLANS SECTION, 200 N.E. 21ST STREET, OKLAHOMA CITY, OKLAHOMA 73105.

PILE DRIVING AND CAPACITY –  
 THE FACTORED PILE REACTION FOR EACH HP12X53 PILE AT EACH ABUTMENT IS 95.0 TONS.

THE FACTORED PILE REACTION FOR EACH HP14X89 PILE AT EACH PIER IS 225.0 TONS.

THE FOLLOWING FORMULA (GATES EQUATION) SHALL BE USED TO DETERMINE THE AXIAL LOAD RESISTANCE OF THE DRIVEN FOUNDATION PILES.

$$\text{AXIAL LOAD RESISTANCE} = \phi[(0.875 \sqrt{E} \log_{10} (10N)) - 50] \quad (\text{TONS})$$

WHERE:  
 $\phi$  = RESISTANCE FACTOR OF 0.4  
 E = ENERGY PRODUCED BY THE HAMMER PER BLOW IN FOOT-POUNDS. FOR GRAVITY AND SINGLE ACTING DIESEL HAMMERS, THE VALUE IS BASED ON THE ACTUAL RAM STROKE OBSERVED IN THE FIELD AND MEASURED IN FEET MULTIPLIED BY THE RAM WEIGHT IN POUNDS.  
 N = AVERAGE NUMBER OF HAMMER BLOWS PER INCH OF PILE PENETRATION FOR THE LAST 10 TO 20 BLOWS DELIVERED TO THE PILE HEAD.

THE ABOVE FORMULA IS ONLY APPLICABLE WHEN:  
 – THE PILE DRIVING HAMMER HAS A FREE FALL(GRAVITY AND SINGLE ACTING HAMMERS ONLY).  
 – THE HEAD OF THE PILE IS NOT BROOMED, CRUSHED OR OTHERWISE DAMAGED.  
 – THE PENETRATION IS QUICK AND UNIFORM.  
 – THERE IS NO APPRECIABLE REBOUND OF THE HAMMER AND A FOLLOWER IS NOT USED.

THE NUMBER OF BLOWS PER INCH OF PILE PENETRATION MAY BE MEASURED EITHER DURING INITIAL DRIVING OR BY RE-DRIVING WITH A WARM HAMMER OPERATED AT FULL ENERGY AFTER A PILE SET PERIOD, AS DETERMINED BY THE ENGINEER.

IF WATER JETS ARE USED IN CONNECTION WITH THE DRIVING, DETERMINE THE AXIAL LOAD RESISTANCE BY THE FORMULA ONLY AFTER THE JETS HAVE BEEN WITHDRAWN.

STRUCTURAL STEEL –  
 STRUCTURAL STEEL FOR PILING SHALL CONFORM TO AASHTO M270 (ASTM A572), GRADE 50.  
 STRUCTURAL STEEL FOR ANCHOR PLATES AND BUILT-UP CONTACT ANGLES SHALL CONFORM TO ASTM A240 (AUSTENITIC STAINLESS STEEL, TYPE 316, CHARPY V-NOTCH TESTING NOT REQUIRED). FOR ANCHOR BOLTS, PROVIDE CONTINUOUSLY THREADED BARS IN ACCORDANCE WITH ASTM A320, CLASS 2, GRADE B8M (AUSTENITIC STAINLESS STEEL, TYPE 316, CHARPY V-NOTCH TESTING NOT REQUIRED). USE AUSTENITIC STAINLESS STEEL NUTS AND WASHERS CONFORMING TO ASTM A194, GRADE 8M AND ASTM A320, RESPECTIVELY. PERFORM ALL WELDING CONSISTENT WITH PROCEDURES FOR STAINLESS STEEL.  
 PROVIDE STRUCTURAL STEEL FOR DIAPHRAGM BOLTS AND PLATE WASHERS IN ACCORDANCE WITH AASHTO M270 (ASTM A709), GRADE 50W (WEATHERING STEEL, CHARPY V-NOTCH TESTING NOT REQUIRED). THE CONTRACTOR MAY SUBSTITUTE A #10 REINFORCING BAR IN ACCORDANCE WITH AASHTO M31, GRADE 60, AND THREADED AT THE ENDS AS SHOWN FOR THE DIAPHRAGM BOLT AT NO ADDITIONAL COST TO THE DEPARTMENT. PROVIDE HEX NUTS IN ACCORDANCE WITH AASHTO M291 (ASTM A563).  
 PAINT EXPOSED DIAPHRAGM BOLT, PLATE WASHER, AND HEX NUT WITH TWO (2) COATS OF ZINC-RICH PAINT (6 MIL MINIMUM THICKNESS) AFTER ASSEMBLY. INCLUDE ALL COST OF DIAPHRAGM BOLT, PLATE WASHER, AND HEX NUT IN THE CONTRACT UNIT PRICE FOR STRUCTURAL STEEL.

DECK SLAB –  
 EPOXY COAT OR GALVANIZE STEEL ITEMS USED TO FACILITATE CONSTRUCTION, SUCH AS DECK FORM HANGERS, TY-BAR CLIPS, INSERT WELD ANCHORS, OR OTHER APPURTENANCES, THAT WILL REMAIN IN PLACE IN THE DECK SLAB. EPOXY-COAT IN ACCORDANCE WITH AASHTO M284 OR GALVANIZE IN ACCORDANCE WITH AASHTO M111.  
 THE DECK SLAB SHALL BE Poured ONE SPAN AT A TIME. NO SPAN SHALL BE Poured UNTIL AT LEAST 48 HOURS AFTER ANY ADJACENT POUR HAS BEEN COMPLETED. IN THE EVENT OF AN EMERGENCY, HALT THE PLACEMENT OF CONCRETE BY FORMING A CONSTRUCTION JOINT MADE PERPENDICULAR TO THE DIRECTION OF TRAFFIC OR AS DIRECTED BY THE ENGINEER. DO NOT PLACE ANY HEAVY EQUIPMENT ON THE FINISHED DECK SLAB WITHIN 5 FEET OF ANY CONSTRUCTION JOINT UNTIL CONCRETE IS IN PLACE ON BOTH SIDES OF THE RESPECTIVE JOINT, AND AT LEAST 48 HOURS HAS ELAPSED SINCE CONCRETE PLACEMENT.  
 SEAL ALL DECK SLAB CONSTRUCTION JOINTS WITH HIGH MOLECULAR WEIGHT METHACRYLATE IN ACCORDANCE WITH SECTION 523 OF THE SPECIFICATIONS. INCLUDE ALL COST OF THE EQUIPMENT AND LABOR FOR THE INSTALLATION OF THE HIGH MOLECULAR WEIGHT METHACRYLATE SEALER IN THE CONTRACT UNIT PRICE OF "SEALER CRACK PREPARATION". INCLUDE ALL COST OF HIGH MOLECULAR WEIGHT METHACRYLATE SEALER IN THE CONTRACT UNIT PRICE OF "SEALER RESIN". THE DEPARTMENT WILL NOT MEASURE THE PREPARATION AND SEALER OF EMERGENCY CONSTRUCTION JOINTS FOR PAYMENT.

**GENERAL NOTES CONTINUED**

CONCRETE –  
 ALL PEDESTAL CONCRETE EDGES SHALL HAVE A 3/4" CHAMFER. ALL OTHER EXPOSED CONCRETE EDGES OF THE SUBSTRUCTURE SHALL HAVE A 1 1/2" CHAMFER UNLESS OTHERWISE SHOWN OR NOTED. ALL EXPOSED CONCRETE EDGES OF THE SUPERSTRUCTURE SHALL HAVE A 3/4" CHAMFER UNLESS OTHERWISE SHOWN OR NOTED. ALL CHAMFER STRIPS SHALL BE SIZED LUMBER.  
 EQUIP CONCRETE VIBRATORS WITH A SHEATH DESIGNED TO PREVENT DAMAGE TO EPOXY COATINGS WHEN VIBRATING CONCRETE CONTAINING EPOXY COATED REINFORCING STEEL.  
 CEMENT USED FOR PIER COLUMNS AND FOOTINGS SHALL BE TYPE V PORTLAND CEMENT IN ACCORDANCE WITH SECTION 701 OF THE STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION. AS AN OPTION, TYPE II PORTLAND CEMENT MAY BE USED WITH THE ADDITION OF CLASS F FLY ASH TO THE MIX DESIGN. IF TYPE II PORTLAND CEMENT IS USED WITH THE ADDITION OF CLASS F FLY ASH, THE CONCRETE MIX DESIGN SHALL BE APPROVED BY THE ENGINEER.

STAY-IN-PLACE DECK FORMS –  
 STAY-IN-PLACE DECK FORMS ARE NOT ALLOWED.

WATER REPELLENT TREATMENT –  
 WATER REPELLENT TREATMENT SHALL BE APPLIED TO THE BRIDGE IN A MANNER CONSISTENT WITH THE DETAILS SHOWN IN THE PLANS.

**ENVIRONMENTAL MITIGATION NOTES**

MIGRATORY BIRD NOTE –  
 CLIFF SWALLOWS AND BARN SWALLOWS ARE SMALL COLONIAL NESTING BIRDS PROTECTED BY THE FEDERAL MIGRATORY BIRD TREATY ACT. THESE SPECIES COMMONLY USE BRIDGES AND CULVERTS FOR NESTING. THE NESTING SEASON FOR THE SWALLOWS RUNS FROM APRIL 1 TO AUGUST 31. SWALLOW USE OF BRIDGE NBI NO. 03444 HAS BEEN OBSERVED DURING THE INITIAL SURVEYS CONDUCTED AS PART OF THE BIOLOGICAL STUDIES IN JUNE, 2013. ANY ACTIVITIES WHICH WOULD DESTROY ACTIVE NESTS OR HARM EGGS OR BIRDS WOULD VIOLATE THE MIGRATORY BIRD TREATY ACT. THE RESIDENT ENGINEER WILL EVALUATE THE CONTRACTOR'S PROPOSED WORK METHODS AND CONCLUDE WHETHER THE PROPOSED WORK WOULD HARM THE NESTING BIRDS BEFORE WORK NEAR THE STRUCTURE IS AUTHORIZED. IF THE PROPOSED WORK WILL HARM THE NESTING BIRDS, THE BRIDGE MAY BE NETTED PRIOR TO APRIL 1 OR THE WORK DELAYED UNTIL THE NESTING SEASON IS COMPLETE. METHODS OTHER THAN NETTING MUST BE PRE-APPROVED BY THE ODOT BIOLOGIST.

THIS DRAWING IS PRELIMINARY IN NATURE. IT IS NOT A FINAL SIGNED AND SEALED DRAWING

DESIGN	J.W.H.	SH34 OVER N. PERSIMMON CREEK BRIDGE A	WOODWARD COUNTY
DRAWN	Z.M.B.		
CHECKED	J.W.H.		
APPROV.	T.A.C.		
SQUAD	CEC		

**BRIDGE GENERAL NOTES**

JOB PIECE NO. 28827(04) SHEET NO. 4

DESCRIPTION	REVISIONS	DATE

**PAY ITEM NOTES**

- B1 PAYMENT TO THE CONTRACTOR WILL BE BASED ON PLAN QUANTITIES.
- B2 CONCRETE MAY BE PLACED AGAINST THE LIMITS OF EXCAVATION IF THE MATERIAL IS EXCAVATED TO THE NEAT LINES OF THE SUBSTRUCTURE AND APPROVED BY THE ENGINEER. MEASUREMENT AND PAYMENT WILL BE AS SHOWN IN THE PLANS.  
  
THE CONTRACTOR WILL INCLUDE ALL COST OF TEMPORARY RETAINING STRUCTURES AND TEMPORARY WATER CONTROL SYSTEMS NECESSARY TO CONSTRUCT THE BRIDGE PIERS, INCLUDING EQUIPMENT, MATERIALS, LABOR, AND INCIDENTALS, IN THE CONTRACT UNIT PRICE BID FOR "SUBSTRUCTURE EXCAVATION COMMON". ANY TEMPORARY RETAINING STRUCTURES AND TEMPORARY WATER CONTROL SYSTEMS WILL BE PROVIDED IN ACCORDANCE WITH SECTION 502 OF THE SPECIFICATIONS.
- B3 THE APPROACH SLABS CONTAIN AN ESTIMATED TOTAL OF 101.6 C.Y. OF CLASS AA CONCRETE AND 19,760 LB. OF EPOXY COATED REINFORCING STEEL. INCLUDE ALL COSTS FOR CONSTRUCTING THE APPROACH SLABS, INCLUDING CONCRETE, REINFORCING STEEL (INCLUDING SLAB TO BRIDGE RAILING BARS), BACKER ROD, RAPID CURE JOINT SEALANT, POLYSTYRENE, LABOR, EQUIPMENT AND INCIDENTALS NECESSARY TO COMPLETE THE WORK, IN THE CONTRACT UNIT PRICE OF "APPROACH SLAB".
- B4 PROVIDE AND INSTALL FIXED BEARING ASSEMBLIES OF THE SIZE, SHAPE AND LOCATION AS DETAILED IN THE PLANS. THE FIXED BEARING ASSEMBLIES CONTAIN AN ESTIMATED TOTAL OF 2,010 LB. OF STRUCTURAL STEEL. INCLUDE ALL COSTS ASSOCIATED WITH PROVIDING AND INSTALLING THE ELASTOMERIC PADS, ANCHOR PLATES, CONTACT ANGLES, ANCHOR BOLTS, NUTS AND WASHERS, INCLUDING ALL MATERIAL, LABOR, EQUIPMENT AND INCIDENTALS NECESSARY TO COMPLETE THE WORK, IN THE CONTRACT UNIT PRICE OF "STAINLESS STEEL FIXED BEARING ASSEMBLY".
- B5 PROVIDE AND INSTALL EXPANSION BEARING ASSEMBLIES OF THE SIZE, SHAPE AND LOCATION AS DETAILED IN THE PLANS. THE EXPANSION BEARING ASSEMBLIES CONTAIN AN ESTIMATED TOTAL OF 4,020 LB. OF STRUCTURAL STEEL. INCLUDE ALL COSTS ASSOCIATED WITH PROVIDING AND INSTALLING THE ELASTOMERIC PADS, ANCHOR PLATES, CONTACT ANGLES, ANCHOR BOLTS, NUTS AND WASHERS, INCLUDING ALL MATERIAL, LABOR, EQUIPMENT AND INCIDENTALS NECESSARY TO COMPLETE THE WORK, IN THE CONTRACT UNIT PRICE OF "STAINLESS STEEL EXPANSION BEARING ASSEMBLY".
- B6 ALL COSTS ASSOCIATED WITH THE USAGE OF TYPE V PORTLAND CEMENT, TYPE II PORTLAND CEMENT AND CLASS F FLY ASH INCLUDING MATERIAL, LABOR, EQUIPMENT, AND INCIDENTALS SHALL BE INCLUDED IN THE PRICE BID.
- B7 PAYMENT TO THE CONTRACTOR WILL BE BASED ON PLAN QUANTITIES UNLESS ADDITIONAL PILING LENGTH IS REQUIRED. ADDITIONAL PILES, FURNISHED, AS AUTHORIZED BY THE ENGINEER, WILL BE PAID FOR AT THE CONTRACT UNIT PRICE.
- B8 PREPARE SURFACE AND INSTALL HIGH MOLECULAR WEIGHT METHACRYLATE SEALER FOR DECK SLAB CONSTRUCTION JOINTS AT LOCATIONS SHOWN IN THE PLANS IN ACCORDANCE WITH SECTION 523 OF THE SPECIFICATIONS. INCLUDE COSTS FOR LABOR, EQUIPMENT AND INCIDENTALS NECESSARY TO COMPLETE THE WORK IN THE CONTRACT UNIT PRICE OF "SEALER CRACK PREPARATION".
- B9 PROVIDE HIGH MOLECULAR WEIGHT METHACRYLATE SEALER FOR DECK SLAB CONSTRUCTION JOINTS AT LOCATIONS SHOWN IN THE PLANS IN ACCORDANCE WITH SECTION 523 OF THE SPECIFICATIONS. INCLUDE ALL COSTS OF THE SEALER RESIN MATERIAL IN THE CONTRACT UNIT PRICE OF "SEALER RESIN". SEALER RESIN QUANTITY ESTIMATED AT 0.011 GALLONS PER FOOT OF CONSTRUCTION JOINT.
- B10 RIPRAP QUANTITY ESTIMATED AT 120 LBS. PER CUBIC FOOT.
- B11 FILTER BLANKET QUANTITY ESTIMATED AT 105 LBS. PER CUBIC FOOT.
- B12 INCLUDE ALL COSTS ASSOCIATED WITH PROVIDING AND INSTALLING THE PERFORATED PIPE AND PIPE UNDERDRAIN COVER MATERIAL (BOTH FILTER SAND AND COARSE), INCLUDING ALL MATERIAL, LABOR, EQUIPMENT AND INCIDENTALS NECESSARY TO COMPLETE THE WORK, IN THE CONTRACT UNIT PRICE OF "6" PERFORATED PIPE UNDERDRAIN ROUND". INSTALLATION SHALL BE AS SHOWN ON STD. B40-C-ABUT-MISC AND STD. PUD-3.
- B13 EXTENT, LOCATIONS AND DEPTH OF NON-PERFORATED PIPE UNDERDRAIN MAY BE ADJUSTED BY THE ENGINEER DURING CONSTRUCTION. INSTALL MARKER POSTS AT THE END OF EACH NON-PERFORATED PIPE. INCLUDE ALL COSTS ASSOCIATED WITH THE PROVIDING AND INSTALLING OF NON-PERFORATED PIPE, MARKER POSTS, AND STANDARD BEDDING MATERIAL, INCLUDING ALL TRENCH EXCAVATION, MATERIAL, LABOR, EQUIPMENT AND INCIDENTALS NECESSARY TO COMPLETE THE WORK, IN THE CONTRACT UNIT PRICE OF "6" NON-PERFORATED PIPE-UNDERDRAIN ROUND". INSTALLATION SHALL BE SHOWN ON STD. B40-I-ABUT-MISC-01E AND STD. PUD-3.
- B14 ITEM "REMOVAL OF EXISTING BRIDGE STRUCTURE" INCLUDES REMOVAL AND DISPOSAL OF SUPERSTRUCTURE AND SUBSTRUCTURE, INCLUDING PULLING EXISTING CONCRETE PILING, OF 7 - 36' I-BEAM SPANS WITH 28' CLEAR ROADWAY IN ACCORDANCE WITH SUBSECTION 619.04(b)-2 OF THE SPECIFICATIONS AND IN A MANNER APPROVED BY THE ENGINEER. THE STRUCTURE AND MATERIALS SHALL BECOME THE PROPERTY OF THE CONTRACTOR. INCLUDE ALL COSTS FOR LABOR, EQUIPMENT AND INCIDENTALS NECESSARY TO COMPLETE THE WORK IN THE CONTRACT UNIT PRICE OF "REMOVAL OF EXISTING BRIDGE STRUCTURE".

THE EXISTING STEEL BEAMS WILL BE SALVAGED FOR REUSE AND BECOME PROPERTY OF WOODWARD COUNTY. THE CONTRACTOR WILL REMOVE EXISTING STEEL BEAMS TAKING CARE TO NOT DAMAGE THE BEAMS. THE BEAMS WILL BE PLACED ON THE RIGHT OF WAY AS DIRECTED BY THE ENGINEER. WOODWARD COUNTY WILL BE INFORMED THAT THE EXISTING BRIDGE BEAMS ARE COATED WITH LEAD PAINT.

J.P. NO. 28827(04) 0200 BRIDGE A			
<b>PAY QUANTITIES</b>			
SH-34 OVER NORTH PERSIMMON CREEK 100' X 100' X 100' TYPE IV P.C. BEAM SPANS, 0° SKEW, 40' CLEAR ROADWAY WITH TR-4 PARAPETS @ STA. 2442+16.00			
ITEM NO.	ITEM	UNIT	TOTAL
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	B1,B2 C.Y.	3,600
501(G) 6309	CLSM BACKFILL	B1 C.Y.	210
503(A) 1313	PRESTRESSED CONCRETE BEAMS (TYPE IV)	B1 L.F.	1,495
504(A) 1304	APPROACH SLAB	B1,B3 S.Y.	281.2
504(B) 1305	SAW-CUT GROOVING	B1 S.Y.	1,607.6
504(C) 6250	SEALED EXPANSION JOINT	B1 L.F.	41.8
504(D) 6245	CONCRETE RAIL (TR4)	B1 L.F.	723.3
506(A) 1322	STRUCTURAL STEEL	B1 LB.	1,430
507(A) 6170	STAINLESS STEEL FIXED BEARING ASSEMBLY	B1,B4 EA.	10
507(B) 6174	STAINLESS STEEL EXPANSION BEARING ASSEMBLY	B1,B5 EA.	20
509(A) 1326	CLASS AA CONCRETE	B1,B6 C.Y.	580.6
509(B) 1328	CLASS A CONCRETE	B1,B6 C.Y.	168.0
509(D) 1331	CLASS C CONCRETE	C.Y.	9.3
511(A) 1332	REINFORCING STEEL	B1 LB.	2,200
511(B) 6010	EPOXY COATED REINFORCING STEEL	B1 LB.	161,450
514(A) 6010	PILES, FURNISHED (HP 10X42)	B7 L.F.	432
514(A) 6011	PILES, FURNISHED (HP 12X53)	B7 L.F.	1,887
514(A) 6016	PILES, FURNISHED (HP 14X89)	B7 L.F.	3,900
514(B) 6292	PILES, DRIVEN (HP 10X42)	L.F.	432
514(B) 6294	PILES, DRIVEN (HP 12X53)	L.F.	1,887
514(B) 6297	PILES, DRIVEN (HP 14X89)	L.F.	3,900
514(L) 6220	PILE SPLICE, H-PILE (NON-BIDDABLE)	EA.	1
515(A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	B1 S.Y.	1,319
523(A) 6550	SEALER CRACK PREPARATION	B1,B8 L.F.	41
523(B) 6560	SEALER RESIN	B1,B9 GAL.	1
601(B) 1353	TYPE I-A PLAIN RIPRAP	B10 TON	1,283
601(C) 1355	TYPE I-A FILTER BLANKET	B11 TON	289
613(H) 6204	6" PERFORATED PIPE UNDERDRAIN ROUND	B1,B12 L.F.	84
613(I) 6207	6" NON-PERF. PIPE UNDERDRAIN RND.	B13 L.F.	68
619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	B14 LSUM	1

THIS DRAWING IS PRELIMINARY IN NATURE. IT IS NOT A FINAL SIGNED AND SEALED DRAWING

DESIGN	J.W.H.
DRAWN	R.A.P.
CHECKED	J.W.H.
APPROV.	T.A.C.
SQUAD	CEC

SH34 OVER N. PERSIMMON CREEK WOODWARD COUNTY  
BRIDGE A  
**PAY ITEMS AND NOTES  
(BRIDGE)**  
JOB PIECE NO. 28827(04) SHEET NO. 5

SUMMARY OF SURFACING									
STATION TO STATION	ALIGNMENT	STABILIZED SUBGRADE	SUBGRADE METHOD B	TACK COAT	PRIME COAT	SUPERPAVE. TYPE S3	SUPERPAVE. TYPE S3	SUPERPAVE. TYPE S4	SUPERPAVE. TYPE S4
		307(G)	310(B)	407(B)	408	(PG 70-28 OK) 411(B)	(PG 54-22 OK) 411(B)	(PG 70-28 OK) 411(C)	(PG 64-22 OK) 411(C)
		SY	SY	GAL	GAL	TON	TON	TON	TON
MAINLINE									
2434+50.00 TO 2440+35.16	CL SURVEY	3,258		1,327	1,141	273	938	177	108
2443+95.83 TO 2449+50.00	CL SURVEY	3,103		1,255	1,081	258	889	167	103
DETOUR									
2428+49.86 TO 2443+00.00	DETOUR			564	1,742		863		423
2443+00.00 TO 2455+03.88	DETOUR			477	1,462		725		356
WIDENING FOR GUARDRAIL									
2437+26.41 TO 2440+35.16 LT	CL SURVEY				49				31
2436+51.41 TO 2440+35.16 RT	CL SURVEY				61				39
2443+96.83 TO 2447+80.58 LT	CL SURVEY				62				39
2443+96.83 TO 2447+05.58 RT	CL SURVEY				49				31
DRIVEWAYS*									
			303	45	106		68		34
<b>TOTAL</b>		<b>6,361</b>	<b>303</b>	<b>3,678</b>	<b>5,753</b>	<b>531</b>	<b>3,483</b>	<b>344</b>	<b>1,164</b>

\*REFERENCE "SUMMARY OF DRIVEWAYS" FOR ADDITIONAL INFORMATION

SUMMARY OF DRIVEWAYS										
SHEET NUMBER	ALIGNMENT	STATION	LT.	RT.	TYPE	LENGTH	WIDTH	RAOI		
						LF	LF	LT	RT.	
18	CL SURVEY	2436+25.00			ASPH. TYPE 1	120	16	15	15	
18	CL SURVEY	2436+25.00			TEMP. ASPH. DR.	51	12	15	15	

NOTE: SEE "SUMMARY OF SURFACING" FOR REQUIRED SURFACING QUANTITIES

SUMMARY OF REMOVALS					
SHEET NUMBER	ALIGNMENT	REMOVAL OF FENCE	REMOVAL OF ASPHALT PAVEMENT	REMOVAL OF ASPHALT OR WEWAY	REMOVAL OF GUARDRAIL
		619(B)	619(B)	619(B)	619(B)
		SY	SY	SY	LF
18	CL SURVEY	1,225	2,147	136	280
19	CL SURVEY	1,314	2,179		280
18	DETOUR		3,780		
19	DETOUR		3,180		79
<b>TOTAL</b>		<b>2,539</b>	<b>11,286</b>	<b>215</b>	<b>560</b>

SUMMARY OF MISCELLANEOUS ITEMS			
SHEET NUMBER	ALIGNMENT	TYPE A SALVAGED TOPSOIL	MOWING
		205(A)	241
		CY	AC
18	CL SURVEY	2,456	6.36
19	CL SURVEY	2,348	5.48
<b>TOTAL</b>		<b>4,804</b>	<b>11.84</b>

REMOVAL OF STRUCTURES AND OBSTRUCTIONS SUMMARY					
ALIGNMENT	STATION	SHEET NO.	DESCRIPTION	QUANTITY	
CL SURVEY	2436+24.99, 100.09' RT	18	TEMPORARY 18" CGMP	24 LF	
CL SURVEY	2437+64.07, 50.00' RT	18	42"x28" HCPA W/ HAD WALLS	31 LF	
CL SURVEY	2442+41.71, 41.38' RT, 108.93' RT	18	TEMPORARY 72" CGSP	68 LF	
CL SURVEY	2442+50.71, 41.26' RT, 108.82' RT	18	TEMPORARY 72" CGSP	68 LF	
CL SURVEY	2442+61.72, 35.77' RT, 114.82' RT	18	TEMPORARY 96" CGSP	79 LF	
CL SURVEY	2442+72.72, 40.99' RT, 108.55' RT	18	TEMPORARY 72" CGSP	68 LF	

SUMMARY OF EARTHWORK				
STATION TO STATION	UNCLASSIFIED EXCAVATION	EMBANKMENT	EXCESS EXCAVATION	UNCLASSIFIED BORROW
	202(A)	+15% CY	CY	202(D) CY
PHASE 1				
2428+49.86 TO 2455+03.88	1,987	6,462		4,475
PHASE 2				
2434+50.00 TO 2449+50.00	3,882	2,481	1,401	
PHASE 3				
2428+49.86 TO 2455+03.88	5,798	2,266	3,532	
<b>TOTAL</b>	<b>11,667</b>	<b>11,209</b>	<b>4,933</b>	<b>4,475</b>

SUMMARY OF PAVEMENT MARKINGS			
SHEET NUMBER	ALIGNMENT	TRAFFIC STRIPE (MULTI-POLY.) (WHITE)	TRAFFIC STRIPE (MULTI-POLY.) (YELLOW)
		(4" WIDE) 856(A)	(4" WIDE) 856(A)
		LF	LF
21	CL SURVEY	3,000	408
<b>TOTAL</b>		<b>3,000</b>	<b>408</b>

SUMMARY OF EROSION CONTROL					
SHEET NUMBER	TEMPORARY SILT FENCE	TEMPORARY SILT DIKE	TEMPORARY ROCK FILTER DAM	SOLID SLAB SODDING	VEGETATIVE MULCHING
	221(C)	221(F)	TYPE 1 221(G)	230(A)	233(A)
		LF	LF	CY	SY
17	768	161	20	22,990	3.80
<b>TOTAL</b>	<b>768</b>	<b>161</b>	<b>20</b>	<b>22,990</b>	<b>3.80</b>

SUMMARY OF FENCE					
ALIGNMENT	STATION TO STATION	LT.	RT.	FENCE-STYLE SWF	
				(5 BARBED WIRE) 624(C)	
				LF	
CL SURVEY	2442+95.00 TO 2446+06.00	X		331	
<b>TOTAL</b>				<b>331</b>	

SUMMARY OF DRAINAGE STRUCTURES										
STRUCTURE NUMBER	SHEET NUMBER	ALIGNMENT	STATION	OFFSET*	DESCRIPTION	DESIGN	FL ELEVATION			TYPE C6 CET (613M)
							PIPE IN	PIPE OUT	%	
							IT	IT		
1	18	CL SURVEY	2436+24.99	47.59' RT	SIDE DRAIN	SPI-4-0	2021.96	2020.95	1.0%	96
2	18	CL SURVEY	2442+41.71	41.38' RT, 108.93' RT	CROSS DRAIN	SPI-4-0	2012.40	2012.00	0.5%	68
3	18	CL SURVEY	2442+50.71	41.26' RT, 108.82' RT	CROSS DRAIN	SPI-4-0	2012.40	2012.00	0.5%	68
4	18	CL SURVEY	2442+61.72	35.77' RT, 114.82' RT	CROSS DRAIN	SPI-4-0	2010.60	2010.00	0.7%	79
5	18	CL SURVEY	2442+72.72	40.99' RT, 108.55' RT	CROSS DRAIN	SPI-4-0	2012.40	2012.00	0.5%	68
6	18	CL SURVEY	2436+24.99	100.09' RT	SIDE DRAIN	SPI-4-0	2021.38	2021.14	1.0%	24
<b>TOTAL</b>										<b>96</b>

SUMMARY OF TRAFFIC CONTROL																	
SHEET NUMBER	SIGN DAYS	CONSTRUCTION TRAFFIC STRIPE (PAINT)(4) 857(A)	PAVEMENT MARKING REMOVAL (TRAFFIC STRIPE) 857(F)	CONSTRUCTION SIGNS						WING BARRICADES (880(C))	WARNING LIGHTS (TYPE A) 880(F)	CHANNELIZER (CONES) 880(G)					
				0 TO 6.25 S.F.		6.26 TO 15.99 S.F.		16.0 TO 32.99 S.F.									
				EA	SD	EA	SD	EA	SD								
43	240	5912	707	10	2,400	11	2,640	7	1,680	6	1,440	2	480	16	3,840	48	11,520
44	240	5,780	690	10	2,400	9	2,160	7	1,580	6	1,440	2	480	16	3,840	48	11,520
<b>TOTAL</b>		<b>11,692</b>	<b>1,397</b>	<b>20</b>	<b>4,800</b>	<b>20</b>	<b>4,800</b>	<b>14</b>	<b>3,360</b>	<b>12</b>	<b>2,880</b>	<b>4</b>	<b>960</b>	<b>32</b>	<b>7,680</b>	<b>96</b>	<b>23,040</b>

SUMMARY OF GUARDRAIL						
STATION TO STATION	LT.	RT.	TOTAL LENGTH	BEAM GUARDRAIL	GUARDRAIL END	GUARDRAIL BRIDGE
			(INCLUDING ANCHORS) UNITS	(W-BEAM SINGLE) 623(A)	(RELATIVE) (31') 623(G)	(CONCRETE) 623(I)
			LF	LF	LA	LA
2437+42.04 TO 2440+35.79		X	293.75	225	1	1
2443+96.21 TO 2446+14.96		X	218.75	150	1	1
2438+17.64 TO 2440+35.79	X		218.75	150	1	1
2443+96.21 TO 2446+14.96	X		293.75	225	1	1
<b>TOTAL</b>			<b>750</b>	<b>750</b>	<b>4</b>	<b>4</b>


FILENAME: 6 SUMMARY SHEET.DWG

DESCRIPTION	REVISIONS	DATE

**MASS DIAGRAM  
PHASE 1 (DETOUR) TOTAL VOLUME**

PHASE 1 (DETOUR) EARTHWORK ESTIMATE  
STA. 2428+49.86 TO STA. 2455+03.88


UNCL. EXCAV. = 1,987 CY  
EMB. + 15% = 6,462 CY  
UNCL. BORROW = 4,475 CY




**MASS DIAGRAM  
PHASE 2 (MAINLINE) TOTAL VOLUME**

PHASE 2 (MAINLINE) EARTHWORK ESTIMATE  
STA. 2434+50.00 TO STA. 2449+50.00

UNCL. EXCAV. = 3,882 CY  
EMB. + 15% = 2,481 CY  
EXCESS EXCAV. = 1,401 CY



MASS DIAGRAM PROVIDED FOR BIDDING PURPOSES ONLY. ACTUAL BALANCE POINTS TO BE DETERMINED BY CONTRACTOR AND VOLUME OF MATERIAL ENCOUNTERED DURING GRADING OPERATIONS. WHENEVER POSSIBLE, THE CONTRACTOR SHALL SEQUENCE EARTHWORK OPERATIONS IN ORDER TO OBTAIN THE MATERIAL FROM THE CUT SECTION FOR USE AS FILL RATHER THAN OBTAINING UNCLASSIFIED BORROW. MATERIAL DEPICTED AS WASTE SHALL ONLY BE CONSIDERED WASTE ONCE ALL EARTHWORK OPERATIONS HAVE BEEN COMPLETED. THIS MATERIAL SHALL BE USED TO REDUCE THE NEED FOR UNCLASSIFIED BORROW AT ANY LOCATION AND TIME THROUGH THE DURATION OF THE PROJECT.



FILENAME: 7A MASS DIAGRAM (SHEET 2 OF 2).DWG

DESIGN	SH-34 OVER N. PERSIMMON CREEK	WOODWARD COUNTY
DRAWN		
CHECKED		
CEC	STATE JOB NO. 28827(04)	SHEET NO. 7

**MASS DIAGRAM  
(SHEET 1 OF 2)**




DESCRIPTION	REVISIONS	DATE

SUMMARY OF EARTHWORK				
STATION TO STATION	UNCLASSIFIED EXCAVATION 202(A)	EMBANKMENT +15%	EXCESS EXCAVATION	UNCLASSIFIED BORROW 202(D)
	CY	CY	CY	CY
PHASE 1				
2428+49.86 TO 2455+03.88	1,987	6,462		4,475
PHASE 2				
2434+50.00 TO 2449+50.00	3,882	2,481	1,401	
PHASE 3				
2428+49.86 TO 2455+03.88	5,798	2,266	3,532	
<b>TOTAL</b>	<b>11,667</b>	<b>11,209</b>	<b>4,933</b>	<b>4,475</b>


**MASS DIAGRAM  
PHASE 3 (DETOUR REMOVAL) TOTAL VOLUME**

PHASE 3 (DETOUR REMOVAL) EARTHWORK ESTIMATE  
STA. 2428+49.86 TO STA. 2455+03.88

UNCL. EXCAV. = 5,798 CY  
EMB. + 15% = 2,266 CY  
EXCESS EXCAV. = 3,532 CY



MASS DIAGRAM PROVIDED FOR BIDDING PURPOSES ONLY. ACTUAL BALANCE POINTS TO BE DETERMINED BY CONTRACTOR AND VOLUME OF MATERIAL ENCOUNTERED DURING GRADING OPERATIONS. WHENEVER POSSIBLE, THE CONTRACTOR SHALL SEQUENCE EARTHWORK OPERATIONS IN ORDER TO OBTAIN THE MATERIAL FROM THE CUT SECTION FOR USE AS FILL RATHER THAN OBTAINING UNCLASSIFIED BORROW. MATERIAL DEPICTED AS WASTE SHALL ONLY BE CONSIDERED WASTE ONCE ALL EARTHWORK OPERATIONS HAVE BEEN COMPLETED. THIS MATERIAL SHALL BE USED TO REDUCE THE NEED FOR UNCLASSIFIED BORROW AT ANY LOCATION AND TIME THROUGH THE DURATION OF THE PROJECT.



FILENAME: 7A MASS DIAGRAM (SHEET 2 OF 2).DWG

DESIGN	SH-34 OVER N. PERSIMMON CREEK	WOODWARD COUNTY
DRAWN		
CHECKED		
CEC	STATE JOB NO. 28827(04)	SHEET NO. 7A

**MASS DIAGRAM  
(SHEET 2 OF 2)**

# STORM WATER MANAGEMENT PLAN

DESCRIPTION	REVISIONS	DATE

## SITE DESCRIPTION

## EROSION AND SEDIMENT CONTROLS

**PROJECT LIMITS:** BEGINS 4,075 FEET SOUTH OF SH-34 AND EW-51 INTERSECTION, CONTINUING NORTH 2,688 FEET NORTH ALONG SH-34.

**PROJECT DESCRIPTION:** RECONSTRUCT BRIDGE AND ROADWAY APPROACHES.

**SUGGESTED SEQUENCE OF EROSION CONTROL ACTIVITIES:**

1. VEGETATIVE STRIPPING
2. UNDERCUT & STOCKPILE EXISTING TOPSOIL, PRESERVE AS MUCH NATIVE VEGETATION AS POSSIBLE.
3. REMOVE AND REPLACE EXISTING PAVEMENT AND BRIDGE
4. SPREAD TOPSOIL
5. INSTALL SOLID SLAB SOD

SOIL TYPE: RUSH SPRINGS

AREA TO BE DISTURBED: 6.45 ACRES

OFFSITE AREA TO BE DISTURBED: \_\_\_\_\_  
(FOR CONTRACTOR USE)

MAXIMUM ACRES TO BE DISTURBED AT ANY ONE TIME: \_\_\_\_\_  
(FOR CONTRACTOR USE)

LATITUDE & LONGITUDE OF CENTER OF PROJECT: 36°16'06.81" N, 99°20'08.81" W

NAME OF RECEIVING WATERS: NORTH PERSIMMON CREEK

SENSITIVE WATERS OR WATERSHEDS: YES  NO

303(d) IMPAIRED WATERS: YES  NO

NOTE:  
THIS SHEET SHOULD BE USED IN CONJUNCTION WITH A DRAINAGE MAP THAT ILLUSTRATES THE DRAINAGE PATTERNS/PATHWAYS AND RECEIVING WATERS FOR THIS PROJECT. THIS SHEET SHOULD ALSO BE USED WITH THE EROSION CONTROL SUMMARIES, PAY ITEMS, & NOTES.

**SOIL STABILIZATION PRACTICES:**

- \_\_\_\_\_ TEMPORARY SEEDING
- PERMANENT SODDING, SPRIGGING OR SEEDING
- VEGETATIVE MULCHING
- \_\_\_\_\_ SOIL RETENTION BLANKET
- PRESERVATION OF EXISTING VEGETATION

NOTE: TEMPORARY EROSION CONTROL METHODS MUST BE USED ON ALL DISTURBED AREAS WHERE CONSTRUCTION ACTIVITIES HAVE CEASED FOR OVER 14 DAYS. METHODS USED WILL BE AS SHOWN ON PLANS, OR AS DIRECTED BY THE ENGINEER.

**STRUCTURAL PRACTICES:**

- \_\_\_\_\_ STABILIZED CONSTRUCTION EXIT
- TEMPORARY SILT FENCE
- TEMPORARY SILT DIKES
- \_\_\_\_\_ TEMPORARY FIBER LOG
- \_\_\_\_\_ DIVERSION, INTERCEPTOR OR PERIMETER DIKES
- \_\_\_\_\_ DIVERSION, INTERCEPTOR OR PERIMETER SWALES
- ROCK FILTER DAMS
- \_\_\_\_\_ TEMPORARY SLOPE DRAIN
- \_\_\_\_\_ PAVED DITCH W/ DITCH LINER PROTECTION
- \_\_\_\_\_ TEMPORARY DIVERSION CHANNELS
- \_\_\_\_\_ TEMPORARY SEDIMENT BASINS
- \_\_\_\_\_ TEMPORARY SEDIMENT TRAPS
- \_\_\_\_\_ TEMPORARY SEDIMENT FILTERS
- TEMPORARY SEDIMENT REMOVAL
- \_\_\_\_\_ RIP RAP
- INLET SEDIMENT FILTER
- \_\_\_\_\_ TEMPORARY BRUSH SEDIMENT BARRIERS
- \_\_\_\_\_ SANDBAG BERMS
- \_\_\_\_\_ TEMPORARY STREAM CROSSINGS

**OFFSITE VEHICLE TRACKING:**

- HAUL ROADS DAMPENED FOR DUST CONTROL
- LOADED HAUL TRUCKS TO BE COVERED WITH TARPULIN
- EXCESS DIRT ON ROAD REMOVED DAILY

**NOTES:**

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**THE CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR THE FOLLOWING:**

**MAINTENANCE AND INSPECTION:**

ALL EROSION AND SEDIMENT CONTROLS WILL BE MAINTAINED IN GOOD WORKING ORDER FROM THE BEGINNING OF CONSTRUCTION UNTIL AN ACCEPTABLE VEGETATIVE COVER IS ESTABLISHED. INSPECTION BY THE CONTRACTOR AND ANY NECESSARY REPAIRS SHALL BE PERFORMED ONCE EVERY 7 CALENDAR DAYS AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAN 0.5 INCH AS RECORDED BY A NON-FREEZING RAIN GAUGE TO BE LOCATED ON SITE. POTENTIALLY ERODIBLE AREAS, DRAINAGEWAYS, MATERIAL STORAGE, STRUCTURAL DEVICES, CONSTRUCTION ENTRANCES AND EXITS ALONG WITH EROSION AND SEDIMENT CONTROL LOCATIONS ARE EXAMPLES OF SITES THAT NEED TO BE INSPECTED.

**WASTE MATERIALS:**

PROPER MANAGEMENT AND DISPOSAL OF CONSTRUCTION WASTE MATERIAL IS REQUIRED BY THE CONTRACTOR. MATERIALS INCLUDE STOCKPILES, SURPLUS, DEBRIS AND ALL OTHER BY-PRODUCTS FROM THE CONSTRUCTION PROCESS. PRACTICES INCLUDE DISPOSAL, PROPER MATERIALS HANDLING, SPILL PREVENTION AND CLEANUP MEASURES. CONTROLS AND PRACTICES SHALL MEET THE REQUIREMENTS OF ALL FEDERAL, STATE AND LOCAL AGENCIES.

**HAZARDOUS MATERIALS:**

PROPER MANAGEMENT AND DISPOSAL OF HAZARDOUS WASTE MATERIAL IS REQUIRED. THE CONTRACTOR IS RESPONSIBLE FOR FOLLOWING MANUFACTURER'S RECOMMENDATIONS, STATE AND FEDERAL REGULATIONS TO ENSURE CORRECT HANDLING, DISPOSAL, SPILL PREVENTION AND CLEANUP MEASURES. EXAMPLES INCLUDE BUT ARE NOT LIMITED TO: PAINTS, ACIDS, CLEANING SOLVENTS, CHEMICAL ADDITIVES, CONCRETE CURING COMPOUNDS AND CONTAMINATED SOILS.

**GENERAL NOTES:**

A STORM WATER POLLUTION PREVENTION PLAN (SWPPP) IS REQUIRED TO COMPLY WITH THE OKLAHOMA POLLUTION DISCHARGE ELIMINATION SYSTEM (OPDES) REGULATIONS. THIS PLAN IS INITIATED DURING THE DESIGN PHASE, CONFIRMED IN THE PRE-WORK MEETINGS AND AVAILABLE ON THE JOB SITE ALONG WITH COPIES OF THE NOTICE OF INTENT (NOI) FORM AND PERMIT CERTIFICATE THAT HAVE BEEN FILED WITH THE OKLAHOMA DEPARTMENT OF ENVIRONMENTAL QUALITY (ODEQ). THE PLAN MUST BE KEPT CURRENT WITH UP-TO-DATE AMENDMENTS DURING THE PROGRESSION OF THE PROJECT. ALL CONTRACTOR OFF-SITE OPERATIONS ASSOCIATED WITH THE PROJECT MUST BE DOCUMENTED IN THE SWPPP, I.E., BORROW PITS, WORK ROADS, DISPOSAL SITES, ASPHALT/CONCRETE PLANTS, ETC. THE BASIC GOAL OF STORM WATER MANAGEMENT IS TO IMPROVE WATER QUALITY BY REDUCING POLLUTANTS IN STORM WATER DISCHARGES. RUNOFF FROM CONSTRUCTION SITES HAS A POTENTIAL FOR POLLUTION DUE TO EXPOSED SOILS AND THE PRESENCE OF HAZARDOUS MATERIALS USED IN THE CONSTRUCTION PROCESS. THE PREVENTION OF SOIL EROSION, CONTAINMENT OF HAZARDOUS MATERIALS AND/OR THE INTERCEPTION OF THESE POLLUTANTS BEFORE LEAVING THE CONSTRUCTION SITE ARE THE BEST PRACTICES FOR CONTROLLING STORM WATER POLLUTION.

**THE FOLLOWING SECTIONS OF THE 2009 ODOT STANDARD SPECIFICATIONS SHOULD BE NOTED:**

- 103.05** BONDING REQUIREMENTS
- 104.10** FINAL CLEANING UP
- 104.12** CONTRACTOR'S RESPONSIBILITY FOR WORK
- 104.13** ENVIRONMENTAL PROTECTION
- 106.08** STORAGE AND HANDLING OF MATERIAL
- 107.01** LAWS, RULES AND REGULATIONS TO BE OBSERVED
- 107.20** STORM WATER MANAGEMENT
- 220** MANAGEMENT OF EROSION, SEDIMENTATION AND STORM WATER POLLUTION PREVENTION AND CONTROL
- 221** TEMPORARY SEDIMENT CONTROL


**IN ADDITION:**

"ODEQ GENERAL PERMIT (OKR10) FOR STORM WATER DISCHARGES FROM CONSTRUCTION ACTIVITIES WITHIN THE STATE OF OKLAHOMA." ODEQ, WATER QUALITY DIVISION, SEPTEMBER 13, 2012.

FILENAME: 8 STORM WATER MANAGEMENT PLAN.DWG

DESIGN		SH-34 OVER N. PERSIMMON CREEK	WOODWARD COUNTY
DRAWN		<h3 style="margin: 0;">STORM WATER MANAGEMENT PLAN</h3>	
CHECKED			
CEC		STATE JOB NO. <u>28827(04)</u>	SHEET NO. <u>8</u>

DESCRIPTION	REVISIONS	DATE



FILENAME: 9 DRAINAGE AREA MAP.DWG		
DESIGN	SH-34 OVER N. PERSIMMON CREEK	WOODWARD COUNTY
DRAWN		
CHECKED		
CEC	<b>DRAINAGE AREA MAP</b>	
	JOB PIECE NO. 28827(04)	SHEET NO. 9

STATE OF OKLAHOMA  
DEPARTMENT OF TRANSPORTATION

SURVEY OF  
**STATE HIGHWAY 34**  
BRIDGE OVER NORTH PERSIMMON CREEK,  
7.6 MILES NORTH OF THE DEWEY COUNTY LINE  
SWO 4844(1)

STATE JOB NO. 28827(04),  
**WOODWARD COUNTY**

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
DESCRIPTION					DATE

STATE OF OKLAHOMA  
DEPARTMENT OF TRANSPORTATION  
SURVEY DIVISION

SWO 4844(1) J/P 28827(04) ; E.C. 1394 WOODWARD CO.

**HORIZONTAL CONTROL:**  
 Oklahoma Coordinate System of 1927 \_\_\_\_\_ Zone.  
 Oklahoma Coordinate System of 1983 (1993) North Zone.  
 Oklahoma Dept. of Transportation Plane Coordinate System of 1927 \_\_\_\_\_ Zone.  
 Oklahoma Dept. of Transportation Plane Coordinate System of 1983 \_\_\_\_\_ Zone.  
 Arbitrary Coordinate System \_\_\_\_\_

**HORIZONTAL PLANE DATUM DEFINITION:**  
 Oklahoma Department of Transportation coordinates were derived by multiplying the Oklahoma Coordinate Systems of 1927 or 1983 by the combined adjustment factor of 1.00010. The ODOT Coordinate System is 2350 feet above sea level.

1. Primary Control adjusted to OBTAINED BY OPUS SOLUTIONS (B) Order  
 Stations \_\_\_\_\_  
 A) Closure before adjustment X \_\_\_\_\_; Y \_\_\_\_\_ Angles \_\_\_\_\_  
 Trav. Length \_\_\_\_\_; No. Angles \_\_\_\_\_; 1: \_\_\_\_\_  
 B) \_\_\_\_\_; is  Order before adjustment.  
 C) Method of Distance Measurement:  
 Electronic  GPS  Triangulation  Chained  
 D) Instrument used for angles \_\_\_\_\_

2. Secondary Control adjusted to Primary Control (B) Order  
 Stations W-77-740, W-77-741  
 A) Closure before adjustment X \_\_\_\_\_; Y \_\_\_\_\_ Angles \_\_\_\_\_  
 B) Secondary Control; is (3rd) Order; Tied to \_\_\_\_\_  
 C) Method of Distance Measurement:  
 Electronic  GPS  Triangulation  Chained  
 D) Instrument used for angles Topcon Hiper II GPS

**VERTICAL CONTROL IS** (3rd) order. Level Line taken from 3" ALUMINUM CAP W-77-740  
(3RD) order and tied to OBTAINED BY OPUS SOLUTIONS (3RD) order.  
 VERTICAL CLOSURE = 0.006 feet before adjustment. 3rd order would allow 0.05 feet.


**ACCURACY DEFINITION:**  NGVD 29 datum  NAVD 88 datum  
 (1) HORIZONTAL: (3rd Order = Class I = 1: 10,000')  
 (3rd Order = Class II = 1: 5,000')  
 (2) VERTICAL: (1st Order = 0.017 Ft. x sqrt. of Mi.) (2nd Order = 0.035 Ft. x sqrt. of Mi.)  
 (3rd Order = 0.050 Ft. x sqrt. of Mi.)

**Distribution:**  
 Copy w/survey reports \_\_\_\_\_ JOSEPH H. FARMER  
 Copy in each Alignment \_\_\_\_\_ Professional Land Surveyor  
 and level book \_\_\_\_\_  
 (FORM SD #20) \_\_\_\_\_ May 29, 2013  
 Rev. 11/03 \_\_\_\_\_ Date

**INDEX OF SHEETS**

SDS 1. TITLE SHEET	SURVEY BEGAN: NOVEMBER 14, 2012
SDS 2. HISTORICAL LETTER	SURVEY COMPLETED: APRIL 16, 2013
SDS 3. LEVEL WORKSHEET ALIGNMENT REPORT COGO LIST	
SDS 4. CONTROL MAP & INFO.	<b>EQUIPMENT:</b>
SDS 5-6. SURVEY DATA SHEETS	TOPCON GR3 GPS
SDS 7. LAND TIES	TOPCON HIPER II GPS
	TOPCON IS 3" IMAGING ROBOTIC TOTAL STATION
	TOPCON FC-2500 DATA COLLECTORS
	GPT-9005A 5" ROBOTIC TOTAL STATION
	TOPCON GPT 3000W TOTAL STATION
	TOPCON GPT 3005W TOTAL STATION
	TOPCON GTS 3000 TOTAL STATION
	TOPCON GTS 313 TOTAL STATION
	TRIMBLE TSC 1 DATA COLLECTORS
	TRIMBLE TSC 2 DATA COLLECTORS
	TRIMBLE 5700 GPS
	TRIMBLE 5800 GPS
	SOKKIA SDL 30 DIGITAL LEVEL
	INROADS WORKING IN AUTOCAD PLATFORMS

**PERSONNEL:**  
 JOE FARMER, P.L.S. TECHNICIAN MANAGER 2  
 TANNER WENTWORTH, L.S.I. SURVEY INTERN 1  
 BRIAN BIRD, L.S.I. SURVEY INTERN 1  
 COREY SIMMONS, TECHNICIAN 1  
 SAM MCGEE, TECHNICIAN 1  
 ERIC MENTZER, TECHNICIAN 3  
 ERIC OLDFHAM, TECHNICIAN 1  
 MATTHEW OVERALL, TECHNICIAN 1  
 REBECCA ROBICHAUX, TECHNICIAN 2  
 PARKER KUGLER, TECHNICIAN 1  
 MATTHEW CHERNICKY, LEAD ROW AGENT



STATE OF OKLAHOMA  
DEPARTMENT OF TRANSPORTATION

SWO 4844(1) JOB/PIECE 28827(04) ENGR. CONTRACT NO. 1394

**LAND SURVEYORS CERTIFICATION**

I hereby certify that all land and property subdivision distances, angles, corners and monuments made or used in conjunction with this survey and depicted or recorded herein or hereon were recovered, established or re-established in substantial conformity with:

- applicable instructions contained in the U.S. Government Bureau of Land Management publication "Manual of Surveying Instructions";
- its supplement, "Restoration of Lost or Obliterated Corners and Subdivision of Sections";
- "Oklahoma Minimum Standards for the Practice of Land Surveying" as adopted by the State Board of Registration for Professional Engineers and Land Surveyors; and
- sound land surveying practices;

including a thorough search, study, analysis and consideration of all existing records and field evidence.

I further certify that all survey monuments depicted exist and that all land survey work was done by me or under my direct supervision and that it is true, accurate and correct to the best of my knowledge and belief.

Dated this 29 day of MAY, 2013.

Land Surveyor Joseph H. Farmer Signature  
 \_\_\_\_\_  
 Joseph H. Farmer Printed Name

Oklahoma Registered Land Surveyor No. 1799  
 Certificate of Authorization No. 32 Exp. Date June 30, 2014

**UTILITY OWNERS CONTACT INFORMATION**

OWNER	ADDRESS	PHONE
OG&E	3220 S. HIGH ST. OKLAHOMA CITY, OK 73129	(405) 553-0902
ONG	4901 N. SANTA FE AVE. P.O. BOX 401 OKC, OK 73118	(405) 556-6411
PIONEER TELEPHONE	205 E. ROBERTS KINGFISHER, OK 73750	(405) 375-0255
TOWN OF SHARON		(580) 334-0174



PROJECT LENGTH: 5,273.4 FT. 1.00 MILE

EQUATIONS: BOP STA. 2416+58.50  
 EOP STA. 2469+31.90

EXCEPTIONS: NONE

Electronic File Transfer Disclaimer:  
 These Files, Drawings and/or Notes are provided for information only. Cobb Engineering Company and the Owner cannot be held responsible for the content or accuracy of these Files, Drawings and/or Notes due to conversions, software translations, or any other manipulation of said Files, Drawings and/or Notes. Cobb Engineering Company expressly disclaims any responsibility arising from any use of these Files, Drawings and/or Notes. To the full extent permitted by applicable law, the recipient of these Files, Drawings and/or Notes hereby agrees to defend, indemnify, and hold harmless Cobb Engineering Company and the Owner from and against any and all claims, suits, actions, damages, loss, liability or costs of every nature or description (including reasonable attorney's fees) arising from, or in any way attributable to or connected with any of these Files, Drawings and/or Notes.

THIS SURVEY MEETS THE OKLAHOMA MINIMUM STANDARDS FOR THE PRACTICE OF LAND SURVEYING AS ADOPTED BY THE OKLAHOMA STATE BOARD OF REGISTRATION FOR PROFESSIONAL ENGINEERS AND LAND SURVEYORS, MAY 11, 2007.

DATE APPROVED \_\_\_\_\_  
 BY \_\_\_\_\_  
 CHIEF OF SURVEYS

PREPARED BY:  
 JOSEPH H. FARMER, PLS  
 COBB ENGINEERING COMPANY

PREPARED FOR:  
 OKLAHOMA DEPARTMENT OF TRANSPORTATION  
 SURVEY DIVISION

SHEET NO. 10



**OKLAHOMA DEPARTMENT OF TRANSPORTATION**  
SURVEY DIVISION (405) 521-2621 FAX (405) 522-0364

05/29/2013

To: Mr. Larry Reser, Chief of Surveys  
From: Joseph H. Farmer, Professional Land Surveyor  
Subject: Re: SWO 4844(1) - S.H. 34, Bridge over North Persimmon Creek, 7.6 miles North of the Dewey County Line, Woodward County, Oklahoma

Historical Letter and Written Report

**1. GENERAL**

- A. Survey began November 12, 2012  
Survey completed April 16, 2013
- B. The measurement unit for this project was the U.S. Survey Foot.

**2. SURVEY ASSIGNMENT**

The above described survey was assigned to me by Mr. Larry Reser, Chief of Surveys, and completed by my crew at Cobb Engineering.

**3. PURPOSE OF THIS SURVEY**

The purpose of this survey is to furnish sufficient data to develop plans to construct a new bridge over North Persimmon Creek south of Sharon. The survey will include the Alignment, Topographic/Planimetric data, Surface Features/DTM data, Land Ties, Utilities, Drainage and all other pertinent information needed to aid in the design.

**4. SURVEY LIMITS**

This survey began at P.O.T. Sta. 2416+58.50 (EW-52 Section Line) and extends North to P.I. Sta. 2469+31.90 (EW-51 Section Line) = P.I. Sta. 2469+33.40 as established under SWO 1994(1) survey and shown on FAP No. F-418 (8) plans (approximate centerline length = 1.00 mile).

**5. ALIGNMENTS**

The Centerline of Survey for this project is along and identical to the centerline of present S.H. 34 as established under SWO 1994(1) survey and shown on FAP No. F-418 (8) plans.

NORTH QUARTER CORNER OF SECTION 28, O.D.O.T. MONUMENT W-77-743, T-21-N, R-20-W, I.M. FOUND 1/2" IRON PIN 6" DEEP. MATCHES MONUMENT DESCRIPTION AND FITS REFERENCES ON OCCR FILED BY R. JVIDEN, LS 1083, ON 07-22-08.

NORTHEAST CORNER OF SECTION 28, O.D.O.T. MONUMENT W-77-744, T-21-N, R-20-W, I.M. FOUND BENT 3/4" IRON PIN 12" DEEP. MONUMENT FITS DISTANCE TO CENTERLINE OF SURVEY FOR SH34 AS CALLED OUT ON SH-34 FAP NO. F-418(8) HIGHWAY PLANS.

SOUTH QUARTER CORNER OF SECTION 28, O.D.O.T. MONUMENT W-77-751, T-21-N, R-20-W, I.M. FOUND 1/2" IRON PIN WITH LS 1083 CAP 6" DEEP. MATCHES MONUMENT DESCRIPTION AND FITS REFERENCES ON OCCR FILED BY R. JVIDEN, LS 1083, ON 12-26-07.

SOUTHEAST CORNER OF SECTION 28, O.D.O.T. MONUMENT W-77-750, T-21-N, R-20-W, I.M. SET 5/8" IRON PIN WITH CA 32 CAP. MONUMENT WAS SET ON NORTH SIDE OF 8" WOOD FENCE POST. MONUMENT FITS WITHIN 0.03' OF PROPORTIONAL DISTANCE TO QUARTER SECTION CORNER 0.5 MILE EAST. OLD FENCE LINE 0.5 MILE NORTH FITS WITHIN 1' OF SINGLE PROPORTION MEASUREMENT BETWEEN THIS CORNER AND SECTION CORNER 1 MILE NORTH.

WEST QUARTER CORNER OF SECTION 28, O.D.O.T. MONUMENT W-77-749, T-21-N, R-20-W, I.M. SET 5/8" IRON PIN WITH CA 32 CAP. MONUMENT WAS SET ON-LINE BETWEEN SECTION CORNERS 0.5 MILE NORTH AND 0.5 MILE SOUTH AND IN-LINE WITH OLD FENCE RUNNING EAST AND WEST.

NORTHWEST CORNER OF SECTION 28, O.D.O.T. MONUMENT W-77-742, T-21-N, R-20-W, I.M. FOUND 60D NAIL 6" DEEP. MONUMENT FITS PROPORTIONAL DISTANCE TO QUARTER SECTION CORNER 0.5 MILE EAST. MONUMENT ALSO FALLS IN CENTER OF EAST-WEST ROAD AND IN-LINE WITH ROAD RUNNING NORTH.

**12. EXISTING RIGHT-OF-WAY**

Existing right of way as shown on this survey is based off of FAP-418 (8) Plans and verified with right-of-way deeds where available.

**13. UTILITIES**

- A. All utility companies servicing this survey project were contacted through "CALL OKIE". Contacts for the town of Sharon water lines and sanitary sewer lines were provided by Ed Laird (Director of Environmental Services, Woodward Public Works Dept.) (580) 254-8554.

**6. STATIONING**

Stationing for this survey was taken from SWO 1994(1) survey and FAP No. F-418 (8) plans.

**7. HORIZONTAL CONTROL**

- A. Horizontal Control for this survey is NAD 83 (1993) Oklahoma State Plane Coordinate System, Lambert Projection, North Zone, and derived utilizing static GPS.
- B. Primary Horizontal control was established on one (1) monument along this survey. It is a 3 inch aluminum cap marked W-77-740.
- C. Secondary horizontal control was established along the centerline of survey and referenced and shown on the survey data sheets of this survey.
- D. The primary control network, the secondary network and section boundaries for this survey are in compliance with NGS Second Order Class 11 standards for horizontal control. (1 : 20,000).

**8. VERTICAL CONTROL**

- A. Level datum for this survey is NGS, NAVD 88, taken from PRIMARY CONTROL POINT NO. W-77-740. A complete set of check levels was run throughout the survey using a Sokkia digital level.
- B. The adjusted levels and vertical differences between bench marks are shown in Following file: SWO4844\_1\_V1.dgn (SDS 3) and SWO4844\_1\_V1\_Level Worksheet.pdf
- C. Accuracy - 3rd order or better before adjustment.

**9. TOPOGRAPHY**

Topography on this survey was obtained by utilizing the Topcon and Trimble GPS RTK systems and Total Station technology with the Trimble TSCI, TSCII, and TOPCON FC-2500 data collectors for field instruments. Centerline profile, bridge profiles, and drainage structures were obtained for the length of the project by utilizing conventional field methods. The supportive information pertaining to the surface features are available in the computer file SWO4844\_1\_V1\_SFF.dgn and SWO 4844\_1\_V1\_TOPO.dgn.

**10. DTM / CROSS SECTIONS**

Cross sections on this survey were provided by the Topcon and Trimble GPS RTK system and total station technology processed and output in the form of a DTM survey and placed in computer file SWO4844\_1\_V1\_SFF.dgn

- B. No utilities of any kind were located by USIC (Utility Locator). There were multiple correspondences between Tanner Wentworth (Cobb Engr. Survey Party Chief) and the USIC utility line locator. The USIC utility line locator said he would mark the lines and then provided dates as to when he would mark them on three separate occasions. After each occasion The USIC locator mentioned that he was "too busy" and could not mark the lines. After two weeks and multiple attempts to get the lines marked by USIC, Tanner Wentworth left messages with Jason Dewey (USIC Northwest Supervisor) and Dave Stewart (USIC West supervisor) in an attempt to get the lines marked. No USIC representatives responded to these messages.
- C. Information regarding type, size, ownerships, location, depth, etc. is placed in computer file SWO4844\_1\_V1\_SD7.pdf.

**14. Environmental Concerns**

There were no environmental concerns that were encountered.

**15. DRAINAGE INFORMATION**

Drainage areas were determined from USGS Stream Stats and USGS Quad Maps. Drainage data was taken from USGS Basin Characteristics Report. Data was field verified for accuracy placed in computer file SWO4844\_1\_V1\_DRA.dgn and SWO4844\_1\_V1\_USGS Drainage.pdf

**16. SURVEY DATA SHEETS**

Survey Data Sheets were submitted in the form of a Microstation Design File archived on the O.D.O.T. Mainframe Computer, as per O.D.O.T. Survey Division Standards. These will be incorporated into the set of design drawings and will be in substantial conformity with the O.D.O.T. Survey Division Standards for Survey Data Sheets, as maintained on O.D.O.T.(s) Intranet.

**17. SUBMISSION OF SURVEY DATA**

- A. Historical Letter & Written Report.
- B. Form SD-1, Transmittal Letter w/FSVARCH INDEX attached.
- C. Form SD-7, Public and Privately Owned Utilities List w/ vicinity maps where available.
- D. Form SD-11, Position and Description of Survey Monuments (GPS control monuments, Brass/Aluminum Caps for benchmarks, etc.) (if applicable).
- E. Form SD-20, Survey Control Data Statement.
- F. Form SD-41, Surveyor's Certification.
- G. Cogo Data (coordinate list with alignments).
- H. Benchmarks & Check Levels list, including the SWO and description of the project.
- I. Original and reduced copy (8" x 11") of each Certified Land Corner form.
- J. NGS Recovery Form for each horizontal and vertical monument recorded or used during the course of the survey.

**11. LAND TIES**

Land ties for this survey were established for the following:

T-21-N, R-20-W, I.M. - Secs. 27 and 28

A search was made for any trace of the original monuments and/or accessories. All filed certified corners received from the Oklahoma Department of Libraries were researched and noted. The original survey and survey notes were used from the following survey:

Ehud Noble Darling 10/02/1873

A complete detailed account of each corner set or used follows:

NORTH QUARTER CORNER OF SECTION 27, O.D.O.T. MONUMENT W-77-745, T-21-N, R-20-W, I.M. FOUND 1/2" IRON PIN 6" DEEP. MATCHES MONUMENT DESCRIPTION AND FITS 3 OF 3 REFERENCES ON OCCR FILED BY R. JVIDEN, LS 1083, ON 01-03-95.

NORTHEAST CORNER OF SECTION 27, O.D.O.T. MONUMENT W-77-746, T-21-N, R-20-W, I.M. FOUND 60D NAIL 6" DEEP. MATCHES MONUMENT DESCRIPTION AND FITS 2 REMAINING REFERENCES ON OCCR FILED BY R. JVIDEN, LS 1083, ON 08-14-85.

EAST QUARTER CORNER OF SECTION 27, O.D.O.T. MONUMENT W-77-747, T-21-N, R-20-W, I.M. SET 5/8" IRON PIN WITH CA 32 CAP 6" DEEP. SINGLE PROPORTION MEASUREMENT BETWEEN SECTION CORNERS 0.5 MILE NORTH AND 0.5 MILE SOUTH.

SOUTHEAST CORNER OF SECTION 27, O.D.O.T. MONUMENT W-77-754, T-21-N, R-20-W, I.M. FOUND 1/2" IRON PIN 2" DEEP. MATCHES MONUMENT DESCRIPTION ON OCCR FILED BY T. JVIDEN, LS 1149, ON 08-14-85.

SOUTH QUARTER CORNER OF SECTION 27, O.D.O.T. MONUMENT W-77-753, T-21-N, R-20-W, I.M. SET 5/8" IRON PIN WITH CA 32 CAP 6" DEEP. MONUMENT WAS SET ON-LINE BETWEEN SECTION CORNERS 0.5 MILE EAST AND 0.5 MILE WEST AND IN-LINE WITH FENCE RUNNING SOUTH.

SOUTHWEST CORNER OF SECTION 27, O.D.O.T. MONUMENT W-77-752, T-21-N, R-20-W, I.M. FOUND 3/4" IRON PIN 10" DEEP. MATCHES MONUMENT DESCRIPTION AND FITS DISTANCE TO CENTERLINE OF SURVEY FOR SH-34 AS CALLED OUT ON SH-34 FAP NO. F-418(8) HIGHWAY PLANS.

WEST QUARTER CORNER OF SECTION 27, O.D.O.T. MONUMENT W-77-748, T-21-N, R-20-W, I.M. SET 5/8" IRON PIN WITH CA 32 CAP. MONUMENT WAS SET FROM SH-34 FAP F-418(8) HIGHWAY PLANS.

**18. EQUIPMENT USED**

- Topcon GR3 GPS
- Topcon Hiper II GPS
- Topcon IS 3" Imaging Robotic Total Station
- Topcon FC-2500 Data Collectors
- GPT-9005A 5" robotic Total Station
- Topcon GTP 3000W Total Station
- Topcon GPT 3005W Total Station
- Topcon GTS 3000 Total Station
- Topcon GTS 313 Total Station
- Trimble TSC 1 Data Collectors
- Trimble TSC 2 Data Collectors
- Trimble 3700 GPS
- Trimble 5800 GPS
- Sokkia SDL 30 Digital Level
- Inroads working in a Microstation Platform
- AutoCAD Civil 3D
- Microstation V8

**19. Personnel**

- Joe Farmer, P.L.S. Technician Manager 2
- Tanner Wentworth, L.S.I. Survey Intern 1
- Brian Bird, L.S.I. Survey Intern 1
- Corey Simmons, Technician 1
- Sam McGee, Technician 1
- Eric Mentzer, Technician 3
- Eric Oldham, Technician 1
- Matthew Overall, Technician 1
- Rebecca Robichaux, Technician 1
- Parker Kugler, Technician 1
- Matthew Chernicky, Lead ROW Agent

P.L.S.	J.H.F.	05/29/13	S.H. 34, BRIDGE OVER N. PERSIMMON CREEK, 7.6 MILES N. OF THE DEWEY COUNTY LINE	WOODWARD COUNTY
DRAWN	J.E.M.	05/29/13	<b>HISTORICAL LETTER &amp; WRITTEN REPORT</b>	
CHECKED	T.J.W.	05/29/13		
APPROV.	J.H.F.	05/29/13		
CREW CHIEF	T.J.W.			
SWO NO. <u>4844(1)</u> J/P NO. <u>28827(04)</u> SHEET NO. <u>11</u>				





FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
DESCRIPTION					DATE

W-77-740

ALL COMPUTED COORDINATE ACCURACIES ARE LISTED AS PEAK-TO-PEAK VALUES.  
FOR ADDITIONAL INFORMATION  
HTTP://WWW.NGS.NOAA.GOV/OPUS/ABOUT.JSP#ACCURACY

USER: TWENTWORTH@COBBENGR.COM DATE: MARCH 28, 2013  
RINEX FILE: LOG2321N.120 TIME: 12:16:06 UTC

SOFTWARE: PAGE5 1209.04 MASTER73.PL 082112 START: 2012/11/16 13:22:00  
EPHEMERIS: 16S17145.EPH (PRECISE) STOP: 2012/11/16 18:41:00  
NAV FILE: BRDC3210.12N OBS USED: 12688/13691 : 93%  
ANT NAME: TPSHIPER\*11 NONE H FIXED AMB: 77/ 88 : 88%  
ARP HEIGHT: 2 OVERALL RMS: 0.013(M)

REF FRAME: NAD83(2011)EPOCH: 2010.0000(1)G508 (EPOCH: 2012.8761)

X: -835316.473(M) 0.013(M) -835317.254(M) 0.013(M)  
Y: -5081202.924(M) 0.006(M) -5081201.541(M) 0.006(M)  
Z: 3751928.817(M) 0.034(M) 3751928.691(M) 0.034(M)

LAT: 36 15 39.38950 0.032(M) 36 15 39.40996 0.032(M)  
E LON: 260 39 52.01981 0.012(M) 260 39 51.97996 0.012(M)  
W LON: 99 20 7.98019 0.012(M) 99 20 8.02004 0.012(M)  
EL HGT: 594.019(M) 0.014(M) 592.947(M) 0.014(M)  
ORTHO HGT: 622.225(M) 0.024(M) [NAVD88 (COMPUTED USING GEOID12A)]

	UTM COORDINATES	STATE PLANE COORDINATES
	UTM (ZONE 14)	SPC (3501 OK N)
NORTHING (Y) [METERS]	4012943.520	140730.921
EASTING (X) [METERS]	469857.562	47990.010
CONVERGENCE [DEGREES]	-0.19846715	-0.78817095
POINT SCALE	0.99961119	0.99994673
COMBINED FACTOR	0.99951801	0.99985352

US NATIONAL GRID DESIGNATOR: 14SMF6985712943INAD 83)

PID	DESIGNATION	BASE STATIONS USED	LATITUDE	LONGITUDE	DISTANCE(M)
DF4058	OKCL CLINTON CORS ARP		N352859.349	W0985817.246	92359.3
DG9774	OKBF BUFFALO CORS ARP		N364940.881	W0993828.840	68633.0
DM7151	TXPY PERRYTON CORS ARP		N362336.089	W1004855.888	133708.4

GJ0245 J 33 NEAREST NGS PUBLISHED CONTROL POINT  
N361449. W0991956. 1586.5

THIS POSITION AND THE ABOVE VECTOR COMPONENTS WERE COMPUTED WITHOUT ANY KNOWLEDGE BY THE NATIONAL GEODETIC SURVEY REGARDING THE EQUIPMENT OR FIELD OPERATING PROCEDURES USED.

STATE OF OKLAHOMA S.D. FORM NO. 11  
DEPARTMENT OF HIGHWAYS REVISED 3/10/75  
SURVEY DIVISION

POSITION AND DESCRIPTION OF SURVEY MONUMENTS

COUNTY WOODWARD STATION NUMBER W-77-740 SWO 484411 DATE 03/28/2013

TYPE OF MONUMENT 5/8" IRON PIN WITH ALUMINUM CAP MONUMENT SET FOR GPS CONTROL

METHOD ESTABLISHED: TRILATERATION, TRIANGULATION, TRAVERSE, OTHER (SPECIFY)


STATIC GPS OBSERVATIONS USING OPUS SOLUTIONS

HEIGHT OF INSTRUMENT ABOVE MONUMENT: \_\_\_\_\_ FEET, TYPE OF WITNESS POST \_\_\_\_\_

WRITTEN DESCRIPTION OF LOCATION: APPROXIMATELY 187' SOUTH OF EW-52 AND APPROXIMATELY 83' EAST OF NS-206.

ESTABLISHED BY: JOSEPH H. FARMER, RPLS

COORDINATE SYSTEM: <input type="checkbox"/> USC&GS, <input type="checkbox"/> OHD, <input checked="" type="checkbox"/> OTHER (SPECIFY) <u>OK STATE PLANE (NAD 83)</u>			
GRID DATA:	COORDINATES (FEET)	GRID BEARING	DISTANCE
NORTH_ZONE	X: 1574761.2245	WEST	80' RP 1 - WEST EDGE OF SH-34
ACCURACY:	Y: 467146866	EAST	77' RP 2 - FENCE LINE
3RD_ORDER		NORTHWEST	187' RP 3 - EAST FACE OF POWER POLE
GEODETIC DATA:	POSITION		ELEVATION
ANGLE OF VARIANCE (D)	LATITUDE	NORTH	
00°41'14.2"	N361539.3895"	209.410"	
	LONGITUDE	WEST	SOURCE: <u>NAVD88</u>
	W992007.9802"		ACCURACY: <u>3RD</u>



STATE OF OKLAHOMA S.D. FORM NO. 11  
DEPARTMENT OF HIGHWAYS REVISED 3/10/75  
SURVEY DIVISION

POSITION AND DESCRIPTION OF SURVEY MONUMENTS

COUNTY WOODWARD STATION NUMBER W-77-741 SWO 484411 DATE 03/28/13

TYPE OF MONUMENT 5/8" IRON PIN WITH ALUMINUM CAP MONUMENT SET FOR GPS CONTROL

METHOD ESTABLISHED: TRILATERATION, TRIANGULATION, TRAVERSE, OTHER (SPECIFY)


NORTHING & EASTING DERIVED BY RTK OBSERVATION AVERAGES & ELEVATION DERIVED BY DIFFERENTIAL LEVEL RUN

HEIGHT OF INSTRUMENT ABOVE MONUMENT: \_\_\_\_\_ FEET, TYPE OF WITNESS POST \_\_\_\_\_


WRITTEN DESCRIPTION OF LOCATION: APPROXIMATELY 177' NORTH OF EW-52 AND APPROXIMATELY 80' EAST OF NS-206.

ESTABLISHED BY: JOSEPH H. FARMER, RPLS

COORDINATE SYSTEM: <input type="checkbox"/> USC&GS, <input type="checkbox"/> OHD, <input checked="" type="checkbox"/> OTHER (SPECIFY) <u>OK STATE PLANE (NAD 83)</u>			
GRID DATA:	COORDINATES (FEET)	GRID BEARING	DISTANCE
NORTH_ZONE	X: 1574813.7028	SOUTH-SOUTHWEST	157' RP 1 - NORTH FACE OF SIGN
ACCURACY:	Y: 4673513882	WEST	77' RP 2 - WEST EDGE OF SH-34
3RD_ORDER		WEST-NORTHWEST	120' RP 3 - EAST FACE OF POWER POLE
GEODETIC DATA:	POSITION		ELEVATION
ANGLE OF VARIANCE (D)	LATITUDE	NORTH	
00°41'17.52"	N361635.354"	2038.405"	
	LONGITUDE	WEST	SOURCE: <u>NAVD88</u>
	W992008.153"		ACCURACY: <u>3RD</u>




# CONTROL MAP




P.L.S.	J.H.F.	05/29/13	S.H. 34, BRIDGE OVER N. PERSIMMON CREEK, 7.6 MILES N. OF THE DEWEY COUNTY LINE	WOODWARD COUNTY
DRAWN	J.E.M.	05/29/13		
CHECKED	T.J.W.	05/29/13	<b>CONTROL MAP &amp; INFORMATION</b>	
APPROV.	J.H.F.	05/29/13		
CREW CHIEF	T.J.W.		SWO NO. <u>484411</u> J/P NO. <u>28827(04)</u> SHEET NO. <u>13</u>	

REV. NO.	DATE	DESCRIPTION



S.H. 34 - BRIDGE OVER NORTH PERSIMMON CREEK  
 SIDE VIEW OF NORTH PERSIMMON CREEK BRIDGE  
 (UPSTREAM SIDE)  
 \*NOT TO SCALE\*

STA. 2442+05.57 31.00'x253.33' CONCRETE BRIDGE  
 DRAINAGE AREA: 59.51 SQUARE MILES  
 BEG. BRIDGE FLOOR ELEV. = 2027.12'  
 END BRIDGE FLOOR ELEV. = 2026.98'  
 LOW BEAM ELEV. = 2024.14'  
 HIGH WATER ELEV. = 2015.60  
 EXTREME HIGH WATER ELEV. = 2022.10  
 -NOTE-  
 -DRAINAGE AREA DETERMINED  
 FROM USGS STREAM STATISTICS.  
 -HIGH WATER ELEV. & EXTREME HIGH WATER ELEV.  
 TAKEN FROM FAP F-418(8) PLANS.



P.L.S.	J.H.F.	05/29/13	S.H. 34, BRIDGE OVER N. PERSIMMON CREEK, 7.6 MILES N. OF THE DEWEY COUNTY LINE	WOODWARD COUNTY
DRAWN	J.E.M.	05/29/13	<b>SURVEY DATA SHEET</b>	
CHECKED	T.J.W.	05/29/13		
APPROV.	J.H.F.	05/29/13		
CREW CHIEF	T.J.W.			
SWO NO. <u>4844W</u> J/P NO. <u>28827(04)</u> SHEET NO. <u>14</u>				

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
DESCRIPTION				REVISION	DATE

NE/4 SEC 28  
T21N R20W

NW/4 SEC 27  
T21N R20W

MATCH LINE SHEET 05

2445+00



2450+00

2455+00

2460+00

2465+00

P.L.S.	J.H.F.	05/29/13	S.H. 34, BRIDGE OVER N. PERSIMMON CREEK, 7.6 MILES N. OF THE DEWEY COUNTY LINE	WOODWARD COUNTY
DRAWN	J.E.M.	05/29/13	<b>SURVEY DATA SHEET</b>	
CHECKED	T.J.W.	05/29/13		
APPROV.	J.H.F.	05/29/13		
CREW CHIEF	T.J.W.	SWO NO. 4844W J/P NO. 28827(04) SHEET NO. 15		



FED. ROAD DIST. NO.	STATE	PROJ. NO.	FEED. NO.	SHEET NO.	TOTAL SHEETS
DESCRIPTION					DATE



NORTHWEST CORNER OF SECTION 28, O.D.O.T. MONUMENT W-77-742, T-21-N, R-20-W I.M. FOUND 60D NAIL 6" DEEP. MONUMENT FITS PROPORTIONAL DISTANCE TO QUARTER SECTION CORNER 0.5 MILE EAST. MONUMENT ALSO FALLS IN CENTER OF EAST-WEST ROAD AND IN-LINE WITH ROAD RUNNING NORTH.

NORTH QUARTER CORNER OF SECTION 28, O.D.O.T. MONUMENT W-77-743, T-21-N, R-20-W I.M. FOUND 1/2" IRON PIN 6" DEEP. MATCHES MONUMENT DESCRIPTION AND FITS REFERENCES ON OCCR FILED BY R. JVIDEN, LS 1083, ON 07-22-08.

NORTHEAST CORNER OF SECTION 28, O.D.O.T. MONUMENT W-77-744, T-21-N, R-20-W I.M. FOUND BENT 3/4" IRON PIN 12" DEEP. MONUMENT FITS DISTANCE TO CENTERLINE OF SURVEY FOR SH-34 AS CALLED OUT ON SH-34 FAP NO. F-418(8) HIGHWAY PLANS.

NORTH QUARTER CORNER OF SECTION 27, O.D.O.T. MONUMENT W-77-745, T-21-N, R-20-W I.M. FOUND 1/2" IRON PIN 6" DEEP. MATCHES MONUMENT DESCRIPTION AND FITS 3 OF 3 REFERENCES ON OCCR FILED BY R. JVIDEN, LS 1083, ON 01-03-95.


NORTHEAST CORNER OF SECTION 27, O.D.O.T. MONUMENT W-77-746, T-21-N, R-20-W I.M. FOUND 60D NAIL 6" DEEP. MATCHES MONUMENT DESCRIPTION AND FITS 2 REMAINING REFERENCES ON OCCR FILED BY R. JVIDEN, LS 1083, ON 08-14-85.



P.L.S.	J.H.F.	05/29/13	SH 34, BRIDGE OVER N. PERSIMMON CREEK, 7.6 MILES N. OF THE DEWEY COUNTY LINE	WOODWARD COUNTY
DRAWN	J.E.M.	05/29/13	<b>LAND TIE SHEET</b>	
CHECKED	T.J.W.	05/29/13		
APPROV.	J.H.F.	05/29/13		
CREW CHIEF	T.J.W.			
SWO NO. <u>4844W</u> J/P NO. <u>28827(04)</u> SHEET NO. <u>16</u>				



DESCRIPTION	REVISIONS	DATE




**LEGEND**

- TEMPORARY SILT FENCE    ······
- TEMPORARY SILT DIKE    ▲▲▲
- SOLID SLAB SOD DITCH    ————
- RIP RAP    [Pattern]
- ROCK FILTER DAM    (RFD)

NOTE: SILT FENCE SHALL BE PLACED AT 5' MINIMUM CLEARANCE TO LIMITS OF CONSTRUCTION.

SUGGESTED PLAN IS NOT ALL INCLUSIVE. PLACEMENT OF EROSION CONTROL DEVICES IS SUBJECT TO CONSTRUCTION PHASING AND CHANGING SITE CONDITIONS. CONTROL OF PROJECT RUN-OFF REMAINS THE RESPONSIBILITY OF THE CONTRACTOR AND IS SUBJECT TO APPROVAL BY THE ENGINEER.



EROSION CONTROL QUANTITIES		
DESCRIPTION	UNITS	QUANTITY
TEMPORARY SILT FENCE	LF	768
TEMPORARY SILT DIKE	LF	161
TEMPORARY ROCK FILTER DAM TYPE 1	CY	20
SOLID SLAB SODDING	SY	22,990
VEGETATIVE MULCHING	AC	3.80

FILENAME: 17 EROSION CONTROL SHEET.DWG

DESIGN	SH-34 OVER N. PERSIMMON CREEK	WOODWARD COUNTY
DRAWN		
CHECKED		
CEC	STATE JOB NO. 28827(04)	SHEET NO. 17

**EROSION CONTROL SHEET**

CURVE 1 DATA	
DETOUR	
P.I. STA.	2429+75.36
N	= 463225.2754
E	= 1574720.0149
R	= 1145.913'
Δ	= 125.498"
T	= 12'30'00"
L	= 249.999'
D	= 5'00'00"
V	= 45 MPH
S	= NO SUPER


CURVE 2 DATA	
DETOUR	
P.I. STA.	2433+25.50
N	= 463567.1229
E	= 1574800.2499
R	= 1145.895'
Δ	= 125.496"
T	= 12'30'00"
L	= 249.995'
D	= 5'00'00"
V	= 45 MPH
S	= NO SUPER

**SECTION 28  
T-21-N, R-20-W**

**2435+00**

**2440+00**


**STA. 2443+00**



**NOTE: ALL DISTANCES SHOWN TO RIGHT OF WAY, FENCES, UTILITIES, AND OTHER EXISTING OBJECTS ARE FROM C.L. OF SURVEY**

**ALL EXISTING UTILITY LOCATIONS ARE APPROXIMATE & SHALL BE FIELD VERIFIED PRIOR TO CONSTRUCTION**

**SECTION 27  
T-21-N, R-20-W**



**STA. 2428+56.19  
BEGIN INCIDENTAL CONST.**

**STA. 2434+50.00  
END INCIDENTAL CONST.  
BEGIN PROJECT**

**PROPOSED BRIDGE**  
CL. STA. 2442+16.00  
3-100' TYPE IV PCB SPAN  
TOTAL LENGTH= 300.50'  
LOW BEAM ELEV.= 2022.07'  
RDWY. OT ELEV.= 2025.80'  
RDWY. OT STA.= 2437+77.57

HYDRAULIC DATA	
DRAINAGE AREA = 59.51 SQ MI.	
CONTROLLED DRAINAGE AREA = 0 SQ MI.	
EFFECTIVE DRAINAGE AREA = 59.51 SQ MI.	
Q2 = 1,180 CFS	Q25 = 7,510 CFS
CHW2 = 2,017.23 FT	CHW25 = 2,020.82 FT
V2 = 3.34 FPS	V25 = 7.30 FPS
Q5 = 2,820 CFS	Q50 = 10,300 CFS
CHW5 = 2,018.46 FT	CHW50 = 2,021.96 FT
V5 = 4.71 FPS	V50 = 8.60 FPS
Q10 = 4,550 CFS	Q100 = 13,200 CFS
CHW10 = 2,019.45 FT	CHW100 = 2,023.02 FT
V10 = 5.78 FPS	V100 = 9.79 FPS
SCOUR (100 YR)	SCOUR (500 YR)
CONTRACTION = 9.05'	CONTRACTION = 21.40'
PIER = 9.30'	PIER = 7.84'
TOTAL = 18.35'	TOTAL = 29.24'

**UTILITY OWNERS CONTACT INFORMATION**

OWNERS	ADDRESS	PHONE
ONEOK	4901 N. SANTA FE OKLAHOMA CITY, OK 73118	THOMAS BROWN 405-323-9045
OGE CORP	P.O. BOX 321 OKLAHOMA CITY, OK 73101-0321	STEPHEN ECHARD 405-553-0902
PIONEER COMMUNICATIONS	205 E. ROBERTS KINGFISHER, OK 73750	BLAKE CALLAHAN 405-375-0255



**SECTION 28  
T-21-N, R-20-W**

**ALL EXISTING UTILITY LOCATIONS  
ARE APPROXIMATE & SHALL BE  
FIELD VERIFIED PRIOR TO  
CONSTRUCTION**


**CURVE 3 DATA**  
DETOUR  
P.I. STA. 2450+75.40  
N = 465317.8827  
E = 1574821.9092  
T = 125.398'  
Δ = 12°30'00"  
L = 249.800'  
D = 5°00'00"  
V = 45 MPH  
S = NO SUPER

**CURVE 4 DATA**  
DETOUR  
P.I. STA. 2454+25.54  
N = 465661.6104  
E = 1574750.1558  
T = 125.498'  
Δ = 12°30'00"  
L = 250.000'  
D = 5°00'00"  
V = 45 MPH  
S = NO SUPER


**NOTE: ALL DISTANCES SHOWN TO  
RIGHT OF WAY, FENCES, UTILITIES,  
AND OTHER EXISTING OBJECTS ARE  
FROM C.L. OF SURVEY**



**SHARON  
PLAT**



**SECTION 27  
T-21-N, R-20-W**



**BENCHMARK #211**  
STA. 2443+32.24 17.24' LT.  
CUT "X" IN BRIDGE NW WINGWALL  
ELEVATION = 2027.50'  
**BENCHMARK #212**  
STA. 2443+41.84 17.75' LT.  
SET MAG NAIL W/ COBB SHINER  
ELEVATION = 2026.86'  
**BENCHMARK #213**  
STA. 2448+69.71 62.73' LT.  
SET R.R. SPIKE IN NE SIDE OF PWR POLE  
ELEVATION = 2023.74'  
**BENCHMARK #214**  
STA. 2455+74.84 38.57' RT.  
CUT "X" IN DRG. STR. SOUTH HEADWALL  
ELEVATION = 2034.99'

DESCRIPTION	REVISIONS	DATE

DESIGN DATA

CONCRETE CLASS A  
 CONCRETE CLASS AA  
 REINFORCING STEEL (GRADE 60)  
 STRUCTURAL STEEL M 270 (GRADE 50W)  
 STAINLESS STEEL A240 (TYPE 316)

f'c = 3 K.S.I.  
 f'c = 4 K.S.I.  
 fy = 60 K.S.I.  
 Fy = 50 K.S.I.  
 Fy = 30 K.S.I.

LOADING:  
 HL-93 OR OKLAHOMA OVERLOAD TRUCK  
 20 P.S.F. FUTURE WEARING SURFACE  
 5 P.S.F. STAY-IN-PLACE FORMS

DESIGN:  
 AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, 7TH EDITION.  
 ANSI/AASHTO/AWS D1.5 BRIDGE WELDING CODE  
 ANSI/AASHTO/AWS D1.6 STRUCTURAL WELDING CODE - STAINLESS STEEL.

LFD OPERATING RATING: HS 50.2

STANDARDS

B40-C-ABUT-MISC-01E  
 B40-C-AS-03E  
 TR4-2-00E  
 EJ-SQ-03E  
 EJ-DTL-01E  
 HP1-2-00E  
 LECS-4-1  
 PUD-3-2

HYDRAULIC DATA


TOTAL DRAINAGE AREA = 59.51 SQ. MI.  
 CONTROLLED DRAINAGE AREA = 0 SQ. MI.  
 EFFECTIVE DRAINAGE AREA = 59.51 SQ. MI.

Q2 = 1,180 CFS	Q5 = 2,820 CFS
CHW2 = 2017.23 FT	CHW5 = 2018.46 FT
V2 = 3.34 FPS	V5 = 4.71 FPS
Q10 = 4,550 CFS	Q25 = 7,510 CFS
CHW10 = 2019.45 FT	CHW25 = 2020.82 FT
V10 = 5.78 FPS	V25 = 7.30 FPS
Q50 = 10,300 CFS	Q100 = 13,200 CFS
CHW50 = 2021.96 FT	CHW100 = 2023.02 FT
V50 = 8.60 FPS	V100 = 9.79 FPS
Q500 = 22,700 CFS	
CHW500 = 2026.71 FT	
V500 = 10.93 FPS	


SCOUR (100YR)	SCOUR (500YR)
CONTRACTION = 9.05'	CONTRACTION = 21.40'
PIER = 9.30'	PIER = 7.84'
TOTAL = 18.35'	TOTAL = 29.24'

QOT = 424

NOTE:  
 FOR FOUNDATION DATA, SUMMARY  
 OF BRIDGE PAY QUANTITIES, AND  
 SHEET INDEX, SEE SHEET 21.




PROFILE DATA  
 C.R.L. & P.G.L. SH34



PLAN

1" = 20'

301'-8"



ELEVATION

1" = 20'

BM #210 CUT "X" IN BRIDGE SOUTHEAST WINGWALL  
 STA. 2440+79.01 17.63' RT.  
 ELEV. 2027.5145

BM #211 CUT "X" IN BRIDGE NORTHWEST WINGWALL  
 STA. 2443+32.24 17.24' LT.  
 ELEV. 2027.5015

NOTE:  
 ▼ DENOTES APPROXIMATE  
 WATER TABLE ELEVATION  
 RECORDED AT TIME OF  
 BRIDGE BORING TESTING.

NOTE: INTERPRETED FOUNDATION  
 MATERIAL LINE FOR ESTIMATING PURPOSES ONLY.

THIS DRAWING  
 IS PRELIMINARY IN  
 NATURE. IT IS NOT  
 A FINAL SIGNED  
 AND SEALED  
 DRAWING

DESIGN	J.W.H.	SH34 OVER N. PERSIMMON CREEK	WOODWARD COUNTY
DRAWN	R.A.P.	BRIDGE A	
CHECKED	J.W.H.	<b>GENERAL PLAN AND ELEVATION</b>	
APPROV.	T.A.C.	100'-100'-100' TYPE IV P.C. BEAM SPANS, 0° SKEW, 40' CLEAR ROADWAY WITH TR-4 PARAPETS @ STA. 2442+16.00	
SQUAD	CEC	JOB PIECE NO. 28827(04)	SHEET NO. 20

DESCRIPTION	REVISIONS	DATE

SUMMARY OF BRIDGE PAY QUANTITIES							
ITEM	UNIT	ABUTMENTS	PIERS	SUPER- STRUCTURE	APPROACH SLAB	SLOPE DRAIN	TOTAL
SUBSTRUCTURE EXCAVATION COMMON	C.Y.	200	3,400				3,600
CLSM BACKFILL	C.Y.	210					210
PRESTRESSED CONCRETE BEAMS (TYPE IV)	L.F.			1,495			1,495
APPROACH SLAB	S.Y.				281.2		281.2
SAW-CUT GROOVING	S.Y.			1,341.0	266.6		1,607.6
SEALED EXPANSION JOINT	L.F.			41.8			41.8
CONCRETE RAIL (TR4)	L.F.			603.3	120.0		723.3
STRUCTURAL STEEL	LB.			1,430			1,430
STAINLESS STEEL FIXED BEARING ASSEMBLY	EA.			10			10
STAINLESS STEEL EXPANSION BEARING ASSEMBLY	EA.			20			20
CLASS AA CONCRETE	C.Y.		222.2	358.4			580.6
CLASS A CONCRETE	C.Y.	97.0	71.0				168.0
CLASS C CONCRETE	C.Y.					9.3	9.3
REINFORCING STEEL	LB.		2,200				2,200
EPOXY COATED REINFORCING STEEL	LB.	11,440	52,180	97,830			161,450
PILES, FURNISHED (HP 10X42)	L.F.	432					432
PILES, FURNISHED (HP 12X53)	L.F.	1,887					1,887
PILES, FURNISHED (HP 14X89)	L.F.		3,900				3,900
PILES, DRIVEN (HP 10X42)	L.F.	432					432
PILES, DRIVEN (HP 12X53)	L.F.	1,887					1,887
PILES, DRIVEN (HP 14X89)	L.F.		3,900				3,900
PILE SPLICE, H-PILE (NON-BIDDABLE)	EA.						1
WATER REPELLENT (VISUALLY INSPECTED)	S.Y.	118	150	995	56		1,319
SEALER CRACK PREPARATION	L.F.			41			41
SEALER RESIN	GAL.			1			1
TYPE I-A PLAIN RIPRAP	TON	1,283					1,283
TYPE I-A FILTER BLANKET	TON	289					289
6" PERFORATED PIPE UNDERDRAIN ROUND	L.F.	84					84
6" NON-PERF. PIPE UNDERDRAIN RND.	L.F.	68					68
REMOVAL OF EXISTING BRIDGE STRUCTURE	LSUM						1

FOUNDATION DATA

PIER NO. 1 & NO. 2 (HP14X89 PILING)  
FACTORED PILE REACTION = 225.0 TON/PILE

ABUTMENT NO. 1 & NO. 2 (HP12X53 PILING)  
FACTORED PILE REACTION = 95.0 TON/PILE

STEEL PILING:  
ALL PILING SHALL BE DRIVEN THRU COMPACTED FILL. PILING SHALL BE DRIVEN TO A POINT BEARING ON SOLID FOUNDATION MATERIAL AT THE APPROXIMATE ELEVATION SHOWN ON THE PLANS. IF THE REQUIRED AXIAL LOAD RESISTANCE IS NOT OBTAINED AT THIS ELEVATION, DRIVING SHALL CONTINUE UNTIL THE REQUIRED AXIAL LOAD RESISTANCE IS OBTAINED. THE LENGTH OF STEEL PILING SHOWN ON THE PLANS IS FOR ESTIMATING PURPOSES ONLY.

SHEET INDEX:

4. BRIDGE GENERAL NOTES
5. PAY ITEMS AND NOTES (BRIDGE)
20. GENERAL PLAN AND ELEVATION
21. SUMMARY OF BRIDGE PAY QUANTITIES
22. FOUNDATION REPORT
23. SUBSTRUCTURE LAYOUT
24. SUBSTRUCTURE EXCAVATION AT PIERS
25. ABUTMENT DETAILS
26. ABUTMENT WING DETAILS
27. PIER NO. 1 AND 2 DETAILS (SHEET 1 OF 3)
28. PIER NO. 1 AND 2 DETAILS (SHEET 2 OF 3)
29. PIER NO. 1 AND 2 DETAILS (SHEET 3 OF 3)
30. PIER STEEL PILING DETAIL AND BAR LIST
31. TYPICAL CROSS SECTION
32. LONGITUDINAL SECTION
33. BEAM FRAMING PLAN
34. P.C.B. DETAILS - TYPE IV
35. DIAPHRAGM AND BEARING DETAILS
36. SUPERSTRUCTURE DETAILS
37. ADDITIONAL SLAB REINFORCING
38. SLOPE DRAIN DETAILS

THIS DRAWING IS PRELIMINARY IN NATURE. IT IS NOT A FINAL SIGNED AND SEALED DRAWING

DESIGN	J.W.H.	SH34 OVER N. PERSIMMON CREEK BRIDGE A	WOODWARD COUNTY
DRAWN	Z.M.B.		
CHECKED	J.W.H.		
APPROV.	T.A.C.		
SQUAD	CEC		

**SUMMARY OF BRIDGE PAY QUANTITIES**



DESCRIPTION	REVISIONS	DATE

BORING NO. B-1  
 STA. 2440+13.00  
 20' RIGHT  
 OF C.R.L. SH 34

ELEVATION 2026.3

SILTY SAND WITH ASPHALT MILLINGS, BROWN (10YR 4/3) AND BLACK (10YR 2/1) (FILL MATERIAL)

CLAYEY SAND, DARK BROWN (10YR 3/3), VERY LOOSE TO LOOSE (POSSIBLE FILL MATERIAL)


SILTY SAND, GRAYISH BROWN (10YR 5/2), VERY LOOSE TO LOOSE

\*N=0, WEIGHT OF HAMMER AT 40 FEET\*

POORLY GRADED SAND WITH SILT, VERY PALE BROWN (10YR 7/4), VERY LOOSE TO MEDIUM DENSE

SILTY SAND, LIGHT REDDISH BROWN (5YR 6/4), VERY LOOSE TO MEDIUM DENSE

SANDY SILTSTONE, RED (2.5YR 5/6), WELL CEMENTED TO VERY WELL CEMENTED



ELEVATION 1877.3  
 TOTAL DEPTH = 149'  
 DATE OF BORING: 6/16/14  
 WATER ELEVATION 2008.3'  
 24 HOURS AFTER DRILLING

NOTES:

- SPT DENOTES STANDARD PENETRATION TESTS
- TCP DENOTES TEXAS CONE PENETRATION TESTS
- ▽ DENOTES WATER ELEVATION DURING DRILLING
- ▽ DENOTES WATER ELEVATION AT NOTED TIME
- ▽ DENOTES CAVE IN DEPTH
- ▨ DENOTES ROCK ELEVATION

BORING NO. B-2  
 STA. 2441+56.00  
 21' LEFT  
 OF C.R.L. SH 34

ELEVATION 2015.4

SANDY LEAN CLAY, DARK BROWN (10YR 3/3), MEDIUM STIFF

SILTY SAND, DARK BROWN (10YR 3/3), VERY LOOSE

POORLY GRADED SAND WITH SILT, DARK BROWN (10YR 3/3), VERY LOOSE

\*N=0, WEIGHT OF HAMMER AT 35 FEET\*

SILTY SAND, GRAYISH BROWN (10YR 5/2), VERY LOOSE TO MEDIUM DENSE

SILTY SAND, WITH GRAVEL, LIGHT GRAY (10YR 7/2) TO LIGHT REDDISH BROWN (5YR 4/4), LOOSE TO MEDIUM DENSE

SILTY SAND, VERY PALE BROWN (5YR 7/4), VERY LOOSE TO MEDIUM DENSE

SILTY SAND, WITH GRAVEL, LIGHT REDDISH BROWN (5YR 6/4), VERY LOOSE TO MEDIUM DENSE

SANDY SILTSTONE, RED (2.5YR 5/6), WELL CEMENTED TO VERY WELL CEMENTED

ELEVATION 1888.9  
 TOTAL DEPTH = 126.5'  
 DATE OF BORING: 5/19/14  
 WATER ELEVATION 2011.4'  
 18 HOURS AFTER DRILLING

INTERPRETED FOUNDATION LINE

GEOLOGICAL STATEMENT

DIVISION SIX OF THE "ENGINEERING CLASSIFICATION OF GEOLOGICAL MATERIALS", PUBLISHED BY THE OKLAHOMA DEPARTMENT OF TRANSPORTATION (ODOT) INDICATES THE PROJECT SITE IS UNDERLAIN BY THE RUSH SPRINGS UNIT (PRS).

THE RUSH SPRINGS UNIT CONSISTS DOMINANTLY OF ORANGE-BROWN, FINE-GRAINED SANDSTONE IN THE UPPER HALF OF THE UNIT AND INTERBEDDED RED-BROWN SILTY SHALE, SILTSTONE AND SANDSTONE IN THE LOWER HALF. SHALE IS DOMINANT IN THE LOWER HALF OF THE UNIT IN THE DIVISION, BUT THE SHALE GRADES TO SANDSTONE ACROSS WOODWARD COUNTY AND BECOMES ALMOST ENTIRELY SANDSTONE IN NORTHERN DEWEY COUNTY OF DIVISION 5.

BORING NO. B-3  
 STA. 2442+77.00  
 21' RIGHT  
 OF C.R.L. SH 34

ELEVATION 2015.7

SANDY LEAN CLAY, DARK BROWN (10YR 3/3), MEDIUM STIFF

SILTY SAND, LIGHT GRAY (10YR 7/2), VERY LOOSE

LEAN CLAY, GRAY (10YR 6/1), SOFT

SILTY SAND, LIGHT GRAY (10YR 7/2) TO DARK GRAY (10YR 4/1), VERY LOOSE TO LOOSE

POORLY GRADED SAND WITH SILT, LIGHT GRAY (10YR 7/2), VERY LOOSE TO LOOSE

SANDY LEAN CLAY, DARK GRAY (10YR 4/1), MEDIUM STIFF

SILTY SAND, REDDISH BROWN (5YR 4/3) WITH GRAY (10YR 6/1), LOOSE TO MEDIUM DENSE

POORLY GRADED SAND, VERY PALE BROWN (10YR 7/3), LOOSE TO MEDIUM DENSE

SANDY SILTSTONE, RED (2.5YR 5/6), CEMENTED TO VERY WELL CEMENTED

ELEVATION 1899.2  
 TOTAL DEPTH = 116.5'  
 DATE OF BORING: 5/20/14  
 WATER ELEVATION 2010.2'  
 0 HOURS AFTER DRILLING

NOTE:  
 INTERPRETED FOUNDATION LINE FOR ESTIMATING PURPOSES ONLY.

WATER ELEVATIONS SHOWN WERE OBTAINED AT THE TIME BORINGS WERE DRILLED AND MAY FLUCTUATE THROUGHOUT THE YEAR.

BORING NO. B-4  
 STA. 2443+60.00  
 50' LEFT  
 OF C.R.L. SH 34

ELEVATION 2015.5

CLAYEY SAND, DARK BROWN (10YR 3/3), VERY LOOSE TO LOOSE

SANDY LEAN CLAY, DARK BROWN (10YR 3/3), VERY SOFT

\*N=0, WEIGHT OF HAMMER AT 15 FEET\*

\*N=0, WEIGHT OF HAMMER AT 20 FEET\*

SILTY SAND, VERY PALE BROWN (10YR 7/4), VERY LOOSE TO MEDIUM DENSE

\*N=0, WEIGHT OF HAMMER AT 50 FEET\*

POORLY GRADED SAND, VERY PALE BROWN (10YR 7/3), VERY LOOSE

\*N=0, WEIGHT OF HAMMER AT 60 FEET\*

LEAN CLAY WITH SAND, SHALEY, RED (5YR 4/6), VERY STIFF TO HARD

SANDY SILTSTONE, RED (2.5YR 5/6), CEMENTED TO VERY WELL CEMENTED

ELEVATION 1899.5  
 TOTAL DEPTH = 116'  
 DATE OF BORING: 6/17/14  
 WATER ELEVATION 2010.5'  
 2 HOURS AFTER DRILLING

THIS DRAWING IS PRELIMINARY IN NATURE. IT IS NOT A FINAL SIGNED AND SEALED DRAWING

DESIGN	J.W.H.
DRAWN	M.R.S.
CHECKED	J.W.H.
APPROV.	T.A.C.
SQUAD	CEC

SH34 OVER N. PERSIMMON CREEK WOODWARD COUNTY BRIDGE A

FOUNDATION REPORT

JOB PIECE NO. 28827(04) SHEET NO. 22

DESCRIPTION	REVISIONS	DATE


2440+00

2441+00

2442+00


2443+00

2444+00



**SUBSTRUCTURE LAYOUT**


1" = 15'



**RIPRAP AND FILTER BLANKET DETAIL**  
(DIMENSIONS AND SLOPE PERPENDICULAR TO FACE OF ABUTMENT)

PILE LOCATIONS, FOR PIER FOOTING, ARE CRITICAL AND MUST BE PLACED STRICTLY WITHIN CONSTRUCTION TOLERANCES.

ABUTMENT SEAT PILES SHALL BE ORIENTATED SUCH THAT THE FACE OF THE WEB IS PERPENDICULAR TO THE FRONT FACE OF THE ABUTMENT BACKWALL. WING PILES SHALL BE ORIENTATED SUCH THAT THE FACE OF THE WEB IS PERPENDICULAR TO THE WINGWALL.




**PIER FOOTING PILE ORIENTATION**

THIS DRAWING IS PRELIMINARY IN NATURE. IT IS NOT A FINAL SIGNED AND SEALED DRAWING

DESIGN	J.W.H.	SH34 OVER N. PERSIMMON CREEK	WOODWARD COUNTY
DRAWN	M.R.S.	BRIDGE A	
CHECKED	J.W.H.	<b>SUBSTRUCTURE LAYOUT</b>	
APPROV.	T.A.C.		
SQUAD	CEC		
		JOB PIECE NO. 28827(04)	SHEET NO. 23


DESCRIPTION	REVISIONS	DATE




NOTE:  
FOR SUBSTRUCTURE EXCAVATION AT ABUTMENTS  
AND PIPE UNDERDRAIN DETAILS, SEE STD.  
B40-C-ABUT-MISC.

NOTE:  
THE CONTRACTOR WILL INCLUDE ALL COST OF  
TEMPORARY RETAINING STRUCTURES AND  
TEMPORARY WATER CONTROL SYSTEMS  
NECESSARY TO CONSTRUCT THE BRIDGE PIERS,  
INCLUDING EQUIPMENT, MATERIALS, LABOR, AND  
INCIDENTALS, IN THE CONTRACT UNIT PRICE BID  
FOR "SUBSTRUCTURE EXCAVATION COMMON".  
ANY TEMPORARY RETAINING STRUCTURES AND  
TEMPORARY WATER CONTROL SYSTEMS WILL BE  
PROVIDED IN ACCORDANCE WITH SECTION 502  
OF THE SPECIFICATIONS.

**SUBSTRUCTURE EXCAVATION PLAN**



**SECTION A-A**



**SECTION B-B**


THIS DRAWING  
IS PRELIMINARY IN  
NATURE. IT IS NOT  
A FINAL SIGNED  
AND SEALED  
DRAWING

DESIGN	J.W.H.
DRAWN	R.A.P.
CHECKED	J.W.H.
APPROV.	T.A.C.
SQUAD	CEC


SH34 OVER N. PERSIMMON CREEK WOODWARD COUNTY  
BRIDGE A

**SUBSTRUCTURE EXCAVATION  
AT PIERS**

DESCRIPTION	REVISIONS	DATE



**ABUTMENT PLAN**  
(ABUTMENT NO. 1 AND 2 SHOWN)




**SECTION THRU SEAT**

NOTE:  
FOR EXTENT OF WATER REPELLENT TREATMENT, SEE SHEET 31.

NOTE:  
FOR WING DETAILS, BAR BENDS, AND BAR LIST, SEE SHEET 26.

NOTE:  
FOR SUBSTRUCTURE EXCAVATION AND PIPE UNDERDRAIN DETAILS, SEE STD. B40-C-ABUT-MISC.



**ABUTMENT ELEVATION**  
(ABUTMENT NO. 1 AND 2 SHOWN)

**ABUTMENT QUANTITIES**


ITEM	UNIT	ABUT. NO. 1	ABUT. NO. 2	TOTAL
SUBSTRUCTURE EXCAVATION COMMON	C.Y.	100	100	200
CLSM BACKFILL	C.Y.	105	105	210
CLASS A CONCRETE	CY.	48.5	48.5	97.0
EPOXY COATED REINFORCING STEEL	LB.	5,720	5,720	11,440
PILES, FURNISHED (HP10X42)	L.F.	236	196	432
PILES, FURNISHED (HP12X53)	L.F.	1,029	858	1,887
PILES, DRIVEN (HP10X42)	L.F.	236	196	432
PILES, DRIVEN (HP12X53)	L.F.	1,029	858	1,887
WATER REPELLENT (VISUALLY INSPECTED)	S.Y.	59	59	118
TYPE I-A PLAIN RIPRAP	TON	702	581	1,283
TYPE I-A FILTER BLANKET	TON	158	131	289
6" PERFORATED PIPE UNDERDRAIN ROUND	L.F.	42	42	84
6" NON - PERF. PIPE UNDERDRAIN RND.	L.F.	34	34	68

THIS DRAWING IS PRELIMINARY IN NATURE. IT IS NOT A FINAL SIGNED AND SEALED DRAWING


DESIGN	J.W.H.	SH34 OVER N. PERSIMMON CREEK	WOODWARD COUNTY
DRAWN	Z.M.B.	BRIDGE A	
CHECKED	J.W.H.		
APPROV.	T.A.C.		
SQUAD	CEC		

**ABUTMENT DETAILS**

DESCRIPTION	REVISIONS	DATE











**WING ELEVATION**



**SECTION THRU WING AT BACK FACE OF ABUTMENT SEAT**

ABUTMENT BAR LIST					
ONE SHOWN - TWO REQUIRED					
EPOXY COATED REINFORCING					
MARK	SIZE	NO.	FORM	LENGTH	LENGTH VARIATION
BH1	#4	10	STR.	44'-8"	
BH2	#4	8	BNT.	46'-0"	
BH3	#9	10	STR.	44'-8"	
BH4	#4	27	BNT.	5'-1"	
① BV1	#4	42	STR.	9'-2" AVG.	9'-0" TO 9'-4"
① BV2	#5	42	STR.	9'-2" AVG.	9'-0" TO 9'-4"
P1	#4	30	BNT.	5'-10"	
P2	#4	20	BNT.	7'-6"	
S1	#5	36	BNT.	12'-7"	
SC	#4	4	BNT.	3'-3"	
WH1	#5	36	STR.	20'-8"	
② WH2	#5	32	STR.	11'-4" AVG.	6'-1" TO 16'-7"
WH3	#5	4	BNT.	21'-8"	
WP1	#4	6	BNT.	8'-8"	
WP2	#4	8	STR.	1'-7"	
WT1	#5	2	BNT.	8'-6"	
③ WT2	#5	6	BNT.	9'-0" AVG.	6'-0" TO 12'-0"
WT3	#5	10	BNT.	17'-0"	
WT4	#5	24	BNT.	11'-0"	
WV1	#4	16	STR.	4'-1"	
④ WV2	#4	72	STR.	7'-3" AVG.	4'-6" TO 10'-0"

- ① TWO SETS OF 21.
- ② FOUR SETS OF 8.
- ③ TWO SETS OF 3.
- ④ FOUR SETS OF 18.






THIS DRAWING IS PRELIMINARY IN NATURE. IT IS NOT A FINAL SIGNED AND SEALED DRAWING

DESIGN	J.W.H.	SH34 OVER N. PERSIMMON CREEK	WOODWARD COUNTY
DRAWN	Z.M.B.	BRIDGE A	
CHECKED	J.W.H.	<b>ABUTMENT WING DETAILS</b>	
APPROV.	T.A.C.		
SQUAD	CEC		
		JOB PIECE NO. 28827(04)	SHEET NO. 26



DESCRIPTION	REVISIONS	DATE





NOTE:  
 FOOTING REINFORCEMENT OMITTED FOR CLARITY. FOR ADDITIONAL FOOTING DETAILS, SEE SHEETS 28 AND 29.

NOTE:  
 FOR BAR BENDS AND BAR LIST, SEE SHEET 30.

NOTE:  
 FOR SUBSTRUCTURE EXCAVATION, SEE SHEET 24.

NOTE:  
 FOR PILING STEEL PLATE REINFORCING TIP DETAILS, SEE SHEET 30.



PIER QUANTITIES				
ITEM	UNIT	PIER NO. 1	PIER NO. 2	TOTAL
SUBSTRUCTURE EXCAVATION COMMON	C.Y.	1,700	1,700	3,400
CLASS AA CONCRETE	C.Y.	111.1	111.1	222.2
CLASS A CONCRETE	C.Y.	35.5	35.5	71.0
REINFORCING STEEL	LB.	1,100	1,100	2,200
EPOXY COATED REINFORCING STEEL	LB.	26,090	26,090	52,180
PILES, FURNISHED (HP 14X89)	L.F.	2,010	1,890	3,900
PILES, DRIVEN (HP 14X89)	L.F.	2,010	1,890	3,900
WATER REPELLENT (VISUALLY INSPECTED)	S.Y.	75	75	150


① QUANTITY USED TO CONSTRUCT PIER COLUMNS AND FOOTING.

W26 COLUMN SPIRAL TO EXTEND 2'-0" MINIMUM INTO PIER CAP AND FOOTING.


THIS DRAWING IS PRELIMINARY IN NATURE. IT IS NOT A FINAL SIGNED AND SEALED DRAWING.

DESIGN	J.W.H.	SH34 OVER N. PERSIMMON CREEK	WOODWARD COUNTY
DRAWN	Z.M.B.	BRIDGE A	
CHECKED	J.W.H.	<b>PIER NO. 1 AND 2 DETAILS (SHEET 1 OF 3)</b>	
APPROV.	T.A.C.		
SQUAD	CEC		
		JOB PIECE NO. 28827(04)	SHEET NO. 27

DESCRIPTION	REVISIONS	DATE




**SECTION C-C**



**PIER FOOTING PLAN**

PILE LOCATIONS AND FOOTING DIM.



**SECTION D-D**

NOTE:  
ALL PIER FOOTING PILES ARE HP14X89

NOTE:  
PLACE BARS AS SHOWN, MINIMUM HORIZONTAL CLEARANCE BETWEEN BARS IS 3".

NOTE:  
FOR REINFORCING PLAN, SEE SHEET 29.

NOTE:  
FOR BAR BENDS AND BAR LIST, SEE SHEET 30.

THIS DRAWING IS PRELIMINARY IN NATURE. IT IS NOT A FINAL SIGNED AND SEALED DRAWING


DESIGN	J.W.H.
DRAWN	R.A.P.
CHECKED	J.W.H.
APPROV.	T.A.C.
SQUAD	CEC

SH34 OVER N. PERSIMMON CREEK WOODWARD COUNTY BRIDGE A


**PIER NO. 1 AND 2 DETAILS  
(SHEET 2 OF 3)**

JOB PIECE NO. 28827(04) SHEET NO. 28


DESCRIPTION	REVISIONS	DATE



**PIER FOOTING REINFORCING PLAN**  
(TOP MAT REINFORCING)



**PIER FOOTING REINFORCING PLAN**  
(BOT. MAT REINFORCING)




**PIER FOOTING REINFORCING PLAN**  
(REINFORCING OVER TOP OF PILES)

- NOTE:  
PLACE BARS AS SHOWN, MINIMUM HORIZONTAL CLEARANCE BETWEEN BARS IS 3".
- NOTE:  
FOR SECTIONS C-C AND D-D, SEE SHEET 28.
- NOTE:  
FOR BAR BENDS AND BAR LIST, SEE SHEET 30.
- ① 5 BARS AT EQ. SPA. BTWN. PILES, SEE SECTION D-D FOR BAR PLACEMENT.


THIS DRAWING IS PRELIMINARY IN NATURE. IT IS NOT A FINAL SIGNED AND SEALED DRAWING

DESIGN	J.W.H.	SH34 OVER N. PERSIMMON CREEK	WOODWARD COUNTY
DRAWN	R.A.P.	BRIDGE A	
CHECKED	J.W.H.	<b>PIER NO. 1 AND 2 DETAILS</b> <b>(SHEET 3 OF 3)</b>	
APPROV.	T.A.C.		
SQUAD	CEC		
		JOB PIECE NO. 28827(04) SHEET NO. 29	


DESCRIPTION	REVISIONS	DATE



**SECTION E-E**



**SECTION F-F**




**ELEVATION OF WEB**


**ELEVATION OF FLANGE**

**DETAIL OF PILING**


NOTE:  
 PROVIDE STRUCTURAL STEEL FOR PILING AND STEEL PLATE REINFORCING TIPS IN ACCORDANCE WITH AASHTO M270 (ASTM A572), GRADE 50. THE CONTRACTOR MAY USE MANUFACTURED DRIVING TIPS AS AN ALTERNATIVE TO THE STEEL PLATE REINFORCING TIPS SHOWN WITH APPROVAL BY THE BRIDGE ENGINEER. THE DEPARTMENT CONSIDERS THE COST OF STEEL PLATE REINFORCING TIPS OR MANUFACTURED DRIVING TIPS TO BE INCLUDED IN THE CONTRACT UNIT PRICE OF PILES, FURNISHED.




**DETAIL OF WELDED SPLICE**




**DETAIL A**




**WATER REPELLENT TREATMENT DETAIL**




**SPIRAL REINFORCING SPLICE DETAIL**



- FB2 #10 X 19'-8"
- FP2 #4 X 3'-7"
- FT1 #6 X 22'-10"
- FT2 #9 X 22'-10"
- FTH1 #6 X 47'-0"
- P1 #4 X 7'-4"
- P2 #4 X 7'-6"
- PH1 #10 X 44'-6"
- PH5 #5 X 5'-8"
- PV1 #5 X 6'-0"



- S1 #6 X 19'-10"
- S2 #6 X 15'-10"



- FB3 #10 X 18'-1"
- PH2 #10 X 42'-11"

**PIER BAR LIST**

ONE SHOWN - TWO REQUIRED				
EPOXY COATED REINFORCING				
MARK	SIZE	NO.	FORM	LENGTH
CV1	#9	28	BNT.	22'-1"
FB1	#6	16	STR.	16'-0"
FB2	#10	40	BNT.	19'-8"
FB3	#10	40	BNT.	18'-1"
FB4	#6	20	STR.	1'-2"
FB5	#6	8	STR.	4'-4"
FB6	#6	6	STR.	10'-4"
FH1	#9	14	STR.	40'-0"
FH2	#6	16	STR.	2'-6"
FH3	#6	2	STR.	5'-0"
FH4	#6	2	STR.	7'-5"
FH5	#6	1	STR.	14'-5"
FP1	#4	12	STR.	15'-6"
FP2	#4	84	BNT.	3'-7"
FT1	#6	16	BNT.	22'-10"
FT2	#9	42	BNT.	22'-10"
FTH1	#6	19	BNT.	47'-0"
P1	#4	30	BNT.	7'-4"
P2	#4	30	BNT.	7'-6"
PH1	#10	9	BNT.	44'-6"
PH2	#10	4	BNT.	42'-11"
PH3	#5	6	STR.	40'-10"
PH4	#10	13	STR.	40'-10"
PH5	#5	8	BNT.	5'-8"
PV1	#5	6	BNT.	6'-0"
S1	#6	48	BNT.	19'-10"
S2	#6	110	BNT.	15'-10"
PLAIN REINFORCING				
MARK	SIZE	NO.	FORM	LENGTH
CS1	W26	2	BNT.	587'-7"

① LENGTH SHOWN DOES NOT ACCOUNT FOR SPLICES. CONTRACTOR MAY ADD SPLICES AS NECESSARY, BUT PAYMENT WILL NOT BE MADE FOR EXTRA LENGTH REQUIRED FOR SPLICES.


THIS DRAWING IS PRELIMINARY IN NATURE. IT IS NOT A FINAL SIGNED AND SEALED DRAWING

DESIGN	J.W.H.
DRAWN	Z.M.B. J.F.R.
CHECKED	J.W.H.
APPROV.	T.A.C.
SQUAD	CEC

SH34 OVER N. PERSIMMON CREEK WOODWARD COUNTY BRIDGE A

**PIER STEEL PILING DETAIL AND BAR LIST**


DESCRIPTION	REVISIONS	DATE



NOTE:  
ROTATE A AND AC BARS TO  
MAINTAIN MINIMUM CLEARANCE.


NOTE:  
FOR SUPERSTRUCTURE QUANTITIES,  
SEE SHEET 32.

NOTE:  
FOR BAR BENDS AND BAR LIST,  
SEE SHEET 36.





**BEAM HAUNCH DETAIL**


NOTE:  
PLAN QUANTITIES FOR CLASS AA CONCRETE INCLUDE 23.1 CY.  
FOR BEAM HAUNCHES. THE HAUNCH HEIGHT SHOWN IS THE  
THEORETICAL HAUNCH HEIGHT AT THE CENTERLINE BEARING  
ONLY, MEASURED FROM THE BOTTOM OF THE DECK SLAB TO  
THE TOP OF THE BEAM, AND VARIES ACROSS THE SPAN.  
DETERMINE THE ACTUAL HAUNCH HEIGHT (ACCOUNTING FOR  
BEAM CAMBER, DEAD LOAD DEFLECTION AND ROADWAY GRADE)  
AFTER ERECTION OF THE BEAMS AND SUBMIT TO THE  
ENGINEER FOR APPROVAL. THE ENGINEER WILL NOT MEASURE  
DIFFERENCES BETWEEN THE THEORETICAL AND THE ACTUAL  
HAUNCH HEIGHTS FOR PAYMENT.



**WATER REPELLENT TREATMENT DETAILS**



**DETAIL A**




**DETAIL B**

THIS DRAWING  
IS PRELIMINARY IN  
NATURE. IT IS NOT  
A FINAL SIGNED  
AND SEALED  
DRAWING

DESIGN	J.W.H.	SH34 OVER N. PERSIMMON CREEK	WOODWARD COUNTY
DRAWN	R.A.P.	BRIDGE A	
CHECKED	J.W.H.	<b>TYPICAL CROSS SECTION</b>	
APPROV.	T.A.C.		
SQUAD	CEC		
		JOB PIECE NO. 28827(04)	SHEET NO. 31

DESCRIPTION	REVISIONS	DATE



EXPANSION JOINT SETTING SCHEDULE	
EXP. JOINT OPENING	TEMPERATURE
	PIER NO. 2
3"	0°F
2 7/8"	2°F
2 3/4"	8°F
2 5/8"	14°F
2 1/2"	20°F
2 3/8"	26°F
2 1/4"	31°F
2 1/8"	37°F
2"	43°F
1 7/8"	49°F
1 3/4"	55°F
1 5/8"	60°F
1 1/2"	66°F
1 3/8"	72°F
1 1/4"	78°F
1 1/8"	84°F
1"	90°F
7/8"	95°F
3/4"	101°F
5/8"	107°F
1/2"	113°F
3/8"	119°F
1/4"	120°F

⊕ DIMENSION IS FROM TOP OF DECK SLAB TO BOTTOM OF BEARING ASSEMBLY AT CL BEARING.

**LONGITUDINAL SECTION**

DO NOT PLACE THE CONCRETE FOR THE DECK SLAB OR APPLY OTHER MASSIVE LOADS TO THE BEAMS UNTIL THE CONCRETE IN THE DIAPHRAGMS HAS BEEN IN PLACE A MINIMUM OF 10 DAYS OR AT THE DISCRETION OF THE ENGINEER. THE ENGINEER MAY APPROVE SHORTENED TIME IF THE BEAM AND DIAPHRAGM CONCRETE HAS ATTAINED 80% OF THE SPECIFIED COMPRESSIVE STRENGTH.

SUPERSTRUCTURE QUANTITIES		
ITEM	UNIT	TOTAL
PRESTRESSED CONCRETE BEAMS (TYPE IV)	L.F.	1,495
SAW-CUT GROOVING	S.Y.	1,341
SEALED EXPANSION JOINT	L.F.	41.8
CONCRETE RAIL (TR4)	L.F.	603.3
STRUCTURAL STEEL	LB.	1,430
STAINLESS STEEL FIXED BEARING ASSEMBLY	EA.	10
STAINLESS STEEL EXPANSION BEARING ASSEMBLY	EA.	20
CLASS AA CONCRETE	C.Y.	358.4
EPOXY COATED REINFORCING STEEL	LB.	97,830
WATER REPELLENT (VISUALLY INSPECTED)	S.Y.	995
SEALER CRACK PREPARATION	L.F.	41
SEALER RESIN	GAL.	1


THIS DRAWING IS PRELIMINARY IN NATURE. IT IS NOT A FINAL SIGNED AND SEALED DRAWING

DESIGN	J.W.H.	SH34 OVER N. PERSIMMON CREEK BRIDGE A	WOODWARD COUNTY
DRAWN	R.A.P.		
CHECKED	J.W.H.		
APPROV.	T.A.C.		
SQUAD	CEC		

**LONGITUDINAL SECTION**

JOB PIECE NO. 28827(04) SHEET NO. 32

DESCRIPTION	REVISIONS	DATE



**BEAM FRAMING PLAN**

THIS DRAWING IS PRELIMINARY IN NATURE. IT IS NOT A FINAL SIGNED AND SEALED DRAWING

DESIGN	J.W.H.
DRAWN	R.A.P.
CHECKED	J.W.H.
APPROV.	T.A.C.
SQUAD	CEC

SH34 OVER N. PERSIMMON CREEK WOODWARD COUNTY BRIDGE A


**BEAM FRAMING PLAN**

JOB PIECE NO. 28827(04) SHEET NO. 33




DESCRIPTION	REVISIONS	DATE

**PRESTRESSED CONCRETE BEAM NOTES**  
 COMPRESSIVE STRENGTH  
 PROVIDE CONCRETE WITH A COMPRESSIVE STRENGTH OF 7,000 P.S.I. AT TRANSFER OF PRESTRESS AND 10,000 P.S.I. AT 28 DAYS.  
 STRAND TYPE  
 PROVIDE LOW-RELAXATION STRANDS HAVING A NOMINAL DIAMETER OF 0.6" WITH ULTIMATE TENSILE STRENGTH OF 270 K.S.I.




**PLAN**


NOTE: PROVIDE AN EMBEDDED SOLE PLATE AT EACH END OF THE BEAM.




**END VIEW**  
**ELEVATION**  
**EMBEDDED SOLE PLATE DETAILS**




**END VIEW**



**ELEVATION**




**ELEVATION**




**TOP VIEW**  
**END VIEW**  
**EMBEDDED BEAM PLATE DETAILS**

NOTE: PROVIDE AN EMBEDDED BEAM PLATE AT EXPANSION ENDS ONLY.



**INTENTIONALLY ROUGHENED SURFACE DETAILS**


TOP SURFACE OF P.C. BEAMS SHALL BE INTENTIONALLY ROUGHENED TO A MINIMUM HEIGHT OF 1/4" OVER A MAXIMUM PITCH OF 2" MEASURED LONGITUDINALLY ALONG THE LENGTH OF THE BEAM. THE CREST AND TROUGH ASSOCIATED WITH THE HEIGHT SHALL NOT BE LESS THAN 1/2" AND SHALL EXTEND THE FULL WIDTH OF THE TOP FLANGE. PRODUCE THE ROUGHENED SURFACE BY USING A SPECIAL TROWEL TO FORM ONE OF THE SURFACES SHOWN IN THE DETAILS, BY CLEANING THE CONCRETE SURFACE WITH A STIFF WIRE BRUSH (OR BLASTING) TO THE EXTENT THAT AGGREGATE IS EXPOSED TO A HEIGHT OF 1/4", OR BY ANOTHER APPROVED METHOD. THE METHOD USED SHALL BE SUBMITTED FOR APPROVAL BY THE ENGINEER. REPAIR ANY DAMAGE TO THE REINFORCEMENT'S EPOXY COATING BEFORE PLACEMENT OF DECK CONCRETE.



**END SECTION**

**CL SECTION**

**BEAM SECTIONS**  
(34 - 0.6" STRANDS)




**TYPE IV P.C. BEAM BAR BEND DETAILS**

THIS DRAWING IS PRELIMINARY IN NATURE. IT IS NOT A FINAL SIGNED AND SEALED DRAWING.

DESIGN	J.W.H.	SH34 OVER N. PERSIMMON CREEK	WOODWARD COUNTY
DRAWN	R.A.P.	BRIDGE A	
CHECKED	J.W.H.		
APPROV.	T.A.C.		
SQUAD	CEC		


**P.C.B. DETAILS-TYPE IV**




**DEAD LOAD DEFLECTION DIAGRAM**

NOTE: THE DEAD LOAD DEFLECTION SHOWN ABOVE AT THE TENTH POINTS ARE THE INITIAL DEFLECTIONS DUE TO DECK SLAB + DIAPHRAGMS + HAUNCH + CONCRETE TRAFFIC RAIL. IT DOES NOT INCLUDE THE BEAM WEIGHT OR FUTURE WEARING SURFACE.


DESCRIPTION	REVISIONS	DATE




SECTION A-A



END DIAPHRAGM




SECTION B-B




INTERMEDIATE DIAPHRAGM

DIAPHRAGM DETAILS


NOTE:  
FOR BAR BENDS,  
SEE SHEET 36.



ANCHOR BOLT DETAIL



DETAIL A




FIX. BRG. EXP. BRG.


DO NOT BOND BEARING PAD TO THE ANCHOR PLATE.

PLAN

BUILT-UP CONTACT ANGLE DETAIL



END VIEW



SIDE VIEW


ELASTOMETRIC BEARING PAD  
60 DURO  
4 5/8" X 6" X 2'-2"  
2 - 1/4" COVER LAYER  
8 - 3/8" INTERNAL LAYERS  
9 - 1/8" LAMINATE PLATES

BEARING DETAILS

THIS DRAWING IS PRELIMINARY IN NATURE. IT IS NOT A FINAL SIGNED AND SEALED DRAWING


DESIGN	J.W.H.	SH34 OVER N. PERSIMMON CREEK	WOODWARD COUNTY
DRAWN	R.A.P.	BRIDGE A	
CHECKED	J.W.H.	<b>DIAPHRAGM AND BEARING DETAILS</b>	
APPROV.	T.A.C.		
SQUAD	CEC		
		JOB PIECE NO. 28827(04)	SHEET NO. 35

DESCRIPTION	REVISIONS	DATE




**SLAB REINFORCING PLAN**

C.R.L. & P.G.L. SH34  
N 00°42'31.65" E




**ABUTMENT NO. 1**

**PIER NO. 1**



**PIER NO. 1**

**PIER NO. 2**



**PIER NO. 2**

**ABUTMENT NO. 2**

**PARAPET ELEVATION**

NOTE: FOR ADDITIONAL DETAIL OF PARAPET, SEE STD. TR4-2.


SUPERSTRUCTURE BAR LIST				
EPOXY COATED REINFORCING				
MARK	SIZE	NO.	FORM	LENGTH
A1	#6	405	BNT.	43'-2"
AC	#5	806	BNT.	9'-11"
AH1	#4	22	BNT.	3'-1"
AH2	#4	64	BNT.	4'-7"
AS	#4	86	BNT.	5'-0"
AT1	#4	4	STR.	41'-10"
B1	#6	409	STR.	41'-10"
EB1	#6	43	STR.	212'-2"
EB2	#6	43	STR.	104'-6"
EPH1	#4	43	BNT.	3'-2"
EPT1	#4	2	STR.	41'-10"
ET1	#4	43	STR.	206'-8"
ET2	#4	43	STR.	102'-8"
F1	#4	120	STR.	8'-0"
F2	#4	96	STR.	7'-2"
FPH1	#4	38	BNT.	4'-10"
FPT1	#4	2	STR.	41'-10"
SR1	#5	1,172	BNT.	4'-1"
U1	#4	108	BNT.	4'-9"
U2	#4	192	BNT.	6'-3"

① INCLUDES 3 LAPS AT 3'-10"  
 ② INCLUDES 1 LAP AT 3'-10"  
 ③ INCLUDES 3 LAPS AT 2'-0"  
 ④ INCLUDES 1 LAP AT 2'-0"  
 ⑤ FOR BAR BEND, SEE STD. TR4-2.


THIS DRAWING IS PRELIMINARY IN NATURE. IT IS NOT A FINAL SIGNED AND SEALED DRAWING

DESIGN	J.W.H.	SH34 OVER N. PERSIMMON CREEK	WOODWARD COUNTY
DRAWN	R.A.P.	BRIDGE A	
CHECKED	J.W.H.	<b>SUPERSTRUCTURE DETAILS</b>	
APPROV.	T.A.C.		
SQUAD	CEC		
		JOB PIECE NO. 28827(04)	SHEET NO. 36


DESCRIPTION	REVISIONS	DATE




**SECTION A**




**SECTION B**



**SECTION C**




**SECTION D**




**SECTION E**

C.R.L. & P.G.L. SH34  
N 00°42'31.65" E


NOTE:  
FOR BAR BENDS AND  
BAR LIST, SEE SHEET 36.



**ABUTMENT**



**PIER NO. 1**



**PIER NO. 2**

**ADDITIONAL SLAB REINFORCING AT DIAPHRAGMS**

THIS DRAWING  
IS PRELIMINARY IN  
NATURE. IT IS NOT  
A FINAL SIGNED  
AND SEALED  
DRAWING


DESIGN	J.W.H.
DRAWN	R.A.P.
CHECKED	J.W.H.
APPROV.	T.A.C.
SQUAD	CEC

SH34 OVER N. PERSIMMON CREEK WOODWARD COUNTY  
BRIDGE A


**ADDITIONAL SLAB  
REINFORCING**

JOB PIECE NO. 28827(04) SHEET NO. 37


DESCRIPTION	REVISIONS	DATE




NOTE:  
FOR ADDITIONAL DETAIL OF GUARDRAIL  
CURBING, SEE STD. THRI-1-02.



**SECTION A**



**SECTION B-B**



**SECTION C-C**

NOTE:  
FOR DETAILS OF ASPHALT ROADWAY AND WIDENING SEE  
ROADWAY PLANS.

SLOPE DRAINS, SPLASH BASINS AND SLOPE DRAIN CURB SHALL BE CONSTRUCTED USING CLASS 'C' CONCRETE AS SHOWN ON THIS SHEET. LENGTH OF SLOPE DRAIN SHOWN IN THE PLANS IS ESTIMATED. ACTUAL LENGTH TO BE DETERMINED IN THE FIELD BY THE ENGINEER. ALL COSTS OF THE SLOPE DRAINS, SPLASH BASINS AND SLOPE DRAIN CURBS INCLUDING REINFORCEMENT SHALL BE INCLUDED IN THE BRIDGE PAY ITEM FOR "CLASS 'C' CONCRETE".

① SLOPE TO MATCH SLOPE OF HEADER




SLOPE DRAINS SCHEDULE	
SLOPE DRAIN	ESTIMATED LENGTH
ABUTMENT NO. 1 - WEST	30'-0"
ABUTMENT NO. 1 - EAST	33'-0"
ABUTMENT NO. 2 - WEST	35'-0"
ABUTMENT NO. 2 - EAST	35'-0"

SLOPE DRAIN QUANTITIES		
ITEM	UNITS	TOTAL
CLASS C CONCRETE	C.Y.	9.3

THIS DRAWING IS PRELIMINARY IN NATURE. IT IS NOT A FINAL SIGNED AND SEALED DRAWING

DESIGN	J.W.H.	SH34 OVER N. PERSIMMON CREEK	WOODWARD COUNTY
DRAWN	Z.M.B.	BRIDGE A	
CHECKED	J.W.H.	<b>SLOPE DRAIN DETAILS</b>	
APPROV.	T.A.C.		
SQUAD	CEC		
		JOB PIECE NO. 28827(04)	SHEET NO. 38


DESCRIPTION	REVISIONS	DATE





FILENAME: 39 SIGNING & STRIPING SHEET.DWG

DESIGN		SH-34 OVER N. PERSIMMON CREEK	WOODWARD COUNTY
DRAWN		<b>SIGNING &amp; STRIPING SHEET</b>	
CHECKED			
CEC		STATE JOB NO. 28827(04)	SHEET NO. 39

DESCRIPTION	REVISIONS	DATE



- COLOR:  
 LEGEND, SYMBOL AND BORDER:  
 BLACK (NON-REFLECTORIZED)  
 RED (TRANSPARENT REFLECTORIZED)  
 BACKGROUND:  
 ▲ FLUORESCENT ORANGE (REFLECTORIZED)  
 \* FLUORESCENT YELLOW (REFLECTORIZED)  
 ● WHITE (REFLECTORIZED)






FILENAME: 40 TRAFFIC CONTROL (SHEET 1 OF 2).DWG

DESIGN	SH-34 OVER N. PERSIMMON CREEK	WOODWARD COUNTY
DRAWN		
CHECKED		
CEC	STATE JOB NO. 28827(04)	SHEET NO. 40

**TRAFFIC CONTROL  
(SHEET 1 OF 2)**




DESCRIPTION	REVISIONS	DATE




FILENAME: 40 TRAFFIC CONTROL (SHEET 1 OF 2).DWG


DESIGN	SH-34 OVER N. PERSIMMON CREEK	WOODWARD COUNTY
DRAWN		
CHECKED		
CEC	<b>TRAFFIC CONTROL (SHEET 2 OF 2)</b>	
	STATE JOB NO. 28827(04)	SHEET NO. 41





**STA. 2428+49.86  
 BEGIN INCIDENTAL CONSTRUCTION  
 (DETOUR ALIGNMENT)**




**CROSS SECTIONS : SH-34**







**STA. 2434+50  
 END INCIDENTAL CONSTRUCTION &  
 BEGIN PROJECT**



2436  
+  
50

AREA	PHASE 1	PHASE 2	PHASE 3
EXC.	15	59	8
EMB.	8	24	15

2436  
+  
50

AREA	PHASE 1	PHASE 2	PHASE 3
EXC.	15	51	4
EMB.	6	24	8

2436  
+  
25

AREA	PHASE 1	PHASE 2	PHASE 3
EXC.	17	51	0
EMB.	5	29	0

2436  
+  
25

AREA	PHASE 1	PHASE 2	PHASE 3
EXC.	18	44	1
EMB.	3	28	12


2436  
+  
00

AREA	PHASE 1	PHASE 2	PHASE 3
EXC.	22	45	2
EMB.	2	32	22

2436  
+  
00

AREA	PHASE 1	PHASE 2	PHASE 3
EXC.	54	79	2
EMB.	2	59	63





2438  
+  
00

AREA	PHASE	EXC.	EMB.
5	30	PHASE 1	
83	32	PHASE 2	
30	5	PHASE 3	

PHASE	EXC.	EMB.
PHASE 1	19	33
PHASE 2	218	42
PHASE 3	33	19

2438  
+  
00

2437  
+  
50

AREA	PHASE	EXC.	EMB.
15	6	PHASE 1	
152	13	PHASE 2	
6	13	PHASE 3	

PHASE	EXC.	EMB.
PHASE 1	25	13
PHASE 2	206	32
PHASE 3	13	27


2437  
+  
50


2437  
+  
00

AREA	PHASE	EXC.	EMB.
13	9	PHASE 1	
70	22	PHASE 2	
9	13	PHASE 3	

PHASE	EXC.	EMB.
PHASE 1	26	15
PHASE 2	119	43
PHASE 3	15	29

2437  
+  
00





2440  
+  
66

1	174	PHASE 1
21	175	PHASE 2
182	1	PHASE 3

1	96	PHASE 1
13	97	PHASE 2
102	1	PHASE 3

2440  
+  
66

2440  
+  
50

1	153	PHASE 1
22	154	PHASE 2
165	1	PHASE 3

3	229	PHASE 1
58	204	PHASE 2
239	3	PHASE 3


2440  
+  
50

2440  
+  
00

2	94	PHASE 1
41	66	PHASE 2
94	2	PHASE 3

5	144	PHASE 1
108	79	PHASE 2
143	6	PHASE 3

2440  
+  
00



2443  
+  
66

AREA	PHASE 1	PHASE 2	PHASE 3
EXC.	7	45	83
EMB.	46	181	8

VOLUME	PHASE 1	PHASE 2	PHASE 3
EXC.	5	21	69
EMB.	52	83	6

2443  
+  
66

2443  
+  
41

AREA	PHASE 1	PHASE 2	PHASE 3
EXC.	3	0	67
EMB.	67	0	3

VOLUME	PHASE 1	PHASE 2	PHASE 3
EXC.	3	0	155
EMB.	0	0	4

2443  
+  
41

2442  
+  
50

AREA	PHASE 1	PHASE 2	PHASE 3
EXC.	12	0	434
EMB.	434	0	12

STR. NO. T1  
STA. 2442+41.71, 41.38' RT, 108.93' RT. C.D.  
CONST. 72" CGSP X 68' LG.

STR. NO. T2  
STA. 2442+50.71, 41.26' RT, 108.82' RT. C.D.  
CONST. 72" CGSP X 68' LG.

STR. NO. T3  
STA. 2442+61.72, 35.77' RT, 114.82' RT. C.D.  
CONST. 96" CGSP X 79' LG.

STR. NO. T4  
STA. 2442+72.72, 40.99' RT, 108.55' RT. C.D.  
CONST. 72" CGSP X 68' LG.

VOLUME	PHASE 1	PHASE 2	PHASE 3
EXC.	27	0	570
EMB.	570	0	31

2442  
+  
50


2441  
+  
00

AREA	PHASE 1	PHASE 2	PHASE 3
EXC.	1	0	221
EMB.	221	0	1

STA. 2441+00.00  
BEGIN EARTHWORK EXCEPTION

VOLUME	PHASE 1	PHASE 2	PHASE 3
EXC.	1	13	254
EMB.	249	110	1

2441  
+  
00



2445  
+  
00

12	32	PHASE 1
77	54	PHASE 2
32	12	PHASE 3

19	63	PHASE 1
140	128	PHASE 2
64	21	PHASE 3

2445  
+  
00

2444  
+  
50

8	36	PHASE 1
74	84	PHASE 2
36	8	PHASE 3

11	64	PHASE 1
130	198	PHASE 2
64	13	PHASE 3


2444  
+  
50

2444  
+  
00

4	33	PHASE 1
66	130	PHASE 2
33	4	PHASE 3

7	49	PHASE 1
70	195	PHASE 2
73	9	PHASE 3

2444  
+  
00



2446  
+  
50

AREA	PHASE	EXC.	EMB.
47	1	PHASE 1	
166	42	PHASE 2	
1	47	PHASE 3	

PHASE	EXC.	EMB.
PHASE 1	75	4
PHASE 2	297	94
PHASE 3	4	87

2446  
+  
50

2446  
+  
00

AREA	PHASE	EXC.	EMB.
34	4	PHASE 1	
155	60	PHASE 2	
3	34	PHASE 3	

PHASE	EXC.	EMB.
PHASE 1	50	21
PHASE 2	235	120
PHASE 3	68	58

2446  
+  
00


2445  
+  
50

AREA	PHASE	EXC.	EMB.
20	19	PHASE 1	
98	70	PHASE 2	
70	20	PHASE 3	

PHASE	EXC.	EMB.
PHASE 1	30	47
PHASE 2	162	115
PHASE 3	95	34

2445  
+  
50





2448  
+  
00

AREA	Exc.	Emb.	PHASE
PHASE 1	23	40	PHASE 1
PHASE 2	106	27	PHASE 2
PHASE 3	40	23	PHASE 3

VOLUME	Exc.	Emb.	PHASE
PHASE 1	50	57	PHASE 1
PHASE 2	217	49	PHASE 2
PHASE 3	57	58	PHASE 3

2448  
+  
00

2447  
+  
50

AREA	Exc.	Emb.	PHASE
PHASE 1	31	21	PHASE 1
PHASE 2	128	26	PHASE 2
PHASE 3	21	31	PHASE 3

VOLUME	Exc.	Emb.	PHASE
PHASE 1	68	22	PHASE 1
PHASE 2	273	50	PHASE 2
PHASE 3	22	79	PHASE 3


2447  
+  
50

2447  
+  
00


AREA	Exc.	Emb.	PHASE
PHASE 1	43	3	PHASE 1
PHASE 2	166	28	PHASE 2
PHASE 3	3	43	PHASE 3

VOLUME	Exc.	Emb.	PHASE
PHASE 1	84	3	PHASE 1
PHASE 2	307	65	PHASE 2
PHASE 3	3	96	PHASE 3

2447  
+  
00



**CROSS SECTIONS: SH-34**



2451  
+  
00

5	146	PHASE 1
0	0	PHASE 2
146	5	PHASE 3

PHASE 1	7	276
PHASE 2	0	0
PHASE 3	276	8

2451  
+  
00

2450  
+  
50

3	152	PHASE 1
0	0	PHASE 2
152	3	PHASE 3

PHASE 1	6	280
PHASE 2	0	0
PHASE 3	280	7


2450  
+  
50

2450  
+  
00

4	150	PHASE 1
0	0	PHASE 2
150	4	PHASE 3

PHASE 1	14	232
PHASE 2	43	11
PHASE 3	232	16

2450  
+  
00



2452  
+  
50

7	90	PHASE 1
0	0	PHASE 2
90	7	PHASE 3

PHASE 1	10	196
PHASE 2	0	0
PHASE 3	196	12

2452  
+  
50

2452  
+  
00

4	122	PHASE 1
0	0	PHASE 2
122	4	PHASE 3

PHASE 1	7	239
PHASE 2	0	0
PHASE 3	239	8

2452  
+  
00

2451  
+  
50

4	136	PHASE 1
0	0	PHASE 2
136	4	PHASE 3

PHASE 1	8	262
PHASE 2	0	0
PHASE 3	261	10

2451  
+  
50

