


REV. NO.	DESCRIPTION	REVISIONS	DATE

SUMMARY OF SIGNS - BRYAN COUNTY (CONTINUED)																				
PLAN ITEM NO.	ALIGNMENT	APPROX. STATION	SIDE	TYPE OF SIGN	DESCRIPTION	SIGNS					POSTS					FOOTINGS			REMOVAL OF SIGNS 805(A)*	REMARKS
						EXTRUDED ALUMINUM PANEL SIGNS 850(B)	4" @ 13 GALV. STEEL WIDE FLANGE BEAM 851(A)	6" @ 15 GALV. STEEL WIDE FLANGE BEAM 851(A)	6" @ 25 GALV. STEEL WIDE FLANGE BEAM 851(A)	8" @ 31 GALV. STEEL WIDE FLANGE BEAM 851(A)	APPROX. POST SPACING	TYPE	STRUC. CONC. 804(A)	REIN. STEEL 804(B)	EA.					
						S.F.	L.F.	L.F.	L.F.	L.F.	FT.					C.Y.	LB.			
51	US-69	494+00	LT	SP-21	FRANKLIN ST 1/2 MILE	150.75			40.0		9.9	KC-2	1.64	348		1	INSTALL NEW			
52	US-69	519+60	LT	SP-20	FRANKLIN ST 1 MILE	150.75			40.0		9.9	KC-2	1.64	348		1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)			
53	US-69	523+00	LT	SP-03	COLBERT LIMITS	36.00	30.0				5.4	KC-0	0.72	130		1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)			
54	US-69	522+90	RT	SP-30	CALERA LIMITS	36.00	30.0				5.4	KC-0	0.72	130		1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)			
55	US-69	618+10	RT	SP-31	D1-1	46.00	30.0				6.9	KC-0	0.72	130		1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)			
56	US-69	628+50	LT	SP-32	D1-1	46.00	30.0				6.9	KC-0	0.72	130		1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)			
57	US-69	664+00	LT	SP-33	D2-3	78.00	35.0				7.5	KC-0	0.72	130			INSTALL NEW			
58	US-69	830+00	RT	E1-5P	EXITS 12A-B	42.00											ATTACH NEW EXIT TAB TO EXISTING US-70 INTERCHANGE GUIDE SIGN			
59	US-69	856+00	RT	E1-5P	EXITS 12A-B	42.00											ATTACH NEW EXIT TAB TO EXISTING US-70 INTERCHANGE GUIDE SIGN			
60	US-69	867+00	RT	SP-34	LAKE TEXOMA	168.00			38.0		12.6	KC-2	1.64	348			INSTALL NEW			
61	US-69	876+00	RT	E1-5P	EXIT 12A	33.00											ATTACH NEW EXIT TAB TO EXISTING US-70 INTERCHANGE GUIDE SIGN			
62	US-69	1112+60	RT	E5-1a(16)	EXIT GORE SIGN	35.00					4.2	KC-0	0.72	130		1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)			
				E13-1(25)	ADVISORY SPEED TAB	14.00		45.0												
63	US-69	882+90	RT	E5-1a(12A)	EXIT GORE SIGN	42.50					5.1	KC-0	0.72	130		1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)			
				E13-1(30)	ADVISORY SPEED TAB	17.00		45.0												
64	US-69	887+00	RT	E1-5P	EXIT 12B	33.00											ATTACH NEW EXIT TAB TO EXISTING US-70 INTERCHANGE GUIDE SIGN			
65	US-69	891+40	LT	E5-1a(12A)	EXIT GORE SIGN	42.50					5.1	KC-0	0.72	130		1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)			
				E13-1(25)	ADVISORY SPEED TAB	17.00		45.0												
66	US-69	898+00	RT	E5-1a(12B)	EXIT GORE SIGN	42.50					5.1	KC-0	0.72	130		1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)			
				E13-1(25)	ADVISORY SPEED TAB	17.00		45.0												
67	US-69	899+50	LT	E1-5P	EXIT 12A	33.00											ATTACH NEW EXIT TAB TO EXISTING US-70 INTERCHANGE GUIDE SIGN			
68	US-69	903+70	RT	SP-35	DURANT EXITS	231.00				43.0	13.2	KC-3	1.98	632		1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)			
69	US-69	907+00	LT	E5-1a(12B)	EXIT GORE SIGN	42.50					5.1	KC-0	0.72	130		1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)			
				E13-1(30)	ADVISORY SPEED TAB	17.00		45.0												
70	US-69	918+80	LT	E1-5P	EXIT 12B	33.00											ATTACH NEW EXIT TAB TO EXISTING US-70 INTERCHANGE GUIDE SIGN			
71	US-69	930+00	LT	E1-5P	EXIT 12A-B	42.00											ATTACH NEW EXIT TAB TO EXISTING US-70 INTERCHANGE GUIDE SIGN			
72	US-69	938+00	LT	SP-34	LAKE TEXOMA	168.00			38.0		12.6	KC-2	1.64	348			INSTALL NEW			
73	US-69	955+00	LT	E1-5P	EXITS 12A-B	42.00											ATTACH NEW EXIT TAB TO EXISTING US-70 INTERCHANGE GUIDE SIGN			
74	US-69	965+00	RT	SP-36	MAIN ST EXIT 1 MILE	118.00			38.0		8.4	KC-1	1.52	212		1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)			
75	US-69	980+00	LT	SP-37	D2-3	71.50	35.0				7.5	KC-0	0.72	130			INSTALL NEW			
76	US-69	986+00	RT	SP-38	MAIN ST EXIT 1/2 MILE	111.00			37.0		8.4	KC-1	1.52	212		1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)			
77	US-69	1004+40	RT	SP-39	MAIN ST EXIT	132.00			40.0		8.4	KC-1	1.52	212		1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)			
78	US-69	1013+70	RT	E5-1a(14)	EXIT GORE SIGN	35.00					4.2	KC-0	0.72	130		1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)			
				E13-1(25)	ADVISORY SPEED TAB	14.00		45.0												
79	US-69	1021+90	LT	E5-1a(14)	EXIT GORE SIGN	35.00					4.2	KC-0	0.72	130		1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)			
				E13-1(35)	ADVISORY SPEED TAB	14.00		45.0												
80	US-69	1027+10	RT	SP-40	UNIVERSITY/BRYAN 1/4 MILE	187.00			41.0		12.0	KC-2	1.64	348		1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)			
81	US-69	1030+50	LT	SP-39	MAIN ST EXIT	132.00			40.0		8.4	KC-1	1.52	212		1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)			
82	US-69	1040+10	RT	SP-41	UNIVERSITY/BRYAN EXIT	227.00				45.0	12.0	KC-3	1.98	632		1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)			
83	SB OFF RAMP			SP-42	D1-2	91.00			36.0		7.8	KC-1	1.52	212			INSTALL NEW			
84	US-69	1043+00	LT	E5-1a(15)	EXIT GORE SIGN	35.00					4.2	KC-0	0.72	130		1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)			
				E13-1(25)	ADVISORY SPEED TAB	14.00		45.0												
85	US-69	1050+00	RT	E5-1a(15)	EXIT GORE SIGN	35.00					4.2	KC-0	0.72	130		1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)			
				E13-1(15)	ADVISORY SPEED TAB	14.00		45.0												
86	NB OFF RAMP			SP-43	D1-2	91.00			36.0		7.8	KC-1	1.52	212		1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)			
87	US-69	1055+00	LT	SP-44	UNIVERSITY/WESTSIDE EXIT	227.00				45.0	12.0	KC-3	1.98	632		1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)			
88	US-69	1072+00	LT	SP-36	MAIN ST 1 MILE	118.00			38.0		8.4	KC-1	1.52	212		1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)			
89	US-69	1072+10	RT	SP-45	WASHINGTON AVE 1/2 MILE	150.00			37.0		12.3	KC-1	1.52	212		1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)			
90	US-69	1079+00	LT	SP-46	UNIVERSITY/WESTSIDE 1/2 MILE	187.00			41.0		12.0	KC-2	1.64	348		1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)			
91	US-69	1093+70	RT	SP-47	WASHINGTON AVE NEXT RIGHT	150.00			37.0		12.3	KC-1	1.52	212		1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)			
92	US-69	1114+00	LT	E5-1a(16)	EXIT GORE SIGN	35.00					4.2	KC-0	0.72	130		1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)			
				E13-1(40)	ADVISORY SPEED TAB	14.00		45.0												
93	US-69	1122+40	RT	SP-48	WASHINGTON AVE EXIT	180.75			40.0		12.3	KC-2	1.64	348		1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)			
94	US-69	1136+50	LT	SP-45	WASHINGTON AVE 1/2 MILE	150.00			37.0		12.3	KC-1	1.52	212		1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)			
95	US-69	1142+50	RT	SP-49	SH-48/SH-78 EXIT 1/2 MILE	141.00			44.0		7.2	KC-1	1.52	212		1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)			
96	US-69	1161+60	RT	SP-50	SH-48/SH-78 EXIT	142.50			47.0		7.2	KC-1	1.52	212		1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)			
97	US-69	1169+80	RT	E5-1a(18)	EXIT GORE SIGN	35.00					4.2	KC-0	0.72	130		1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)			
				E13-1(40)	ADVISORY SPEED TAB	14.00		45.0												
98	NB OFF RAMP			SP-51	D1-1	33.25	28.0				5.7	KC-0	0.72	130		1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)			
99	SB OFF RAMP			SP-51	D1-1	33.25	28.0				5.7	KC-0	0.72	130		1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)			
100	SH-48/SH-78			SP-52	D1-2	63.25	32.0				6.9	KC-0	0.72	130		1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)			
<b>SUBTOTALS 'B'</b>						4,728.00	773.0	467.0	278.0	133.0			50.06	9,476	36					

\*QUANTITY IS APPROXIMATE AND FOR INFORMATION ONLY. REMOVE ALL EXISTING SIGNS THAT CONFLICT WITH NEW SIGN REPLACEMENTS. REUSE EXISTING POSTS IF REMOVED IN SUITABLE CONDITON AS APPROVED BY ENGINEER.



1000 WEST WILSHIRE BLVD.  
SUITE 403-E  
OKLAHOMA CITY, OK 73116  
PHONE: (405) 384-5127

US - 69 DIVISION 2      BRYAN COUNTY PITTSBURG COUNTY

**SUMMARY SHEET**  
(2 OF 6)