


REV. NO.	DESCRIPTION	REVISIONS	DATE

SUMMARY OF SIGNS - BRYAN COUNTY (CONTINUED)																			
PLAN ITEM NO.	ALIGNMENT	APPROX. STATION	SIDE	TYPE OF SIGN	DESCRIPTION	SIGNS		POSTS					FOOTINGS			REMOVAL OF SIGNS 805(A)*	REMARKS		
						EXTRUDED ALUMINUM PANEL SIGNS 850(B)	4" @ 13 GALV. STEEL WIDE FLANGE BEAM 851(A)	6" @ 15 GALV. STEEL WIDE FLANGE BEAM 851(A)	6" @ 25 GALV. STEEL WIDE FLANGE BEAM 851(A)	8" @ 31 GALV. STEEL WIDE FLANGE BEAM 851(A)	APPROX. POST SPACING	TYPE	STRUC. CONC. 804(A)	REIN. STEEL 804(B)	EA.				
						S.F.	L.F.	L.F.	L.F.	L.F.	FT.		C.Y.	LB.					
101	SH-48/SH-78			SP-53	NORTH US-69 MCALESTER	73.50	36.0					6.3	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)		
102	SH-48/SH-78			SP-05	SOUTH US-69 DALLAS	66.50	36.0					5.7	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)		
103	SH-48/SH-78			SP-54	D1-2	60.50	32.0					6.6	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)		
104	US-69	1202+70	RT	SP-55	URY DR EXIT 1/2 MILE	90.25		36.0				6.9	KC-1	1.52	212	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)		
105	US-69	1205+50	LT	SP-49	SH-48/SH-78 EXIT 1/2 MILE	141.00		44.0				7.2	KC-1	1.52	212	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)		
106	US-69	1163+00	LT	SP-56	DURANT EXITS	231.00				43.0		13.2	KC-3	1.98	632	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)		
107	US-69	1235+80	RT	SP-57	URY DR EXIT	102.00		40.0				6.0	KC-1	1.52	212	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)		
108	US-69	1241+10	RT	E5-1a(19)	EXIT GORE SIGN	35.00						4.2	KC-0	0.72	130	1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)		
				E13-1(40)	ADVISORY SPEED TAB	14.00	45.0												
109	NB OFF RAMP			SP-58	D1-1	72.50	32.0					8.7	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)		
110	SB OFF RAMP			SP-59	D1-1	72.50	32.0					8.7	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)		
111	US-69	1260+90	LT	E5-1a(19)	EXIT GORE SIGN	35.00						4.2	KC-0	0.72	130	1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)		
				E13-1(40)	ADVISORY SPEED TAB	14.00	45.0												
112	US-69	1262+90	LT	SP-57	URY DR EXIT	102.00		40.0				6.0	KC-1	1.52	212	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)		
113	US-69	1293+00	LT	SP-55	URY DR EXIT 1/2 MILE	90.25		36.0				6.9	KC-1	1.52	212	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)		
114	US-69	1300+00	RT	SP-60	BLUE RIVER	30.00	30.0					3.6	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)		
115	US-69	1305+90	LT	SP-60	BLUE RIVER	30.00	30.0					3.6	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)		
116	US-69	1311+00	RT	SP-61	D2-3	84.50	35.0					7.8	KC-0	0.72	130		INSTALL NEW		
117	US-69	1398+00	RT	SP-62	CR N3760 EXIT 1/2 MILE	111.00		39.0				7.2	KC-1	1.52	212		INSTALL NEW		
118	US-69	1422+20	RT	SP-63	CR N3760 EXIT	129.00		42.0				7.2	KC-1	1.52	212	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)		
119	US-69	1429+20	RT	E5-1a(23)	EXIT GORE SIGN	35.00						4.2	KC-0	0.72	130	1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)		
				E13-1(40)	ADVISORY SPEED TAB	14.00	45.0												
120	US-69	1459+90	LT	E5-1a(23)	EXIT GORE SIGN	35.00						4.2	KC-0	0.72	130	1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)		
				E13-1(40)	ADVISORY SPEED TAB	14.00	45.0												
121	US-69	1466+90	LT	SP-63	CR N3760 EXIT	129.00		42.0				7.2	KC-1	1.52	212	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)		
122	US-69	1492+00	LT	SP-62	CR N3760 EXIT 1/2 MILE	111.00		39.0				7.2	KC-1	1.52	212		INSTALL NEW		
123	US-69	1566+80	RT	SP-64	SH-22 EXIT 1 MILE	142.00		48.0				6.0	KC-1	1.52	212	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)		
124	US-69	1592+00	RT	SP-65	SH-22 EXIT 1/2 MILE	153.50			47.0			6.9	KC-2	1.64	348		INSTALL NEW		
125	US-69	1596+90	LT	SP-66	D2-3	78.00	35.0					7.8	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)		
126	US-69	1615+30	RT	SP-67	SH-22 EXIT	135.00		50.0				5.4	KC-1	1.52	212	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)		
127	US-69	1625+60	RT	E5-1a(27)	EXIT GORE SIGN	35.00						4.2	KC-0	0.72	130	1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)		
				E13-1(40)	ADVISORY SPEED TAB	14.00	45.0												
128	US-69	1634+00	RT	SP-68	CADDO LIMITS	36.00	30.0					5.4	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)		
129	NB OFF RAMP			SP-69	D1-2	52.25	32.0					5.7	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)		
130	SB OFF RAMP			SP-70	D1-2	52.25	32.0					5.7	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)		
131	US-69	1657+80	LT	E5-1a(27)	EXIT GORE SIGN	35.00						4.2	KC-0	0.72	130	1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)		
				E13-1(40)	ADVISORY SPEED TAB	14.00	45.0												
132	US-69	1665+10	LT	SP-67	SH-22 EXIT	135.00		50.0				5.4	KC-1	1.52	212	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)		
133	US-69	1682+00	LT	SP-68	CADDO LIMITS	36.00	30.0					5.4	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)		
134	US-69	1689+50	LT	SP-65	SH-22 EXIT 1/2 MILE	153.50			47.0			6.9	KC-2	1.64	348		INSTALL NEW		
135	US-69	1713+70	LT	SP-64	SH-22 EXIT 1 MILE	142.00		48.0				6.0	KC-1	1.52	212	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)		
136	US-69	1730+60	RT	SP-71	D2-3	84.50	35.0					7.8	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)		
137	US-69	1738+00	LT	DHW	DON'T HIT OUR WORKERS			36.0				7.8	KC-1	1.52	212		INSTALL NEW (SIGN TO BE PROVIDED BY ODOT DIVISION 2)		
138	US-69	1743+90	LT	SP-02	BRYAN COUNTY	37.50	32.0					4.5	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)		
139	US-69	1744+10	RT	SP-72	ATOKA COUNTY	37.50	32.0					4.5	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)		
140	US-69	1752+10	RT	DHW	DON'T HIT OUR WORKERS			36.0				7.8	KC-1	1.52	212		INSTALL NEW (SIGN TO BE PROVIDED BY ODOT DIVISION 2)		
<b>SUBTOTALS 'C'</b>						3,296.00	791.0	626.0	94.0	43.0				43.90	7,368	33			
<b>TOTALS</b>						13,334	2,605	1,361	650	568				152.08	29,460	112			

\*QUANTITY IS APPROXIMATE AND FOR INFORMATION ONLY. REMOVE ALL EXISTING SIGNS THAT CONFLICT WITH NEW SIGN REPLACEMENTS. REUSE EXISTING POSTS IF REMOVED IN SUITABLE CONDTION AS APPROVED BY ENGINEER.



1000 WEST WILSHIRE BLVD.  
SUITE 403-E  
OKLAHOMA CITY, OK 73116  
PHONE: (405) 384-5127

US - 69 DIVISION 2      BRYAN COUNTY PITTSBURG COUNTY

**SUMMARY SHEET**  
(3 OF 6)

State Job No. 33252(04)      Sheet No.   5   OF 123