

REV. NO.	DESCRIPTION	REVISIONS	DATE

SUMMARY OF SIGNS - PITTSBURG COUNTY																				
PLAN ITEM NO.	ALIGNMENT	APPROX. STATION	SIDE	TYPE OF SIGN	DESCRIPTION	SIGNS			POSTS				FOOTINGS			REMOVAL OF SIGNS 805(A)*	REMARKS			
						EXTRUDED ALUMINUM PANEL SIGNS 850(B)	EXTRUDED ALUMINUM PANEL SIGNS (OVERHEAD SIGNS) 850(B)	ALUMINUM OVHD. SIGN STRS. - BRIDGE MOUNTED 852(F)	4" @ 13 GALV. STEEL WIDE FLANGE BEAM 851(A)	6" @ 15 GALV. STEEL WIDE FLANGE BEAM 851(A)	6" @ 25 GALV. STEEL WIDE FLANGE BEAM 851(A)	8" @ 31 GALV. STEEL WIDE FLANGE BEAM 851(A)	APPROX. POST SPACING	TYPE	STRUC. CONC. 804(A)			REIN. STEEL 804(B)	EA.	
						S.F.	S.F.	EA.	L.F.	L.F.	L.F.	L.F.	FT.		C.Y.			LB.	EA.	
1	US-69	-21+20	LT	DHW	DON'T HIT OUR WORKERS					36.0				7.8	KC-1	1.52	212		INSTALL NEW (SIGN TO BE PROVIDED BY ODOT DIVISION 2)	
2	US-69	-3+20	LT	SP-01	ATOKA COUNTY	37.50			32.0					5.4	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
3	US-69	3+40	RT	SP-02	PITTSBURG COUNTY	45.00			32.0						KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
4	US-69	24+60	RT	DHW	DON'T HIT OUR WORKERS					36.0				7.8	KC-1	1.52	212		INSTALL NEW (SIGN TO BE PROVIDED BY ODOT DIVISION 2)	
5	US-69	139+50	LT	SP-03	D2-3	81.25			35.0					7.5	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
6	US-69	150+50	RT	SP-04	KIOWA LIMITS	36.00			30.0					5.4	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
7	US-69	224+00	LT	SP-04	KIOWA LIMITS	36.00			30.0					5.4	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
8	US-69	249+00	RT	SP-05	D2-3	84.50			35.0					7.8	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
9	US-69	297+50	RT	SP-06	D1-1	36.75			29.0					6.3	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
10	US-69	305+20	LT	SP-07	D1-1	36.75			29.0					6.3	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
11	US-69	556+00	LT	SP-08	D2-3	78.00			35.0					7.2	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
12	US-69	559+10	RT	SP-09	SAVANNA LIMITS	40.00			30.0					6.0	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
13	US-69	627+60	RT	SP-10	US ARMY EXIT 1/2 MILE	163.50					39.0			11.7	KC-2	1.64	348	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
14	US-69	650+40	RT	SP-11	US ARMY EXIT		209.00	1										1	INSTALL NEW (BRIDGE MOUNTED)(REMOVE EXISTING SIGN)	
15	C TREE RD		RT	SP-12	US-69 NORTH/SOUTH EXIT	199.50						41.0		12.6	KC-3	1.98	632	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
16	C TREE RD		RT	SP-13	US-69 NORTH EXIT	105.00					37.0			8.4	KC-1	1.52	212	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
17	US-69	654+30	RT	E5-1a(82) E13-1(25)	EXIT GORE SIGN ADVISORY SPEED TAB	35.00 14.00			45.0					4.2	KC-0	0.72	130	1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)	
18	US-69	655+00	LT	SP-14	AMMO PLANT RIGHT	55.00			32.0					6.6	KC-1	1.52	212	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
19	US-69	658+80	LT	E5-1a(82) E13-1(25)	EXIT GORE SIGN ADVISORY SPEED TAB	35.00 14.00			45.0					4.2	KC-0	0.72	130	1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)	
20	US-69	662+70	RT	SP-15	D2-3	84.50			35.0					7.8	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
21	US-69	663+20	LT	SP-16	US ARMY EXIT	202.50						43.0		11.7	KC-3	1.98	632	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
22	US-69	699+50	RT	SP-17	INDIAN NATION 1 MILE	216.00						54.0		8.1	KC-3	1.98	632	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
23	US-69	739+50	LT	SP-18	D2-3	78.00			35.0					7.2	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
24	US-69	753+30	LT	SP-09	SAVANNA LIMITS	40.00			30.0					6.0	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
25	US-69	755+10	RT	SP-20	INDIAN NATION SOUTH EXIT	225.00					47.0			10.8	KC-3	1.98	632	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
26	US-69	762+60	RT	E5-1 E13-1(30)	EXIT GORE SIGN ADVISORY SPEED TAB	30.00 12.00			45.0					3.6	KC-0	0.72	130	1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)	
27	US-69	763+70	LT	SP-21	INDIAN NATION SOUTH LEFT	237.50						47.0		11.4	KC-3	1.98	632	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
28	US-69	768+40	RT	SP-22	INDIAN NATION NORTH EXIT	256.25						47.0		12.3	KC-3	1.98	632	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
29	US-69	774+30	LT	E5-1 E13-1(25)	EXIT GORE SIGN ADVISORY SPEED TAB	30.00 12.00			45.0					3.6	KC-0	0.72	130	1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)	
30	US-69	776+30	LT	SP-23	INDIAN NATION SOUTH ADV	195.75						49.0		8.7	KC-3	1.98	632	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
31	US-69	779+60	LT	E5-1 E13-1(30)	EXIT GORE SIGN ADVISORY SPEED TAB	30.00 12.00			45.0					3.6	KC-0	0.72	130	1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)	
32	US-69	785+40	LT	SP-22	INDIAN NATION NORTH EXIT	256.25					47.0			12.3	KC-3	1.98	632	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
33	US-69	807+00	RT	SP-24	D2-3	81.25			35.0					7.5	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
34	US-69	846+60	LT	SP-17	INDIAN NATION 1 MILE	216.00						54.0		8.1	KC-3	1.98	632	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
35	US-69	872+40	RT	SP-26	MCALESTER LIMITS	46.00			30.0					6.9	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
36	US-69	875+00	LT	SP-27	D2-3	78.00			35.0					7.2	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
37	US-69	890+40	RT	SP-28 SP-29	US-69 BUSINESS LEFT LANE US-69 NORTH RIGHT LANE		169.50 123.50											1 1	INSTALL NEW ON EXISTING OVERHEAD SIGN STRUCTURE (REMOVE EXISTING SIGNS)	
38	US-69	901+30	RT	SP-30	US-69 BUSINESS/NORTH		384.50											2	INSTALL NEW ON EXISTING OVERHEAD SIGN STRUCTURE (REMOVE EXISTING SIGNS)	
39	US-69	908+50	RT	E5-1a(88)	EXIT GORE SIGN (LEFT EXIT)	30.00												1	INSTALL NEW EXIT SIGN IN GORE (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)	
40	US-69	1107+70	RT	E5-1a(91A) E13-1(20)	EXIT GORE SIGN ADVISORY SPEED TAB	42.50 17.00			45.0					5.1	KC-0	0.72	130	1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)	
41	US-69	1109+80	LT	E5-1a(91A) E13-1(20)	EXIT GORE SIGN ADVISORY SPEED TAB	42.50 17.00			45.0					5.1	KC-0	0.72	130	1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)	
42	US-69	1113+40	RT	SP-31	US-270 WEST EXIT		227.25	1										1	INSTALL NEW (BRIDGE MOUNTED)(REMOVE EXISTING SIGN)	
43	US-69	1114+30	LT	SP-32	US-270 EAST EXIT		247.50	1										1	INSTALL NEW (BRIDGE MOUNTED)(REMOVE EXISTING SIGN)	
44	US-69	1117+80	RT	E5-1a(91B) E13-1(20)	EXIT GORE SIGN ADVISORY SPEED TAB	42.50 17.00			45.0					5.1	KC-0	0.72	130	1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)	
45	US-69	1120+40	LT	E5-1a(91B) E13-1(20)	EXIT GORE SIGN ADVISORY SPEED TAB	42.50 17.00			45.0					5.1	KC-0	0.72	130	1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)	
46	US-69	1124+80	LT	SP-31 SP-33	US-270 WEST EXIT US-270 EAST 1/4 MILE		227.25 265.50												1 1	INSTALL NEW ON EXISTING OVERHEAD SIGN STRUCTURE (REMOVE EXISTING SIGNS)
47	US-270		RT	SP-19	US-69 1/2 MILE	156.00					46.0			7.8	KC-2	1.64	348	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
48	US-270		RT	SP-35	US-69 SOUTH EXIT	168.75					49.0			7.5	KC-2	1.64	348	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
49	US-270		RT	E5-1 E13-1(20)	EXIT GORE SIGN ADVISORY SPEED TAB	30.00 12.00			45.0					3.6	KC-0	0.72	130	1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)	
50	US-270		RT	SP-36	US-69 NORTH EXIT	149.50					45.0			7.8	KC-2	1.64	348	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
SUBTOTALS 'A'						4,256.00	1,854.00	3	999.0	109.0	179.0	429.0			49.18	11,308	49			

*QUANTITY IS APPROXIMATE AND FOR INFORMATION ONLY. REMOVE ALL EXISTING SIGNS THAT CONFLICT WITH NEW SIGN REPLACEMENTS. REUSE EXISTING POSTS IF REMOVED IN SUITABLE CONDITION AS APPROVED BY ENGINEER.



US - 69 DIVISION 2 BRYAN COUNTY PITTSBURG COUNTY

SUMMARY SHEET (4 OF 6)