

REV. NO.	DESCRIPTION	REVISIONS	DATE

SUMMARY OF SIGNS - PITTSBURG COUNTY (CONTINUED)

PLAN ITEM NO.	ALIGNMENT	APPROX. STATION	SIDE	TYPE OF SIGN	DESCRIPTION	SIGNS			POSTS				FOOTINGS			REMOVAL OF SIGNS 805(A)*	REMARKS		
						EXTRUDED ALUMINUM PANEL SIGNS 850(B)	EXTRUDED ALUMINUM PANEL SIGNS (OVERHEAD SIGNS) 850(B)	ALUMINUM OVHD. SIGN STRS. - BRIDGE MOUNTED 852(F)	4" @ 13 GALV. STEEL WIDE FLANGE BEAM 851(A)	6" @ 15 GALV. STEEL WIDE FLANGE BEAM 851(A)	6" @ 25 GALV. STEEL WIDE FLANGE BEAM 851(A)	8" @ 31 GALV. STEEL WIDE FLANGE BEAM 851(A)	APPROX. POST SPACING	TYPE	STRUC. CONC. 804(A)			REIN. STEEL 804(B)	EA.
						S.F.	S.F.	EA.	L.F.	L.F.	L.F.	L.F.	FT.		C.Y.			LB.	EA.
51	US-270		LT	E5-1 E13-1(20)	EXIT GORE SIGN ADVISORY SPEED TAB	30.00 12.00			45.0				3.6	KC-0	0.72	130	1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)	
52	US-270		RT	E5-1 E13-1(20)	EXIT GORE SIGN ADVISORY SPEED TAB	30.00 12.00			45.0				3.6	KC-0	0.72	130	1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)	
53	US-270		LT	SP-35	US-69 SOUTH EXIT	168.75					49.0		7.5	KC-2	1.64	348	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
54	US-270		LT	E5-1 E13-1(20)	EXIT GORE SIGN ADVISORY SPEED TAB	30.00 12.00			45.0				3.6	KC-0	0.72	130	1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)	
55	US-270		LT	SP-36	US-69 NORTH EXIT	149.50					45.0		7.8	KC-2	1.64	348	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
56	US-270		RT	SP-37	SH-31 EXIT ONLY		170.20										1	INSTALL NEW ON EXISTING OVERHEAD SIGN STRUCTURE (REMOVE EXISTING SIGN)	
57	US-270		LT	SP-34	US-69 1/4 MILE	156.00					46.0		7.8	KC-2	1.64	348	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
58	US-69	1129+00	RT	SP-38	ELECTRIC AVE 1/2 MILE	126.00				37.0				KC-1	1.52	212	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
59	US-69	1144+00	LT	SP-39	US-270 1/2 MILE	243.50						54.0	9.3	KC-3	1.98	632	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
60	US-69	1144+70	RT	SP-40	ELECTRIC AVE EXIT	150.75					40.0		9.9	KC-2	1.64	348	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
61	US-69	1153+80	RT	E5-1a(92) E13-1(40)	EXIT GORE SIGN ADVISORY SPEED TAB	35.00 14.00			45.0				4.2	KC-0	0.72	130	1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)	
62	US-69	1163+50	LT	SP-41	GEORGE NIGH EXPWY		112.00	1										INSTALL NEW (BRIDGE MOUNTED)(REMOVE EXISTING SIGN)	
63	US-69	1173+70	LT	E5-1a(92) E13-1(40)	EXIT GORE SIGN ADVISORY SPEED TAB	35.00 14.00			45.0				4.2	KC-0	0.72	130	1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)	
64	US-69	1182+00	LT	SP-40	ELECTRIC AVE EXIT	150.75					40.0		9.9	KC-2	1.64	348	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
65	US-69	1192+00	RT	SP-42	HEREFORD LN 1/2 MILE	112.25				36.0			9.3	KC-2	1.64	348	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
66	US-69	1204+10	LT	SP-38	ELECTRIC AVE 1/2 MILE	126.00				37.0				KC-1	1.52	212	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
67	US-69	1217+00	RT	SP-43	HEREFORD LN EXIT	143.25				40.0			9.3	KC-1	1.52	212	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
68	US-69	1224+70	RT	E5-1a(93) E13-1(30)	EXIT GORE SIGN ADVISORY SPEED TAB	35.00 14.00			45.0				4.2	KC-0	0.72	130	1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)	
69	US-69	1238+80	LT	E5-1a(93) E13-1(40)	EXIT GORE SIGN ADVISORY SPEED TAB	35.00 14.00			45.0				4.2	KC-0	0.72	130	1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)	
70	US-69	1245+20	LT	SP-43	HEREFORD LN EXIT	143.25				40.0			9.3	KC-1	1.52	212	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
71	US-69	1270+40	LT	SP-42	HEREFORD LN 1/2 MILE	112.25				36.0			9.3	KC-1	1.52	212	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
72	US-69	1314+90	RT	SP-44	SH-113/SH-69B 1 MILE	244.50					55.0		8.7	KC-3	1.98	632	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
73	US-69	1346+60	RT	SP-45	SH-113/SH-69B 1/2 MILE	230.00					53.0		8.7	KC-3	1.98	632	1	INSTALL NEW	
74	US-69	1363+70	LT	SP-46	D2-3	78.00			35.0				7.2	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
75	US-69	1371+40	RT	SP-47	SH-113/SH-69B EXIT	259.00					59.0		8.7	KC-3	1.98	632	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
76	US-69	1378+30	RT	E5-1a(96) E13-1(30)	EXIT GORE SIGN ADVISORY SPEED TAB	35.00 14.00			45.0				4.2	KC-0	0.72	130	1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)	
77	US-69	1401+90	LT	E5-1a(96) E13-1(30)	EXIT GORE SIGN ADVISORY SPEED TAB	35.00 14.00			45.0				4.2	KC-0	0.72	130	1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)	
78	US-69	1413+00	LT	SP-47	SH-113/SH-69B EXIT	259.00					59.0		8.7	KC-3	1.98	632	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
79	US-69	1428+00	LT	SP-45	SH-113/SH-69B 1/2 MILE	230.00					53.0		8.7	KC-3	1.98	632	1	INSTALL NEW	
80	US-69	1428+70	RT	SP-48	D2-3	84.50			35.0				7.8	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
81	US-69	1453+00	RT	SP-49	LAKE EUFAULA	37.50			32.0				4.5	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
82	US-69	1454+00	LT	SP-44	SH-113/SH-69B 1 MILE	244.50					55.0		8.7	KC-3	1.98	632	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
83	US-69	1565+00	RT	SP-50	SHADY GROVE 1/2 MILE	131.00				39.0			8.4	KC-1	1.52	212	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
84	US-69	1588+00	RT	SP-51	SHADY GROVE EXIT	159.00					43.0		8.4	KC-2	1.64	348	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
85	US-69	1596+30	RT	E5-1a(100) E13-1(40)	EXIT GORE SIGN ADVISORY SPEED TAB	42.50 17.00			45.0				5.1	KC-0	0.72	130	1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)	
86	US-69	1616+40	LT	E5-1a(100) E13-1(40)	EXIT GORE SIGN ADVISORY SPEED TAB	42.50 17.00			45.0				5.1	KC-0	0.72	130	1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)	
87	US-69	1627+00	LT	SP-51	SHADY GROVE EXIT	159.00					43.0		8.4	KC-2	1.64	348	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
88	US-69	1655+00	LT	SP-50	SHADY GROVE 1/2 MILE	131.00				39.0			8.4	KC-1	1.52	212	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
89	US-69	1731+00	RT	SP-52	ROCK CREEK RD 1/2 MILE	120.50				42.0			7.5	KC-1	1.52	212	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
90	US-69	1753+80	RT	SP-53	ROCK CREEK RD EXIT	145.50				46.0			7.5	KC-1	1.52	212	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
91	US-69	1755+70	RT	E5-1a(103) E13-1(40)	EXIT GORE SIGN ADVISORY SPEED TAB	42.50 17.00			45.0				5.1	KC-0	0.72	130	1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)	
92	US-69	1776+90	LT	E5-1a(103) E13-1(40)	EXIT GORE SIGN ADVISORY SPEED TAB	42.50 17.00			45.0				5.1	KC-0	0.72	130	1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)	
93	US-69	1789+80	LT	SP-53	ROCK CREEK RD EXIT	145.50				46.0			7.5	KC-1	1.52	212	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
94	US-69	1805+00	LT	SP-52	ROCK CREEK RD 1/2 MILE	120.50				42.0			7.5	KC-1	1.52	212	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
95	US-69	1831+70	RT	SP-54	NALE RD 1 MILE	115.50				43.0			6.6	KC-1	1.52	212	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
96	US-69	1854+80	LT	SP-55	D2-3	84.50			35.0				7.8	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
97	US-69	1859+00	RT	SP-56	NALE ROAD 1/2 MILE	110.00				42.0			6.6	KC-1	1.52	212	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
98	US-69	1885+30	RT	SP-57	NALE ROAD EXIT	132.00				46.0			6.6	KC-1	1.52	212	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
99	US-69	1886+60	RT	E5-1a(106) E13-1(40)	EXIT GORE SIGN ADVISORY SPEED TAB	42.50 17.00			45.0				5.1	KC-0	0.72	130	1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVSIORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)	
100	NALE RD		RT	SP-58	D1-1	30.00			28.0				6.0	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
SUBTOTALS 'B'						5,751.00	283.00	1	795.0	611.0	306.0	388.0				61.94	12,646	47	



US - 69 DIVISION 2 BRYAN COUNTY PITTSBURG COUNTY

SUMMARY SHEET
(5 OF 6)

*QUANTITY IS APPROXIMATE AND FOR INFORMATION ONLY. REMOVE ALL EXISTING SIGNS THAT CONFLICT WITH NEW SIGN REPLACEMENTS. REUSE EXISTING POSTS IF REMOVED IN SUITABLE CONDITON AS APPROVED BY ENGINEER.