


REV. NO.	DESCRIPTION	REVISIONS	DATE

SUMMARY OF SIGNS - PITTSBURG COUNTY (CONTINUED)

PLAN ITEM NO.	ALIGNMENT	APPROX. STATION	SIDE	TYPE OF SIGN	DESCRIPTION	SIGNS			POSTS				FOOTINGS			REMOVAL OF SIGNS 805(A)*	REMARKS		
						EXTRUDED ALUMINUM PANEL SIGNS 850(B)	EXTRUDED ALUMINUM PANEL SIGNS (OVERHEAD SIGNS) 850(B)	ALUMINUM OVHD. SIGN STRS. - BRIDGE MOUNTED 852(F)	4" @ 13 GALV. STEEL WIDE FLANGE BEAM 851(A)	6" @ 15 GALV. STEEL WIDE FLANGE BEAM 851(A)	6" @ 25 GALV. STEEL WIDE FLANGE BEAM 851(A)	8" @ 31 GALV. STEEL WIDE FLANGE BEAM 851(A)	APPROX. POST SPACING	TYPE	STRUC. CONC. 804(A)			REIN. STEEL 804(B)	EA.
						S.F.	S.F.	EA.	L.F.	L.F.	L.F.	L.F.	FT.		C.Y.			LB.	
101	NALE RD		LT	SP-59	D1-1	30.00			28.0				6.0	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
102	US-69	1905+00	RT	SP-60	D2-3	81.25			35.0				7.5	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
103	US-69	1917+40	LT	E5-1a(106)	EXIT GORE SIGN	42.50			45.0				5.1	KC-0	0.72	130	1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVISORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)	
				E13-1(30)	ADVISORY SPEED TAB	17.00													
104	US-69	1922+20	LT	SP-57	NALE ROAD EXIT	132.00				46.0			6.6	KC-1	1.52	212	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
105	US-69	1946+00	LT	SP-56	NALE ROAD 1/2 MILE	110.00				42.0			6.6	KC-1	1.52	212	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
106	US-69	1967+00	LT	SP-54	NALE ROAD 1 MILE	115.50				43.0			6.6	KC-1	1.52	212	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
107	US-69	1991+40	RT	SP-61	SH-113 SOUTH 1 MILE	195.50						53.0	7.8	KC-3	1.98	632	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
108	US-69	2019+00	RT	SP-62	SH-113 SOUTH 1/2 MILE	189.00						51.0	7.8	KC-3	1.98	632	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
109	US-69	2025+20	LT	SP-63	D2-3	84.50			35.0				7.8	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
110	US-69	2029+00	RT	SP-64	ARROWHEAD STATE PARK	211.50						45.0	10.2	KC-3	1.98	632	1	INSTALL NEW	
111	US-69	2045+30	RT	SP-65	SH-113 SOUTH EXIT	215.00						56.0	7.8	KC-3	1.98	632	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
112	US-69	2053+80	RT	E5-1a(109)	EXIT GORE SIGN	42.50			45.0				5.1	KC-0	0.72	130	1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVISORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)	
				E13-1(40)	ADVISORY SPEED TAB	17.00													
113	SH-113			SP-66	D1-2	117.00				40.0				KC-1	1.52	212		INSTALL NEW	
114	SH-113			SP-67	D1-2	117.00				40.0				KC-1	1.52	212		INSTALL NEW	
115	US-69	2077+70	LT	E5-1a(109)	EXIT GORE SIGN	42.50			45.0				5.1	KC-0	0.72	130	1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVISORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)	
				E13-1(40)	ADVISORY SPEED TAB	17.00													
116	US-69	2085+50	LT	SP-65	SH-113 SOUTH EXIT	215.00					56.0	7.8	KC-3	1.98	632	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)		
117	US-69	2101+50	LT	SP-64	ARROWHEAD STATE PARK	211.50					45.0	10.2	KC-3	1.98	632		INSTALL NEW		
118	US-69	2107+40	RT	SP-68	D2-3	81.25			35.0				7.5	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
119	US-69	2111+00	LT	SP-62	SH-113 SOUTH 1/2 MILE	189.00						51.0	7.8	KC-3	1.98	632	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
120	US-69	2131+20	LT	SP-61	SH-113 SOUTH 1 MILE	195.50						53.0	7.8	KC-3	1.98	632	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
121	US-69	2197+20	RT		SH-9A 1 MILE							50.0	10.2	KC-3	1.98	632	1	INSTALL NEW (SIGN TO BE PROVIDED BY ODOT DIVISION 2)(REMOVE EXISTING)	
122	US-69	2212+00	LT	SP-69	D2-3	91.00			35.0				7.8	KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
123	US-69	2221+00	RT	SP-70	SH-9A 1/2 MILE	221.00						48.0	10.2	KC-3	1.98	632		INSTALL NEW	
124	US-69	2244+00	RT		SH-9A EXIT							52.0	10.2	KC-3	1.98	632	1	INSTALL NEW (SIGN TO BE PROVIDED BY ODOT DIVISION 2)(REMOVE EXISTING)	
125	US-69	2254+80	RT	E5-1a(113)	EXIT GORE SIGN	42.50			45.0				5.1	KC-0	0.72	130	1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVISORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)	
				E13-1(40)	ADVISORY SPEED TAB	17.00													
126	US-69	2255+40	LT	E5-1a(113)	EXIT GORE SIGN	42.50			45.0				5.1	KC-0	0.72	130	1	INSTALL NEW EXIT SIGN IN GORE WITH YELLOW ADVISORY SPEED TAB (REMOVE EXISTING SIGNS, POSTS, & FOOTINGS)	
				E13-1(40)	ADVISORY SPEED TAB	17.00													
127	US-69	2271+70	LT		SH-9A EXIT						52.0	10.2	KC-3	1.98	632	1	INSTALL NEW (SIGN TO BE PROVIDED BY ODOT DIVISION 2)(REMOVE EXISTING)		
128	US-69	2286+50	LT	SP-70	SH-9A 1/2 MILE	221.00					48.0	10.2	KC-3	1.98	632		INSTALL NEW		
129	US-69	2288+80	RT	SP-71	MCINTOSH COUNTY	42.50			32.0					KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
130	US-69	2289+40	LT	SP-02	PITTSBURG COUNTY	45.00			32.0					KC-0	0.72	130	1	INSTALL NEW (REMOVE EXISTING SIGNS, POSTS & FOOTINGS)	
131	US-69	2310+10	LT		SH-9A 1 MILE							50.0	10.2	KC-3	1.98	632	1	INSTALL NEW (SIGN TO BE PROVIDED BY ODOT DIVISION 2)(REMOVE EXISTING)	
SUBTOTALS 'C'						3,409.00	0.00	0	457.0	211.0	0.0	710.0				44.00	11,468	25	
TOTALS						13,416	2,137	4	2,251	931	485	1,527				155.12	35,422	121	

*QUANTITY IS APPROXIMATE AND FOR INFORMATION ONLY. REMOVE ALL EXISTING SIGNS THAT CONFLICT WITH NEW SIGN REPLACEMENTS. REUSE EXISTING POSTS IF REMOVED IN SUITABLE CONDITION AS APPROVED BY ENGINEER.



1000 WEST WILSHIRE BLVD.
SUITE 403-E
OKLAHOMA CITY, OK 73116
PHONE: (405) 384-5127

US - 69 DIVISION 2

BRYAN COUNTY
PITTSBURG COUNTY

SUMMARY SHEET
(6 OF 6)

State Job No. 33252(04) Sheet No. 8 OF 123