FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
	OKLA.	26879(04)		10	22

FACILITY

39+00 40+00 41+00 42+00 43+00 44+00 45+00

MATCHLINE 38+99.34

MATCHLINE

RESIDENTIAL DR.

FL N=1178.76

CONTRACTOR TO REPLACE 44 LF OF 6" CURB AND GUTTER, 74 SQ-YDS OF CONCRETE DRIVE PER ODOT STANDARD

NOTE:
CONTRACTOR TO BE CAREFUL NOT TO DISTURB EXISTING MSE WALL STRAPS DURING CONSTRUCTION. ANY DAMAGE TO EXISTING WALL OR STRAPS WILL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO REPAIR.

PROTECT EXISTING TUG LINE IN PLACE

LIMIT OF CONSTRUCTION

EXISTING R/W

EXISTING R/W

Tug Sign

Tug Sign

10' WIDE CONCRETE TRAIL

ARMORED SWALE

RAIL

REMOVE EXISTING INLET

CONCRETE DRIVE

556 LF BLOCK RETAINING WALL

10' WIDE CONCRETE TRAIL WITH WALL

STATE HIGHWAY 9

STATE HWY 9

PI: 40+30.78

PI: 40+44.91

PI: 40+60.79

PI: 41+96.66

PI: 43+86.4

PI: 43+96.02

PC: 44+29.46
PI: 44+33.52
PT: 44+36.17

PC: 43+60.00
PI: 43+62.70
PT: 43+65.39

S89° 36' 32.75"E
35.86

N89° 59' 02.37"E
15.88

N89° 39' 59.45"E
14.13

N90° 00' 00.00"E
10.00

S89° 14' 04.76"E
253.34

S87° 55' 27.37"E
31.14

S85° 14' 57.24"E
9.61

L=5.27, R=230

L=8.71, R=70

S82° 53' 38.45"E
33.44

SCALE 1" = 20 FEET

SOUTH EDGE OF SIDEWALK
Horizontal Scale: 1" = 20'
Vertical Scale: 1" = 4'
Vertical Exaggeration: x 5

STA = 39+13.05 ELEV = 1176.07
STA = 39+98.34 ELEV = 1171.89
STA = 40+20.91 ELEV = 1171.47
STA = 40+41.05 ELEV = 1171.47
STA = 40+49.56 ELEV = 1171.05
STA = 40+72.43 ELEV = 1171.07
STA = 41+38.07 ELEV = 1169.21
STA = 41+61.30 ELEV = 1168.26
STA = 41+93.13 ELEV = 1167.62
STA = 42+25.00 ELEV = 1166.67
STA = 42+38.92 ELEV = 1166.18
STA = 43+38.68 ELEV = 1163.58
STA = 44+37.98 ELEV = 1158.71
STA = 44+76.87 ELEV = 1157.46

-0.93% -4.90% -1.87% -0.01% -4.97% -0.09% -2.82% -4.10% -2.01% -2.99% -3.52% -2.60% -4.00% -3.22%

EXISTING TUG EXACT DEPTH UNKNOWN

EXISTING WTR EXACT DEPTH UNKNOWN

PROPOSED GRADE AT SOUTH EDGE OF WALK

EXISTING GRADE AT SOUTH EDGE OF WALK

STA 43+87.40
TOP OF WALL
ELEV 1162.78

PROPOSED CONCRETE RETAINING WALL

1180 1170 1160 1150

1175.5 1176.19 | 1175.2 1174.26 | 1174.2 1171.86 | 1170.9 1171.05 | 1170.3 1170.29 | 1168.9 1168.72 | 1167.7 1167.41 | 1166.1 1165.89 | 1164.9 1164.59 | 1163.6 1163.03 | 1161.8 1160.58 | 1161.2 1158.32 | 1160.0 1156.80

39+00 40+00 41+00 42+00 43+00 44+00

State Job No. 26879(04) Sheet No. 10