

SUMMARY OF DRIVEWAYS											
P&P SHEET	STATION	OFF.	DRIVE LENGTH (FT)	DRIVE WIDTH (FT)	RADIUS (FT)	S3 ASPHALT (PG 64-22 OK) (TON)	S5 ASPHALT (PG 70-28 OK) (TON)	TACK COAT (GAL)	PRIME COAT (GAL)	TBSC TYPE E (TONS)	6" PC CONCRETE DRIVE (SY)
4	27+66.25	LT	56.0	37.0	30.0	0.0	0.0	0.0	0.0	63.9	203.0
5	36+15.46	LT	30.8	26.0	30.0	0.0	0.0	0.0	0.0	41.6	132.0
6	40+39.76	LT	30.4	12.0	25.0	0.0	0.0	0.0	0.0	23.3	74.0
9	63+12.86	LT	30.0	62.0	50.0	0.0	0.0	0.0	0.0	81.3	258.0
TOTALS						0.0	0.0	0.0	0.0	210.1	667.0

SUMMARY OF REMOVALS						
P&P SHEET	STATION TO STATION		REMOVAL OF CONCRETE PAVEMENT (SY)	REMOVAL OF ASPHALT PAVEMENT (SY)	SAWING PAVEMENT (LF)	REMOVAL OF CURB & GUTTER (LF)
4	27+00.00	- 33+00.00	233.9	0.0	95.9	75.0
5	33+00.00	- 39+00.00	437.0	0.0	107.0	69.0
6	39+00.00	- 45+00.00	74.0	0.0	70.1	44.0
9	57+00.00	- 63+00.00	299.1	0.0	157.0	70.0
TOTALS			1044.0	0.0	430.0	258.0

SUMMARY OF EARTHWORK						
STATION TO STATION			TOTAL CUT VOLUME (C.Y.)	TOTAL FILL VOLUME +15% (C.Y.)	EXTRA CUT (C.Y.)	EXTRA FILL (C.Y.)
10+00.00	TO	15+00.00	94.9	469.3	0.0	374.4
15+00.00	TO	21+00.00	53.2	599.0	0.0	545.8
21+00.00	TO	27+00.00	279.8	25.6	254.2	0.0
27+00.00	TO	33+00.00	522.4	21.6	500.8	0.0
33+00.00	TO	39+00.00	1031.8	84.0	947.9	0.0
39+00.00	TO	45+00.00	392.6	31.3	361.3	0.0
45+00.00	TO	51+00.00	613.5	9.0	604.5	0.0
51+00.00	TO	57+00.00	157.4	136.9	20.6	0.0
57+00.00	TO	63+00.00	48.7	640.4	0.0	591.7
63+00.00	TO	64+08.59	0.2	16.0	0.0	15.8
TOTAL			3194.5	2033.0	2689.3	1527.7

SUMMARY OF SIDEWALK				
STATION TO STATION			SIDEWALK (5') (L.F.)	SIDEWALK (10') (L.F.)
10+00.00	TO	14+19.89	80.0	419.9
14+19.89	TO	20+95.15		675.3
20+95.15	TO	27+15.02		619.9
27+15.02	TO	32+95.36		464.8
32+95.36	TO	38+03.30		447.1
38+03.30	TO	44+38.97		622.0
44+38.97	TO	50+56.92		618.0
50+56.92	TO	55+27.31		470.4
55+27.31	TO	62+55.95		728.6
62+55.95	TO	63+72.67		5.2
TOTAL				5071.1

SUMMARY OF EROSION CONTROL						
P&P SHEET	STATION TO STATION		SLAB SOD (SY)	TEMP. SILT FENCE (LF)	TEMP. SILT DIKE (LF)	TEMP. INLET SEDIMENT FILTER (EACH)
1	10+00.00	- 15+00.00	986.0	435.1	0.0	0.0
2	015+00.00	- 21+00.00	1113.5	584.3	0.0	0.0
3	021+00.00	- 27+00.00	509.5	685.0	0.0	1.0
4	027+00.00	- 33+00.00	591.6	474.7	0.0	0.0
5	033+00.00	- 39+00.00	1589.6	529.6	0.0	1.0
6	039+00.00	- 45+00.00	583.9	535.2	0.0	0.0
7	045+00.00	- 51+00.00	512.1	599.4	0.0	0.0
8	051+00.00	- 57+00.00	730.8	841.2	0.0	0.0
9	057+00.00	- 63+00.00	1275.4	645.5	0.0	0.0
10	063+00.00	- 64+08.59	0.0	0.0	0.0	0.0
TOTALS			7892.4	5330.0	0.0	2.0

NOTE: QUANTITIES SHOWN ARE BASED UPON PER SHEET VOLUME ESTIMATES. CONTRACTOR WILL BE PAID FOR ACTUAL VOLUMES OF UNCLASSIFIED EXCAVATION PERFORMED. CONTRACTOR SHOULD SEQUENCE THEIR OPERATIONS SUCH THAT THE FILL VOLUMES WILL BE AVAILABLE FROM MATERIAL EXCAVATED WITHIN THE PROJECT EXTENTS FOR ALL PHASES OF THE PROJECT.