FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
	OKLA.	26879(04)		9	22

= REMOVE EXISTING TREE

NOTE:
ALL OTHER TREES TO BE PROTECTED IN PLACE.

CONTRACTOR TO PHASE CONSTRUCTION AT EACH ENTRANCE TO THE POSTAL TRAINING FACILITY TO ALLOW ACCESS TO BOTH ENTRANCES AT ALL TIMES.

CONTRACTOR TO REPLACE 69 LF OF 6" CURB AND GUTTER, 132 SQ-YDS OF CONCRETE DRIVE PER ODOT STANDARD

CONTRACTOR TO INSTALL 4.5" REMOVABLE BOLLARD SEE DETAIL SHEET 21

CONTRACTOR TO INSTALL 4.5" REMOVABLE BOLLARD SEE DETAIL SHEET 21

CONTRACTOR TO INSTALL ODOT TYPE "B" WHEELCHAIR RAMP W/TACTILE WARNING SURFACE

CONCRETE DRIVE

6' WIDE RIPRAP APRON
12" DIA. ROCK
T=18"

PIPE – (2)
24-IN CONCRETE PIPE
60.83-FT @ 1.76% INTO EXISTING MH

REPLACE EX 4' DIA. PRECAST MANHOLE
RIM 1175.43
N: 676159.72
E: 2148681.86
NEW 24" (NE) = 1169.42
EX 24" INV (W) = 1170.33
EX 36" INV (S) = 1169.17

STRUCTURE – (1)
N 676181.30
E 2148742.28
GRATE 1174.55
FL OUT 1170.55
ODOT MEDIAN DRAIN (SMD-2)

CONTRACTOR TO BERM AND CREATE A SWALE TO INTERCEPT FLOW FROM THE NORTH

REMOVE EXISTING INLET

REMOVE EXISTING 24" RCP

REMOVE EXISTING CONCRETE PAVING

10' WIDE CONCRETE TRAIL

EXISTING R/W

LIMIT OF CONSTRUCTION

E. IMHOFF DR

STATE HIGHWAY 9

MATCHLINE

SCALE 1" = 20

SOUTH EDGE OF SIDEWALK
Horizontal Scale: 1" = 20'
Vertical Scale: 1" = 4'
Vertical Exaggeration: x 5

EXISTING TUG EXACT DEPTH UNKNOWN

PROPOSED GRADE AT SOUTH EDGE OF WALK

EXISTING GRADE AT SOUTH EDGE OF WALK

EXISTING WTR EXACT DEPTH UNKNOWN

State Job No.	26879(04)	Sheet No.	9