

SUMMARY OF DRAINAGE STRUCTURES

STR. NO.	P & P SHT. NO.	ALIGN.	STATION	OFFSET	DESCRIPTION	DESIGN	MANHOLES					CONDUITS													
							509(C)	611(L)	611(A)	611(B)	611(A)	611(B)	611(G)	611(H)	611(G)	613(A)					613(L)				
							CLASS A CONCRETE, SMALL STRUCTURES	JUNCTION BOXES	MANHOLE (4' DIA.)	ADDL. DEPTH IN MANHOLE (4' DIA.)	MANHOLE (6' DIA.)	ADDL. DEPTH IN MANHOLE (6' DIA.)	CURB INLETS	ADDL. DEPTH IN CURB INLET	INLET (SMD-TYPE 2)	REINFORCED CONCRETE PIPE					PREFABRICATED CULVERT END SECTION				
													18 IN	24 IN	30 IN	36X22	42 IN	18 IN	24 IN	30 IN	36X22	42 IN			
							CY	CF	EA	VF	EA	VF	EA	VF	EA	EA	EA	EA	EA	EA	EA	EA	EA		
49	16	12th Ave SE	102+16.93	70.40' LT.	CONST. 6' STD MH W/18"x96" LG RCP W/PCES, ROUND	MJB-3, SPI4, PCES-4					1	4							1						
50	16	12th Ave SE	102+18.33	-	CONST. 42"x125" LG RCP W/PCES, ROUND	SPI4, PCES-4																	1		
51	16	12th Ave SE	103+05.00	47.69' LT.	CONST. 4' STD MH W/24"x82 LF LG RCP W/PCES, ROUND	SPI4, MJB-3			1	1										1					
52	16	12th Ave SE	103+05.00	34.43' LT.	CONST. DES 2 (STD) CURB INLET W/18"x13" LG RCP STUBBED INTO STR. NO. 51	CH-1, SPI4							1	1											
53	16	12th Ave SE	103+05.00	34.40' RT.	CONST. DES 2 (STD) CURB INLET W/18"x69" LG RCP STUBBED INTO STR. NO. 52	SPI4, CH-1							1	1											
54	16	12th Ave SE	105+50.08	38.17' LT.	CONST. 4x3' JCT BOX W/24"x262" LG RCP STUBBED INTO STR. NO. 57	MJB-3, SPI4	2.00	45																	
55	16	12th Ave SE	105+50.07	34.44' LT.	CONST. DES 2 (STD) CURB INLET W/18"x4" LG RCP STUBBED INTO STR. NO. 54	SPI4, CH-1							1	2											
56	16	12th Ave SE	105+50.08	34.43' RT.	CONST. DES 2 (STD) CURB INLET W/18"x69" LG RCP STUBBED INTO STR. NO. 55	SPI4, CH-1							1	1											
57	17	12th Ave SE	108+12.77	38.92' LT.	CONST. 4x3' JCT BOX W/24"x16" LG RCP W/PCES, ROUND	MJB-3, SPI4, PCES-4	2	45												1					
58	17	12th Ave SE	108+12.72	35.17' LT.	CONST. DES 2 (STD) CURB INLET W/18"x4" LG RCP STUBBED INTO STR. NO. 57	SPI4, CH-1							1	1											
59	17	12th Ave SE	108+11.78	34.70' RT.	CONST. DES 2 (STD) CURB INLET W/18"x70" LG RCP STUBBED INTO STR. NO. 58	SPI4, CH-1							1	1											
60	17	12th Ave SE	113+00.09	56.17' LT.	CONST. 4x3' JCT BOX W/24"x134" LG RCP STUBBED INTO STR. NO. 63	MJB-3, SPI4	2	45																	
61	17	12th Ave SE	113+00.06	52.47' LT.	CONST. DES 2 (STD) CURB INLET W/18"x4" LG RCP STUBBED INTO STR. NO. 60	SPI4, CH-1							1	2											
62	17	12th Ave SE	113+00.04	40.46' RT.	CONST. DES 2 (STD) CURB INLET W/18"x93" LG RCP STUBBED INTO STR. NO. 61	SPI4, CH-1							1	1											
63	18	12th Ave SE	114+34.04	56.30' LT.	CONST. 4' STD MH W/24"x77" LG RCP STUBBED INTO STR. NO. 64	MJB-3, SPI4			1																
64	18	12th Ave SE	115+16.33	56.19' LT.	CONST. 4x3' JCT BOX W/24"x167" LG RCP STUBBED INTO STR. NO. 66	MJB-3, SPI4	2	45																	
65	18	12th Ave SE	115+16.52	52.47' LT.	CONST. DES 2 (STD) CURB INLET W/18"x4" LG RCP STUBBED INTO STR. NO. 64	SPI4, CH-1							1	1											
66	18	12th Ave SE	116+99.59	56.23' LT.	CONST. 4x3' JCT BOX W/24"x87" LG RCP STUBBED IN STR. NO. 68	MJB-3, SPI4	2	45																	
67	18	12th Ave SE	116+99.59	52.44' LT.	CONST. DES 2 (STD) CURB INLET W/18"x4" LG RCP STUBBED INTO STR. NO. 66	SPI4, CH-1							1	1											
68	18	12th Ave SE	117+87.37	92.93' LT.	CONST. 6' STD MH W/24"x26" LG RCP W/PCES, ARCH	MJB-3, SPI4					1	2											1		
69	18	12th Ave SE	117+88.42	40.43' LT.	CONST. DES 2 (STD) CURB INLET W/36"x22"x53" LG RCP STUBBED INTO STR. NO. 68	SPI4, CH-1							1	3											
70	18	SH-9	304+46.57	2.95' LT.	CONST. 4' STD MH W/24"x30" LG RCP W/PCES, ROUND	MJB-3, SPI4			1														1		
71	18	SH-9	305+43.04	4.17' RT.	CONST. 4' STD MH	MJB-3, SPI4			1																
72	18	12th Ave SE	118+61.48	78.51' RT.	CONST. SMD-TYPE 2 W/18"x33" LG RCP STUBBED INTO STR. NO. 71	SMD-3, SPI4																			
75	18	12th Ave SE	119+56.66	-	CONST. 30"x116" LG RCP W/PCES, ROUND	SPI4, PCES-4																			
TOTAL							10	225	4	1	2	6	11	15	1	463	563	116	228	125	1	3	2	1	1

2/15/2017 5:16:13 PM - P:\0851213-08512-13001\CAD\SHEETLESS\SUMMARY\SUMMARY SHEET.DWG - RODRIGUEZ, AMY

DESIGN	SKC	OKLAHOMA DEPARTMENT OF TRANSPORTATION
DRAWN	TI	
CHECKED	SKC	
APPROVED	MNR	
SQUAD	TI	

SUMMARY SHEET 2

STATE JOB NO. 29289(04) SHEET NO. 10
CLEVELAND COUNTY