

FED. ROAD DIST. NO.	STATE	STATE JOB NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS	
	OKLA	29289(04)		11		
DESCRIPTION					REVISIONS	DATE

STRIPING SUMMARY									
SHEET NO.	STATION TO STATION	855(A)	855(A)	855(B)	856(A)	856(A)	856(A)	856(A)	856(B)
		TRAFFIC STRIPE(PLASTIC)(4" WIDE)	TRAFFIC STRIPE(PLASTIC)(24" WIDE)	TRAF.STR(PLAST)(SYMBOLS, WORDS, ETC)	TRAFFIC STRIPE(MULTI-POLY)(4" WIDE)	TRAFFIC STRIPE(MULTI-POLY)(6" WIDE)	TRAFFIC STRIPE(MULTI-POLY)(8" WIDE)	TRAFF. STRIPE(MULTI-POLY)(24" WIDE)	TRAF.STR.(MULTI-POLY)(SYM,WRD, ETC)
12th AVE SE									
25-26	101+91.18 TO 121+56.70	-	-	-	4,477	2,677	601	178	45
SH-9									
27-28	301+30 TO 309+90.30	2137	504	14	-	-	-	-	-
TOTAL		2,137	504	14	4,477	2,677	601	178	45

SUMMARY OF SIGNS								
SHEET NO.	SIGN NO.	APPROXIMATE STATION/OFFSET	TYPE OF SIGNS	FOOTING DESIGN	850(A)	851(C)	805(A)	(PL)REMOVAL OF EXISTING SIGNS
					SHEET ALUMINUM SIGNS	2" SQUARE TUBE POST	EA	
12th AVE SE								
					SF	LF	EA	
25	1	102+00.00, 39' RT	R3-9B	A-1	6.00	10	24	
25	2	101+75.00, 39' RT	R3-17	A-1	3.00	10		
25	3	103+70.00, 38' LT	R3-17	A-1	3.00	10		
25	4	104+54.07, 58' RT	R1-1	A-1	5.18	10		
6	5	109+00.00, 45' LT	R3-17	A-1	3.00	10		
25	6	110+42.25, 60.96' RT	R1-1	A-1	5.18	10		
25	7	112+80.00, 56' LT	R3-9B	A-1	6.00	10		
25	8	113+00.00, 45' RT	R4-4	A-1	7.50	10		
26	9	115+60.00, 56' LT	R2-1	A-1	5.00	10		
26	10	116+60.00, 56' LT	W9-2, W4-2	A-2	9.00	13		
26	11	117+32.00, 45' RT	R3-7R	A-1	6.25	10		
26	12	117+74.00, 76' LT	R1-5	A-1	9.00	10		
26	13	117+92.00, 48' RT	R6-3	A-1	5.00	10		
26	14	119+80.00, 24' LT	R6-3	A-1	5.00	10		
26	15	119+80.00, 24' RT	R3-17, M6-3	A-1	3.00	13		
26	16	120+20.00, 30' LT	R3-7	A-1	9.00	10		
26	17	120+70.00, 30' RT	R8-3A	A-1	6.25	10		
26	18	121+10.00, 30' LT	R8-3A	A-1	6.25	10		
26	19	121+48.00, 30' RT	R1-1	A-1	5.18	10		
SH-9								
27	20	304+22.00, 54' RT	R5-1	A-1	6			
27	21	304+34.00, 8' LT	R4-7	A-1	5	10		
27	22	305+64.00, 12' RT	R4-7	A-1	5	10		
27	23	305+85.00, 6' LT	R5-1	A-1	6	10		
27	24	305+85.00, 63' LT	R5-1	A-1	6	10		
28	25	308+80.00, 3' RT	R6-1A	A-1	6	10		
TOTAL					142	246	24	

TRAFFIC CONTROL SUMMARY										
PHASE	DESCRIPTION	857(A)	857(E)	857(F)	880(B)	880(B)	880(B)	880(C)	880(E)	880(F)
		CONSTRUCTION TRAFF. STR.(PAINT)(4" WIDE)	(PL)CONST.ZON E PAV.MKRS(FLEX TAB)TYP.2-2	PAVEMENT MRKNG.REMOVAL(TRAFF.STRP)	CONSTRUCTION SIGNS 0 TO 6.25 SF	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	CONSTRUCTION BARRICADES(TYPE III)	WARNING LIGHTS(TYPE A)	DRUMS
		LF	EA	LF	SD	SD	SD	SD	SD	SD
1	PHASE I	-	-	-	-	1,120	1,680	560	1,120	-
2	PHASE II	-	-	-	30	45	30	-	30	360
3	PHASE III	3,340	388	3,340	120	540	480	480	480	25,200
4	PHASE IV	3,340	368	3,340	120	540	480	480	480	25,200
5	PHASE V	1,450	-	1,450	40	120	80	80	80	300
6	PHASE VI	1,450	-	1,450	40	120	80	80	80	300
TOTAL		9,580	736	9,580	350	2,485	2,830	1,680	2,270	51,360

DESIGN	SKC	OKLAHOMA DEPARTMENT OF TRANSPORTATION
DRAWN	TI	
CHECKED	SKC	
APPROVED	MNR	
SQUAD	TI	
		SUMMARY SHEET 3
		STATE JOB NO. 29289(04)
		SHEET NO. 11

2/16/2017 5:26:32 PM - P:\085121\131-08512-13001\CAD\SHEETFILES\SUMMARY\SUMMARY SHEET.DWG - RODRIGUEZ, AMY