

FED. ROAD DIST. NO.	STATE	STATE JOB NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
	OKLA	29289(04)		4	

DESCRIPTION	REVISIONS	DATE
REMOVE PAY ITEM		9/7/2017



0100				
ROADWAY				
ITEM NO.	CODE NO.	DESCRIPTION	UNITS	QUANTITY
201(A)	0102	CLEARING AND GRUBBING	(1) LSUM	1.00
202(A)	0183	UNCLASSIFIED EXCAVATION	(3)(17) CY	8,440.00
202(D)	0184	UNCLASSIFIED BORROW	(R-4) CY	1,600.00
205(A)	4229	TYPE A-SALVAGED TOPSOIL	(R-5)(R-7) LSUM	1.00
221(C)	2801	TEMPORARY SILT FENCE	(4)(6) LF	3,800.00
221(D)	2803	TEMPORARY SEDIMENT FILTER	(4) EA	10.00
221(F)	0100	TEMPORARY SILT DIKE	(4) LF	8.00
230(A)	2806	SOLID SLAB SODDING	(R-8)(5)(7)(8) SY	6,373.00
233(A)	2817	VEGETATIVE MULCHING	(R-11) AC	1.00
241	2832	MOWING	(R-16) AC	2.00
307(A)	4200	FLY ASH	(R-20) TON	985.00
307(E)	4240	CEMENTITIOUS STABILIZED SUBGRADE	SY	18,695.00
317	4270	CEMENT TREATED BASE	(10) SY	17,484.00
402(E)	0225	TRAFFIC BOUND SURFACE COURSE TYPE E	TON	68.00
407(B)	0250	TACK COAT	GAL	205.00
408	5774	PRIME COAT	(R-28) GAL	6,542.00
411(B)	5945	SUPERPAVE, TYPE S3(PG 64-22 OK)	(R-32)(9) TON	527.00
411(C)	5950	SUPERPAVE, TYPE S4(PG 76-28 OK)	(R-32) TON	666.00
411(C)	5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	(R-32) TON	34.00
412	5267	COLD MILLING PAVEMENT	(R-49) SY	5,298.00
414(B)	5725	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	(24) SY	16,589.00
414(G)	5275	P.C. CONCRETE FOR PAVEMENT	CY	3,686.00
509(B)	1328	CLASS A CONCRETE	(R-40) CY	22.00
509(C)	0322	CLASS A CONCRETE, SMALL STRUCTURES	CY	10.00
509(D)	0325	CLASS C CONCRETE	(R-41) CY	80.00
609(A)	0380	CONC.CURB(8" BARRIER-INTEGRAL)	(18) LF	4,083.00
609(B)	1514	1'-8" COMB.CRB & GUT.(8" BARRIER)	(R-44)(11) LF	1,000.00
610(A)	0605	6" CONCRETE SIDEWALK	(15)(19) SY	2,046.00
610(B)	0604	6" CONCRETE DRIVEWAY	(14) SY	657.00
611(A)	2657	MANHOLE (4' DIA.)	(20)(21) EA	4.00
611(A)	2659	MANHOLE (6' DIA.)	(20)(21) EA	2.00
611(B)	2680	ADD'L.DEPTH IN MANHOLE (4' DIA.)	VF	1.00
611(B)	2682	ADD'L.DEPTH IN MANHOLE (6' DIA.)	VF	6.00
611(G)	5112	INLET C/DES. 2 (STD)	(22) EA	11.00
611(G)	6002	INLET (SMD-TYPE 2)	(22) EA	1.00
611(H)	5325	ADD'L DEPTH IN INLET C/DES. 2	VF	15.00
611(L)	0487	JUNCTION BOXES	CF	225.00
613(A)	0491	18" R.C.PIPE CLASS III	(16) LF	463.00
613(A)	0492	24" R.C.PIPE CLASS III	(16) LF	563.00
613(A)	0493	30" R.C.PIPE CLASS III	(16) LF	116.00
613(A)	0495	42" R.C.PIPE CLASS III	(16) LF	125.00
613(A)	4497	36" X 22" R.C.PIPE ARCH CLASS A-III	(16) LF	228.00
613(H)	6204	6" PERFORATED PIPE UNDERDRAIN ROUND	(2) LF	660.00
613(I)	1096	6" NON-PERF.PIPE UNDERDRAIN RND.	(2) LF	130.00
613(L)	4526	36" X 22" PREFAB. CULVERT END SEC., ARCH	EA	1.00
613(L)	5726	18" PREFAB. CULVERT END SEC., ROUND	EA	1.00
613(L)	5730	24" PREFAB. CULVERT END SEC., ROUND	EA	3.00
613(L)	5732	30" PREFAB. CULVERT END SEC., ROUND	EA	2.00
613(L)	5736	42" PREFAB. CULVERT END SEC., ROUND	EA	1.00
619(A)	0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	(R-48)(R-49)(12) LSUM	1.00
619(B)	4725	REMOVAL OF FENCE	(R-49) LF	946.00
619(B)	4726	REMOVAL OF CURB AND GUTTER	(R-49) LF	1,543.00
619(B)	4727	REMOVAL OF CONCRETE PAVEMENT	(R-49) SY	25.00
619(B)	4728	REMOVAL OF ASPHALT PAVEMENT	(R-49)(R-50) SY	7,375.00
619(B)	4766	REMOVAL OF CONCRETE DRIVEWAY	(R-49)(R-50) SY	621.00
619(B)	4767	REMOVAL OF ASPHALT DRIVEWAY	(R-49)(R-50) SY	408.00
619(B)	4792	REMOVAL OF SIDEWALK	(R-49) SY	469.00
619(C)	0924	SAWING PAVEMENT	(23) LF	492.00

0600				
STAKING				
ITEM NO.	CODE NO.	DESCRIPTION	UNIT	QUANT.
642(B)	0096	CONSTRUCTION STAKING LEVEL II	LSUM	1.00

0640				
CONSTRUCTION				
ITEM NO.	CODE NO.	DESCRIPTION	UNIT	QUANT.
220	2800	SWPPP DOCUMENTATION AND MANAGEMENT	(13) LSUM	1.00
640(A)	1426	FIELD OFFICE	EA	1.00
641	1552	MOBILIZATION	LSUM	1.00
643	0087	(SP) CONTRACTORS QUALITY CONTROL	LSUM	1.00



DESIGN	SKC	OKLAHOMA DEPARTMENT OF TRANSPORTATION
DRAWN	Tt	
CHECKED	SKC	
APPROVED	MNR	
SQUAD	Tt	
		SUMMARY OF PAY QUANTITIES (ROADWAY)
		STATE JOB NO. 29289(04)
		SHEET NO. 4