



29946(04)

SUMMARY OF PAY QUANTITIES

0200 BRIDGE TYPE II-60' P.C. BEAM, 26'-0" CL RDWY, TR3-2

ITEM NO.	DESCRIPTION	UNIT	ABUT 1	ABUT 2	SUPERSTR	WINGS	TOTAL
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	CY	60.00	60.00		60.00	180.00
501(G) 6309	CLSM BACKFILL	CY	46.75	46.75			93.50
503(A) 1311	PRESTRESSED CONCRETE BEAMS (TYPE II)	LF			179.00		179.00
504(A) 1304	APPROACH SLAB	SY	57.40	57.40			114.80
504(B) 1305	SAW-CUT GROOVING	SY	43.98	43.98	152.00		239.96
504(D) 6239	CONCRETE RAIL (TR3)	LF			126.40	49.60	176.00
506(A) 1322	STRUCTURAL STEEL	LB.	450.00	450.00	500.00		1400.00
507(A) 6172	WEATHERING STEEL FIXED BEARING ASSEMBLY	EA	3.00				3.00
507(B) 6176	WEATHERING STEEL EXPANSION BEARING ASSEMBLY	EA		3.00			3.00
509(A) 1326	CLASS AA CONCRETE	CY			48.50		48.50
509(B) 1328	CLASS A CONCRETE	CY	21.40	21.40		17.60	60.40
509(D) 1331	CLASS C CONCRETE	CY			20.00		20.00
511(A) 1332	REINFORCING STEEL	LB.	2,740.00	2740.00	11680.00	3000.00	20160.00
514(A) 6010	PILES, FURNISHED (HP 10X42)	LF				106.96	106.96
514(A) 6011	PILES, FURNISHED (HP 12X53)	LF	99.92	134.72			234.64
514(B) 6292	PILES, DRIVEN (HP 10X42)	LF				106.96	106.96
514(B) 6294	PILES, DRIVEN (HP 12X53)	LF	99.92	134.72			234.64
514(L) 6220	PILE SPLICE, H-PILE (NON-BIDDABLE)	EA					1.00
601(B) 1353	TYPE I-A PLAIN RIPRAP	TON	171.00	203.00			374.00
601(I) 6312	FILTER BLANKET (RIPRAP)	SY	211.00	250.00			461.00
619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	LSUM					1.00

EW-1470/SW-LIMESTONE RD. LATIMER COUNTY

SOUTHEAST #3 CIRCUIT ENGINEERING DISTRICT

STAKING LAYOUT

STATE JOB NO. 29946(04) SHEET NO. 8002