

SUMMARY OF EROSION CONTROL

SHEET NO	STATION TO STATION	TEMPORARY SILT FENCE 221(C)	TEMPORARY SILT DIKE 221(F)	VEGETATIVE MULCHING 233(A)	SOLID SLAB SODDING 230(A)	TYPE I PLAIN RIPRAP 601(A)	TYPE I-A PLAIN RIPRAP	NYLON EROSION CONTROL MAT 228	TYPE I-A FILTER BLANKET
		LF	LF	AC	SY	TON	TON	SY	TON
R002	100+15 - 110+00		126	2.32	11,229	380		1,220	
R002	110+00 - 125+00		154	2.75	13,310	26		2,402	
R003	125+00 - 140+00	1,112	140	2.67	12,923	14		2,534	
R003	140+00 - 155+00	904	126	2.85	13,794	13		2,321	
R004	155+00 - 170+00	1,000	112	2.39	11,568	24		1,030	
R004	170+00 - 185+00		140	2.68	12,971	103		2,702	
R005	185+00 - 200+00	94	84	2.55	12,342			1,556	
R005	200+00 - 215+00	330	140	2.49	12,052	170		445	
R006	215+00 - 230+00		126	3.06	14,810	263		1,936	
R006	230+00 - 245+00	400	84	2.55	12,342		10	2,895	5
R007	245+00 - 260+00	1,106	294	3.11	15,052	34	95	1,430	30
R007	260+00 - 275+00		56	2.66	12,874			2,668	
R008	275+00 - 290+00	238	140	2.39	11,568	61		2,138	
R008	290+00 - 305+00	238	168	2.95	14,278			1,012	
R009	305+00 - 320+00		84	3.13	15,149		464	2,094	148
R009	320+00 - 335+00		140	2.57	12,439		659	2,992	210
R010	335+00 - 350+00	450	126	2.81	13,600	72		1,055	
R010	350+00 - 365+00	1,338	182	2.52	12,197	156		1,699	
R011	365+00 - 380+00	200	84	2.42	11,713			2,631	
R011	380+00 - 395+00	242	112	2.61	12,632	844		1,742	226
R012	395+00 - 410+00	640	182	2.37	11,471	222		1,070	
R012	410+00 - 418+30		98	1.58	7,647	485		1,080	
TOTAL		8,292	2,898	57.43	277,961	2,867	1228	40,652	619

SUMMARY OF SIGNS

DESCRIPTION	SIGN NO.	STATION	SIDE	READ FROM	SHEET ALUMINUM SIGNS 850(A)	2 1/4" SQUARE TUBE POST 851(C)	REMOVE AND RESET EXISTING SIGNS 805(D)
CEMETERY ARROW W/SIGN		100+39	RT	NORTH/WEST			1
SIMON-OSWALT RD SIGN		100+46	RT	NORTH/WEST			1
STOP SIGN	R1-1	100+50	LT	EAST	5.18	13	
STOCKTON & OSWALT		100+45	RT	NORTH/WEST			2
SIMMONS CEMETERY SIGN		179+63		NORTH			1
STOP SIGN	R1-1	179+68	RT	SOUTH	5.18	13	
STOP SIGN	R1-1	205+40	LT	NORTH	5.18	13	
MORGAN ROAD SIGN		206+17	LT	WEST			1
BUS STOP AHEAD SIGN		219+15	RT	WEST			1
STOP SIGN	R1-1	258+40	LT	NORTH	5.18	13	
STOP SIGN	R1-1	259+00	RT	SOUTH	5.18	13	
BUS STOP AHEAD SIGN		362+60	LT	EAST			1
STOP SIGN	R1-1	363+25	LT	NORTH	5.18	13	
CEMETERY SIGN		363+34	LT	EAST			1
STOP SIGN	R1-1	363+84	RT	SOUTH	5.18	13	
PIKE ROAD SIGN		363+84	RT	WEST			1
OSWALT RD SIGN		369+23	RT	WEST			2
TOTALS					36.26	91	12

SUMMARY OF FENCING

SIDE LEFT			SIDE RIGHT		
BEGIN STA.	END STA.	LENGTH (L.F)	BEGIN STA.	END STA.	LENGTH (L.F)
100+60	152+89	5253	100+50	152+95	5272
168+77	182+50	1412	179+58	194+98	1562
184+26	197+96	1372	195+85	206+00	1049
200+11	205+45	539	208+87	223+83	1505
205+93	211+35	548	224+49	258+53	3406
211+71	240+72	2913	259+07	270+15	1117
242+37	250+95	859	272+83	284+28	1150
251+40	258+50	725	282+36	284+51	215
259+05	282+04	2318	285+18	301+58	1639
284+74	363+32	7879	302+77	343+68	4144
363+92	384+94	2105	356+84	363+29	649
385+44	401+05	1570	363+88	397+70	3404
401+55	416+44	1490	398+17	407+09	924
			407+65	416+44	923
SUBTOTAL		28,983	SUBTOTAL		26,959
			TOTAL		55,942

SUMMARY OF MAILBOXES

NO.	STATION	SIDE	DESCRIPTION
1	154+80.36	RT	REMOVE AND RESET MAILBOX
2	156+58.14	LT	REMOVE AND RESET MAILBOX
3	159+72.40	RT	REMOVE AND RESET MAILBOX
4	162+32.88	LT	REMOVE AND RESET MAILBOX
5	199+79.48	LT	REMOVE AND RESET MAILBOX
6	211+24.80	LT	REMOVE AND RESET MAILBOX
7	224+24.92	LT	REMOVE AND RESET MAILBOX
8	251+53.23	LT	REMOVE AND RESET MAILBOX
9	272+73.39	RT	REMOVE AND RESET MAILBOX
10	284+76.95	LT	REMOVE AND RESET MAILBOX
11	302+13.41	RT	REMOVE AND RESET MAILBOX
12	306+52.93	LT	REMOVE AND RESET MAILBOX
13	320+65.40	RT	REMOVE AND RESET MAILBOX
14	348+62.44	LT	REMOVE AND RESET MAILBOX
15	354+59.91	LT	REMOVE AND RESET MAILBOX
16	369+89.34	LT	REMOVE AND RESET MAILBOX

SUMMARY OF DISTURBED AREAS

DISTURBED AREA NO.	OUTFALL STATION	STR. NO.	AREA AC.	SEDIMENT CONTROL MEASURES	DISTURBED AREA STA. TO STA.	STANDARDS
1	106+86	1	3.51	TEMPORARY SILT DIKE	100+15 TO 116+00	TSD-2-0
2	118+50	2	2.50	TEMPORARY SILT DIKE & FENCE	116+20 TO 131+00	TSD-2-0 & TCS2-3-2
3	140+00	5	2.71	TEMPORARY SILT DIKE & FENCE	131+00 TO 145+31	TSD-2-0 & TCS2-3-2
4	158+10	10	3.51	TEMPORARY SILT DIKE & FENCE	145+00 TO 166+00	TSD-2-0 & TCS2-3-2
5	184+16	BRIDGE EXCEPTION	5.68	TEMPORARY SILT DIKE & FENCE	165+00 TO 198+32	TSD-2-0 & TCS2-3-2
6	205+37	18	2.16	TEMPORARY SILT DIKE & FENCE	198+00 TO 211+37	TSD-2-0 & TCS2-3-2
7	218+00	20	3.50	TEMPORARY SILT DIKE	211+37 TO 229+00	TSD-2-0
8	245+38	BRIDGE "A"	8.08	TEMPORARY SILT DIKE & FENCE	229+00 TO 273+00	TSD-2-0 & TCS2-3-2
9	282+88	29	3.48	TEMPORARY SILT DIKE & FENCE	273+00 TO 293+87	TSD-2-0 & TCS2-3-2
10	293+87	33	0.43	TEMPORARY SILT DIKE & FENCE	293+00 TO 296+48	TSD-2-0 & TCS2-3-2
11	305+62	BRIDGE "B"	3.73	TEMPORARY SILT DIKE	296+48 TO 314+00	TSD-2-0
12	323+53	BRIDGE "C"	4.01	TEMPORARY SILT DIKE & FENCE	313+41 TO 336+00	TSD-2-0 & TCS2-3-2
13	348+70	42	0.82	TEMPORARY SILT DIKE & FENCE	336+00 TO 341+00	TSD-2-0 & TCS2-3-2
14	349+96	45	2.87	TEMPORARY SILT DIKE	341+00 TO 355+00	TSD-2-0
15	356+75	46	2.25	TEMPORARY SILT DIKE & FENCE	354+45 TO 370+00	TSD-2-0 & TCS2-3-2
16	388+63	53	3.33	TEMPORARY SILT DIKE & FENCE	369+85 TO 389+00	TSD-2-0 & TCS2-3-2
17	389+09	54	1.10	TEMPORARY SILT DIKE & FENCE	389+00 TO 396+24	TSD-2-0 & TCS2-3-2
18	396+09	55	0.79	TEMPORARY SILT DIKE & FENCE	396+24 TO 401+30	TSD-2-0 & TCS2-3-2
19	403+78	57	0.93	TEMPORARY SILT DIKE & FENCE	401+30 TO 407+46	TSD-2-0 & TCS2-3-2
20	414+63	59	2.08	TEMPORARY SILT DIKE & FENCE	407+46 TO 418+30	TSD-2-0 & TCS2-3-2
TOTAL DISTURBED AREA:			57.47			

SUMMARY OF GUARDRAILS

STATION TO STATION	LT.	RT.	BEAM GUARD RAIL W-BEAM SINGLE (FEET)	TYPE D-BF (EACH)	TYPE A (EACH)	TOTAL PANEL LENGTH INCLUDING ANCHOR UNITS (FEET)
181+42.52 - 183+55.02	X		112.50	1	1	212.50
182+30.02 - 183+55.02		X	25.00	1	1	125.00
184+80.83 - 186+05.83	X		25.00	1	1	125.00
184+80.83 - 186+05.83		X	25.00	1	1	125.00
204+00.00 - 207+00.00		X	150.00		2	300.00
249+50.00 - 252+50.00		X	150.00		2	300.00
TOTALS			487.50	4	8	1187.50