

SCALE:


HORIZ. 1 in = 300 FT. VERT. 1 in = 3,000 C.Y.

CRL - MILE 6

PHASED SCHEDULE OF EARTHWORK				
STATION TO STATION	UNCLASSIFED EXCAVATION 202(A)	EMBANKMENT +15%	UNCLASSIFIED BORROW 202(D)	EXCESS EXCAVATION
	C.Y.	C.Y.	C.Y.	C.Y.
MILE 1	25,087.27	9,240.87	-	15,846.40
MILE 2	18,985.78	2,818.36	-	16,167.42
MILE 3	16,970.09	34,849.10	17,879.01	-
MILE 4	43,546.71	8,303.72	-	35,242.99
MILE 5	27,052.41	9,939.34	-	17,113.07
MILE 6	18,429.24	7,259.34	-	11,169.90
TOTALS	150,071.50	72,410.74	17,879.01	79,693.37

NOTE: THE CONTRACTOR SHALL NOT WASTE ANY EXCESS EXCAVATION UNTIL ALL PLANNED EMBANKMENTS ARE COMPLETED. IF CONTRACTOR OPERATIONS REQUIRE HIM TO STOCKPILE THE EXCESS EXCAVATION, THE COST OF THE SECOND HANDLING SHALL BE INCLUDED IN OTHER ITEMS OF WORK





OSWALT ROAD LOVE COUNTY MASS HAUL DIAGRAM

(SHEET 6 OF 6)

JOB PIECE NO. 25447(04) SHEET NO. R019