


REVISIONS		
REV. NO.	DESCRIPTION	DATE

SUMMARY OF SIGN QUANTITIES								
ITEM NO.	APPROXIMATE LOCATION	SIGN DESIGNATION	SQ TUBE POST		POST SPACING FT.	SIGN AREA S.F.	REMOVAL OF EXIST. SIGNS 805(A) EA	REMARKS
			A	B				
			2"					
1	1776+00 RT	ROUTE ASSEMBLY 1	15.00	15.00	2.33	34.38	1.00	INSTALL NEW SIGN & POLE
2	1779+70 RT	W2-1E, SPECIAL SIGN 1	14.00			13.50	1.00	INSTALL NEW SIGN & POLE
3	1780+25 LT	R1-1	13.50			5.18	1.00	INSTALL NEW SIGN & POLE
3A	1780+25 LT	RPM (45,02,19,20)				2.33	1.00	INSTALL ON BACK OF SIGN 3
4	1780+85 LT	R1-1	13.50			5.18	1.00	INSTALL NEW SIGN & POLE
5	1781+00 LT	R2-1	13.50			5.00	1.00	INSTALL NEW SIGN & POLE
6	1783+25 RT	W10-2	14.00			6.25	1.00	INSTALL NEW SIGN & POLE
7	1783+85 LT	ROUTE ASSEMBLY 2	15.00			6.00	1.00	INSTALL NEW SIGN & POLE
8	1784+65 RT	ROUTE ASSEMBLY 3	15.00	15.00	2.33	21.38	1.00	INSTALL NEW SIGN & POLE
9	1784+60 LT	R1-2					1.00	REMOVE & DISCARD
10	1786+70 RT	R1-2	13.50			3.90	1.00	INSTALL NEW SIGN & POLE
10A	1786+70 RT	R5-1				6.25	1.00	INSTALL ON BACK OF SIGN 10
11	1786+80 LT	ROUTE ASSEMBLY 4	15.00	15.00	2.33	16.38	1.00	INSTALL NEW SIGN & POLE
12	1787+90 RT	ROUTE ASSEMBLY 5	15.00			6.00	1.00	INSTALL NEW SIGN & POLE
13	1792+40 LT	ROUTE ASSEMBLY 6	15.00	15.00	2.33	16.38	1.00	INSTALL NEW SIGN & POLE
14	1792+90 RT	R2-1	13.50			5.00	1.00	INSTALL NEW SIGN & POLE
15	1795+60 LT	W2-1E, SPECIAL SIGN 1	14.00			13.50	1.00	INSTALL NEW SIGN & POLE
16	14+75 RT	W3-1					1.00	REMOVE & DISCARD
17	14+75 RT	W3-1					1.00	REMOVE & DISCARD
18	15+05 LT	R2-1	13.50			5.00	1.00	INSTALL NEW SIGN & POLE
19	15+05 LT	R2-1	13.50			5.00	1.00	INSTALL NEW SIGN & POLE
20	16+00 RT	SPECIAL SIGN 2, I-5, W16-5P	15.00	15.00	3.00	27.00	1.00	INSTALL NEW SIGN & POLE
21	17+55 RT	ROUTE ASSEMBLY 7	15.00			8.19	1.00	INSTALL NEW SIGN & POLE
22	18+05 LT	SPECIAL SIGN 3	15.00	15.00	3.00	21.00	1.00	INSTALL NEW SIGN & POLE
23	19+75 RT	R3-7(R)	13.50			6.25	1.00	INSTALL NEW SIGN & POLE
24	20+70 RT	R5-1a	13.00			6.00	1.00	INSTALL NEW SIGN & POLE
25	20+70 RT	R5-1a	13.00			6.00	1.00	INSTALL NEW SIGN & POLE
26	22+25 RT	ROUTE ASSEMBLY 8	15.00			8.19	1.00	INSTALL NEW SIGN & POLE
27	22+25 RT	VETERAN'S MUSEUM					1.00	REMOVE & DISCARD
28	23+20 LT	ROUTE ASSEMBLY 9	15.00	15.00	2.33	16.38	1.00	INSTALL NEW SIGN & POLE
29	23+45 RT	R4-7	13.50			5.00	1.00	INSTALL NEW SIGN & POLE
30	23+75 RT	R1-1, R5-1					1.00	REMOVE & DISCARD
31	24+75 LT	R1-1					1.00	REMOVE & DISCARD
32	25+15 LT	VETERAN'S MUSEUM					1.00	REMOVE & DISCARD
32A	25+15 RT	W10-1	14.00			7.07		INSTALL NEW SIGN & POLE
33	26+30 LT	R1-1	13.50			5.18	1.00	INSTALL NEW SIGN & POLE
34	28+40 RT	SPECIAL SIGN 4	15.00	15.00	4.83	15.00	1.00	INSTALL NEW SIGN & POLE
35	29+75 LT	R1-1	13.50			5.18	1.00	INSTALL NEW SIGN & POLE
36	30+25 LT	R5-2a	13.00			4.00	1.00	INSTALL NEW SIGN & POLE
37	31+25 LT	W10-1	14.00			7.07	1.00	INSTALL NEW SIGN & POLE
38	33+00 LT	W3-1					1.00	REMOVE & DISCARD
39	35+35 RT	R2-1	13.50			5.00	1.00	INSTALL NEW SIGN & POLE
40	35+35 LT	ROUTE ASSEMBLY 10	15.00			6.19	1.00	INSTALL NEW SIGN & POLE
			586.00			335.31	42.00	



REFERENCE POINT MARKER (RPM)

DIVISION 2 US-70B		MCCURTAIN COUNTY		DETAIL:	JF	8/16	
SIGN SUMMARY				CHECK:	GF	8/16	
				ENGINEER:	KCD	8/16	
				GROUP:	ABRAHAM EM: MAAROUF		
STATE OF OKLAHOMA		DEPARTMENT OF TRANSPORTATION		JOBPIECE NO.	33075(56)	SHEET NO.	T005