

REVISIONS		
REV. NO.	DESCRIPTION	DATE

SUMMARY OF REMOVAL					
STATION TO STATION	LT	RT	REMOVAL OF CURB & GUTTER	REMOVAL OF ASPHALT PAVING	REMOVAL OF CONCRETE DRIVEWAY
			LF	SY	SY
354+30.00 TO 358+50.00		X			130
358+50.00 TO 364+00.00					
364+00.00 TO 369+50.00					
369+50.00 TO 375+00.00		X	179	114	138
375+00.00 TO 380+50.00		X	188	109	163
380+50.00 TO 383+00.00		X	60	40	88
383+00.00 TO 386+00.00		X	215	175	304
386+00.00 TO 391+37.65		X	452	158	791
TOTAL			1094	596	1614

SUMMARY OF ADJUST TO GRADE				
STATION	LT	RT	MANHOLE LID	EA
390+95.75		X		1
TOTAL				1

SUMMARY OF SAWING				
STATION TO STATION	LT	RT	LENGTH	LF
354+30.00 TO 358+50.00		X	118	
358+50.00 TO 364+00.00				
364+00.00 TO 369+50.00				
369+50.00 TO 375+00.00		X	278	
375+00.00 TO 380+50.00		X	258	
380+50.00 TO 383+00.00		X	131	
383+00.00 TO 386+00.00		X	416	
386+00.00 TO 391+37.65		X	860	
TOTAL			2061	

SUMMARY OF REMOVE AND RESET SIGNS				
STATION	LT	RT	SIGN	EA
356+18.18		X		1
356+84.20		X		1
380+31.94		X		1
380+42.00		X		1
TOTAL				4

SUMMARY OF RETAINING WALL				
STATION TO STATION	LT	RT	LENGTH	4" THK. SAND
			LF	CY
354+30.00 TO 358+50.00		X	88	2
364+00.00 TO 369+50.00		X	316	8
TOTAL			404	10

SUMMARY OF PROPOSED DRIVES							
STATION	LT	RT	WIDTH	LENGTH	RADIUS	6" THK. CONCRETE DRIVEWAY	4" THK. SAND
			FT	FT	FT	SY	CY
355+21.00		X	32	20.0	20, 15	113	13
371+65.75		X	30	23.4	5, 10	81	9
372+64.30		X	16	20.0	15	48	5
376+50.50		X	23.6	27.4	25	82	9
380+04.50		X	23.5	23.4	15	71	8
380+78.30		X	30	23.2	15	89	10
383+79.20		X	29	16.5	15, 10	91	10
384+29.25		X	36	16.4	10	91	10
384+88.90		X	36	16.2	10, 15	91	10
385+84.50		X	30	14.3	15	57	6
387+04.00		X	28	23.1		164	18
387+63.29		X	35	23.3		164	18
388+90.00		X	36	23.9	10, 15	105	12
389+70.50		X	36	25.4	10, 15	113	13
390+24.60		X	15	14.0	15	35	4
390+97.00		X	47.75	14.0	15	86	10
TOTAL						1481	165

SUMMARY OF P.C. CONCRETE PAVEMENT							
STATION	LT	RT	WIDTH	LENGTH	RADIUS	9" THK. CONCRETE ROADWAY	4" THK. SAND
			FT	FT	FT	CY	CY
371+14.00		X	28	18.8	15	18	8
378+65.60		X	26.75	23.5	20	22	10
388+21.00		X	33.25	18.5	30	18	8
TOTAL						57	25

SUMMARY OF PROPOSED SIDEWALKS / CURB AND GUTTER					
STATION TO STATION	LT	RT	5" THK. SIDEWALK	CURB & GUTTER	4" THK. SAND
			SY	LF	CY
354+30.00 TO 358+50.00		X	228	83	28
358+50.00 TO 364+00.00		X	308		34
364+00.00 TO 369+50.00		X	303		34
369+50.00 TO 375+00.00		X	206	152	28
375+00.00 TO 380+50.00		X	216	186	30
380+50.00 TO 383+00.00		X	99	60	13
383+00.00 TO 386+00.00		X	60	215	14
386+00.00 TO 391+37.65		X	131	452	29
TOTAL			1551	1148	210

SUMMARY OF ASPHALT PAVING				
STATION TO STATION	LT	RT	2" THK. S5 SUPERPAVE	TON
354+30.00 TO 358+50.00				
358+50.00 TO 364+00.00				
364+00.00 TO 369+50.00				
369+50.00 TO 375+00.00		X	5	
375+00.00 TO 380+50.00		X	4	
380+50.00 TO 383+00.00		X	2	
383+00.00 TO 386+00.00		X	7	
386+00.00 TO 391+37.65		X	10	
TOTAL			28	

SULPHUR SIDEWALK IMPROVEMENTS SUMMARY SHEET				Drawn	J ALEX	7/27/17
CITY OF SULPHUR				Design	WTM	7/27/17
BROADWAY - CHARLES F. COOPER				Checked	WTM	7/27/17
MEMORIAL ROAD TO 12TH STREET				JOB NO. 210101		
STATE OF OKLAHOMA		DEPARTMENT OF TRANSPORTATION				
		DIVISION 7			SHEET NO. 3 OF 34	