

Summary of Signs

ASSY #	Notes	Station	Offset	Sign(s)	Size	Sheet Aluminum Signs		Mast Arm Mounted Signs (Aluminum)		2" Ø3.65 GALV.STL. Pipe Post	
						850(A) 8110	850(C) 8118	851(B) 3216	851(B) 3216		
						S.F.	S.F.	L.F.	L.F.		
1A	Maple Crossing	17+14	66' RT	R5-3	24X24	4.00				9.00	
1B	Advance for Maple	17+17	56' LT	W11-15 / W16-9P	30X30 / 24X12	8.25				10.67	
1C	at Maple	17+18	44' RT	W11-15 / W11-15p / W16-7P(I)	30X30 / 24X18 / 24X12	11.25				12.33	
1D	at Maple	17+57	64' RT	W11-15 / W11-15p / W16-7P(I)	30X30 / 24X18 / 24X12	11.25				12.33	
1E	Maple Crossing	17+62	45' RT	R5-3	24X24	4.00				9.00	
1F	Advance for Maple	17+86	163' RT	W11-15 / W16-9P	30X30 / 24X12	8.25				10.67	
2A	Felix Crossing	33+35	43' RT	R5-3	24X24	4.00				9.00	
2B	Advance for Felix	33+42	70' LT	W11-15 / W16-9P	30X30 / 24X12	8.25				10.67	
2C	at Felix	33+46	23' RT	W11-15 / W11-15p / W16-7P(I)	30X30 / 24X18 / 24X12	11.25				12.33	
2D	at Felix	33+78	45' RT	W11-15 / W11-15p / W16-7P(I)	30X30 / 24X18 / 24X12	11.25				12.33	
2E	Advance for Felix	33+81	138' RT	W11-15 / W16-9P	30X30 / 24X12	8.25				10.67	
2F	Felix Crossing	33+85	27' RT	R5-3	24X24	4.00				9.00	
3A	Retaining Wall EB	45+22	30' RT	OM3-L	6X18	0.75				8.50	
3B	Stop at Key (trail)	46+62	43' RT	R1-1	18X18	2.25				8.50	
3C	Key Crossing	46+62	47' RT	R5-3	24X24	4.00				9.00	
3D	at Key	46+65	18' LT	W11-15 / W11-15p	30X30 / 24X18	11.25				12.33	
3E	Advance for Key	46+65	68' LT	W11-15 / W16-9P	30X30 / 24X12	8.25				10.67	
3F	at Key	47+01	49' RT	W11-15 / W11-15p / W16-7P(I)	30X30 / 24X18 / 24X12	11.25				12.33	
3G	Stop at Key (trail)	47+08	44' RT	R1-1	18X18	2.25				8.50	
3H	Key Crossing	47+08	47' RT	R5-3	24X24	4.00				9.00	
3I	Advance for Key	47+09	140' RT	W11-15 / W16-9P	30X30 / 24X12	8.25				10.67	
3J	Retaining Wall WB	48+87	31' RT	OM3-R	6X18	0.75				8.50	
4A	Advance for Hawk	56+62	87' LT	W11-15 / W16-9P	30X30 / 24X12	8.25				10.67	
4B	Stop Here	56+98	5' LT	R10-6a	24X30	5.00				9.00	
4C	at HAWK	57+11	25' RT	W11-15 / W16-7P(I)	30X30 / 24X12	8.25				10.67	
4D	HAWK sign	Pole A		R10-23M	60X48		20.00				
4E	HAWK Crossing	Pole A		Trail Sign	24X7		12.00				
4F	HAWK sign	Pole B		R10-23M	60X48		20.00				
4G	HAWK Crossing	Pole B		Trail Sign	24X7		12.00				
4H	at HAWK	57+76	46' RT	W11-15 / W16-7P(I)	30X30 / 24X12	8.25				10.67	
4I	Stop Here	57+91	71' RT	R10-6a	24X30	5.00				9.00	
4J	Advance for Hawk	58+33	150' RT	W11-15 / W16-9P	30X30 / 24X12	8.25				10.67	
SA	End of Trail (15th)	69+00	41' RT	R5-3	24X24	4.00				9.00	
TOTAL						194.00		64.00		295.67	

Summary of Ramps

STA.	Offset	Type	Width (FT)	EL (at bottom)	Tactile Warning Device - New	
					610(C) 4610	S.F.
					17+23	55
17+50	53	B (X2)	10	1233.87	20	
33+48	35	B (X2)	10	1248.4	20	
33+74	34	B (X2)	10	1248.6	20	
46+69	37	A-D	10	1228.2	20	
46+96	36	A-D	10	1228.3	20	
57+15	60	B	5	1248.5	0	
57+17	29	B	5	1246.6	10	
57+21	39	B	5	1246.9	10	
57+65	30	B	5	1246.9	10	
57+69	39	B	5	1246.9	10	
TOTAL					160	

Summary of Surfacing

STA.	to STA.	Notes	Retaining Wall	Concrete Curb (6" Barrier - Dowelled)	4" Concrete Sidewalk (6")
			510(A) 6333	609(A) 5864	610(A) 0602
			S.Y.	L.F.	S.Y.
17+04	17+23	W of Maple			20
17+50	33+48	Maple to Felix			1854
33+74	46+69	Felix to Key	40		1454
46+96	57+21	Key to Midwest	64	36	1203
57+65	75+48	Midwest to End		5	1553
TOTAL			104	41	6085

1. Sidewalk alternate 1 or 2 could be direct substitute for 4" concrete sidewalk if approved by Midwest City after bid, prior to award. All places in plan where it refers to 4" Sidewalk would be therefore changed to the approved alternate.

Summary of Removals

STA.	to STA.	Notes	Removal of Concrete Driveway	Removal of Curb	Removal of Sidewalk
			619(B) 4766	619(B) 4791	619(B) 4792
			S.Y.	L.F.	S.Y.
17+23		for ramp		16	
17+50		for ramp		16	
33+45		old sdwk (Felix)			44
33+48		for ramp		18	
33+74		for ramp		16	
46+69		for ramp		22	
46+96		for ramp		22	
56+73	57+24	old sdwk (Midwest)			45
57+08	57+24	part of parking lot	26.0	29	
57+65		part of parking lot		17	
70+83	71+53	old sdwk (SE 15th)			41
TOTAL			26.0	156	130