


REVISIONS		
NO.	DESCRIPTION	DATE

SIGN SUMMARY (2 OF 6)

SHEET NO.	ITEM NO.	APPROXIMATE LOCATION		SIGN	TYPE	POSTS				FOOTINGS				SIGN AREA			REMARKS			
						TYPE	A L.F.	B L.F.	SPACING	DESIGN NO.	CLASS A CONCRETE C.Y.	CLASS AA CONCRETE C.Y.	STEEL 511(A) LBS.	60" DRILLED SHAFT L.F.	STRUCTURAL CONCRETE C.Y.	STEEL 804(B) LBS.		SHEET S.F.	PANEL S.F.	PANEL OVERHEAD S.F.
T086	61	AS SHOWN	I-35 NB	SPECIAL SIGNS NO. 59															EXISTING STRUCTURE	
T086	62	AS SHOWN	I-35 NB	E5-1, E13-1(45)	4" WF @ 13	22.0	23.0	3'-8"	KC-0					0.72	130.00		42.00	210.00	EXISTING STRUCTURE	
T087	63	AS SHOWN	I-35 NB	SPECIAL SIGNS NO. 65, 66, 67														611.00	EXISTING STRUCTURE	
T087	64	AS SHOWN	I-35 NB	SPECIAL SIGNS NO. 68, 69														420.50	EXISTING STRUCTURE	
T087	65	AS SHOWN	I-35 NB	D10-3F(127)	2" SQ. TUBE POST	10.0										4.00			REMOVE EXISTING SIGN	
T087	66	AS SHOWN	I-35 NB	SPECIAL SIGNS NO. 71, 71A	6" WF @ 25	24.0	24.0	10'-6"	KC-2					1.64	348.00			297.50	TWO SIGNS BACK TO BACK	
T087	67	AS SHOWN	I-35 NB	SPECIAL SIGNS NO. 72, 73														420.50	EXISTING STRUCTURE	
T087	68	AS SHOWN	I-35 NB	E5-1A(127), E13-1(35)	4" WF @ 13	22.0	23.5	5'-5"	KC-0					0.72	130.00		52.50			
T088	69	AS SHOWN	I-35 NB	SPECIAL SIGN NO. 76														246.50	EXISTING STRUCTURE	
T088	70	AS SHOWN	I-35 NB	D10-3F(128)	2" SQ. TUBE POST	10.0										4.00			REMOVE EXISTING SGN	
T088	71	AS SHOWN	I-35 NB	SPECIAL SIGN NO. 77														170.00	EXISTING STRUCTURE	
T088	72	AS SHOWN	I-35 NB	SPECIAL SIGN NO. 78														132.00	EXISTING STRUCTURE	
T088	73	AS SHOWN	I-35 NB	E5-1A(129), E13-1(40)	4" WF @ 13	22.0	23.5	5'-5"	KC-0					0.72	130.00		52.50			
T088	74	AS SHOWN	I-35 NB	D10-3F(129)	2" SQ. TUBE POST	10.0										4.00			REMOVE EXISTING SGN	
T089	75	AS SHOWN	I-35 NB	SPECIAL SIGN NO. 80														220.50	EXISTING STRUCTURE	
T089	76	AS SHOWN	I-35 NB	SPECIAL SIGN NO. 81									35.00					198.00	NEW TYPE C MONOTUBE	
T089	77	AS SHOWN	I-35 NB	E5-1A(130), E13-1(20)	4" WF @ 13	22.0	23.5	5'-5"	KC-0					0.72	130.00		52.50			
T089	78	AS SHOWN	I-35 NB	D10-3F(130)	2" SQ. TUBE POST	10.0										4.00			REMOVE EXISTING SGN	
T090	79	AS SHOWN	I-35 NB	SPECIAL SIGN NO. 83														130.50	EXISTING STRUCTURE	
T090	80	AS SHOWN	I-35 NB	SPECIAL SIGN NO. 84	6" WF @ 15	17.5	19.5	7'-10"	KC-1					1.52	106.00		65.00			
T090	81	AS SHOWN	I-35 NB	SPECIAL SIGN NO. 85														180.00	EXISTING STRUCTURE	
T090	82	AS SHOWN	I-35 NB	SPECIAL SIGN NO. 86														134.75	EXISTING STRUCTURE	
T090	83	AS SHOWN	I-35 NB	E5-1A(131), E13-1(20)	4" WF @ 13	22.0	23.5	5'-5"	KC-0					0.72	130.00		52.50			
T090	84	AS SHOWN	I-35 NB	SPECIAL SIGN NO. 88														136.50	EXISTING STRUCTURE	
T091	85	AS SHOWN	I-35 NB	D10-3F(131)	2" SQ. TUBE POST	10.0										4.00			REMOVE EXISTING SGN	
T091	86	AS SHOWN	I-35 NB	SPECIAL SIGN NO. 89														215.25	EXISTING STRUCTURE	
T091	87	AS SHOWN	I-35 NB	SPECIAL SIGNS NO. 90, 91														288.00	EXISTING STRUCTURE	
T091	88	AS SHOWN	I-35 NB	E5-1A(132A), E13-1(40)	4" WF @ 13	22.0	23.5	5'-5"	KC-0					0.72	130.00		63.00			
T091	89	AS SHOWN	I-35 NB	D10-3F(132)	2" SQ. TUBE POST	10.0										4.00			REMOVE EXISTING SGN	
T091	90	AS SHOWN	I-35 NB	SPECIAL SIGN NO. 93														205.00	EXISTING STRUCTURE	
T091	91	AS SHOWN	I-35 NB	SPECIAL SIGNS NO. 94, 95, 96														633.00	EXISTING STRUCTURE	
T091	92	AS SHOWN	I-35 NB	E5-1A(132B), E13-1(40)	4" WF @ 13	22.0	23.5	5'-5"	KC-0					0.72	130.00		63.00			
T091	93	AS SHOWN	I-35 NB	D10-3F(133)	2" SQ. TUBE POST	10.0										4.00			REMOVE EXISTING SGN	
T091	94	AS SHOWN	I-35 NB	SPECIAL SIGN NO. 98, 99														478.50	EXISTING STRUCTURE	
T092	95	AS SHOWN	I-35 NB	SPECIAL SIGN NO. 100														146.75	EXISTING STRUCTURE	
T092	96	AS SHOWN	I-35 NB	D10-3F(134)	2" SQ. TUBE POST	10.0										4.00			REMOVE EXISTING SGN	
T092	97	AS SHOWN	I-35 NB	SPECIAL SIGN NO. 101														199.25	EXISTING STRUCTURE	
T092	98	AS SHOWN	I-35 NB	SPECIAL SIGNS NO. 102, 103, 104														519.25	EXISTING STRUCTURE	
T092	99	AS SHOWN	I-35 NB	E5-1A(134), E13-1(40)	4" WF @ 13	22.0	23.5	5'-5"	KC-0					0.72	130.00		52.50			
T092	100	AS SHOWN	I-35 NB	D10-3F(134)	2" SQ. TUBE POST	10.0										4.00			REMOVE EXISTING SGN	
T093	101	AS SHOWN	I-35 NB	SPECIAL SIGN NO. 106														193.50	EXISTING STRUCTURE	
T093	102	AS SHOWN	I-35 NB	SPECIAL SIGN NO. 107														129.25	EXISTING STRUCTURE	
T093	103	AS SHOWN	I-35 NB	E5-1A(135), E13-1(40)	4" WF @ 13	22.0	23.5	5'-5"	KC-0					0.72	130.00		52.50			
T093	104	AS SHOWN	I-35 NB	D10-3F(135)	2" SQ. TUBE POST	10.0										4.00			REMOVE EXISTING SGN	
T093	105	AS SHOWN	I-35 NB	SPECIAL SIGN NO. 109														120.75	EXISTING STRUCTURE	
T093	106	AS SHOWN	I-35 NB	SPECIAL SIGN NO. 110														200.00	EXISTING STRUCTURE	
T093	107	AS SHOWN	I-35 NB	D10 3F(136)	2" SQ. TUBE POST	10.0										4.00			REMOVE EXISTING SGN	
T093	108	AS SHOWN	I-35 NB	SPECIAL SIGN NO. 111														126.50	EXISTING STRUCTURE	
T093	109	AS SHOWN	I-35 NB	E5-1A(136), E13-1(40)	4" WF @ 13	22.0	23.5	5'-5"	KC-0					0.72	130.00		52.50			
T093	110	AS SHOWN	I-35 NB	SPECIAL SIGN NO. 113														137.00	EXISTING STRUCTURE	
T094	111	AS SHOWN	I-35 NB	SPECIAL SIGN NO. 114														200.00	EXISTING STRUCTURE	
T094	112	AS SHOWN	I-35 NB	D10-3F(137)	2" SQ. TUBE POST	10.0										4.00			REMOVE EXISTING SGN	
T094	113	AS SHOWN	I-35 NB	SPECIAL SIGNS NO. 115, 116, 117														521.00	EXISTING STRUCTURE	
T094	114	AS SHOWN	I-35 NB	E5-1A(137), E13-1(40)	4" WF @ 13	22.0	23.5	5'-5"	KC-0					0.72	130.00		52.50			
T094	115	AS SHOWN	I-35 NB	SPECIAL SIGN NO. 119														159.00	EXISTING STRUCTURE	
T094	116	AS SHOWN	I-35 NB	SPECIAL SIGNS NO. 120, 121, 122									70.00					708.00	NEW 100' TYPE B MONOTUBE	
T094	117	AS SHOWN	I-35 NB	SPECIAL SIGN NO. 123														241.50	EXISTING STRUCTURE	
T094	118	AS SHOWN	I-35 NB	E5-1A(138A), E13-1(45)	4" WF @ 13	22.0	23.5	5'-5"	KC-0					0.72	130.00		63.00			
T094	119	AS SHOWN	I-35 NB	SPECIAL SIGNS NO. 125, 126, 127														532.50	EXISTING STRUCTURE	
T094	120	AS SHOWN	I-35 NB	D10-3F(138)	2" SQ. TUBE POST	10.0										4.00			REMOVE EXISTING SGN	
T094	121	AS SHOWN	I-35 NB	SPECIAL SIGN NO. 128														219.00	EXISTING STRUCTURE	
TOTAL																				
					2" SQ. TUBE POST	130.0								105.00	11.80	2014.00	52.00	716.00	9681.25	
					2-1/2" PIPE POST															
					3" PIPE POST															
					3-1/2" PIPE POST															
					4" WF @ 13	545.5														
					6" WF @ 15															
					6" WF @ 20															
					6" WF @ 25	48.0														
					8" WF @ 31															
					10" WF @ 45															

G:\0\Projects\T-2598 I-35 Signing Project - EC-885B.Task I\CAD\T002-32625(04)-SIGN SUMMARY.dgn 09/14/17

Design	SDH	09/14/17
Drawn	GDB	09/14/17
 <small>A CLEAR DIRECTION</small>		

SIGN SUMMARY (SHEET 2 OF 6)